

Case File Number: PLN18490-REV02, PLN18490-REV01-PUDF01, PLN18490-REV01-PUDF02, PLN18490-REV01-PUDF03, PLN18521-R01

November 4, 2020

| | |
|--------------------------------------|--|
| Location: | West Oakland BART 1451 7 th St. |
| Assessor's Parcel Number(s): | APN 004 007700300, 004 007100300 |
| Proposal: | Revision to Preliminary Development Plan (PDP), including changes to residential unit allocation, reduction in office, retail, parking, residential open space, and removal of under-track retail. Updated State Density Bonus request with additional waivers/concessions. Variance request for off-street commercial loading. Vesting Tentative Parcel Map with 3 parcels and a designated remainder. Final Development Plan (FDP) for Horizontal Improvements, including final design for sidewalks, bike lanes, and plazas. Final Development Plan for development of area T1, a market-rate 320 ft tall residential tower with 522 residential units, 14,350 sf of retail, and 125 parking spaces. Final Development Plan for development of area T3, an affordable housing project with 240 affordable residential units, 15,957 sf of retail, and 50 parking spaces. |
| Applicant: | China Harbour Engineering (CHEC) |
| Contact Person/ Phone Number: | Ronnie Turner (510) 395-27664 |
| Owner: | San Francisco Bay Area Rapid Transit District (BART) |
| Case File Number: | PLN18490-REV02, PLN18521-R01, PLN18490-REV01-PUDF01, PLN18490-REV01-PUDF02, PLN18490-REV01-PUDF03 |
| Planning Permits Required: | PDP Revision, Variance for commercial loading, Three FDPs, Design Review, Vesting Tentative Parcel Map, compliance with CEQA |
| General Plan: | Community Commercial |
| Zoning: | Transit-Oriented Development Commercial Zone (S-15W) |
| Environmental Determination: | Reliance on prior CEQA document |
| Historic Status: | Non-Historic Property |
| City Council District: | CCD1 |
| Action to Be Taken | Consider approval of: <ul style="list-style-type: none"> • Revision to PDP, with Minor Variance, and revision to Vesting TPM 10940 • FDP for T1 market-rate residential tower • FDP for Horizontal Improvements • FDP for T3 affordable housing Based on attached findings and relevant conditions of approval |
| Finality of Decision: | Appealable to City Council |
| For Further Information: | Contact case planner Dara O'Byrne at 510-238-6983 or by e-mail at dobyrne@oaklandca.gov |


1. SUMMARY

The proposed project is a revision to a previously approved Preliminary Development Plan (PDP) for a Planned Unit Development at the West Oakland BART station (1451 7th St.). The PDP was initially entitled on February 6, 2019. The proposed revision consists of 762 residential units (of which 240 are affordable units), 300,000 square feet of office space, 53,491 square feet of retail, and 385 parking spaces. The project includes plazas and public right-of-way improvements. In 2019, the project was granted one concession and two waivers through the

State Affordable Housing Bonus Program and the project is now requesting two additional waivers, plus a revision to an existing waiver. The proposed revision includes the following changes to the entitlement:

- Changes the single, shared 400-car parking garage to three separate garages with separate entrances, adding driveways on Mandela Parkway, with a total of 385 parking spaces.

CITY OF OAKLAND PLANNING COMMISSION



Case File: PLN18490-REV02, PLN18521-R01, PLN18490-REV01-PUDF01
PLN18490-REV01-PUDF02, PLN18490-REV01-PUDF03
Applicant: China Harbour Engineering (CHEC)
Address: West Oakland BART 1451 7th St
Zone: S-15W
Height Area: 60 ft, 100 ft

- Removes the undertrack retail and removes the Condition of Approval to provide an equivalent amount of retail on 7th Street
- Requests additional Affordable Housing Density Bonus waivers for parking, open space, and additional stories, specifically:
 - Waiver for reduction of overall required residential usable open space from 77,123 square feet with a variance to permit 42,463 square feet. The initial entitlement included a variance from the PUD requirements for residential group usable open space, but that variance is being replaced with a State Affordable Housing Density Bonus waiver.
 - Waiver for reduction of overall parking spaces from 400 spaces to 385 spaces, with individual parking garages for each building.
 - Waiver for increase in number of stories on T1 from 30 to 31.
- Changes to each development area include the following:
 - T1:
 - Eliminates the 82,460 square feet of office;
 - Moves 22 market rate units from T3 to T1;
 - Reduces retail from 17,185 square feet to 14,350 square feet; and
 - Increases the number of stories from 30 to 31.
 - T2: Eliminates retail located under the BART tracks and revises the related condition of approval. Reduces the public open space area by 10,425 square feet to accommodate wider sidewalks and design of the Class IV bike lane on 7th St.
 - T3: Reduces residential units from 262 to 240 units
 - T4: Reduces the retail from 30,800 square feet to 23,184 square feet. Requests a variance for off-street commercial loading.

The Final Development Plan for Horizontal Improvements (PLN18490-REV01-PUDF02) includes final designs for public plazas, sidewalks, bike lanes, and associated phasing of the improvements.

The Final Development Plan for development area T1 (PLN18490-REV01-PUDF01) at the corner of 7th St and Mandela Parkway includes 522 residential market-rate units with 14,350 square feet of retail and 125 parking spaces in a 320 ft tall tower.

The Final Development Plan for development area T3 (PLN18490-REV01-PUDF03) at 5th St. and Chester St. includes 240 affordable residential units (79 units at 30% AMI, 11 units at 50% AMI, 148 units at 60% AMI, and 2 units at 120% AMI) 15,957 square feet of retail, and 50 parking spaces in an 80 foot tall mid-rise building.

The project also includes a revision to the Vesting Tentative Parcel Map for 3 new parcels and a Designated Remainder.

2. PROJECT SITE AND SURROUNDING AREA

The West Oakland BART TOD site encompasses 5.58 acres and is bounded by 7th Street to the north, 5th Street to the south, Chester Street to the west, and Mandela Parkway to the east. The project site consists of two parcels at 1451 7th Street (Assessor's Parcel Numbers: 004-007-700-300 and 004-007-100-300).

3. PROJECT BACKGROUND

3.1 Project History

The proposed project is located at the site of the West Oakland BART station, which currently includes BART parking and a BART station. The San Francisco Bay Area Rapid Transit District (BART) owns the land to be developed and will have a long-term lease with the proposed developer. The BART station will remain, but the BART parking and vehicular access will be removed from the site.

The project applicant first submitted a pre-application to the City of Oakland in October 2017 to receive initial feedback on preliminary site layout and design. The Preliminary Development Plan for a Planned Unit Development was submitted in November 2018. The project went through an expedited review process in order to compete for an Affordable Housing Sustainable Communities (AHSC) funding award and was approved by the Planning Commission on February 6, 2019.

In June 2019, a revision to the Preliminary Development Plan was submitted with three Final Development Plans. In December 2019, a separate revision to the Preliminary Development Plan was submitted.

The revised project and three Final Development Plans were presented to the Design Review Committee on August 12, 2020. The project applicant has been working with the community, through an established Community Advisory Council, to receive input on the proposed project.

3.2 Previous Public Hearings

3.2.1 February 6, 2019 Planning Commission

The previously approved PDP bypassed the Design Review Committee due to expedited review. During the February 6, 2019 Planning Commission Hearing, Commissioners added two conditions of approval to the project based on commitments the applicant made during the hearing:

- **Condition of Approval 74: Below market rate retail.** If feasible, a minimum of 20% of the total retail square footage or number of tenants shall be provided below market rate.
- **Condition of Approval 75: Level of affordable housing provided.** Provide one third (1/3) of all affordable residential units below 30% Area Median Income (AMI)

3.2.2 August 12, 2020 Design Review Committee

The revision to the PDP and the three Final Development Plans were presented at the August 12, 2020 Design Review Committee hearing. The DRC members had the following feedback to the applicant:

- Provide more activation of the plaza areas, particularly for children. Provide children's play area as part of the overall plaza design.
- Make sure art wall does not include advertising or other signage.
- Provide the Program for Art for Planning Commission consideration.
- Provide distant views of the tower at key vantage points.
- Provide more details on the building materials for Planning Commission consideration, particularly the color of glass.
- Ensure that the affordable housing is built before, or concurrently with, the market rate housing.

4. PROJECT DESCRIPTION

The proposed West Oakland BART TOD project is a revision to a previously approved preliminary development plan for a mixed-use project surrounding the West Oakland BART station. The project is located at the approximately 5.58- acre site encompassing the West Oakland BART station bounded by 7th Street to the north, 5th Street to the south, Chester Street to the west, and Mandela Parkway to the east. The project site consists of two parcels at 1451-7th Street (Assessor's Parcel Number: 004-007-700-300 and 004-007-100-300). The proposal also includes three Final Development Plans associated with the PDP revision.

4.1 Existing Conditions and Surrounding Land Uses

The project site is a rectangular lot occupied by the West Oakland BART station and associated surface parking and circulation. Vegetation onsite is currently limited to some street and parking lot landscaping and trees. Existing land uses in the vicinity include multi- story commercial and residential development to the north, parking/fuel station/vacant lot to the east, light industrial and low- rise residential to the south, and low- rise residential to the west.

4.2 Project Overview for PDP Revision

The Project is a multi-phase Planned Unit Development that will include 3 parcels and a designated remainder:

- T1 (Lot 1): 522 market-rate residential units, 14,350 square feet of retail, and 125 parking spaces in a 320 foot tall tower¹
- T3 (Lot 3): 240 affordable residential units, 15,957 square feet of retail, and 50 parking spaces in an 80 foot tall building
- T4 (Lot 2): 300,000 square feet of office space, 23,184 square feet of retail, and 210 parking spaces in a 100 foot tall building.
- Designated Remainder: Includes the West Oakland BART station, BART tracks, a bike station, public plazas, and Emergency Vehicle Access.

The entire project includes 762 residential units, 300,000 square feet of office, 53,491 square feet of retail, and 385 parking spaces. The proposed revision includes the following changes to the entitlement:

¹ Although ground floor retail uses are being proposed as part of the project, the applicant or successor in interest will need to apply for future entitlements as to the specific type of retail or commercial use being proposed to occupy the retail spaces.

- Changes the single, shared 400-car parking garage to three separate garages with separate entrances, adding driveways on Mandela Parkway with a total of 385 parking spaces.
- Requests additional Affordable Housing Density Bonus waivers for parking, open space, and additional stories, specifically:
 - Reduction of overall residential usable open space from the previously approved 77,123 square feet to 42,463 square feet. The initial entitlement included a variance from the PUD requirements for residential group usable open space, but that variance is being replaced with a State Affordable Housing Density Bonus waiver.
 - Reduction of overall parking spaces from 400 spaces to 385 spaces, with individual parking garages.
 - Increase in the number of stories on T1 from 30 to 31.
- Changes to each building include the following:
 - T1:
 - Eliminates the 82,460 square feet of office;
 - Moves 22 market rate units from T3 to T1;
 - Reduces retail from 17,185 square feet to 14,350 square feet; and
 - Increases the number of stories from 30 to 31.
 - T2: Eliminates retail located under the BART tracks and revises the related condition of approval. Reduces the public open space area by 10,425 square feet to accommodate wider sidewalks and design of the Class IV bike lane on 7th St.
 - T3: Reduces residential units from 262 to 240 units
 - T4: Reduces the retail from 30,800 square feet to 23,184 square feet. Requests a variance for off-street commercial loading.

The associated project-specific Design Guidelines remain unchanged. The initial approved PDP and Design Guidelines can be found in Attachment B to this report. Plans, elevations, design guidelines, and illustratives for the revision to the Preliminary Development Plan are provided in Attachment C to this report.

Project Development Summary (change from 2019 Project in parentheses)

| Uses | T1 | T2 | T3 | T4 | Total |
|------------------------|-----------------------------------|---------------------|----------------------------------|-----------------------------------|----------------------------|
| Office | 0 sf (-82,460 sf) | | | 300,000 sf | 300,000 sf (-82,460 sf) |
| Retail | 14,350 sf (-2,835 sf) | 0 sf (-7,670 sf) | 15,944 sf (+794 sf) | 23,184 sf (-7,616 sf) | 53,478 sf (-17,377 sf) |
| Residential | 522 units (+22 units) | | 240 units (-22 units) | | 762 units |
| Public Open Space | | | | | 75,368 sf (-10,425 sf) |
| Residential Open Space | 17,648 sf (-1,454sf) | | 24,815 sf (-33,941 sf) | | 42,463 sf (-35,395 sf) |
| Parking | 125 stalls (previously shared) | | 50 stalls (previously shared) | 210 stalls (previously shared) | 385 stalls (-15 stalls) |

4.4 Project Overview for T1

The Final Development Plan for the T1 building includes 522 market-rate residential units, 14,350 square feet of retail, and 125 parking spaces in a 320-foot tall tower located at 7th St. and Mandela Parkway. This is a prominent corner in West Oakland and is the project’s primary frontage on 7th St. Retail faces 7th Street on the ground floor with retail wrapping around to Mandela Parkway. The parking garage access, loading, and utility access are ganged on Mandela Parkway.

The breakdown by residential unit type includes:

- 80 3-bedroom units;
- 96 2-bedroom units;
- 228 1 bedroom units; and
- 118 studio units.

The following requested waivers/concessions apply to this project: maximum height at the street frontage, parking, open space, building height, and number of stories.

4.5 Project Overview for Horizontal Improvements

The Final Development Plan for Horizontal Improvements includes final designs for plazas and streetscape improvements. The project includes a plaza at 7th St. and Chester St. (Mandela Plaza), an undertrack plaza off of Chester St., and an Art Alley that runs along the south side of the BART tracks from Chester St. to Mandela Pkwy. A plaza is also provided at Center and 5th St. (Center Square). The overall size of the public open space is reduced by 10,425 square feet from the initial PDP to accommodate the accommodation of the full 8 foot pedestrian through zone on the sidewalks and the design of the Class IV bike lane on 7th St. The following streetscape improvements are included in the FDP:

- 7th Street Improvements:
 - Raised Class IV one-way separated bikeways on 7th St. between Chester St. and Mandela Pkwy.;

- Minimum 8 ft pedestrian through zone on the sidewalk between Chester St. and Mandela Pkwy.;
- Approximately 270-foot extended bus stop on eastbound 7th St. at Mandela Pkwy.
- Approximately 130-foot bus stop on westbound 7th St. just west of Center St.
- Approximately 250-feet of linear curb designated for passenger loading and unloading on eastbound 7th St. between Chester St. and Center St., with about 50 feet of curb on eastbound 7th St. just west of Center St. designated as blue accessible loading zone.
- Blues Walk of Fame Plaques relocated to a new position on the sidewalk.
- Existing Dancing Lights removed to accommodate the new streetscape with bike lane and extended sidewalk. OakDOT to review and approve permit for removal of Dancing Lights at the PX permit.
- Mandela Parkway Improvements
 - Class IV one-way separated bikeways on both sides of Mandela Pkwy. between 7th St. and 5th St.
 - Minimum 8 ft pedestrian through zone on the sidewalk between 7th St. and 5th St.
 - Parking removed on the west side of Mandela Parkway between 5th St. and 7th St.
- 5th Street Improvements
 - Minimum 8 ft pedestrian through zone on the sidewalk between Chester Street and Mandela Parkway
 - Approximately 170-foot long bus stop and layover zone with a concrete bus pad on 5th Street just west of Mandela Pkwy.
 - Approximately 100-feet of linear curb designated for passenger loading and unloading east of Center St. and about 200 feet west of Center St.
- Chester Street Improvements
 - Minimum 8 ft pedestrian through zone on the sidewalk between 7th St. and 5th St.
 - Centerline redesigned to facilitate northbound bus turning movements.
 - Prohibit parking on the east side of Chester St. between 5th St. and 7th St. and on the west side of Chester St. for about 100 feet south of 7th St.

Intersection Improvements

- 5th St. and Center St.
 - All-way stop control
 - High-visibility crosswalks and directional ramps
 - Curb extensions
- 5th St. and Chester St.
 - High-visibility crosswalks and directional ramps
- 5th St. and Mandela Pkwy.
 - High-visibility crosswalks and directional ramps
 - Curb extensions at the NE, SE, and SW corners
- 7th St. and Center St.
 - Pedestrian scramble signal phasing
 - Protected intersection with designated pedestrian and bicycle crossing
- 7th St. and Chester St.
 - Curb extensions at the NW, NE, and SW corners

- Mandela Pkwy. and 7th St.
 - Dedicated bicycle signal phase
 - Signal timing for bus-only phase
- Mandela Pkwy. between 5th St. and 7th St.
 - High-visibility, mid-block pedestrian crossing

The bike station on the east side of the existing BART station will be reviewed and approved by BART, under their jurisdiction. It is proposed to accommodate at least 300 bicycles. The City and BART will enter into a separate Memorandum of Understanding (MOU) delineating the permitting and review authority of the respective agencies with respect to the designated remainder and the bike station.

The horizontal improvements do impact previously implemented streetscape improvements, including the Blues Walk of Fame and the 7th Street Streetscape Improvements Dancing Lights, as discussed below:

4.5.1 Blues Walk of Fame

“The Music They Played on 7th Street Oakland” Walk of Fame lines the Seventh Street sidewalk in front of the West Oakland BART station and features 88 plaques of honorees, including Aretha Franklin, Ike and Tina Turner, the Pointer Sisters, B.B. King, John Lee Hooker and Ray Charles. The Bay Area Blues Society implemented the Blues Walk of Fame, with funding and support from the City of Oakland, Bay Area Rapid Transit, and private donations.

The FDP for Horizontal Improvements proposes the removal of the plaques during construction and placing the plaques back in the sidewalk along 7th St. when the final sidewalks are constructed. OakDOT will review the final location for the plaques at the time of the PX Permit to ensure there is no potential damage to the plaques due to future root upheaval.

4.5.2 Seventh Street Concept and Urban Design Plan

In 2004, a California Department of Transportation (Caltrans) grant for Environmental Justice funded a streetscape design concept for 7th St., which included a streetscape design and urban design elements that were implemented by the City of Oakland. The purpose of the plan was to:

- Reduce the adverse impacts of transportation on the immediate Seventh Street project site.
- Recommend amenities conducive to future transit oriented development and activity with a strong civic character that creates a “place” identity

The implemented improvements included a landscaped median, sidewalk and intersection improvements, as well as a number of urban design elements. The urban design elements included Dancing Lights, which were placed in front of the BART station between Chester St. and Mandela Parkway, a transit canopy structure at the BART station, and a Gateway Feature near Union St. The urban design concept contemplated the inclusion of the Blues Walk of Fame and associated plaques.

The FDP for Horizontal Improvements proposes removal of the Dancing Lights to accommodate a Class IV bike lane, loading zones, and widened sidewalk where the dancing lights are currently located. The matching transit canopy structure would also be removed to accommodate the

redesigned bus stop and streetscape design. The applicant has committed to work with the community to consider options for relocation of the Dancing Lights. These proposed changes to the public Rights-of-Way will be overseen by OakDOT at the time of the PX Permit approval.

4.6 Project Overview for T3

The Final Development Plan for T3 includes a mixed use building at the corner of 5th St. and Chester St. The proposed project includes 240 affordable residential units, at the following affordability levels:

- 79 units at 30% AMI;
- 11 units at 50% AMI;
- 148 units at 60% AMI; and
- 2 units at 120% AMI.

The breakdown by unit type includes:

- 14 3-bedroom units;
- 47 2-bedroom units; and
- 137 1-bedroom units.

The project also includes 15,957 square feet of retail fronting 5th St., Center Square, and the Art Alley. The project includes 50 parking spaces. Residential-oriented uses, including a residential lobby, are located along Chester St., and the building steps down from 80 feet to 38 ft tall along Chester St. to transition to the single-family scale of the Prescott Neighborhood. The project includes an art wall along the north elevations, facing the BART tracks.

The following requested waivers/concessions apply to this project: maximum height at the street frontage, parking, open space, and building height.

4.7 Project Overview for T4

The Final Development Plan for T4 will be submitted in a later phase of the project and therefore a full analysis of T4 is not included in this staff report. The PDP Revision is reducing the retail in T4 from 30,800 square feet to 23,184 square feet and requesting a variance for off-street commercial loading. The Planning Code requires 3 off-street loading berths for 160,000 sq. ft or more of commercial space. The project provides one code compliant off-street loading space. The variance is requested for the two other spaces. The applicant provides two loading spaces within the T4 parking garage, but they do not meet the dimensional requirements.

5. GENERAL PLAN ANALYSIS

The West Oakland BART TOD project site is located in the Community Commercial (CC) General Plan (GP) land use designation. The intent of the CC land use designation is to “identify, create, maintain, and enhance areas suitable for a wide variety of commercial and institutional operations along the City’s major corridors and in shopping districts or centers.” In terms of desired character, future development may include “neighborhood center uses and larger scale retail and commercial uses, such as auto related businesses, business and personal services, health services and medical uses, educational facilities, and entertainment uses.

Community Commercial areas can be complemented by the addition of urban residential development and compatible mixed use development.” The maximum allowed intensity is 125 residential units per gross acre and the maximum FAR for this classification is 5.0. At this time, the total count of residential units considered under the Preliminary Development Permit is 762 units, within the General Plan allowance. The proposed commercial FAR is within the General Plan maximum FAR.

The West Oakland BART site is also designated as a Transit-oriented district, which are “designated to take advantage of the opportunities presented by Oakland’s eight BART stations...” “Easy pedestrian and transit access to mixed use development characterize these areas. A strong identity is to be created through careful design and mix of activity.” West Oakland BART is “uniquely situated as the first station linking San Francisco and Oakland, and the only station serving four BART routes.”

The following is an analysis of how the proposed project meets applicable General Plan objectives (staff analysis in indented, italicized text below each objective):

- Policy T2.1 Encouraging Transit-Oriented Development
 - *The proposed project is a transit-oriented development with a mix of office, residential, and ground floor, pedestrian-oriented retail.*
- Policy T2.3 Promoting Neighborhood Services
 - *The proposed project includes up to 55,000 square feet of neighborhood-serving commercial, including a proposed food market and other local retail.*
- Policy N1.1 Concentrating Commercial Development
 - *The proposed project concentrates neighborhood-oriented retail around the West Oakland BART station. There are many smaller scale retail locations that will serve residents and BART riders alike.*
- Policy N3.1 Facilitating Housing Construction
 - *The proposed project includes the creation of 762 new housing units, of which 240 are affordable units.*
- Policy N3.2 Encouraging Infill Development
 - *The proposed project converts an existing parking lot into a mixed-use infill development, consistent with the General Plan.*
- N6.1 Mixing Housing Types
 - *The proposed project includes a mix of housing types and unit sizes, which are available to households with a range of incomes. The project includes studios, 1-bedroom, 2-bedroom, and 3-bedroom types.*
- Policy N8.1 Developing Transit Villages
 - *The proposed project creates a Transit Village at the West Oakland BART station.*
- Policy N8.2 Making Compatible Interfaces Between Densities
 - *The proposed project includes a step-down to 38 feet along Chester Street, as the project transitions to the South Prescott neighborhood.*
- Policy N9.5 Marking Significant Sites
 - *The proposed project will work to incorporate public art and installations that identify locations of interest and historic significance, including the Blues Walk of Fame.*

5.1 West Oakland Specific Plan Analysis

The proposed project is located in the West Oakland Specific Plan (WOSP) area. The WOSP provides specific land use scenarios and policies for West Oakland BART, as follows:

- Intent: Implement the City's long-term vision for a Transit-Oriented Development (TOD) project at the West Oakland BART station, in the area generally coinciding with the boundaries of the City's existing S-15 Transit Oriented Development Zone.
 - *The proposed project implements the vision for a TOD project at the West Oakland BART station.*
- 7th Street TOD Land Use-1: Select a site with immediate proximity to the West Oakland BART Station which can serve as the catalyst, first-phase development of the TOD.
 - *The proposed project will serve as a catalyst for future development in West Oakland. The proposed project will be developed in phases.*
- Intent: Ensure a mix of land uses in the BART Station TOD to ensure the site becomes an integral and fully integrated component of West Oakland.
 - *The proposed project includes residential, office, and retail land uses. The project proposes neighborhood serving retail and flexible commercial spaces for small scale retail so it becomes an integral component in West Oakland.*
- 7th Street TOD Land Use-6: Plazas and open space should contribute to a secure and aesthetically pleasing pedestrian experience at and around the BART Station TOD.
 - *The proposed project includes a public plaza at 7th St. and Chester St. as well as pedestrian walkways and a 'Center Square' that provide public access to the BART station.*
- 7th Street TOD Env-2: The new buildings envisioned to surround the West Oakland BART station as part of the TOD project are expected to provide a noticeable and significant noise buffer between portions of both the freeway and the BART tracks, and existing residential neighborhoods. The noise attenuation benefits from the proposed new buildings should be fully considered in final designs for these structures.
 - *The conditions of approval ensure that this project will support noise attenuation for the surrounding neighborhood and not aggravate noise conditions for the community.*
- TOD-2: Create a high-density residential, commercial, and mixed-use development which might also include the artistic economic enterprises within the West Oakland district with creative working space for technology, innovative science activities drawing upon the desires of some in those industries for creative space with room for innovative production.
 - *The proposed project provides a high-density mixed-use development at the West Oakland BART site. Local retail spaces are proposed as part of the project, providing opportunities for creating working spaces.*
- TOD-3: Ensure a safe and pleasant pedestrian environment near the West Oakland BART Station.
 - *The proposed project provides safe and pleasant pedestrian connections both along the streets surrounding the project, but also through the site to connect to the BART station.*

- TOD-5: Provide amenities such as benches, kiosks, lighting, public art, high quality pavement materials, drought tolerant landscaping, and specialty uses such as outdoor cafes.
 - *The proposed project includes conceptual designs for improved streetscapes and public plazas with high quality pavement materials, pedestrian-scaled lighting, and pedestrian-oriented retail with outdoor seating throughout the site.*
- TOD-6: Limit conflicts between vehicles and pedestrians, and add urban infrastructure as demonstrations of the best of the new industry standards.
 - *The proposed project removes all vehicular access on the site (except emergency vehicles and service vehicles), creating pedestrian walkways that are separated from vehicular travel. The project also proposes improved pedestrian crossings at the surrounding intersections.*
- TOD-7: New residential and commercial development along the perimeter of the TOD site, nearest to the South Prescott neighborhood, should include a gradual transition in height and density to the surrounding lower-density residential neighborhoods, with building heights stepping down to as low as 2-stories immediately adjacent to existing homes
 - *The proposed residential building at T3 steps down from 80 feet to 38 feet tall along Chester St. to transition to the single-family scale of the Prescott Neighborhood,, providing a transition to the smaller scaled residential units across the street.*

Circulation

- Streetscape-4: Prioritize the development of local streetscape improvement plans, including lights, trees, bulb outs, sidewalks, etc., on: Mandela Parkway from 7th to 8th Street;
 - *The project team developed an Access Study for the proposed project, which includes recommendations for improvements to the intersection at 7th Street and Mandela Parkway.*
- Pedestrian-1: Promote street right-of-way design standards that make walking convenient and enjoyable.
 - *The proposed project incorporates streetscape designs that will improve the pedestrian environment and improve pedestrian connections to and from the BART station. Improvements include improved sidewalks, improved crosswalks, and internal walkways, connecting pedestrians to the development and the BART station.*
- Bicycle-3: Make bicycle riding more safe, secure and convenient.
 - *The proposed project incorporates Class IV separated bikeways along 7th Street and Mandela Parkway, creating safer bicycle access to the development and to the BART station. In addition, the project is providing a 300-space bike station with valet surface on site. The project is also providing long-term bike parking within the buildings and short-term bike parking around the site.*
- Existing Transit Enhance-1: Seek and identify funding mechanisms to increase the frequency of AC Transit bus service and make other transit improvements in and through West Oakland.

- *The approved TDM plan provides an option for the developer to invest in increased AC Transit service to the project site by funding the implementation of AC Transit's ACgo plan. In particular, lines 14, 29, 36 and 62 serve to connect West Oakland BART and nearby destinations. Operations investments should serve to increase frequency of these routes to meet ACgo full implementation goals (weekday peak and off peak: 15 minute headways for lines 14 and 62, and 20 minute headways for lines 29 and 36; weekend: 20 minute headways for lines 14, 29, 36 and 62).*

Neighborhood-Serving Retail & Services

- Intent: Support community-based efforts to improve West Oakland residents' access to everyday goods and services.
 - *The proposed project would greatly increase the amount of neighborhood-serving retail, including retail along 7th St., 5th St., and at the interior of the site with up to 55,000 square feet of retail proposed. The project proposes the potential for uses such as a food market, cafes, and numerous local retail spaces.*
- EED-13: Support the expansion of an existing grocery store and/or the establishment of new grocery stores in West Oakland.
 - *The proposed project includes ground floor retail on 7th St., 5th St, and facing the interior of the site. Specific commercial activities have not been identified for these locations, but a grocery store or other food market may be considered. While a small foot market may be contemplated for this space, this application does not include entitlements for a food market, which will need to be obtained at a later date.*
- EED-14: Promote the development of community-based, neighborhood-serving retail and service businesses.
 - *The project is required, if feasible, to provide 20% of the retail square footage below market rate.*

6. ZONING ANALYSIS OVERVIEW

The West Oakland BART TOD project is located within the Transit-Oriented Development Commercial Zone (S-15W). The intent of the S-15W Zone is to create, preserve and enhance areas devoted primarily to serve multiple nodes of transportation and to feature high-density residential, commercial, and mixed-use developments to encourage a balance of pedestrian-oriented activities, transit opportunities, and concentrated development; and encourage a safe and pleasant pedestrian environment near transit stations by allowing a mixture of Residential, Civic, Commercial, and Light Industrial Activities, allowing for amenities such as benches, kiosks, lighting, and outdoor cafes; and by limiting conflicts between vehicles and pedestrians, and is typically appropriate around transit centers such as Bay Area Rapid Transit (BART) stations, AC Transit centers, and other transportation nodes. The following discussion outlines the purpose of the S-15W zone, with staff analysis provided below in indented, italicized text:

- Create, preserve, and enhance areas devoted primarily to serve multiple nodes of transportation and to feature high-density residential, commercial, and mixed-use developments.

- *The proposed project is a mixed-use project at the West Oakland BART station, with high-density residential, office, and retail.*
- Encourage a balance of pedestrian-oriented activities, transit opportunities, and concentrated development
 - *The proposed project provides pedestrian-oriented retail along the ground floor of the development as well as a series of pedestrian-oriented public plazas and walkways. The proposed project integrates the BART station and AC Transit bus stops into the overall development. The proposed project incorporates concentrated development at the site with 762 residential units, 300,000 square feet of office, and up to 55,000 square feet of retail.*
- Encourage a safe and pleasant pedestrian environment near transit stations by allowing a mixture of Residential, Civic, Commercial, and Light Industrial Activities, allowing for amenities such as benches, kiosks, lighting, and outdoor cafes.
 - *The proposed project provides a safe and pleasant pedestrian environment by improving sidewalks along the perimeter of the site as well as creating pedestrian walkways through the site to the BART station. The pedestrian walkways include pedestrian-scaled lighting, seating, and cafes.*
- Limit conflicts between vehicles and pedestrians
 - *The proposed project removes vehicles (except Emergency Vehicles and Service Vehicles) from the site and creates a pedestrian-oriented environment.*

17.97.035 - Special regulations applying to mixed-use developments on Bay Area Rapid

Transit (BART) stations on sites with one (1) acre or more land area.

No mixed-use developments that include Bay Area Rapid Transit (BART) stations located on sites with one (1) acre or more land area shall be permitted except upon the granting of a conditional use permit pursuant to Section 17.97.025 and the conditional use permit procedure in Chapter 17.134 or upon the granting of a Planned Unit Development permit pursuant to Chapters 17.140 and 17.142, and shall be subject to the following special regulations:

- A. Intermodal Activities and Pedestrian Plaza. Developments should incorporate multiple forms of public transportation and a pedestrian plaza.

The project has incorporated a pedestrian plaza at the corner of 7th and Chester St. as well as at 5th St. and Center St. The project is accommodating multiple forms of public transportation by providing AC Transit bus stops along 7th St. and 5th St.

- B. Professional Design. The application shall utilize the following professionals in the design process for the development:

1. An architect licensed by the state of California; and
2. A landscape architect licensed by the state of California, or an urban planner holding or capable of holding membership in the American Institute of Certified Planners.

The project is utilizing a licensed architect and a licensed landscape architect.

- C. Undergrounding of Utilities. All electric and telephone facilities; fire alarm conduits; street light wiring; and other wiring, conduits, and similar facilities shall be placed

underground by the developer as required by the city. Electric and telephone facilities shall be installed in accordance with standard specifications of the serving utilities. Street lighting and fire alarm facilities shall be installed in accordance with standard specifications of the Electrical Department.

All utilities are underground or located inside the building.

- D. Performance Bonds. The City Planning Commission or, on appeal, the City Council may, as a condition of approval of any said development, require a cash bond or surety bond for the completion of all or specified parts of the development deemed to be essential to the achievement of the purposes set forth in Section 17.97.010. The bond shall be in a form approved by the City Attorney, in a sum of one hundred fifty percent (150%) of the estimated cost of the work, and conditioned upon the faithful performance of the work specified within the time specified. This requirement shall not apply if evidence is provided to the city which indicates that alternative bonding or other assurances have been secured by the Bay Area Rapid Transit District.

A Condition of Approval has been added to require Performance Bonds for public improvements that facilitate public access to the BART station.

6.1 Residential Land Use and Density Analysis

The applicable zoning regulations include land use and density allowances. The project size is split into two zoning designations:

- Development Areas T2, T3 have a height limit of 60 ft, Commercial FAR maximum of 3.0, and a maximum residential density of 375 square feet of lot area required per dwelling unit.
- Development Areas T1, T4 have a height limit of 100 ft, commercial FAR maximum of 5.0, and a maximum residential density of 225 square feet of lot area required per dwelling unit.

Residential Land Use and Density Analysis

The applicable zoning regulations include land use and density allowances. The project size is split into two zoning designations:

- Development Areas T2, T3 have a height limit of 60 ft, Commercial FAR maximum of 3.0, and a maximum residential density of 375 square feet of lot area required per dwelling unit.
- Development Areas T1, T4 have a height limit of 100 ft, commercial FAR maximum of 5.0, and a maximum residential density of 225 square feet of lot area required per dwelling unit.

With a total developable area of 243,130 square feet, the following calculations show the allowable density based on the proposed project.

| <u>Commercial FAR</u> | |
|---------------------------------|------------|
| T2, T3: 3.0 FAR allowed | 333,690 sf |
| T1, T4: 5.0 FAR allowed | 659,500 sf |
| Total Commercial Allowed: | 993,190 sf |
| Total Commercial Proposed: | 353,478 sf |
| Percent of development capacity | 36% |

Residential Density

| | |
|---|-----------|
| T2, T3: 375 sf of lot area allowed | 296 units |
| T1, T4: 225 sf of lot area allowed | 586 units |
| Total Allowed Residential Density | 882 units |
| Percent of development capacity remaining | 64% |
| Residential Units Allowed | 565 units |
| Allowed With PUD Bonus 25% | 706 units |
| Allowed with State AH Bonus 35% | 953 units |

The commercial development is approximately 353,478 square feet, which is approximately 36% of the development capacity allowed through the base FAR, leaving 64% of the development capacity for residential density. Under the base density, that would result in a maximum 586 residential units. Adding the Planned Unit Development 25 percent density bonus would allow for 706 residential units. The State Affordable Housing Density Bonus increase of 35 percent would allow up to 953 residential units, which is more than the 762 units proposed.

The project proposes 240 affordable dwelling units, including 11% very low income units (84 units) and 20% low income units (156 units), qualifying the project for the State Affordable Housing Density Bonus of 35%. In addition, the previously approved project received a concession to increase the maximum height for Development Area T1 from 100 ft to 320 ft and the maximum height for Development Area T3 from 60 ft to 80 ft. The previously approved project received a concession to increase the number of stories allowable under the Specific Plan and Zoning from 9 stories at Development Area T1 to 30 stories and Development Area T3 from 5 stories to 8 stories.

6.3 State Affordable Housing Density Bonus

The project proposes 90 units of very low income units (up to 50% AMI), 148 low income units (51-80% AMI), and 2 moderate income units (81-120% AMI) qualifying the project for the State Affordable Housing Density Bonus of 35%. The specific affordability levels are as follows:

- 79 units at 30% AMI (32% of affordable units; 10% of total units) This meets the Condition of Approval requiring 30% of the affordable units to be at or below 30% AMI.
- 11 units at 50% AMI (5% of the affordable units; 1% of total units)
- 148 units at 60% AMI (62% of the affordable units; 19% of total units)
- 2 units at 120% AMI (.8% of the affordable units; .2% of total units)

Below is a summary of the requested waivers and concession related to the State Affordable Housing Bonus:

- Concession to increase the maximum height at street frontage required by the West Oakland Specific Plan for T-1 (75' required and 320' requested) and T-3 (25' required and 80' requested) (granted by the Planning Commission on February 6, 2019);
- Waiver to increase the number of stories allowed by the West Oakland Specific Plan (granted by the Planning Commission on February 6, 2019), updated request for increase for T-1 from 30 stories to 31;

- Waiver to eliminate the height limits required by the West Oakland Specific Plan for T-1 (100' required and 320' requested) and for T-3 (60' required and 80' requested) (granted by the Planning Commission on February 6, 2019);
- Waiver of the group usable open space requirements for T-1 and for T-3 from 152,400 square feet (collectively) to a total of 42,314 square feet. Waiver request based on site constraints; and
- Waiver of the residential off-street parking requirements for T-1 and for T-3 a total required number of 211 stalls to 175 provided. Waiver request based on site constraints.

The applicant has submitted an Affordable Housing Density Bonus supplemental form and letter explaining their justifications for the additional waiver requests. Staff finds the justifications for the requested waivers to satisfy the requirements of the State Government Code.

7. PROJECT SPECIFIC ZONING ANALYSIS AND DESIGN REVIEW

7.1 Revision to Preliminary Development Plan (PDP) for the Planned Unit Development (PLN18490 – REV02)

7.1.1 Zoning Analysis for PDP Revision

| Development Standard | Required S-15W – 60' 004007700300 (T2, T3) | Required S-15W – 100' 004007100300 (T1, T4) | Proposed 111,230 (T2, T3) | Proposed 131,900 (T1, T4) | Consistency Analysis |
|--|---|---|---|---------------------------|---|
| Use | | | | | |
| Multifamily | P | | P | P | Complies |
| Administrative | P | | P | P | Complies |
| General Retail | P | | P | P | Complies |
| Community Assembly | P | | P | | Complies |
| Height | 60 ft | 100 ft | 80 ft | 320 ft, 100 ft | Does not comply. Waiver previously granted |
| Max height within 10' of the front property line | 25 ft | 75 ft | 38 ft | 320 ft | Does not comply. Concession previously granted |
| Residential Density | 375 sq ft (296 units before commercial calculation) | 225 sq ft (586 units before commercial calculation) | 240 units | 522 units | PUD bonus and State Affordable Housing Bonus previously granted |
| Max Nonresidential FAR | 3.0 | 5.0 | 0.16 | 2.62 | Complies |
| Open Space | | | | | |
| Group usable open space per regular unit | 150 sf per unit 150x240 = 36,000 | 75 sf per unit 75x522 = 39,150 | Total required = 75,150 sf Total open space provided = 42,463 sf | | Does not comply. Waiver requested |

| Development Standard | Required S-15W – 60' 004007700300 (T2, T3) | Required S-15W – 100' 004007100300 (T1, T4) | Proposed 111,230 (T2, T3) | Proposed 131,900 (T1, T4) | Consistency Analysis |
|--|---|---|--|---------------------------|--|
| 17.142.110 Development standards. F. Usable Open Space | IF PUD bonus requested, 200 sf/du of group usable open space required = 152,400 sf | | Total open space provided = 42,463 sf | | Does not comply Waiver requested |
| 17.116 Parking - Multifamily | Min: 0.50 space per dwelling unit Max: 1.25 spaces per dwelling unit 381 parking spaces required Can take advantage of up to 50% reduction in parking requirement if meet criteria. 191 required | | 150 | | Does not comply Waiver requested |
| 17.116 Parking - Office | Min: No parking required Max: 1 space per 300 sq ft | | 190 parking spaces provided | | Complies |
| 17.116 Parking - Commercial | 1 space for each 600 sq ft of floor area on the ground floor of a building; 1 space for each 1,000 sq ft of floor area not on the ground floor of a building =53,478/600 = 89 T1: 24 = 12 T3: 27 = 14 T4: 39 = 20 | | 45 | | Complies with 50% reduction |
| Total Parking | Total Parking Required: 470 spaces required. If comply with reduction requirements, 280 spaces | | 385 total parking spaces provided | | Complies |
| Loading | | | | | |
| 17.97.060 Loading | Driveway cannot be located within 20 ft from walkways and plazas or need CUP | | Complies | | Complies |
| Residential Loading | 1 berth for T1 and T3 | | Loading has been reduced from 2 to 1 on T3, and 2 to 1 on T1 | | Complies |
| Commercial Loading | 160,000 sq ft or more provide 3 berths | | Loading has been reduced from 2 to 1 loading spaces on T4, reduction does not comply. | | Does not comply. Variance requested |
| Bike Parking | | | | | |
| 17.117 Multifamily Bike Parking | Long-term: 1 space/4 du = 191 Short-term: 1 space/20 du = 39 | | Complies Long-term: 220 spaces: T3: 70; T1: 150; 191 spaces for residential Short-term: 90 total spaces provided, 39 applied for residential | | Complies |
| 17.117 Retail Bike Parking | Long-term: 1 space/12,000 sq ft = 5 spaces required Short-term: 1 space/2,000 sq ft = 27 spaces required | | Complies Long-term: 29 Short-term: 27 | | Complies |

| Development Standard | Required S-15W – 60’ 004007700300 (T2, T3) | Required S-15W – 100’ 004007100300 (T1, T4) | Proposed 111,230 (T2, T3) | Proposed 131,900 (T1, T4) | Consistency Analysis |
|----------------------------|--|---|--|---------------------------------|----------------------|
| 17.117 Office Bike Parking | Long-term: 1 space/10,000 sq ft = 30 Short-term: 1 space/20,000 sq ft = 15 | | Complies Long-term: 55 Short-Term: 24 | | Complies |
| TOTAL Bike Parking | Long-term: 226 spaces required Short-term: 81 spaces required | | Complies Long-term: 220+55 spaces provided Short-term: 90 short-term spaces provided | | Complies |
| Lockers/showers | A minimum of two (2) showers per gender plus one (1) shower per gender for each 150,000 sf. above 150,000 sf. = 3 showers per gender Four (4) lockers per shower = 20 lockers | | Meets requirement. 3 showers and 12 lockers per gender provided on the ground floor of T4 | | Complies |

7.1.2 Design Review for Preliminary Development Plan (PLN18490-REV02)

The Preliminary Development Plan provides conceptual designs for the overall project with supporting Design Guidelines generally remain unchanged, except for the following:

- Removal of undertrack retail. The removal of the undertrack retail creates a larger public plaza but also removes activating uses and creates an undertrack space that creates design challenges.
- Parking redesign. The change to the parking arrangement impacts Mandela Parkway by adding curb cuts, driveways, and garage entries that were not there under the previous entitlement. The added garage access for T1 and T4 means that the majority of Mandela is now dedicated to back of house activities.

7.2 Zoning Analysis and Design Review for Final Development Plan (FDP) for T1 (PLN18490-REV01-PUDF01)

7.2.1 Zoning Analysis for T1

| Development Standard | Required S-15W – 100’ (T1: 32,054 sf) | Proposed (T1) | Consistency Analysis |
|--|--|---------------|--|
| Use | | | |
| Multifamily | P | P | Complies |
| General Retail | P | P | Complies |
| Maximum Height | 100 ft | 320 ft | Does not comply, Waiver previously granted |
| Max height within 10’ of the front property line | 75 ft | 320 ft | Does not comply, Concession previously granted |
| Residential Density | 225 sq ft (586 units before commercial calculation) | 522 units | Does not comply, PUD bonus and State Affordable Housing Bonus previously granted |

| Development Standard | Required S-15W – 100’ (T1: 32,054 sf) | Proposed (T1) | Consistency Analysis |
|--|--|--|--|
| Max Nonresidential FAR | 5.0 | 0.45 | Complies |
| Max number of stories | 9 | 31 | Does not comply, Waiver previously granted for 30 stories, request to extend to 31 stories |
| Open Space | | | |
| Group usable open space per regular unit | 75 sf per unit 75x522 = 39,150 | 17,648 sf | Does not comply, Waiver requested |
| 17.142.110 Development standards. F. Usable Open Space | 200 sf/unit = 104,400 | 17,648 sf | Does not comply Waiver requested |
| Parking and Loading | | | |
| 17.116 Parking - Multifamily | Min: 0.50 space per dwelling unit Max: 1.25 spaces per dwelling unit 261 parking spaces required Can take advantage of up to 50% reduction in parking requirement if meet criteria = 130 spaces | 117 | Does not comply Waiver requested |
| 17.116 Parking - Commercial | 1 space for each 600 sq ft of floor area on the ground floor of a building; (first 3000 sf not counted) 19 spaces required, 50% reduction | 8 | Does not comply Waiver requested |
| Total Parking | 140 spaces required | 125 | Does not comply Waiver requested |
| 17.97.060 Loading | Driveway cannot be located within 20 ft from walkways and plazas or need CUP | | Complies |
| Residential Loading | 1 berth required | 1 berth provided | Complies |
| 17.117 Multifamily Bike Parking | Long-term: 1 space/4 du = 131 Short-term: 1 space/20 du = 27 | 131 LT spaces 27 ST spaces | Complies |
| 17.117 Retail Bike Parking | Long-term: 1 space/12,000 sq ft = 2 spaces required Short-term: 1 space/2,000 sq ft = 8 spaces required | 2 LT spaces 8 ST spaces, covered by PDP | Complies |
| TOTAL Bike Parking | Long-term: 133 spaces required Short-term: 35 spaces required | 250 LT spaces 36 ST spaces | Complies |

7.2.2 Design Review for FDP for T1 (PLN18490-REV01-PUDF01)

The Final Development Plan is required to be consistent with the Preliminary Development Plan and the associated Design Guidelines. Staff feedback is indented and in italics below.

West Oakland BART Design Guidelines

Activated 7th Street Corridor

2. The minimum depth of retail space from storefront to rear should be at least 40 feet to promote viable uses

- *Most of the proposed retail along 7th Street meets this design guideline.*
- 3. The retail frontage should be built with adequate set-back to the property line to provide public transit use of the sidewalk and possible café tables and other retail uses at the sidewalk edge.
 - *Proposed setbacks do allow for minimum required clear pedestrian through-zone, with some space for café tables or other retail uses.*
- 5. Building entries should be oriented to the street or promenade with intervals that promote active street experience, except for major anchor tenants such as grocery or drug stores, which could be a greater interval.
 - *The building entries are oriented to the street.*
- 6. Shop fronts should be designed with a high level of transparency – at least 75% glass storefront along the 7th Street edge.
 - *The retail fronting 7th St. provides a high level of transparency, meeting or exceeding this guideline.*

Mandela Parkway

Building facades along Mandela Parkway will be designed to become lively and delightful edges to streets and open spaces through the variation of building materials and facade typologies.

- *The retail space at 7th and Mandela does a good job of wrapping the corner and providing entrances on Mandela Parkway. The rest of Mandela Parkway is dedicated to back of house activities that are not active, but the applicant claims that they cannot be further minimized or located anywhere else.*
2. Service and Loading areas should be well designed and visually protected from pedestrian view. Service and loading areas should be designed to minimize pedestrian disruption and to ensure pedestrian safety.
 - *The service and loading areas that have to be located on Mandela shall have improved design, with high quality doors that are integrated into the overall design of the building.*
 5. Retail and other public uses should be provided where possible. Shop fronts should be designed with a high level of transparency and visual interest.
 - *The only retail provided on Mandela Pkwy is at the corner of 7th St. The rest of the Mandela Pkwy frontage is dedicated to back of house activities.*
 6. Service and loading areas should be designed to minimize pedestrian disruption and to ensure pedestrian safety.
 - *Design of garage and loading doors as well as doors for transformers and gas meter could be higher quality and more visually attractive.*

7.3 Zoning Analysis and Design Review for Final Development Plan (FDP) for Horizontal Improvements (PLN18490-REV01-PUDF02)

7.3.1 Zoning Analysis for FDP for Horizontal Improvements

The Final Development Plan for Horizontal Improvements does not require a zoning analysis because the improvements are related to portions of the project that are non-development related.

7.3.2 Design Review for FDP for Horizontal Improvements

The streets and open spaces proposed in the Preliminary Development Plan are further refined in the Final Development Plan and should be consistent with the PDP and the West Oakland BART Design Guidelines. Staff feedback is indented and in italics below.

West Oakland BART TOD Design Guidelines

Public Space Goals: The following urban design principles are intended to support public space strategy:

- Establish a continuous, diverse and active network of public open spaces, including plazas, activated streetscapes and pedestrian paseos that connect site and BART station to the surrounding community.
 - *The project provides a plaza at 7th St. and Chester St. (Mandela Plaza), a plaza at 5th St. and Center St. (Center Square), and an Art Alley along the BART tracks. The public spaces are well connected and activated with retail and design elements.*
- Configure and design the open space system to serve as center for the West Oakland community and a destination for Oakland and the East Bay.
 - *The applicant has added landscaping and design features to the open space system since the first submittal, but it is still unclear if the design elements are creating a true destination where people will want to stop and spend time. The addition of interactive art for children will help activate the space, but this addition will not be determined until building permit. The Conditions of Approval require programming, which will help activate the space and create a destination.*
- Create walkable and lively public streets, open spaces and pedestrian ways that provide a delightful, safe and activated 7 day-a-week destination for the neighborhood, transit riders and East Bay.
 - *The design of the public streets and pedestrian ways provide critical multimodal access to the West Oakland BART station.*
- Provide a range of cultural, recreational and commercial activities that reinforce the public destination appeal and civic role of the Station site as a whole.
 - *The project provides a wide range of commercial activities and will retain the Blues Walk of Fame. The Public Art component of the project has the potential to provide further cultural attraction to the site, but the details of the Public Art are still unknown at this time.*
 - *The Dancing Lights will be removed to accommodate the updated streetscape designs to accommodate bicycle, pedestrian, and transit access to this site. Conversations between OakDOT and the community about potential relocation of the Dancing Lights are ongoing.*

7.4 Zoning Analysis and Design Review for Final Development Plan (FDP) for T3 (PLN18490-REV01-PUDF03)

7.4.1 Zoning Analysis for FDP for T3 (PLN18490-REV01-PUDF03)

| Development Standard | Required S-15W – 60’ (T3:53,652sf) | Proposed T3 | Consistency Analysis |
|--|--|---|--|
| Use | | | |
| Multifamily | P | P | Complies |
| General Retail | P | P | Complies 15,944 sf |
| Community Assembly | P | P | Complies 1,719 sf |
| Maximum Height | 60 ft | 80 ft | Does not comply. Waiver previously granted. |
| Max height within 10’ of the front property line | 25 ft | 38 ft | Does not comply, Concession previously granted |
| Residential Density | 375 sq ft (296 units before commercial calculation) | 240 units | Complies with approved PDP (with 35% SAHB) |
| Max Nonresidential FAR | 3.0 | 0.33 | Complies |
| Max number of stories | 5 | 8 | Does not comply. Waiver previously granted. |
| Open Space | | | |
| Group usable open space per regular unit | 150 sf per unit 150x240 = 36,000 sf | Total open space provided = 24,815 sf | Does not comply. Waiver requested |
| 17.142.110 Development standards. F. Usable Open Space | PUD bonus requested, 200 sf/du of group usable open space required = 48,000 sf | Total open space provided = 24,815 sf | Does not comply. Waiver requested |
| Parking and Loading | | | |
| 17.116 Parking - Multifamily | Min: 0.50 space per dwelling unit Max: 1.25 spaces per dwelling unit 120 parking spaces required Can take advantage of up to 50% reduction, 60 parking spaces | 34 provided. | Does not comply Waiver requested |
| 17.116 Parking - Commercial | 1 space for each 600 sq ft of floor area on the ground floor of a building; Subtract first 3000 sf. 22 spaces required, apply 50% reduction for 11 spaces required | 13 provided | Complies |
| Total Parking | Total Parking Required: 141 spaces required. If comply with reduction requirements, 71 spaces required | 50 spaces provided (ADA plus Car Share spaces) | Does not comply Waiver requested |
| 17.97.060 Loading | Driveway cannot be located within 20 ft from walkways and plazas or need CUP | Driveways are more than 20 ft from a walkway or plaza | Complies |
| Residential Loading | 1 berth | 1 berth provided | Complies. |
| Commercial Loading | Not required | None | Complies |

| Development Standard | Required S-15W – 60' (T3:53,652sf) | Proposed T3 | Consistency Analysis |
|---------------------------------|--|---|----------------------|
| 17.117 Multifamily Bike Parking | Long-term: 1 space/4 du = 60 Short-term: 1 space/20 du = 12 | Long-term: 118 Short-term: 12 | Complies |
| 17.117 Retail Bike Parking | Long-term: 1 space/12,000 sq ft = 2 spaces required Short-term: 1 space/2,000 sq ft = 1 spaces required | Long-term: 2 Short-term: 8 | Complies |
| TOTAL Bike Parking | Long-term: 62 spaces required Short-term: 13 spaces required | Long-term: 68 spaces provided Short-term: 20 spaces provided | Complies |

7.4.2 Design Review for FDP for T3 (PLN18490-REV01-PUDF03)

The Final Development Plan is required to be consistent with the Preliminary Development Plan and the associated Design Guidelines. Staff response to the relevant design guidelines are indented and italicized below.

West Oakland BART TOD Design Guidelines

Activated 5th Street Corridor

1. The ground floor-to-floor dimension should promote viable retail uses that are welcoming and transparent in nature, with a minimum floor-to-floor height of 20'
 - *The floor to floor height is increased to 20ft along 5th St., complying with this guideline.*
2. The minimum depth of retail space from storefront to rear should be at least 25-30 feet to promote viable uses
 - *Some of the retail spaces along the Art Walk Plaza are only 20 ft deep and therefore do not comply with this requirement.*
5. Building entries should be oriented to the street or promenade with intervals that promote active street experience, except for major anchor tenants such as grocery or drug stores, which could be a greater interval.
 - *Building entries along 5th St. are oriented to the street with intervals that promote active street experience. Along the Art Alley, there are two areas that front the parking garage with windows, so it is unclear what will be visible to the pedestrian. It would be better to relocate the car-share spaces and extend the retail space.*
6. Shop fronts should be designed with a high level of transparency – at least 60% glass storefront along the 5th Street edge.
 - *Retail has been moved back to 5th St. and storefront windows have a high level of transparency.*
7. Use architectural details on residential structures such as balconies, railings, lighting, canopies, and other elements that enliven the facade and reinforce the human scale of the development
 - *Architectural details are provided to reinforce the human scale of the development. The bay projections facing Chester Street encroach over the property line into the City right-of-way. This will require City Council approval.*

Chester Street

2. Residential uses should have individual entries that activate the street and provide a more traditional neighborhood scale.
 - *Residential lobby, community assembly, and other residential amenity space faces Chester. There are no ground floor units.*

8. ZONING AND DESIGN RELATED ISSUES

8.1 Design

Staff has worked with the applicant to refine the design of the project to maximize access to the BART Station, activate the public spaces, and create pedestrian-oriented design at the ground floor. The building designs for T1 and T3 have been refined through the design review process.

8.2 Issues

In general, staff finds the project to be well-designed and generally consistent with the previously approved PDP and associated Design Guidelines. That said, the following issues should be considered in reviewing the project for approval:

8.2.1 Preliminary Development Plan Revision (PLN18490-REV02):

- Removal of under track retail. The approved PDP included retail under the BART tracks, providing a continuation of retail along 7th St. and activating the plaza. The applicant is proposing to remove the retail under the track and expanding the plaza space. As part of the February 6, 2019 entitlement, **Condition of Approval #68** requires:

“The project applicant shall provide approximately 7,610 square feet of retail under the BART tracks between Chester Street and the BART Station, consistent with the approved PDP. If retail uses under the BART tracks are deemed infeasible by the City of Oakland, then an equivalent amount of retail shall be provided along 7th St. between Chester Street and Center Street. Retail can be provided in kiosks, containers, or other small-scale retail buildings. At the same time, if retail cannot be provided under the BART tracks on Development Area T2, then the applicant shall design the space under the tracks as an attractive, delightful space for residents, community members, and BART riders to spend time with adequate provisions for safety such as security and lighting improvements.”

The retail under the tracks has been deemed infeasible, due to BART safety requirements, which made the retail too expensive to provide. The applicant is also unable to provide an equivalent amount of retail along 7th St., and is therefore seeking a revision to this Condition. The applicant is proposing a continuous plaza from 7th St. to the T3 development. The space under the track is a difficult space to activate and to create a safe, attractive, and delightful space. The applicant has continued to improve and refine the proposed design for the under track plaza.

- Variance for off-street loading on T4. A Minor Variance is requested for off-street loading for the administrative activity in the T4 building. The Planning Code requires 3 off-street loading berths for 160,000 sq. ft or more of commercial space. The project provides one code compliant off-street loading space. The variance is requested for the two other spaces. The applicant provides two loading spaces within the T4 parking

garage, but they do not meet the dimensional requirements. Staff supports this variance, with attached findings. Two additional loading berths would be very difficult to fit on Mandela Parkway while meeting the 20 ft separation of driveways from a pedestrian walkway. In addition, additional curb cuts would negatively impact the Class IV cycletrack along Mandela. 5th St is also constrained by bus stops and key pedestrian connections. The applicant has provided loading areas within the building.

- Project Phasing. The phasing of the project requires the affordable housing portion of the project (T3) to be built before or concurrently with the market rate portion of the project (T1) because the market rate tower is dependent on the State Affordable Housing Bonus, which provides a 35% density bonus plus concessions and waivers for a 320 foot tall tower in a zone that has a maximum height of 100 ft, as well as waivers for open space and parking for the T1 market rate tower.

The applicant has requested that the City change the phasing to allow the market rate tower to be built first. Staff does not support this change because it is inconsistent with the City's Standard Conditions of Approval for affordable housing projects and it is inconsistent with the City's affordable housing regulations in O.M.C. Section 15.72.100.A.5, which states that "All affordable housing units in a development project and phases of a development project must be constructed concurrently with or prior to the construction of the market-rate units." Both the applicable Standard Condition of Approval and the O.M.C are regulated under the authority of Department of Housing and Community Development, with advice from the City Attorney's Office.

This requirement for concurrent phasing and construction of the affordable and market rate units ensure that the community receives the affordable units in exchange for the bonuses the project receives through state density bonus law. Staff has added Condition #78, which was not a Standard Condition of Approval in February 2019 when the project was initially approved, but is now applied to all affordable housing projects.

- Phasing of public improvements. The conditions of approval have been updated to allow for phased implementation of public improvements to allow for more flexibility for the applicant based on the site constraints related to construction. Please see Condition #70 and Condition #72. Working with OakDOT, the conditions have been amended to allow the public improvements to be implemented related to the phases of development, rather than requiring the public improvements all at the beginning of the project. The Final Development Plan for Horizontal Improvements details the phasing of construction and phasing of implementation of public improvements. The applicant will be required to bond for public improvements that are not included in the first phase of implementation, in order to ensure the City receives the improvements promised as part of this entitlement and as articulated in the Planning Code, 17.97.035. This is particularly important for the improvements deemed to be essential to the achievement of providing multimodal access to the BART station, including sidewalks, bus stops, bike lanes, as well as emergency vehicle access.

In addition, in coordination with OakDOT, staff has revised the conditions of approval to ensure delivery of 7th Street improvements and the off-site improvements prior to the issuance of Certificate of Occupancy of the market rate residential tower at T1.

8.2.2 FDP for T1 (PLN18490-REV01-PUDF01):

- **Mandela Pkwy.** All of the back of house activities for the T1 project are ganged on Mandela Parkway, including the garage access, loading access, and utility areas. This lack of activation isn't consistent with the design guidelines for Mandela Parkway, but this is a better location for these back of house activities than 7th St. The applicant has wrapped the retail from 7th St at the corner of Mandela, providing a pedestrian entrance on Mandela, improving the activation of the corner. Staff considers this the best solution for the project, acknowledging that these back of house activities need to be located somewhere along the street. DRC was generally supportive of this site plan. Staff has requested that the utility and garage doors along the Mandela frontage be high quality.
- **Materials.** DRC requested more details about the proposed materials for the T1 high rise tower. The applicant has updated the material exhibits within the Final Development Plan. The applicant has also put together a physical materials board and taken pictures to help provide more details about the texture and depth of materials, which are often hard to decipher in the electronic submittals. In general, staff finds the materials to be high-quality and appropriate for the design of the building.
- **Tower.** DRC requested more views of the tower from vantage points throughout the neighborhood. The applicant has provided these views in the FDP for T1 on A-01.08 and A-01.09 and in the PDP Revision on A-00.18 through A-00.21.

8.2.3 FDP for Horizontal Improvements (PLN18490-REV01-PUDF02):

- **Plazas.** The project specific conditions of approval require that the ground floor public plazas and walkways "be high-quality, well-designed spaces that include excellent pedestrian-scaled lighting, extensive furnishings, and interactive art or other amenities for children." Based on DRC feedback, the applicant has proposed two potential locations for interactive art for children to help create more amenities for children, with some potential ideas included in the plans.
- **Blues Walk of Fame.** The "The Music They Played on 7th Street Oakland" Walk of Fame lines the 7th Street sidewalk in front of the West Oakland BART station and features 88 plaques. The Bay Area Blues Society implemented the Blues Walk of Fame, with funding and support from the City of Oakland, Bay Area Rapid Transit, and private donations. The applicant proposes removing the plaques to protect them during construction and putting them back in the sidewalk along 7th St. when the streetscape improvements are finalized. OakDOT will review and approve the final location of the plaques during the PX permit review phase.

- **Dancing Lights.** The dancing lights were part of a 2004 Caltrans grant, which funded the concept for the urban design elements called the Dancing Lights. The lights are located in front of the BART station between Chester St. and Mandela Parkway along 7th St. The City of Oakland implemented this streetscape improvement. The new multimodal streetscape design does not provide room for these urban design features, with a loading zone, a sidewalk grade bike lane, and a wide pedestrian through zone. Just as with their initial approval, the applicant is proposing removal of these urban design features to allow for the streetscape improvements. There may be potential for the relocation of the dancing lights to a new location. The applicant has discussed a future engagement process with the community and OakDOT to identify potential locations, but there is not specific commitment at this time.
- **Incident Command Center.** The Incident Command Center for the BART station is currently proposed in three alternative locations: one in the T3 building along the Art Alley and two under the BART tracks near the station. The Oakland Fire Department has requested that the Command Center not be located in T3, but rather located under the BART tracks closer to the station. This is articulated in OFD conditions of approval.
- **Bike Station under the BART track.** The jurisdiction for the review and approval of the under track Bike Station is still being considered between BART and the City of Oakland. Conceptual designs of the bike station are included by the applicant for context purposes. Permitting responsibility for the bike station and remainder parcel will be negotiated through a Memorandum of Understanding (MOU) between the City and BART.

8.2.4 FDP for T3 (PLN18490-REV01-PUDF03):

- **Materials.** DRC requested more details about the proposed materials for the T1 high rise tower. The applicant has updated the material exhibits within the Final Development Plan. The applicant has also put together a physical materials board and taken pictures to help provide more details about the texture and depth of materials, which are often hard to decipher in the electronic submittals. In general, staff finds the materials to be high-quality and appropriate for the design of the building.
- **Art Wall:** The project contains a 16,000 square foot blank wall with very little glazing facing the BART tracks, which is envisioned as an “Art Gallery Wall” with rotating art. The wall acts as a sound barrier, with a corridor facing the tracks and units facing away from the BART tracks.

This wall is a significant architectural feature of the building and the overall project. The wall is visible from BART as people leave and enter Oakland and it is visible from 7th St. Because of the visibility and prominence of the wall, staff needs to understand what will be implemented on the wall as part of the City’s Design Review procedures. In order to make the design review findings for the project, the wall’s scale, bulk, height, and texture need to be analyzed. This is not an analysis of the potential art in this location, but an analysis of the architectural design of the prominent, highly visible wall.

Consistent with direction from the DRC and input from the Cultural Arts Division, staff has requested more details on the approach to the rotating art on this wall before going to public hearing, to help provide more details about how the concept will work, including who will manage the rotating art, how it will be paid for, how often the art will be updated, how often the wall will be without art, and how the art is chosen. DRC also requested an art plan to help provide details on the approach to Public Art. The applicant has provided the Mandela Station Public Art Summary (Attachment I), which helps to provide the intent of the applicant and outlines the process the applicant will follow to determine the approach to the wall after the entitlement process.

Staff supports the community-driven vision of having a rotating art gallery featuring local artists visible to hundreds of thousands of BART riders, but without more clarity and details about how the rotating art wall will be implemented, it is difficult to complete the required design review analysis.

The applicant has proposed a ‘non-art wall’ with color blocks for consideration, should the proposed Rotating Art Gallery Wall not be feasible. Since the August 12th DRC hearing, the applicant has improved the materials of this wall to include metal panels, to ensure the vibrant colors are maintained over time. Staff supports this improvement and thinks this will ensure the wall colors will remain vibrant and visually interesting between exhibits. Staff provided design review feedback requesting more articulation, depth, or texture to the wall, but because the applicant wants to ensure a smooth “canvas” for art, significant changes were not incorporated.

In order to provide the applicant with the flexibility to work through the community process to determine their full approach to the “Art Gallery Wall”, staff has included a condition of approval (Condition #77) that would allow the applicant to follow the proposed process for the rotating Art Gallery Wall. If the rotating Art Gallery Wall is deemed infeasible, due to cost or other unforeseen implementation complexities, then the applicant can provide permanent art in its place, therefore providing visual interest on this highly visible wall. If permanent art is deemed infeasible, then the applicant can bring the project back to the Design Review Committee to review the wall to ensure the ‘non-art wall’ provides enough depth, texture, articulation, modulation, or other architectural interest for this prominent site.

- Major Encroachment. The proposed T3 building has livable space that extends three feet over the property line into the public right-of-way on Chester Street. This will require a Major Encroachment Permit and will require City Council approval.

CALIFORNIA ENVIRONMENTAL QUALITY ACT

The City Council certified an Environmental Impact Report (EIR) for the West Oakland Specific Plan on July 15, 2014. The West Oakland Specific Plan Environmental Impact Report [SCH No. 2012102047] is provided under separate cover to the Planning Commission (Attachment A) and

is available to the public on the web at: <https://www.oaklandca.gov/resources/current-environmental-review-ceqa-eir-documents-2011-2020>.

On February 6, 2019, staff determined that an Addendum to the West Oakland Specific Plan EIR was appropriate for the initial entitlement of this project because no new information about the site, changes to the project, or circumstances under which the project would be undertaken occurred. The California Public Resources Code section 21166 and CEQA Guidelines section 15164 state that an Addendum to a certified EIR is allowed when minor changes or additions are necessary and none of the conditions for preparation of a Subsequent EIR are met. Because the revision to the PDP and the three FDPs are a refinement of, and not a substantive change to, the approved project, no further environmental review is required beyond the Addendum. As documented by the City's environmental consultant, this 2020 revision would not require subsequent analysis per CEQA Guidelines Section 15162 because:

- (1) The 2020 Project would not result in new significant environmental effects or a substantial increase in the severity of previously identified significant effects;
- (2) There are no changes in circumstances that would result in new significant environmental effects or a substantial increase in the severity of previously identified significant effects;
- or
- (3) There is no new information resulting in a new significant effect not discussed that would result in new significant environmental effects, a substantial increase in the severity of previously identified significant effects, or a change in the feasibility (or acceptance) of mitigation measures.

While changes to the project have occurred after the City's adoption of the 2019 EIR Addendum, this assessment has determined that no further documentation is required per CEQA Guidelines Section 15162. The 2019 EIR Addendum continues to serve as the applicable environmental review document pursuant to the requirements of CEQA for approval of the 2020 Project and the associated adopted Standard Conditions of Approval and Mitigation Monitoring and Reporting Program would remain fully applicable.


RECOMMENDATION

The proposed West Oakland BART Transit-Oriented Development is consistent with and delivers on the vision of transit-oriented development envisioned in the West Oakland Specific Plan and the S-15W zoning district. Staff finds the proposed project to be well designed, responsive to staff comments, and recommends approval. Staff specifically recommends that the Planning Commission:


1. Rely on the West Oakland Specific Plan (WOSP) EIR as adequate under CEQA for analysis of the West Oakland BART TOD and adopt CEQA finding that no further environmental review is required pursuant to Public Resources Code Section 21166 and CEQA Guidelines Section 15162;
2. Approve the revision to the Preliminary Development Plan, subject to the attached findings and revised conditions.
3. Approve a Minor Variance for reduction of off-street commercial loading, based on the attached findings.

4. Approve the Final Development Plan for T1, subject to the attached findings.
5. Approve the Final Development Plan for Horizontal Improvements, subject to the attached findings.
6. Approve the Final Development Plan for T3, subject to the attached findings
7. Approve the revision to the Vesting Tentative Parcel Map 10940.


Prepared by:


Dara O'Byrne, Planner IV

Reviewed by:


Catherine Payne, Acting Development Planning Manager
Bureau of Planning

Approved for forwarding to the Planning Commission:


Ed Manasse, Deputy Director
Bureau of Planning

Attachment A:

1. West Oakland Specific Plan EIR and Addendum #1; available to the public at <https://www.oaklandca.gov/resources/current-environmental-review-ceqa-eir-documents-2011-2020>
2. West Oakland BART TOD – Transportation Analysis (non-CEQA)
3. West Oakland BART TOD – Transportation and Parking Demand Management Plan
4. CEQA Technical Memo: West Oakland BART TOD Project – Assessment of Project Changes, dated October 22, 2020

Attachment B: Previously Approved West Oakland BART TOD Preliminary Development Plan and Design Guidelines, February 6, 2019

Attachment C: Proposed Revision to West Oakland BART TOD Preliminary Development Plan, dated September 16, 2020

Attachment D: Proposed Revision to Vesting Tentative Parcel Map, 10940

Attachment E: Proposed T1 Final Development Plan, dated September 16, 2020

Attachment F: Proposed Horizontal Improvements Final Development Plan, dated September 16, 2020

Attachment G: Proposed T3 Final Development Plan, dated September 16, 2020

Attachment H: Conditions of Approval:

1. Standard Conditions of Approval, with proposed revisions and clean copy
2. Oakland Department of Transportation, Engineering Services Conditions of Approval
3. Oakland Department of Transportation, City Surveyor Conditions of Approval
4. Oakland Fire Department Conditions of Approval

Attachment I: Mandela Station Public Art Program, September 16, 2020

**REQUIRED FINDINGS:
WEST OAKLAND BART TOD PROJECT (MANDELA STATION)
PRELIMINARY DEVELOPMENT PLAN REVISION**

Required findings include:

- California Environmental Quality Act
- Regular Design Review: Planning Code Section 17.136.050
- Minor Variance Findings: Planning Code Section 17.148.050
- Subdivision Findings
- PUD Findings

California Environmental Quality Act

The City Council certified an Environmental Impact Report (EIR) for the West Oakland Specific Plan on July 15, 2014. The West Oakland Specific Plan Environmental Impact Report [SCH No. 2012102047] is provided under separate cover to the Planning Commission (Attachment A) and is available to the public on the web at: <https://www.oaklandca.gov/resources/current-environmental-review-ceqa-eir-documents-2011-2020>.

Staff has determined that an Addendum to the West Oakland Specific Plan EIR is appropriate because no new information about the site, changes to the project, or circumstances under which the project would be undertaken have occurred. The California Public Resources Code section 21166 and CEQA Guidelines section 15164 State CEQA Guidelines Section 15164 states that an Addendum to a certified EIR is allowed when minor changes or additions are necessary and none of the conditions for preparation of a Subsequent EIR are met.

Staff has determined, through the environmental checklist, that there is substantial evidence that the project would not require preparation of a Supplemental EIR and that an Addendum is the appropriate CEQA document, per the following conclusions:

- (1) The proposed project adds project-level details to a site identified in the WOSP for transit-oriented development within the Zoning and General Plan densities proposed (while the applicant also leverages the State Affordable Housing Density Bonus Law (Government Code Section 65915 et seq., City of Oakland Municipal Code Chapter 17.107)) to allow for the increased density and heights proposed. The increased density and project concessions are required under state law and ministerial, therefore beyond CEQA analysis. The project would not result in new significant environmental effect or a substantial increase in the severity of impacts identified in the WOSP EIR because the project, being a transit-oriented development, is consistent in character and density with what the WOSP and zoning contemplated. The State Density Bonus law requires the City to provide a 35% density bonus and is therefore a ministerial action beyond the scope of additional CEQA review.
- (2) Although the Addendum was prepared to take into account current conditions, including updated Plan Area development, there would be no new significant environmental effect or a substantial increase in the severity of impacts identified in the WOSP EIR due to changes in circumstances.
- (3) Although the Addendum was completed to take into account new information, including updated transportation and emissions assessments per current guidelines and implementation of current SCAs, there would be no new significant environmental effect or a substantial increase in the severity of impacts identified in the WOSP EIR due to new information.

Therefore, in accordance with California Public Resources Code section 21166 and CEQA Guidelines section 15164, the WOSP EIR and this Addendum comprise the full and complete CEQA evaluation necessary for the proposed project and no further CEQA evaluation for the project is required.

The revisions proposed to the PDP in the 2020 project would not require subsequent analysis per CEQA Guidelines Section 15162, as confirmed by the following statements:

- (1) The 2020 Project would not result in new significant environmental effects or a substantial increase in the severity of previously identified significant effects;
- (2) There are no changes in circumstances that would result in new significant environmental effects or a substantial increase in the severity of previously identified significant effects;
or
- (3) There is no new information resulting in a new significant effect not discussed that would result in new significant environmental effects, a substantial increase in the severity of previously identified significant effects, or a change in the feasibility (or acceptance) of mitigation measures.

While changes to the project have occurred after acceptance of the 2019 EIR Addendum, this assessment has determined that no further documentation is required per CEQA Guidelines Section 15162. The 2019 EIR Addendum continues to serve as the applicable environmental review document pursuant to the requirements of CEQA for approval of the 2020 Project and the associated adopted Standard Conditions of Approval and Mitigation Monitoring and Reporting Program would remain fully applicable.

City of Oakland Design Review Findings

The proposed West Oakland BART TOD Preliminary Development Plan revision design is subject to Planning Code Section 17.136.050 - Regular design review criteria. Accordingly, regular design review approval may be granted only if the proposal conforms to all of the following general design review criteria, as well as to any and all other applicable design review criteria:

17.136.050 Regular design review criteria.

Regular design review approval may be granted only if the proposal conforms to all of the following general design review criteria, as well as to any and all other applicable design review criteria:

For Residential Facilities.

1. That the proposed design will create a building or set of buildings that are well related to the surrounding area in their setting, scale, bulk, height, materials, and textures:

The proposed West Oakland BART TOD project includes two mixed-use buildings with residential facilities. Both buildings are designed to comply with the applicable design regulations for the site. Each building on the site is designed to complement, but not mimic, the other. The modern style of the project and the highly articulated facades ensure that the neighborhood will be attractive, visually complex and varied. The project fits the vision set forth in the West Oakland Specific Plan (WOSP) Design Guidelines

2. That the proposed design will protect, preserve, or enhance desirable neighborhood characteristics;

The West Oakland BART TOD project is adjacent to the South Prescott neighborhood, which is part of the broader West Oakland neighborhood. The project complies with the intent of the WOSP design guidelines and provides massing and style that support a unique visual appearance in the neighborhood, while respecting the adjacent residential neighborhood height and character.

3. That the proposed design will be sensitive to the topography and landscape.

The West Oakland BART TOD site is located in a generally flat area. The project site is bounded by 7th Street to the north, 5th Street to the south, Chester Street to the west, and Mandela Parkway to the east. Existing land uses in the vicinity include multi-story commercial and residential development to the north, parking/fuel station/vacant lot to the east, light

industrial and low-rise residential to the south, and low-rise residential to the west.

The site is currently surface parking with the BART tracks running diagonally through it with the BART station in the center. The project creates a signature tower at the corner of Mandela Pkwy and 7th St, which was envisioned with the WOSP.

4. That, if situated on a hill, the design and massing of the proposed building relates to the grade of the hill;

NA.

5. That the proposed design conforms in all significant respects with the Oakland General Plan and with any applicable design review guidelines or criteria, district plan, or development control map which have been adopted by the Planning Commission or City Council.

As noted throughout this staff report, the West Oakland BART TOD Preliminary Development Plan is consistent with the General Plan and West Oakland Specific Plan and complies with the underlying regulations controlling development of the site, when considering the density and height increases and the reduction in parking and open space as a result of the State Affordable Housing Bonus. The project meets the intent of the West Oakland Specific Plan design guidelines.

For Nonresidential Facilities and Signs.

1. That the proposal will help achieve or maintain a group of facilities which are well related to one another and which, when taken together, will result in a well-composed design, with consideration given to site, landscape, bulk, height, arrangement, texture, materials, colors, and appurtenances; the relation of these factors to other facilities in the vicinity; and the relation of the proposal to the total setting as seen from key points in the surrounding area. Only elements of design which have some significant relationship to outside appearance shall be considered, except as otherwise provided in Section 17.136.060;

The proposed project creates a well-composed design in relationship to the West Oakland BART station and the surrounding neighborhood. The project includes three distinct buildings with retail on the ground floor throughout the site, creating activated public spaces. The project is well positioned to the total setting of the surrounding area, with the high-rise tower creating a signature element in the neighborhood at 7th St and Mandela Pkwy, with mid-rise buildings and three-story residential units facing residential neighborhoods.

2. That the proposed design will be of a quality and character which harmonizes with, and serves to protect the value of, private and public investments in the area;

The proposed project transforms a surface parking lot into a dynamic transit-oriented development, which is of a quality and character envisioned in the West Oakland Specific Plan. The project will protect the value of the neighborhood by providing affordable housing, office space, and neighborhood serving retail.

2. That the proposed design conforms in all significant respects with the Oakland General Plan and with any applicable design review guidelines or criteria, district plan, or development control map which have been adopted by the Planning Commission or City Council.

The proposed project complies with the vision of a transit-oriented district in the Oakland General Plan and the West Oakland Specific Plan. The project also complies with the West Oakland Specific Plan Design Guidelines, providing a transit-oriented development with residential, office, and neighborhood-serving retail on the ground floor. The project provides active pedestrian-oriented facades along all street frontages and facing the public spaces around the BART station.

City of Oakland Variance Findings

The proposed West Oakland BART TOD project requires a minor variance for reduced on-street commercial loading. Accordingly, minor variance approval may be granted only if the proposal conforms to all of the following general variance findings, below:

17.148.050 Findings required.

A. With the exception of variances for Adult Entertainment Activities or Sign Facilities, a variance may be granted only upon determination that all of the following conditions are present:

1. That strict compliance with the specified regulation would result in practical difficulty or unnecessary hardship inconsistent with the purposes of the zoning regulations, due to unique physical or topographic circumstances or conditions of design; or, as an alternative in the case of a minor variance, that such strict compliance would preclude an effective design solution improving livability, operational efficiency, or appearance.

Strict compliance with the off-street loading regulations would preclude an effective design solution. The project is required to have three commercial loading berths, each measuring 12'w x 33'd x 14'h. Loading access is limited to the building frontage along Mandela Parkway because curb cuts or driveways for off-street loading are not feasible on 5th St due to AC Transit bus stop and bus layover areas along 5th St. Three full sized berths would limit the Mandela frontage to only vehicular access/usage and reduce the potential retail area on the ground level. Additional curb cuts would also negatively impact the Class IV Cycletrack along Mandela and the pedestrian environment. In addition, the Planning Code discourages driveways from being located within 20 feet of pedestrian walkways or plazas. Therefore the proposed variance is to provide one full sized berth on the ground level and two smaller 12'w x 25'd x 8'-2''h berths in the uppermost basement parking level.

2. That strict compliance with the regulations would deprive the applicant of privileges enjoyed by owners of similarly zoned property; or, as an alternative in the case of a minor variance, that such strict compliance would preclude an effective design solution fulfilling the basic intent of the applicable regulation.

Strict compliance with the regulations would lead to the entire length of Mandela being dedicated to loading and parking, with very large curb cuts that would likely not meet City regulations for distance from the intersection and distance from pedestrian walkways. Accommodating three full sized berths would eliminate all retail frontage and pedestrian entries on Mandela Parkway. Maximizing retail uses on Mandela Parkway is desirable to activate this corner.

3. That the variance, if granted, will not adversely affect the character, livability, or appropriate development of abutting properties or the surrounding area, and will not be detrimental to the public welfare or contrary to adopted plans or development policy.

The proposed project, specifically T4, provides one loading berth that complies with the Planning Code and two loading berths that do not comply with the height requirements, so smaller trucks or vans could use these spaces for loading.

4. That the variance will not constitute a grant of special privilege inconsistent with limitations imposed on similarly zoned properties or inconsistent with the purposes of the zoning regulations.

Most of the building program is dedicated to office space, which generally requires loading from smaller vans that can be accommodated in the two basement loading berths. The larger ground floor loading berth can accommodate full sized trucks for the offices but will mostly be utilized by the retail tenants.

5. That the elements of the proposal requiring the variance (e.g., elements such as buildings, walls, fences, driveways, garages and carports, etc.) conform with the regular design review criteria set forth in the design review procedure at Section 17.136.050.

Off-street loading that is located off the street improves the overall site plan and design of the building, which is a well-designed and articulated mixed-use, transit-oriented development.

6. That the proposal conforms in all significant respects with the Oakland General Plan and with any other applicable guidelines or criteria, district plan, or development control map which have been adopted by the Planning Commission or City Council.

The proposed project complies with the applicable regulatory framework in all ways, with the exception of this minor variance and the waivers and concessions allowed by the State Affordable Housing Bonus program. The proposed project otherwise conforms to the underlying Planned Unit Development regulations, zoning district, WOSP, and General Plan designation.

7. For proposals involving one (1) or two (2) residential dwelling units on a lot: That, if the variance would relax a regulation governing maximum height, minimum yards, maximum lot coverage or maximum floor area ratio, the proposal also conforms with at least one of the following additional criteria:

1. The proposal when viewed in its entirety will not adversely impact abutting residences to the side, rear, or directly across the street with respect to solar access, view blockage and privacy to a degree greater than that which would be possible if the residence were built according to the applicable regulation and, for height variances, the proposal provides detailing, articulation or other design treatments that mitigate any bulk created by the additional height; or
2. Over sixty percent (60%) of the lots in the immediate vicinity are already developed and the proposal does not exceed the corresponding as-built condition on these lots and, for height variances, the proposal provides detailing, articulation or other design treatments that mitigate any bulk created by the additional height. The immediate context shall consist of the five (5) closest lots on each side of the project site plus the ten (10) closest lots on the opposite side of the street (see illustration I-4b); however, the Director of City Planning may make an alternative determination of immediate context based on specific site

conditions. Such determination shall be in writing and included as part of any decision on any variance.

NA.

**Vesting Tentative Parcel Map
Findings for Approval**

Lot Design Standards (Section 16.24.040 O.M.C.):

1. No lot shall be created without frontage on a public street, as defined by Section 16.04.030, except:

The three proposed lots and designated remainder have frontages on four public streets, including 7th St to the north, 5th St to the south, Chester St to the west, and Mandela Pkwy to the east.

2. The side lines of lots shall run at right angles or radially to the street upon which the lot fronts, except where impractical by reason of unusual topography:

The proposed side lines of the three lots run at right angles to the street upon which the lot fronts. The interior lot lines follow the angles of the BART track and BART station.

3. All applicable requirements of the zoning regulations shall be met:

As described in the staff report above, all applicable requirements of the zoning regulations are met.

4. Lots shall be equal or larger in measure than the prevalent size of existing lots in the surrounding area except:
 - a. Where the area is still considered acreage;
 - b. Where a deliberate change in the character of the area has been initiated by the adoption of a specific plan, a change in zone, a development control map, or a planned unit development:

The three lots and designated remainder are larger in measure than the prevalent size of existing single-family lots to the north and west of the project. The lots are similar in measure to the prevalent size of existing industrial lots to the south and east of the project.

5. Lots shall be designed in a manner to preserve and enhance natural out-croppings of rock, specimen trees or group of trees, creeks or other amenities.

The lot does not contain natural amenities, other than street trees. The lot currently consists of a BART station, BART tracks, and surface parking lots. The street trees are not considered specimen trees.

Tentative Map Findings (Section 16.08.030 O.M.C. & California Government Code §66474):

6. The proposed map is consistent with applicable general and specific plans as specified in the State Government Code Section 65451:

As discussed in the staff report above, the proposed map is consistent with the City of Oakland's General Plan and the West Oakland Specific Plan.

7. The design or improvement of the proposed subdivision is consistent with applicable general and specific plans:

As discussed in the staff report above, the design of the proposed subdivision is consistent with the City of Oakland's General Plan and the West Oakland Specific Plan.

8. The site is physically suitable for the type of development:

The site is physically suitable for the type of development proposed. The site is designated Community Commercial in the Oakland General Plan and the WOSP and is designated as a transit-oriented development site.

9. The site is physically suitable for the proposed density of development:

The site is sufficiently sized and physically suitable to accommodate the proposed density of the project. The West Oakland Specific Plan and the Oakland General Plan anticipated significant density at the site with a Transit-oriented development. The Project is consistent with the redevelopment envisioned by the City for the project site, and the density/intensity of the project is within the maximum limits established by the General Plan.

10. The design of the subdivision or the proposed improvements are not likely to cause substantial environmental damage or substantially and avoidably injure fish or wildlife or their habitat:

The site is currently a surface parking lot without significant environmental or ecological value. The proposed improvements will replace the trees on site and will add additional vegetation. There is no fish or wildlife habitat on site.

11. The design of the subdivision or type of improvements is not likely to cause serious public health problems:

The proposed project incorporates design and development elements that promote public health. The project includes improved bicycle and pedestrian access to the site, with Class IV separated bikeways, wider sidewalks, and improved intersections. The project also improves pedestrian access through the site, with pedestrian walkways through the interior of the site, connecting to the BART station.

Air Quality was analyzed in the WOSP EIR, which found impacts related to

construction-period and operational air pollutant emissions and operational toxic air contaminants to be significant and unavoidable under build-out of the WOSP EIR. Construction-period dust and toxic air contaminants were found to be reduced to a less-than-significant level through implementation of SCAs. All other impacts were found to be less-than-significant.

12. The design of the subdivision or the type of improvements will not conflict with easements, acquired by the public at large, for access through or use of, property within the proposed subdivision. In this connection, the governing body may approve a map if it finds that alternate easements, for access or for use, will be provided, and that these will be substantially equivalent to ones previously acquired by the public. (This subsection shall apply only to easements of record or to easements established by judgment of a court of competent jurisdiction):

The design of the subdivision of the type of improvements will not conflict with easements for access through or use of property within the proposed subdivision.

13. The design of the subdivision provides to the extent feasible, for future passive or natural heating or cooling opportunities in the subdivision:

As reflected in the VTPM, the design and organization of the proposed project site provides for passive or natural heating or cooling opportunities.

Planned Unit Development Findings

17.140.080 Permit criteria.

A Planned Unit Development permit may be granted only if it is found that the development (including conditions imposed under the authority of Sections 17.142.060 and 17.140.030) conforms to all of the following criteria, as well as to the Planned Unit Development regulations in Chapter 17.142:

- A. That the location, design, size, and uses are consistent with the Oakland General Plan and with any other applicable plan, development control map, design guidelines, or ordinance adopted by the City Council or Planning Commission;

The location, design, size, and uses in the proposed project are consistent with the Oakland General Plan, the West Oakland Specific Plan (WOSP), the WOSP Design Guidelines, and the S-15W designation in the Planning Code, as described in the staff report above. The Oakland General Plan and WOSP designate the site Community Commercial and as transit-oriented development. This designation seeks to encourage neighborhood center uses and larger scale retail and commercial uses, which can be complemented by the addition of urban residential development and compatible mixed use development. The project site is zoned as Transit-Oriented Development Commercial Zone (S-15W), which is intended to feature high-density residential, commercial, and mixed-use developments to encourage a balance of pedestrian-oriented activities, transit opportunities, and concentrated development near transit stations. The proposed uses (mixed-use multi-family residential, office, and retail) are allowable under the General Plan designation and zoning.

The project would be substantially consistent with the development density established by existing zoning, community plan, or General Plan policies and the State Affordable Housing Density Bonus Law, which requires that the City grant a density bonus if the project meets affordable housing requirements. Requested variations from base zoning, community plan or General Plan requirements are allowable under the applicable local and State regulations and would therefore not represent conflicts with applicable plans.

- B. That the location, design, and size are such that the development can be well integrated with its surroundings, and, in the case of a departure in character from surrounding uses, that the location and design will adequately reduce the impact of the development;

The development adheres to the WOSP Design Guidelines to ensure the location, design, and size are integrated into the surroundings of the neighborhood. The WOSP envisioned a signature tower at the corner of Mandela Pkwy and 7th St, which is included in the proposed development. This tower is a departure from existing community character, but is responding to the community's vision for the future of the neighborhood. The WOSP EIR determined that the increased height and density was appropriate for the transit site and would not result in a substantial conflict with existing uses if building height transitions were considered at boundaries. The project proposes low-rise residential units along the Chester Street boundary with the South Prescott neighborhood low-rise residential units consistent with this conclusion and would therefore be consistent with the less-than-significant conclusion in the WOSP EIR.

- C. That the location, design, size, and uses are such that traffic generated by the development can be accommodated safely and without congestion on major streets and will avoid traversing other local streets;
Consistent with the findings of the WOSP EIR, the WOSP EIR Addendum #1 finds that the project would not result in any significant impacts related to transportation or circulation. Further, based on an examination of the other Program EIRs, implementation of the project would not result in an increase in the severity of any previously identified impacts, nor would it result in new significant impacts related to transportation or circulation that were not previously identified in the WOSP EIR and Program EIRs.

The project is required to prepare and implement a Transportation and Parking Demand Management Plan (TDM Plan) because it would generate more than 50 peak hour trips. The TDM Plan includes on-going operational strategies, as well as infrastructure improvements in the project vicinity, that encourage the use of non-automobile travel modes.

The project aims to improve access to the site by walking, biking, and transit to replace the more auto-oriented existing site. The major infrastructure improvements included in the project consist of:

- New Class IV bicycle lanes along both directions of 7th Street and Mandela Parkway adjacent to the project.*
- Improved sidewalks and other pedestrian amenities along the project frontages and pedestrian safety and accessibility improvements along the corridor and at intersections*
- Enhanced bus facilities along the project frontage.*

- D. That the location, design, size, and uses are such that the residents or establishments to be accommodated will be adequately served by existing or proposed facilities and services;
The project can be adequately served by existing and proposed services and facilities. The WOSP EIR concluded that while development of the Plan Area would increase demand for public services and recreation, it also includes improvements and would pay development fees to support services and the impacts in this regard would be less-than-significant or reduced to that level through implementation of applicable SCAs. The project would comply with the following SCAs related to public services, parks, and recreation: SCA-GEN-1: Compliance with Other Requirements (#3), SCA-PUB-1: Capital Improvements Impact Fee (#74), and SCA-HAZ-4: Fire Safety Phasing Plan (#46).

- E. That the location, design, size, and uses will result in an attractive, healthful, efficient, and stable environment for living, shopping, or working, the beneficial effects of which environment could not otherwise be achieved under the zoning regulations;
The project's location, design, size and uses will result in an attractive, healthful, efficient and stable environment for living, shopping and working. As discussed in the General Plan, WOSP, and Zoning analysis, the project brings to fruition the vision of transit-oriented development surrounding the BART station. The project introduces up to 55,000 square feet of neighborhood-serving retail, 300,000 square feet of office, and 762 housing units to the

community.

The PUD regulations provide the project with the flexibility to create a cohesive and integrated project with three separate primary buildings, particularly with the constraints of the BART station and BART tracks. The PUD regulations also provide more flexibility for phasing the implementation of the project.

- F. That the development will be well integrated into its setting, will not require excessive earth moving or destroy desirable natural features, will not be visually obtrusive and will harmonize with surrounding areas and facilities, will not substantially harm major views for surrounding residents, and will provide sufficient buffering in the form of spatial separation, vegetation, topographic features, or other devices.

The proposed project will be well integrated into its setting. West Oakland is an urban setting with a combination of residential and industrial character. While the proposed project includes a modern, glass tower that will be distinct in the neighborhood, this site is implementing the vision of the WOSP by creating a signature tower at this location. The tower will not substantially harm major views for surrounding residents. The project site does not contain any natural features and earth moving will be limited to what is needed to create the basement, foundations, and a level site for walkways and plazas. The project creates a transition from the high rise tower to mid-rise building, to 38 ft tall residential units across from the South Prescott neighborhood on Chester St.

**REQUIRED FINDINGS:
WEST OAKLAND BART TOD PROJECT (MANDELA STATION)
FINAL DEVELOPMENT PLAN T1**

Required findings include:

- California Environmental Quality Act (provided throughout this record)
- Regular Design Review: Planning Code Section 17.136.050
- Final Development Plan Conformity with PDP

City of Oakland Design Review Findings for FDP T1

The proposed West Oakland BART TOD Final Development Plan for T1 design is subject to Planning Code Section 17.136.050 - Regular design review criteria. Accordingly, regular design review approval may be granted only if the proposal conforms to all of the following general design review criteria, as well as to any and all other applicable design review criteria:

17.136.050 Regular design review criteria.

Regular design review approval may be granted only if the proposal conforms to all of the following general design review criteria, as well as to any and all other applicable design review criteria:

For Residential Facilities.

1. That the proposed design will create a building or set of buildings that are well related to the surrounding area in their setting, scale, bulk, height, materials, and textures:

The proposed high rise residential tower at T1 project is a 320 foot tall mixed-use building with residential facilities. The site was designated in the West Oakland Specific Plan for a 100 foot tall transit-oriented development. The State Affordable Housing Bonus allows the project to exceed the height contemplated in the Planning Code and in the Specific Plan. While the tower is significantly taller than initially contemplated, the narrow design of the tower plus the pedestrian-oriented base of the building allow the building to fit into the surrounding area. The corner of 7th St and Mandela Parkway is a prominent corner in West Oakland and the West Oakland BART station is a significant location in the region, so this signature tower helps distinguish the location. The base of the building relates to the neighborhood scale, with pedestrian-oriented storefronts, significant glazing, and activities that establish this as a neighborhood-oriented building. The materials and textures used on both the tower and the base of the building create a signature building while also relating to the surrounding area. The modern style of the project and the highly articulated facades ensure that the neighborhood will be attractive, visually complex and varied. The project fits the vision set forth in the West Oakland Specific Plan (WOSP) Design Guidelines and the project specific Design Guidelines.

2. That the proposed design will protect, preserve, or enhance desirable neighborhood characteristics;

The T1 residential tower restores the neighborhood oriented retail character of the 7th St corridor, as envisioned in the WOSP and the WOSP design guidelines. The building also creates a signature building at 7th St

and Mandela Parkway, which is a significant corner within the community. The building also enhances the pedestrian experience for residents going to and from the BART station by providing ground floor activation.

3. That the proposed design will be sensitive to the topography and landscape.

The T1 residential tower site is located in a generally flat area. The building will reestablish street trees and other landscaping along 7th St and Mandela Parkway.

The site is currently surface parking with the BART tracks running diagonally through it with the BART station in the center. The project creates a signature tower at the corner of Mandela Pkwy and 7th St, which was envisioned with the WOSP.

4. That, if situated on a hill, the design and massing of the proposed building relates to the grade of the hill;

NA.

5. That the proposed design conforms in all significant respects with the Oakland General Plan and with any applicable design review guidelines or criteria, district plan, or development control map which have been adopted by the Planning Commission or City Council.

As noted throughout this staff report, the residential tower T1 Final Development Plan is consistent with the General Plan and West Oakland Specific Plan and complies with the underlying regulations controlling development of the site, when considering the density and height increases and the reduction in parking and open space as a result of the State Affordable Housing Bonus. The project meets the intent of the West Oakland Specific Plan design guidelines as well as the project specific design guidelines.

For Nonresidential Facilities and Signs.

1. That the proposal will help achieve or maintain a group of facilities which are well related to one another and which, when taken together, will result in a well-composed design, with consideration given to site, landscape, bulk, height, arrangement, texture, materials, colors, and appurtenances; the relation of these factors to other facilities in the vicinity; and the relation of the proposal to the total setting as seen from key points in the surrounding area. Only elements of design which have some significant relationship to outside appearance shall be considered, except as otherwise provided in Section 17.136.060;

The proposed project creates a well-composed design in relationship to the West Oakland BART station and the surrounding neighborhood. The

project includes a 320 ft tall residential tower with a pedestrian-oriented base. The project is well positioned to the total setting of the surrounding area, with the high-rise tower creating a signature element in the neighborhood at 7th St and Mandela Pkwy. The non-residential facilities are a minor component of this project, focused on the ground floor, pedestrian-oriented retail facing 7th St.

2. That the proposed design will be of a quality and character which harmonizes with, and serves to protect the value of, private and public investments in the area;

The proposed project transforms a surface parking lot into a dynamic transit-oriented development, which is of a quality and character envisioned in the West Oakland Specific Plan. The project will protect the value of the neighborhood by providing affordable housing and neighborhood serving retail.

3. That the proposed design conforms in all significant respects with the Oakland General Plan and with any applicable design review guidelines or criteria, district plan, or development control map which have been adopted by the Planning Commission or City Council.

The proposed project complies with the vision of a transit-oriented district in the Oakland General Plan and the West Oakland Specific Plan. The project also complies with the West Oakland Specific Plan Design Guidelines, providing a transit-oriented development with residential, office, and neighborhood-serving retail on the ground floor. The project provides active pedestrian-oriented facades along 7th Street and at the corner of Mandela Parkway, as well as attractive public plaza spaces as part of the entire project to draw pedestrians, children and BART customers into an outdoor communal setting for everyone to enjoy.

**Final Development Plan Conformity with
Preliminary Development Plan Findings for T1**

1. The final plan shall conform in all major respects with the approved preliminary development plan.
The FDP for residential tower T1 substantially conforms in all major respects with the proposed revision to the Preliminary Development Plan, including number of residential units, height, scale, and proposed land use activities.

2. The final plan shall include all information included in the preliminary development plan plus the following: the location of water, sewerage, and drainage facilities; detailed building and landscaping plans and elevations; the character and location of signs; plans for street improvements; and grading or earth-moving plans.
The FDP for residential tower T1 includes all information in the PDP plus details related to utilities, building design, and grading. The FDP includes details for street improvements, but these are also addressed in detail in the FDP for Horizontal Improvements.

3. The final plan shall be sufficiently detailed to indicate fully the ultimate operation and appearance of the development. Copies of legal documents required for dedication or reservation of group or common spaces, for the creation of nonprofit homes' association, or for performance bonds, shall also be submitted.
The FDP for residential tower T1 is sufficiently detailed to indicate the ultimate operation and appearance of the development.

**REQUIRED FINDINGS:
WEST OAKLAND BART TOD PROJECT (MANDELA STATION)
FINAL DEVELOPMENT PLAN HORIZONTAL IMPROVEMENTS**

Required findings include:

- California Environmental Quality Act (provided throughout this record)
- Final Development Plan Conformity with PDP Findings

City of Oakland Design Review Findings for FDP Horizontal Improvements

The proposed West Oakland BART TOD Final Development Plan for Horizontal Improvements design is subject to Planning Code Section 17.136.050 - Regular design review criteria. Accordingly, regular design review approval may be granted only if the proposal conforms to all of the following general design review criteria, as well as to any and all other applicable design review criteria:

17.136.050 Regular design review criteria.

Regular design review approval may be granted only if the proposal conforms to all of the following general design review criteria, as well as to any and all other applicable design review criteria:

For Nonresidential Facilities and Signs.

1. That the proposal will help achieve or maintain a group of facilities which are well related to one another and which, when taken together, will result in a well-composed design, with consideration given to site, landscape, bulk, height, arrangement, texture, materials, colors, and appurtenances; the relation of these factors to other facilities in the vicinity; and the relation of the proposal to the total setting as seen from key points in the surrounding area. Only elements of design which have some significant relationship to outside appearance shall be considered, except as otherwise provided in Section 17.136.060;

The proposed project creates a well-composed design in relationship to the West Oakland BART station and the surrounding neighborhood. The project includes a 320 ft tall residential tower with a pedestrian-oriented base. The project is well positioned to the total setting of the surrounding area, with the high-rise tower creating a signature element in the neighborhood at 7th St and Mandela Pkwy. The non-residential facilities are a minor component of this project, focused on the ground floor, pedestrian-oriented retail facing 7th St.

2. That the proposed design will be of a quality and character which harmonizes with, and serves to protect the value of, private and public investments in the area;

The proposed project transforms a surface parking lot into a dynamic transit-oriented development, which is of a quality and character envisioned in the West Oakland Specific Plan. The project will protect the value of the neighborhood by providing affordable housing and neighborhood serving retail.

3. That the proposed design conforms in all significant respects with the Oakland General Plan and with any applicable design review guidelines or criteria, district plan, or

development control map which have been adopted by the Planning Commission or City Council.

The proposed project complies with the vision of a transit-oriented district in the Oakland General Plan and the West Oakland Specific Plan. The project also complies with the West Oakland Specific Plan Design Guidelines, providing a transit-oriented development with residential, office, and neighborhood-serving retail on the ground floor. The project provides active pedestrian-oriented facades along all 7th Street and at the corner of Mandela Parkway.

**Final Development Plan Conformity with
Preliminary Development Plan Findings for Horizontal Improvements**

1. The final plan shall conform in all major respects with the approved preliminary development plan.
The FDP for Horizontal Improvements substantially conforms in all major respects with the proposed revision to the Preliminary Development Plan, including streetscape improvements in the public right-of-way and the improvements on private property, including plazas and walkways.

2. The final plan shall include all information included in the preliminary development plan plus the following: the location of water, sewerage, and drainage facilities; detailed building and landscaping plans and elevations; the character and location of signs; plans for street improvements; and grading or earth-moving plans.
The FDP for Horizontal Improvements includes all information in the PDP plus details related to utilities, design, and grading. This FDP includes all details for street improvements, including plans and cross sections.

3. The final plan shall be sufficiently detailed to indicate fully the ultimate operation and appearance of the development. Copies of legal documents required for dedication or reservation of group or common spaces, for the creation of nonprofit homes' association, or for performance bonds, shall also be submitted.
The FDP for Horizontal Improvements is sufficiently detailed to indicate the ultimate operation and appearance of the development.

**REQUIRED FINDINGS:
WEST OAKLAND BART TOD PROJECT (MANDELA STATION)
FINAL DEVELOPMENT PLAN T3**

Required findings include:

- California Environmental Quality Act (provided throughout this record)
- Regular Design Review: Planning Code Section 17.136.050
- Final Development Plan Conformity with PDP

City of Oakland Design Review Findings for FDP T3

The proposed West Oakland BART TOD Final Development Plan for T3 design is subject to Planning Code Section 17.136.050 - Regular design review criteria. Accordingly, regular design review approval may be granted only if the proposal conforms to all of the following general design review criteria, as well as to any and all other applicable design review criteria:

17.136.050 Regular design review criteria.

Regular design review approval may be granted only if the proposal conforms to all of the following general design review criteria, as well as to any and all other applicable design review criteria:

For Residential Facilities.

1. That the proposed design will create a building or set of buildings that are well related to the surrounding area in their setting, scale, bulk, height, materials, and textures:

The proposed T3 mid-rise residential building is an 80 foot tall mixed-use building (stepping down to 38 ft on Chester St) with 240 affordable residential units. The site was designated in the West Oakland Specific Plan for a 60 foot tall transit-oriented development. The State Affordable Housing Bonus allows the project to exceed the height contemplated in the Planning Code and in the Specific Plan. While the building is taller than initially contemplated, the building steps down along Chester St to reduce the scale of the building adjacent to the residential neighborhood to the west. The building is well articulated along Chester St, providing a residential scale facing the residential neighborhood. The façade facing 5th St provides an appropriate scale with pedestrian-oriented ground floor retail and well-articulated upper stories. The bulk and scale of the non-articulated wall facing 7th St is broken up by art that will be visible from 7th St and from the BART tracks. If art is not provided along this wall, the applicant will revise the wall with additional articulation, depth, or texture to reduce the bulk of the wall and return to DRC for review. The project fits the vision set forth in the West Oakland Specific Plan (WOSP) Design Guidelines and the project specific Design Guidelines.

2. That the proposed design will protect, preserve, or enhance desirable neighborhood characteristics;

The T3 mid-rise affordable housing building provides a good transition from the residential neighborhood to the west to the T1 high rise residential tower to the east. The project has residential activities along Chester St with a 38 ft high building facade, stepping up to 80 ft in height along 5th St. The building provides pedestrian-oriented facades along all

4 sides of the building, enhancing 5th St and Chester St while also activating the plaza spaces around the BART station.

3. That the proposed design will be sensitive to the topography and landscape.

The T3 mid-rise affordable housing building is located in a generally flat area. The building will reestablish street trees and other landscaping along Chester St and 5th St.

The site is currently surface parking with the BART tracks running diagonally through it with the BART station in the center.

4. That, if situated on a hill, the design and massing of the proposed building relates to the grade of the hill;

NA.

5. That the proposed design conforms in all significant respects with the Oakland General Plan and with any applicable design review guidelines or criteria, district plan, or development control map which have been adopted by the Planning Commission or City Council.

As noted throughout this staff report, the mixed-use building T3 Final Development Plan is consistent with the General Plan and West Oakland Specific Plan and complies with the underlying regulations controlling development of the site, when considering the density and height increases and the reduction in parking and open space as a result of the State Affordable Housing Bonus. The project meets the intent of the West Oakland Specific Plan design guidelines as well as the project specific design guidelines.

For Nonresidential Facilities and Signs.

4. That the proposal will help achieve or maintain a group of facilities which are well related to one another and which, when taken together, will result in a well-composed design, with consideration given to site, landscape, bulk, height, arrangement, texture, materials, colors, and appurtenances; the relation of these factors to other facilities in the vicinity; and the relation of the proposal to the total setting as seen from key points in the surrounding area. Only elements of design which have some significant relationship to outside appearance shall be considered, except as otherwise provided in Section 17.136.060;

The proposed project creates a well-composed design in relationship to the West Oakland BART station and the surrounding neighborhood. The project includes an 80-ft tall residential building with a pedestrian-oriented base. The project is well positioned to the total setting of the surrounding area. The non-residential facilities are a minor component of

this project, including the ground floor, pedestrian-oriented retail facing 5th St and the plazas on the interior of the site.

5. That the proposed design will be of a quality and character which harmonizes with, and serves to protect the value of, private and public investments in the area;

The proposed project transforms a surface parking lot into a dynamic transit-oriented development, which is of a quality and character envisioned in the West Oakland Specific Plan. The project will protect the value of the neighborhood by providing affordable housing and neighborhood serving retail.

6. That the proposed design conforms in all significant respects with the Oakland General Plan and with any applicable design review guidelines or criteria, district plan, or development control map which have been adopted by the Planning Commission or City Council.

The proposed project complies with the vision of a transit-oriented district in the Oakland General Plan and the West Oakland Specific Plan. The project also complies with the West Oakland Specific Plan Design Guidelines, providing a transit-oriented development with residential, office, and neighborhood-serving retail on the ground floor. The project provides active pedestrian-oriented facades along all facades of the building.

**Final Development Plan Conformity with
Preliminary Development Plan Findings for T3**

1. The final plan shall conform in all major respects with the approved preliminary development plan.
The FDP for residential building T3 substantially conforms in all major respects with the proposed revision to the Preliminary Development Plan, including number of residential units, height, scale, and proposed land use activities.

2. The final plan shall include all information included in the preliminary development plan plus the following: the location of water, sewerage, and drainage facilities; detailed building and landscaping plans and elevations; the character and location of signs; plans for street improvements; and grading or earth-moving plans.
The FDP for residential building T3 includes all information in the PDP plus details related to utilities, building design, and grading. The FDP includes details for street improvements, but these are also addressed in detail in the FDP for Horizontal Improvements.

3. The final plan shall be sufficiently detailed to indicate fully the ultimate operation and appearance of the development. Copies of legal documents required for dedication or reservation of group or common spaces, for the creation of nonprofit homes' association, or for performance bonds, shall also be submitted.
The FDP for residential building T3 is sufficiently detailed to indicate the ultimate operation and appearance of the development.

ATTACHMENT A:

**All materials available to the public at
<https://www.oaklandca.gov/resources/current-environmental-review-ceqa-eir-documents-2011-2020>**

- 1. West Oakland Specific Plan EIR and Addendum #1;**
- 2. West Oakland BART TOD – Transportation Analysis (non-CEQA)**
- 3. West Oakland BART TOD – Transportation and Parking Demand Management Plan**
- 4. CEQA Technical Memo: West Oakland BART TOD Project – Assessment of Project Changes, dated October 22, 2020**

WOB TOD Project
Addendum #1
to the WOSP EIR (SCH#2012102047)
January 2019

Lead Agency:

City of Oakland
Planning and Building Department
250 Frank H. Ogawa Plaza
Suite 2114
Oakland, CA 94612

Prepared By:

Lamphier-Gregory
1944 Embarcadero
Oakland, CA 94606




Table of Contents

| | |
|--|-----------|
| I. Project Characteristics | 1 |
| II. Executive Summary | 2 |
| III. Purpose and Organization of this CEQA Document | 3 |
| Purpose | 3 |
| Standard Conditions of Approval | 4 |
| Organization..... | 4 |
| IV. Project Description | 5 |
| Project Location | 5 |
| Proposed Project | 5 |
| Project Approvals | 21 |
| V. Project Consistency Assessment | 22 |
| Proposed Project | 22 |
| Project Consistency | 22 |
| VI. Summary of CEQA Findings | 30 |
| VII. Environmental Checklist | 31 |
| A. Aesthetics, Shadow, and Wind..... | 32 |
| B. Air Quality | 33 |
| C. Biological Resources | 36 |
| D. Cultural Resources..... | 37 |
| E. Geology, Soils, and Geohazards..... | 39 |
| F. Greenhouse Gas Emissions and Climate Change | 40 |
| G. Hazards and Hazardous Materials..... | 43 |
| H. Hydrology and Water Quality | 45 |
| I. Land Use..... | 47 |
| J. Noise | 48 |
| K. Population & Housing..... | 50 |
| M. Transportation and Circulation..... | 52 |
| N. Utilities and Service Systems..... | 60 |
| Acronyms and Terms | 61 |

Attachments

- A: City of Oakland Standard Conditions of Approval

Tables

| | | |
|----|--|----|
| 1: | Project Development Summary | 6 |
| 2: | Evaluation of Consistency with General Plan and WOSP | 24 |
| 3: | Summary of Project GHG Emissions | 41 |
| 4: | Trip Generation for Development Projects within the WOSP Area..... | 54 |
| 5: | Daily Vehicle Miles Traveled Summary..... | 58 |

Figures

| | | |
|-----|--|----|
| 1: | Project Location | 7 |
| 2: | Project Development Areas and Possible Phasing..... | 8 |
| 3: | Floor Plan, Ground Level..... | 9 |
| 4: | Floor Plan, 2 nd Floor | 10 |
| 5: | Floor Plan, 3 rd -4 th Floors..... | 11 |
| 6: | Floor Plan, 5 th Floor..... | 12 |
| 7: | Floor Plan, 6 th Floor..... | 13 |
| 8: | Floor Plan, 7 th Floor..... | 14 |
| 9: | Floor Plan, 8 th -18 th Floors..... | 15 |
| 10: | Floor Plan, 19 th -28 th Floors..... | 16 |
| 11: | Floor Plan, Basement Level..... | 17 |
| 12: | Illustrative View, Looking South | 18 |
| 13: | Illustrative View, Looking North | 19 |

I. Project Characteristics

- 1. Project Title:** West Oakland BART Transportation-Oriented Development (WOB TOD) Project
- 2. Lead Agency Name and Address:** City of Oakland
Bureau of Planning
250 Frank H. Ogawa Plaza, Suite 2114
Oakland, CA 94612
- 3. Contact Person and Phone Number:** Dara O’Byrne, City Planner
510.238.6983
DO'Byrne@oaklandca.gov
- 4. Project Location:** 1451 7th Street
Oakland, CA
Assessor’s Parcel Numbers: 004-0077-003 and 004-0071-003
- 5. Project Sponsors’ Names and Addresses:** China Harbour Engineering Company (CHEC) /
Strategic Urban Development Alliance (SUDA) JV
Partnership
4000 Executive Parkway, Suite 275
San Ramon, CA 94583
- 6. Existing General Plan Designations:** Community Commercial (West Oakland Specific Plan)
- 7. Existing Zoning:** S-15W (Transit-Oriented Development Commercial Zones)

Height Limit: 60’ (western half) and 100’ (eastern half)
- 8. Requested Approvals:** Planned Unit Development / Preliminary Development Plan

Regular Design Review

Vesting Tentative Parcel Map

II. Executive Summary

The project represents establishment of the transit-oriented development (TOD) as contemplated in the West Oakland Specific Plan (WOSP) on the site surrounding the West Oakland BART station. The project would demolish the existing 451-space West Oakland BART station surface parking lot and associated circulation and construct three new mid-rise and high-rise buildings, retail under the BART tracks, and a row of residential duplexes for a total of 762 residential units, 382,460 square feet of office space, and up to 75,000 square feet of ground-floor retail uses. The project also includes a 400-space underground parking lot, a surface plaza, and circulation elements. The project takes advantage of the 25 percent PUD residential bonus, the 35 percent State Affordable Housing Density Bonus, and includes a minor variance for group open space.

As presented in Section VI: Summary of Findings, this Addendum has determined that the West Oakland BART TOD project qualifies for an Addendum pursuant to CEQA Guidelines Section 15164 and that the WOSP EIR and this Addendum comprises the full and complete CEQA evaluation necessary for the proposed project and no further CEQA evaluation for the project is required.

The Section V: Project Consistency Assessment provides substantial evidence that the project is generally consistent with applicable plans and regulations.

The Section VII: Environmental Checklist provides substantial evidence pursuant to CEQA Guidelines Section 15162 that with implementation of the applicable SCAs, the proposed project would not result in a substantial increase in the severity of significant impacts previously identified in the WOSP EIR or any new significant impacts that were not previously identified in the WOSP EIR.

III. Purpose and Organization of this CEQA Document

Purpose

The purpose of this CEQA document is to analyze the West Oakland BART TOD Project, proposed at 1451 7th Street (Assessor's Parcel Number: 004-007-700-300 and 004-007-100-300), to determine if it qualifies for an Addendum pursuant to Public Resources Code Section 21166 and State CEQA Guidelines Section 15164 such that no additional environmental review is required.

The project site is within the 7th Street Opportunity Area of the West Oakland Specific Plan (WOSP) Area. The City adopted the WOSP and certified the associated EIR in 2014 (State Clearinghouse No. 2012102047). The WOSP identifies policies to guide future development in West Oakland by providing a comprehensive and multi-faceted strategy for development and redevelopment of vacant and/or underutilized commercial and industrial properties in strategic areas (Opportunity Areas) of West Oakland. The WOSP establishes a land use and development framework, identifies needed transportation and infrastructure improvements, and recommends implementation strategies needed to develop these areas. Subsequent activities under the WOSP are subject to environmental requirements pursuant to the WOSP EIR. The effects of future growth and development within West Oakland were fully considered in the cumulative growth projections factored into the WOSP EIR analysis. The WOSP EIR analyzed the environmental impacts of implementation of the WOSP, including development of the project site.

The WOSP EIR is hereby incorporated by reference and can be obtained from the City of Oakland Bureau of Planning at 250 Frank H. Ogawa Plaza, Suite 2114, Oakland, California, 94612, and on the City of Oakland Planning and Building Department website at:

<http://www2.oaklandnet.com/Government/o/PBN/OurServices/Application/DOWD009157>.

State CEQA Guidelines Section 15164 states that an Addendum to a certified EIR is allowed when minor changes or additions are necessary and none of the conditions for preparation of a Subsequent EIR pursuant to Section 15162 are satisfied. Section 15162 further specifies that no subsequent EIR shall be prepared unless one or more of the following conditions are met:

- 1) Substantial changes are proposed in the project which will require major revisions of the previous EIR or negative declaration due to the involvement of new significant environmental effects or a substantial increase in the severity of previously identified significant effects;
- 2) Substantial changes occur with respect to the circumstances under which the project is undertaken which will require major revisions of the previous EIR or Negative Declaration due to the involvement of new significant environmental effects or a substantial increase in the severity of previously identified significant effects; or
- 3) New information of substantial importance, which was not known and could not have been known with the exercise of reasonable diligence at the time the previous EIR was certified as complete or the Negative Declaration was adopted, shows any of the following:
 - A) The project will have one or more significant effects not discussed in the previous EIR or negative declaration;

- B) Significant effects previously examined will be substantially more severe than shown in the previous EIR;
- C) Mitigation measures or alternatives previously found not to be feasible would in fact be feasible, and would substantially reduce one or more significant effects of the project, but the project proponents decline to adopt the mitigation measure or alternative; or Mitigation measures or alternatives which are considerably different from those analyzed in the previous EIR would substantially reduce one or more significant effects on the environment, but the project proponents decline to adopt the mitigation measure or alternative.

The Environmental Checklist contained in this document summarizes the impact findings of the WOSP EIR, which is the underlying EIR for the proposed project, and assesses whether impacts of the proposed project would fall within those identified in the WOSP EIR or whether new or more significant environmental impacts than those identified in the WOSP EIR are identified which would trigger the need for a subsequent EIR.

Standard Conditions of Approval

The City established its Standard Conditions of Approval and Uniformly Applied Development Standards in 2008, and they have since been amended and revised several times. The City's SCAs are incorporated into new and changed projects as conditions of approval regardless of a project's environmental determination. The SCAs incorporate policies and standards from various adopted plans, policies, and ordinances (such as the Oakland Planning and Municipal Codes, Oakland Creek Protection Ordinance, Stormwater Water Management and Discharge Control Ordinance, Oakland Protected Trees Ordinance, Oakland Grading Regulations, National Pollutant Discharge Elimination System (NPDES) permit requirements, Housing Element-related mitigation measures, California Building Code and Uniform Fire Code, among others), which have been found to substantially mitigate environmental effects. The SCAs are adopted as requirements of an individual project when it is approved by the City and are designed to, and will, substantially mitigate environmental effects.

Note that the SCAs included in this document are referred to using an abbreviation for the environmental topic area and are numbered sequentially for each topic area—e.g., SCA-AIR-1, SCA-AIR-2. The SCA title is also provided—e.g., SCA-AIR-1: Construction-Related Air Pollution (Dust and Equipment Emissions). Finally, the current City of Oakland master-list SCA numbering is included though it should be noted that this numbering can change as SCAs are added or deleted.

Consistent with the requirements of CEQA, a determination of whether the project would have a significant impact assumes implementation of required SCAs. Attachment A includes the complete Standard Conditions of Approval and Mitigation Monitoring and Reporting Program (SCAMMRP).

Organization

This document describes the proposed project in Section IV, Project Description, and documents the project's consistency with the WOSP in Section V, Project Consistency Assessment. Section VI, Summary of Findings, provides an overview of the environmental analysis conclusions. The potential environmental impacts of the project are detailed in Section VII, Environmental Checklist, which identifies the impact findings of the WOSP Environmental Impact Report (EIR) and relevant City of Oakland Standard Conditions of Approval (SCAs) and explains whether the project would cause new or more significant environmental impacts than those identified in the WOSP EIR.

IV. Project Description

This section describes the proposed West Oakland BART TOD project evaluated in this Addendum and includes a description of the project site, existing site conditions, the proposed development, and the required project approvals.

Project Location

As shown in **Figure 1**, the approximately 5.58-acre site encompassing the West Oakland BART station is bounded by 7th Street to the north, 5th Street to the south, Chester Street to the west, and Mandela Parkway to the east. The project site consists of two parcels at 1451 7th Street (Assessor's Parcel Number: 004-007-700-300 and 004-007-100-300).

Existing Conditions and Surrounding Land Uses

The project site is a rectangular lot occupied by the West Oakland BART station and associated surface parking and circulation. Vegetation onsite is currently limited to some street and parking lot landscaping and trees.

Existing land uses in the vicinity include multi-story commercial and residential development to the north, parking/fuel station/vacant lot to the east, light industrial and low-rise residential to the south, and low-rise residential to the west.

General Plan and Zoning Designations

The Oakland General Plan and WOSP designate the project site as Community Commercial. This designation seeks to encourage neighborhood center uses and larger scale retail and commercial uses, which can be complemented by the addition of urban residential development and compatible mixed use development.

The project site is zoned as Transit-Oriented Development Commercial Zone (S-15W), which is intended to feature high-density residential, commercial, and mixed-use developments to encourage a balance of pedestrian-oriented activities, transit opportunities, and concentrated development near transit stations.

The proposed uses (mixed-use multi-family residential, office, and retail) are allowable under the General Plan designation and zoning. A more detailed consistency discussion is included in Section VI of this document.

Proposed Project

The project sponsor is proposing to demolish the existing 451-space West Oakland BART station surface parking lot and associated circulation and construct three new mid-rise and high-rise buildings, retail under the BART tracks, and a row of residential duplexes for a total of 762 residential units, 382,460 square feet of office space, and up to 75,000 square feet of ground-floor retail uses. The project also includes a 400-space underground parking lot, a surface plaza, and circulation elements. The BART station and tracks will remain. The project represents establishment of the transit-oriented development (TOD) contemplated in the WOSP on the site surrounding the West Oakland BART station.

The proposed project would consist of the following development, split into four development areas labeled T-1 through T-4 as shown on **Figure 2** and summarized in **Table 1**:

- T-1: 28-story 320-foot tall high-rise building with 500 residential units, 82,460 square feet of office, and 17,185 square feet of ground-floor retail
- T-2: surface plaza with 7,670 square feet of retail under the BART tracks
- T-3: 7-story, 80-foot tall mid-rise residential building of 240 multi-family units and 22 3-story residential duplex units and 15,200 square feet of ground-floor retail
- T-4: 8-story, 100-foot tall mid-rise commercial office building with 300,000 square feet of office and 30,800 square feet of ground-floor retail

Table 1. Project Development Summary

| Uses | T1 | T2 | T3 | T4 | Total |
|--|-----------|----------|----------------------------|------------|------------------------------|
| Office | 82,460 sf | | | 300,000 sf | 382,460 sf |
| Retail | 17,185 sf | 7,670 sf | 15,200 sf | 30,800 sf | up to 75,000 sf ¹ |
| Residential | 500 units | | 240 units + 22 duplexes | | 762 units |
| Parking | | | 286 stalls | 114 stalls | 400 stalls |
| ¹ Total retail square footage has been increased from the proposed 70,855 square feet to allow some flexibility in ground level design tweaks for up to 75,000 square feet of retail, which is what has been analyzed in this document. | | | | | |

Figures 3 through **11** show the floor plans and **Figures 12** and **13** show illustrative views of the project. Additional plans and elevations are available as part of the project file with the City of Oakland.

The proposed residential units would include market-rate units but also affordable units amounting to at least 20% of the base units (at least 152 units) and would rely upon the and the State Affordable Housing Density Bonus Law (Government Code Section 65915 et seq.), which is locally enacted through City of Oakland Municipal Code Chapter 17.107, to allow for the increased density and heights. A more detailed discussion of consistency and the required approvals is included in Section VI of this document.

As detailed in the consistency assessment in Section V, the project would be substantially consistent with the development density established by existing zoning, community plan, or General Plan policies and the State Affordable Housing Density Bonus Law, which requires that the City grant a density bonus if the project meets affordable housing requirements. Requested variations from base zoning, community plan or General Plan requirements are allowable under the applicable local and State regulations and would therefore not represent conflicts with applicable plans.

The proposed 400-space parking area would be accessed through T3 via Chester Street and includes 129 stalls within the first and second levels of T3, 143 stalls in the basement of T3, and 128 stalls in the basement of T4.



LOCATION OF PROJECT SITE WITHIN WEST OAKLAND NEIGHBORHOOD



5 ACRE PROJECT SITE

Figure 1. Project Location




Figure 2. Project Development Areas and Possible Phasing




Figure 3. Floor Plan, Ground Floor




Figure 4. Floor Plan, 2nd Floor




Figure 5. Floor Plan, 3rd-4th Floors




Figure 6. Floor Plan, 5th Floor




Figure 7. Floor Plan, 6th Floor




Figure 8. Floor Plan, 7th Floor




Figure 9. Floor Plan, 8th–18th Floors




Figure 10. Floor Plan, 19th-28th Floors




Figure 11. Floor Plan, Basement Level



Figure 12. Illustrative View, Looking South



Figure 13. Illustrative View, Looking North

This page has been intentionally left blank

Retail space is proposed at the ground level under the BART tracks and along the ground level of proposed high- and mid-rise buildings and is intended to include smaller local retail spaces and food options as well as a larger food market and co-working maker lab space. Also on the ground floor would be ancillary areas for on-site uses including lobby/office areas, trash/recycling areas, loading areas, utility areas, and bicycle parking. The BART station, a surface plaza, and pedestrian circulation elements take up the remainder of the ground level.

The project would include public ground level open space consisting of plaza and pedestrian circulation areas totaling 89,073 square feet. Additionally, the two buildings containing residential uses also have common open space, including in T1: a 7,830 square foot landscaped terrace and 1,100 square feet of private decks on level 5, a 5,712 square foot landscaped terrace on level 28, and 3,360 square feet of other common use decks; and in T3: a 8,380 square foot landscaped courtyard on level 3 with 17,584 square feet of private open space, and on level 7, a 1,673 square foot landscaped terrace and 15,000 square feet of common use terrace space.

Project Construction

The project is currently in the design phase of development and no details are as-yet available regarding the construction schedule and phasing. For the purpose of this analysis, however, it has been assumed that project construction would last at least 14 months and likely substantially longer due to phasing of building construction.

Project Approvals

The project requires the following discretionary actions/approvals, including without limitation:

Discretionary Actions by the City of Oakland

City discretionary approvals include, but may not be limited to:

- Planned Unit Development / Preliminary Development Plan including use of State Affordable Housing Density Bonus waivers/concessions
- Minor Variance for residential open space requirements
- Regular Design Review for new building construction
- Vesting Tentative Parcel Map
- Subsequent approval of Final Development Plans for each phase

Administrative/ministerial City permits required for the project include, but may not be limited to:

- Tree Protection Removal Permit
- Building permit and other related on-site and off-site work permits

Actions by Other Agencies

The project will require other administrative approvals from other agencies and utility providers such as East Bay Municipal Utility District (EBMUD), PG&E, and California Regional Water Quality Control Board (RWQCB). The project may require additional approvals related to potential contaminants at the site, as applicable.

V. Project Consistency Assessment

Proposed Project

The project would establish the transit-oriented development (TOD) originally contemplated in the WOSP on the site surrounding the West Oakland BART station, which is currently a surface parking lot. The project would redevelop a surface parking lot with three new mid-rise and high-rise buildings, a row of residential duplexes, and a surface plaza and would provide affordable and market-rate multi-family housing, office space, and ground-floor retail space, which is intended to include a food market and co-working maker lab space. See the project description in Section V of this document for additional detail.

Under State Affordable Housing Density Bonus Law and the City's Density Bonus and Incentive Procedure, because the project proposes to set aside approximately 20 percent of the residential units for very low income and/or low income units, the project is entitled to increase the project's base allowable density by up to 35 percent and request up to two additional concessions/incentives.^{1,2}

Project Consistency

Considering the bonuses allowed under the State Affordable Housing Density Bonus Law, the proposed project is permitted in the zoning district in which it is located, and is consistent with the bulk, density, and land uses envisioned in the Plan Area, as outlined below, as determined by the City of Oakland Bureau of Planning.

- In the West Oakland Specific Plan, the project site is located in the 7th Street Opportunity Area on site #23. The project is consistent with the plan policies for the 7th Street Opportunity Area, which contemplate higher-density housing, commercial office, and government/institutional office space around the core of the BART Station, and neighborhood-serving retail as well as custom manufacturing / industrial arts/ artist exhibition space on the ground floor.
- The project site is zoned as Transit-Oriented Development Commercial Zone (S-15W), which is intended to create, preserve and enhance areas devoted primarily to serve multiple modes of transportation and to feature high-density residential, commercial, and mixed-use developments to encourage a balance of pedestrian-oriented activities, transit opportunities, and concentrated development; and encourage a safe and pleasant pedestrian environment near transit stations by allowing a mixture of Residential, Civic, Commercial, and Light Industrial Activities, allowing for amenities such as benches, kiosks, lighting, and outdoor cafes; and by limiting conflicts between vehicles and pedestrians, and is typically appropriate around transit centers such as Bay Area Rapid Transit (BART) stations, AC Transit centers, and other transportation modes.

1 Government Code Sections 65915-65918; City of Oakland, 2017. Oakland Planning Code, Chapter 17.107: Density Bonus and Incentive Procedure. Section 17.107.090-Permitted Number of Density Incentives or Concessions.

2 Government Code Sections 65915-65918; City of Oakland, 2017. Oakland Planning Code, Chapter 17.107: Density Bonus and Incentive Procedure. Section 17.107.095-Waiver of Development Standards.

The proposed uses (multi-family residential, office, and retail) are allowable in this zone. The site spans two height districts, with the T2 and T3 areas in the 60' height zone and the T1 and T4 areas in the 100' height zone. The project proposes 262 units in the 60' zone, which would be 1 unit per 424 square feet, within the maximum density of 1 unit per 375. The project proposes 500 units in the 100' zone, which would be 1 unit per 263 square feet, within the maximum density of 1 unit per 225.

However, the non-residential FAR also factors into the density calculations. For the entire site, non-residential uses account for approximately 46% of the base FAR. Under the base density, that would result in a maximum 476 residential units. The allowable units, including the Planned Unit Area 25 percent density bonus would be 595. The State Affordable Housing Density Bonus increase of 35 percent would allow up to 803 residential units, which is more than the 762 units proposed.

Additionally, both residential towers would require waivers of the following development standards imposed by the Specific Plan and Planning Code: i) increase the number of stories allowable under the Specific Plan and Planning Code; and ii) elimination of the height limits to allow the T1 building to reach a height of 320' in the 100' zone and the T3 building to reach a height of 80' in a 60' zone. The applicant requests the right to determine a second concession, if needed, as final design plans are prepared.

- The General Plan land use designation for the site is Community Commercial. The intent of the Community Commercial designation is to “identify, create, maintain, and enhance areas suitable for a wide variety of commercial and institutional operations along the City’s major corridors and in shopping districts or centers.” This designation seeks to encourage neighborhood center uses and larger scale retail and commercial uses, which can be complemented by the addition of urban residential development and compatible mixed use development. The maximum FAR for this classification is 5.0 and maximum residential density is 125 units per gross acre, not including the State Affordable Housing Density Bonus.³

The project includes market-rate and affordable multi-family residential, office space, and ground-floor retail and would create ground-floor commercial uses at the site complimented by mixed-use, including urban residential uses. Because the project is consistent with the intent of the land use designations, the project would be consistent with the General Plan.⁴

As **Table 2** demonstrates, the project would also be consistent with the relevant policies of the General Plan and West Oakland Specific Plan.

³ City of Oakland, 1998. General Plan, Land Use and Transportation Element, p. 150.

⁴ State law “does not require precise conformity of a proposed project with the land use designation for a site, or an exact match between the project and the applicable general plan... Instead, a finding of consistency requires only that the proposed project be ‘compatible with the objectives, policies, general land uses, and programs specified in’ the applicable plan. State of California, 2015. Court of Appeals of California, Fourth District, Division One. Save Our Heritage Organization v. City of San Diego (2015) 237 Cal.App.4th 163, 185-186, 187.

TABLE 2: EVALUATION OF CONSISTENCY WITH GENERAL PLAN AND WOSP

| Relevant Policies, Principles, and Guidelines of the General Plan and WOSP | Project Consistency |
|---|---|
| <p>Policy N3.1 Facilitating Housing Construction. Facilitating the construction of housing units should be considered a high priority for the City of Oakland.</p> | <p>Consistent. The project would involve redevelopment of the site to add 762 new housing units, including at least 152 affordable units.</p> |
| <p>Policy N3.2 Encouraging Infill Development. In order to facilitate the construction of needed housing units, infill development that is consistent with the General Plan should take place throughout the City of Oakland.</p> | <p>Consistent. The project site is surrounded by development and represents an infill development opportunity.</p> |
| <p>Policy N3.5 Encouraging Housing Development. The City should actively encourage development of housing in designated mixed housing type and urban housing areas through regulatory and fiscal incentives, assistance in identifying parcels that are appropriate for new development, and other measures.</p> | <p>Consistent. The project would add housing to an urban housing area and would utilize the state’s affordable housing density bonus regulatory incentive as well as potentially other TOD and/or affordable housing incentives/funding.</p> |
| <p>Policy N3.8 Required High-Quality Design. High-quality design standards should be required of all new residential construction. Design requirements and permitting procedures should be developed and implemented in a manner that is sensitive to the added costs of those requirements and procedures.</p> | <p>Consistent. The project would be designed pursuant to California Building Code and other applicable codes, and would be subject to Design Review approval by the City.</p> |
| <p>Policy N3.9 Orienting Residential Development. Residential developments should be encouraged to face the street and to orient their units to desirable sunlight and views, while avoiding unreasonably blocking sunlight and views for neighboring buildings, respecting the privacy needs of residents of the development and surrounding properties, providing for sufficient conveniently located on-site open space, and avoiding undue noise exposure.</p> | <p>Consistent. The project is on an already-busy BART station site indicated for TOD development and is expected to develop taller and denser than surrounding uses and therefore, any change in sunlight, views, and privacy in the vicinity would not be considered unreasonable. As appropriate for a busy BART station site, the project includes mostly hardscape plaza and walkways and as part of an area plan (WOSP), more noise-sensitive open space is located elsewhere in the Plan Area.</p> |
| <p>Policy N3.10 Guiding the Development of Parking. Off-street parking for residential buildings should be adequate in amount and conveniently located and laid out, but its visual prominence should be minimized.</p> | <p>Consistent. Four hundred parking spaces would be provided in below-ground garage on the project site, using the allowed reductions under Municipal Code 17.116.110 (transit accessible area).</p> |
| <p>Policy N4.2 Advocating for Affordable Housing. The City encourages local non-profit organizations, affordable housing proponents, the business community, the real estate industry, and other local policy makers to join in efforts to advocate for the provision of affordable housing in communities throughout the Bay Area region.</p> | <p>Consistent. The project would involve redevelopment of the site to add at least 152 (20%) new affordable units.</p> |
| <p>Policy N7.1 Ensuring Compatible Development. New residential development in Detached Unit and Mixed Housing Type areas should be compatible with the density, scale, design, and existing or desired character of surrounding development.</p> | <p>Consistent. The project’s choice of materials, design features, and scale of development would be compatible with existing character of surrounding development.</p> |
| <p>Policy N7.2 Defining Compatibility. Infrastructure availability, environmental constraints and natural features, emergency response and evacuation</p> | <p>Consistent, with density bonus. The project design would be consistent with the values that define compatibility. The project is located near infrastructure for utilities, transit, and</p> |

times, street width and function, prevailing lot size, predominant development type and height, scenic values, distance from public transit, and desired neighborhood character are among the factors that could be taken into account when developing and mapping zoning designations or determining compatibility. These factors should be balanced with the citywide need for additional housing.

Policy N9.7 Creating Compatible but Diverse Development.

Diversity in Oakland's built environment should be as valued as the diversity in population. Regulations and permit processes should be geared toward creating compatible and attractive development, rather than "cookie cutter" development.

Policy N11.4 Alleviating Public Nuisances.

The City should strive to alleviate public nuisances and unsafe and illegal activities. Code Enforcement efforts should be given as high a priority as facilitating the development process. Public nuisance regulations should be designed to allow community members to use City codes to facilitate nuisance abatement in their neighborhood.

community services. In height, scale, and development type, the project would be consistent with existing community character.

The residential use would therefore be compatible with the Mixed Housing Type Residential land use goals in the General Plan.

Consistent. The project's choice of materials, design features, and scale of development would be compatible with existing character of surrounding development and is subject to Design Review approval by the City.

Consistent. The project site would be redeveloped to accommodate new residential uses and commercial uses per applicable codes.

West Oakland Specific Plan Guidelines – Applicant-Submitted Consistency Assessment

1. Enhancements could include mitigating the sound and visual effects of the elevated BART tracks

Consistent. Residential and commercial buildings will be constructed with required sound insulating window and wall construction to meet planning and building code requirements. The station location has reduced BART noise due to low speed of trains at this station.

2. Create an enhanced local transit system involving streetcar, light rail, buses, and/or shuttles to serve employment, business, and community centers.

Consistent. Site design complies. Access plan is designed to accommodate maximum flexibility of current and future transit modes. This includes planned curb space for AC buses and curb drop-off for transit riders. The site has been designed to maximize the pedestrian access from all surrounding blocks. Bike access is enhanced with dedicated bike tracks on the 7th Street and Mandela Street sides of the project.

3. Ensure adequate parking to attract and support development while encouraging alternative travel modes

Consistent. Site design complies. The on-site Parking exceeds minimum requirement for proposed uses, and is planned to provide adequate parking for the residential, commercial and retail uses on site. The site plan is also designed to maximize the use of transit and non-vehicular use of the site. The Site design is planned to encourage pedestrian and bike access to the BART station and the public uses on site.

4. Improve lighting and street appearance so as to deter dumping and blight.

Consistent. The Lighting plan will be designed to create well lighted plazas and pedestrian pathways through the site. The visual security of all pedestrian spaces within the site is facilitated by locating retail and other public activities along all edges of the development.

5. Ensure that new development employs sustainable "green" building practices, facilitates access to pedestrian

Consistent. All new buildings and the site design meet or exceed requirements for energy efficiency and sustainable

and transit networks, and enhances streetscapes and open spaces.

development. By developing an infill site with a high density of residential and commercial uses, this development is “green” in terms of land use. The site plan has been designed to maximize transit access, and pedestrian and bike use and access to the site, and to the BART station.

6. Promote energy efficiency throughout all aspects of new development and redevelopment.

Consistent. All new buildings and the site are designed to incorporate energy efficient systems and design standards. The buildings will be designed to meet or exceed local Green Building standards. Measures employed during the design and construction of the project will contribute additional environmental benefits. These measures will promote occupant comfort while conserving water, energy, water and natural resources.

7. Encourage sustainable development that incorporates innovative approaches to storm water management and air pollution mitigation, and continues to enhance the well-being of residents of West Oakland.

Consistent. Site is designed to provide innovative strategies policy for achieving storm water management on site. The overall site design will meet or exceed city standard for water management and air pollution mitigation. Wellness design is incorporated into the master plan design concept to encourage the overall comfort and wellbeing of residents and visitors to the site. These measures will promote occupant comfort while conserving water, energy, water and natural resources.

8. Recognize and market the artisan and arts community for their contribution to social, cultural, youth education and the economic development in West Oakland.

Consistent. The site program will incorporate significant and innovative arts, education and cultural programming on site. The open spaces will be programmed with year round cultural, community and arts events that encourages use of the site, and encourages local arts and artists within the West Oakland community. This cultural, education and arts programming is incorporated into the overall design, leasing and operations to encourage and incubate the arts in West Oakland.

9. Establish new grocery stores in West Oakland that can serve the un-met food needs of current and future West Oakland consumers. A grocery anchor can also create a customer flow that can be leveraged to successfully attract other retail shops that can then draw patrons from the anchor tenant’s shoppers. A safe and pleasant pedestrian environment will be necessary, especially near the transit station.

Consistent. It is anticipated food, grocery or other neighborhood serving retail will be incorporated into the tenant leasing of the ground floor retail. Planning incorporates large retail spaces with loading and transit access that are conducive to these neighborhood serving uses. The pedestrian environment is designed to encourage local shopping by planning safe, active pedestrian spaces and access and to promote community use and a quality shopping pedestrian experience.

10. Neighborhood amenities such as benches, kiosks, lighting, and outdoor cafes are needed to enrich and enhance the urban setting.

Consistent. The site design is designed to facilitate flexible community uses including: recreation, community events, farmers markets, makers markets, arts events, festivals and other events that promote this as a central destination for the local and regional community. Neighborhood amenities, such as seating, lighting, retail kiosks, cafes, maker spaces and other activated uses will be incorporated into the pedestrian edges of all public edges of the development. This will ensure that the overall development becomes a year round activated urban community destination.

11. Potential conflicts between vehicles and pedestrians in and around the station will need to be eliminated.

Consistent. The Site Circulation and Access plan is designed to coordinate the vehicle and pedestrian access and use of the site. The design intentionally mitigates these conflicts to

ensure site use enjoyment for all users. Vehicular traffic is minimized on site to ensure maximum pedestrian safety, access and use. Parking is restricted to non-pedestaling areas. Building loading areas are located to minimize pedestrian conflicts, and to minimize conflicts with transit and other access modes to the site.

12. Noise from the BART tracks needs to be mitigated with sound barriers.

Consistent. Residential and commercial buildings will be constructed with additional sound insulating window and wall construction to meet planning code and building code requirement. This station site location has reduced BART noise due to low speed of trains at this station.

13. Mandela/7th 1: Site Planning. Close to the West Oakland BART station, a large civic plaza should be created near the intersection of Mandela Parkway and 7th Street that is surrounded by ground floors that include publicly accessible uses such as restaurants, retail, building lobbies, galleries, and studios.

Consistent. Site design complies. A larger civic plaza and pedestrian passages have been designed into the site design to celebrate the central location of the site and the Mandela corridor. The large civic plaza has been located at the center of the site at the gateway to the BART station. This plaza is located to be more central to the overall site in order to increase its public importance, public access, and public use for community, arts and cultural events. The central plaza is visible and accessible from Mandela and 7th Street.

14. Mandela/7th -2: Massing, Height. Taller buildings are encouraged along Mandela Parkway and in particular to mark intersection of 7th St and Mandela Parkway.

Consistent. Site design complies. Larger buildings are located on 7th street and Mandela. A signature tower will be located at the intersection of Mandela and 7th Street to create a visual icon for the West Oakland community. This massing will reinforce the importance of Mandela and 7th Street corridors.

15. Mandela/7th- 3: Height. It is encouraged that taller buildings mark the intersection of 7th Street and Mandela Parkway.

Consistent. Site design complies. Larger buildings are located on 7th street and Mandela. This massing will reinforce the importance of Mandela and 7th Street corridors. The urban design of the overall site locates smaller buildings along 5th and Chester Streets to transition the scale lower to the south and west portions of the site.

16. Mandela /7th -4: Fenestration. Ground floors should have large openings and a high degree of transparency in the blocks adjacent to the West Oakland BART Station.

Consistent. Site design complies. Ground floors have high floor to floor heights and retail with high proportion of glass store front for good retail transparency. The ground floor retail spaces are planned at all building ground floors to provide activated street edges, and to activate the interior plazas and pedestrian passages. Quality materials and varied design will be incorporated into the ground floor retail design to create visual interest for shoppers and pedestrians using the site.

17. Mandela/7th - 5: Landscape. Landscaping should be coordinated with that of the existing public landscaped areas along Mandela Parkway and should include a similarly high quality of planting and paving.

Consistent. Site design complies. Landscape plan is designed to enhance 7th street corridor and to create a high quality of pedestrian experience and civic prominence. The existing trees will be replaced because of conflicts with the access plan. The new tree planting will complement the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience. Planting and paving materials will be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events. The landscape plan is

designed to create a visually significant destination and center for the West Oakland community and users of the transit hub.

18. 7th Street TOD Env-1: New residences within the West Oakland BART Station TOD area will be subject to Title 24 of the California Code of Regulations, which requires an interior noise standard of 45 dBA DNL in any habitable room, and requires an acoustical analysis demonstrating how dwelling units have been designed to meet this interior standard. To meet the interior noise standard, a noise level reduction of up to nearly 35 dBA will likely be necessary from the exterior façades of the buildings facing towards the I-880 freeway and BART tracks and station.

Consistent. Residential and commercial buildings will be constructed with code complying sound insulating window and wall construction to meet planning and building code requirement. This includes required sound insulation from the I-880 freeway to ensure development meets necessary noise reduction criteria. The station location has reduced BART noise due to low speed of trains at this station.

19. 7th Street TOD Env.-4: New development of all sensitive receptor uses at the West Oakland BART Station TOD sites must mitigate the anticipated health risks and air quality hazards at this location through implementation of Best Management Practices (BMPs) for air quality.

Consistent. Site design complies. The building design will use practical and cost effective Best Management Practices (BPM) practices in the design of all structures and open space to mitigate the anticipated health risks and air quality hazards. It is also the intent of the overall plan to facilitate dramatic increases in transit use which will have a major impact on the decrease in air quality hazards in the community.

20. Provide a more effective and substantial transition in building heights nearest to the South Prescott neighborhood, with buildings nearest to this neighborhood as low as 2- stories.

Consistent. Site Design complies. The master plan development places the maximum height along Mandela and 7th Street, and transitions down to 5th Street and Chester Street. The Chester Street frontage has been designed with 3 level residential buildings that reflect more of the scale and detail of the structures of the South Prescott neighborhood, to further mitigate the height of the larger structures and to create a good urban scale transition to the smaller structures in the neighborhood. It is the intent to use a more modern design vocabulary along Chester Street that uses scale and fenestration elements that relate to the neighboring structures.

21. Ensure that new development projects along 7th Street are of compatible height and mass as the existing, newer developments within Mandela Gateway.

Consistent. Site design complies. The base of the larger buildings has been articulated with a cornice height, materials and a variety of window fenestrations that intentionally scales the buildings to relate to the lower existing structures along 7th Street and 5th Street neighborhood context. These larger buildings are designed with a clear separation of lower tower and upper towers to differentiate the higher structures, and to emphasize the importance of the lower buildings that create the activated street elevations.

22. Target 15% of the new units to be built in the Plan Area between now and 2035 for low and moderate income households.

Consistent. Site complies. The development plan will meet or exceed the requirement for affordable units on-site.

23. Neighborhood Commercial 3: Height. Except when located at important intersections such as Mandela Parkway and 7th Street, buildings over 5 stories in height should generally include a significant step-back along commercial arterial roadways to harmonize the scale of new buildings with the existing neighborhood.

Consistent. Site design complies. The lower 5 floors of the high rise buildings have been articulated with a cornice and clear differentiation between the lower and upper portions of the building. The building massing is designed to provide a varied base and street elevation that relates to the smaller scale of the surrounding buildings along the 7th Street

corridor. Residential buildings along 5th Street exceed the 5 floor set back in order to have a better proportioned street façade. The building base massing to provide a variety of scales to provide a visually active street scape, and to relate better to the varied neighborhood context.

24. Neighborhood Commercial 8: Landscape. Publicly accessible outdoor space areas should be comprehensively designed with high quality pavement, landscaping, and seating, and are encouraged at the following locations: Mandela and 7th Street.

Consistent. Site design complies. The landscape materials are designed with high quality stone, brick, finished concrete and other materials to create a high quality public pedestrian experience and to maximize the types of uses that can occur on site. The landscape will be designed to relate to a larger vision for the 7th Street corridor. The new tree planting will complement the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience. Planting and paving materials will be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events. The landscape plan is designed to create a visually significant destination and center for the West Oakland community and users of the transit hub.

Based on the above, the project would be substantially consistent with the development density established by existing zoning, community plan, or General Plan policies and the State Affordable Housing Density Bonus Law, which requires that the City grant a density bonus if the project meets affordable housing requirements. Requested variations from base zoning, community plan or General Plan requirements are allowable under the applicable local and State regulations and would therefore not represent conflicts with applicable plans.

VI. Summary of CEQA Findings

California Public Resources Code section 21166 and CEQA Guidelines section 15164 State CEQA Guidelines Section 15164 states that an Addendum to a certified EIR is allowed when minor changes or additions are necessary and none of the conditions for preparation of a Subsequent EIR are met.

Section VII: Environmental Checklist below provides substantial evidence that the project would not require preparation of a Supplemental EIR and that an Addendum is the appropriate CEQA document, per the following conclusions:

- (1) Although the proposed project adds project-level details to a site identified in the WOSP for development and leverages the State Affordable Housing Density Bonus Law (Government Code Section 65915 et seq., City of Oakland Municipal Code Chapter 17.107), to allow for the increased density and heights proposed, these project changes would not result in new significant environmental effect or a substantial increase in the severity of impacts identified in the WOSP EIR.
- (2) Although the Environmental Checklist was completed to take into account current conditions, including updated Plan Area development, there would be no new significant environmental effect or a substantial increase in the severity of impacts identified in the WOSP EIR due to changes in circumstances.
- (3) Although the Environmental Checklist was completed to take into account new information, including updated transportation and emissions assessments per current guidelines and implementation of current SCAs, there would be no new significant environmental effect or a substantial increase in the severity of impacts identified in the WOSP EIR due to new information.

Therefore, in accordance with California Public Resources Code section 21166 and CEQA Guidelines section 15164, the WOSP EIR and this Addendum comprise the full and complete CEQA evaluation necessary for the proposed project and no further CEQA evaluation for the project is required.

Catherine Payne, Planner IV
Environmental Review Officer

Date

VII. ENVIRONMENTAL CHECKLIST

The Abbreviated Appendix N Checklist below compares potential environmental impacts of the project to the findings of the WOSP EIR, notes whether the project would result in new significant impacts or impacts substantially greater or more severe than those previously identified in WOSP EIR, and includes an explanation substantiating the findings for each topic. It uses the abbreviation SU for significant and unavoidable and LTS for less-than-significant and LTS w/ SCAs of MM for impacts that are reduced to LTS with implementation of identified SCAs and/or Mitigation Measures. Topics for which No Impact was identified in the WOSP EIR were assessed against the proposed project and determined to remain applicable so are not further discussed in this document.

The checklist also lists mitigation measures and standard conditions of approval applicable to the impacts. A full list of the SCAs and Mitigation Measures (MMs) applicable to the project can be found in Attachment A, Standard Conditions of Approval and Mitigation Monitoring and Reporting Program (SCAMMRP). More detail regarding the significance criteria used in this Addendum and the environmental impacts of implementation of the WOSP is available in the WOSP Draft and Final EIR at the following link:

<http://www2.oaklandnet.com/Government/o/PBN/OurOrganization/PlanningZoning/OAK028334>.

When a dash (--) appears in the checklist below, it means that the WOSP EIR did not identify any MMs or SCAs related to that environmental impact. N/A appears when an MM or SCA was identified but it does not apply to the project (e.g., the project location does not meet the criteria specified in the MM or SCA). The SCAs that appear in the checklist represent the City's latest standards, revised November 5, 2018. In many cases, newer SCAs from the 2018 update have superseded the SCAs originally listed in the WOSP EIR and functionally equivalent SCA are substituted without further comment. The numbers used to identify the SCAs are also reflective of the 2018 SCAs, not the numbers used in the WOSP EIR.

A. Aesthetics, Shadow, and Wind

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|--------------------------------|---|-------------------------------------|----------------------------------|----------------|--------------------------------|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Scenic Vistas or Resources | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| b. Visual Character or Quality | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| c. Light or Glare | LTS w/ SCA | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-AES-1: Lighting Plan (#19) | LTS w/ SCA |
| d. Shadows | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| e. Wind | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |

Discussion

Under Public Resources Code Section 21099(d), effective January 1, 2014, aesthetics of “a residential, mixed-use residential, or employment center project on an infill site located within a transit priority area” shall no longer be considered significant impacts on the environment. As a result, no further analysis is needed for the proposed project related to aesthetics and the following is provided for informational purposes.

Consistent with WOSP EIR conclusions, implementation of SCA-AES-1: Lighting (#19) will ensure the project will comply with guidelines related to light and glare.

Consistent with WOSP EIR conclusions, due to distance and intervening development, there are no public parks that the project would substantially shadow and no historic resources nearby that contain light-sensitive features with the potential to be substantially affected by shadowing.

Consistent with WOSP EIR conclusions, the project is not within an area where the City requires a wind study for tall projects.

Independent of the Addendum, the project would be required to implement the following additional SCAs related to aesthetics, as found in Attachment A: SCA-AES-1: Trash and Blight Removal (#16), SCA-AES-2: Graffiti Control (#17), and SCA-AES-3: Landscape Plan (#18).

B. Air Quality

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|-------------------------------------|---|-------------------------------------|----------------------------------|------------------|--|---|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Criteria Air Pollutant Emissions | SU | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-AIR-1 Dust Controls- Construction Related (#21) SCA-AIR-2 Criteria Air Pollutant Controls - Construction-Related (#22) SCA-AIR-3 Diesel Particulate Matter Controls- Construction Related (#23) SCA-TRANS-4 Transportation and Parking Demand Management (#79) | SU |
| b. Toxic Air Contaminants | Construction LTS w/SCAs Operational SU | <input checked="" type="checkbox"/> | <input type="checkbox"/> | N/A ^a | SCA-AIR-1 Dust Controls- Construction Related (#21) SCA-AIR-2 Criteria Air Pollutant Controls - Construction-Related (#22) SCA-AIR-3 Diesel Particulate Matter Controls- Construction Related (#23) SCA-AIR-4: Stationary Sources of Air Pollution (Toxic Air Contaminants) (#25) | Construction LTS w/SCAs Operational SU |

^a Mitigation Measures Air-9, -9B, -9C, and -10 are now incorporated into SCA-AIR-4 and SCA-AIR-6. Only the SCAs appear in Attachment A, not the mitigation measure.

Discussion

Air Quality was analyzed in the WOSP EIR, which found impacts related to construction-period and operational air pollutant emissions and operational toxic air contaminants to be significant and unavoidable under build-out of the WOSP EIR. Construction-period dust and toxic air contaminants were found to be reduced to a less-than-significant level through implementation of SCAs. All other impacts were found to be less-than-significant.

The proposed project would construct mid-rise and high-rise residential and office uses with ground-floor retail. It is assumed the high-rise building and potentially also the mid-rise buildings would include emergency generators that would not be used regularly, but that could be used to operate

elevators in the event of an emergency. The project is consistent with the assumptions used in the WOSP EIR for the 7th Street Opportunity Area. The WOSP and the associated EIR intend to provide flexibility in the location, amount, and type of development. Therefore, the project would contribute to the identified emissions and significant impacts identified in the WOSP EIR, and the air quality impact analysis and conclusions presented in the WOSP EIR remains valid so long as the development in the overall Plan Area remains below the forecasted level. Since the approval of the WOSP EIR, eleven developments, including this project, have been proposed and are under construction or are in some stage of the City's approval process. As detailed in subsection M, Transportation and Circulation, the current proposal is within the overall development assumed in the WOSP EIR.

Construction-Period

Because of the size of the project site, the City's basic and enhanced control measures for construction dust and emissions would apply, as described under SCA-AIR-1: Dust Controls – Construction Related (#21) and SCA-AIR-2: Criteria Air Pollutant Controls – Construction Related (#22), originally combined as SCA A of the WOSP EIR. Although not yet required at the time of the WOSP EIR, SCA-AIR-3: Diesel Particulate Matter Controls-Construction Related (#23) is a currently required SCA and would further reduce diesel particulate matter emissions and related health risk during construction. As reported in the WOSP EIR, these SCAs would keep fugitive dust levels and construction-related TAC emissions to less-than-significant levels.

However, consistent with the findings of the WOSP EIR, it is assumed that the project is one of the large construction projects pursuant to the WOSP that would result in a significant and unavoidable impact for construction-related criteria air pollutant emissions. This significant construction-related criteria pollutant emission impact was studied in the WOSP EIR under Impact Air-5. The WOSP did not have any additional mitigation measures for this impact, but the project would comply with the relevant SCAs listed in Attachment A.

With implementation of SCA-Air-1, SCA-AIR-2, and SCA-AIR-3, the project impact would be consistent with WOSP Impacts Air-4, Air-5, and Air-6 and no further analysis is required for construction-period air pollutant and toxic air contaminant emissions.

Operational

The WOSP EIR identified functionally equivalent SCA-TRANS-4: Transportation and Parking Demand Management (#79) as reducing the operational air pollutant emissions through reduction of vehicle emissions though not below significance levels. With implementation of SCA-TRANS-4, the project impact would be consistent with WOSP Impact Air-7 and no further analysis is required with respect to operational air pollutant emissions.

Residential, office, and retail uses are not generally considered substantial sources of operational toxic air emissions. However, while specifics would be determined during building-specific permitting, it is likely that the project would include a back-up diesel generator on the high-rise building and potentially also back-up generators for the mid-rise building(s), which would generate some amount of stationary-source toxic air contaminants. Consistent with the findings of the WOSP EIR, health risk impacts related to the project's operational-emitted TACs to nearby existing sensitive receptors would be considered significant and unavoidable, even with inclusion of SCA-AIR-4: Stationary Sources of Air Pollution (Toxic Air Contaminants) (#25) (which includes elements

functionally equivalent to WOSP EIR Mitigation Measure AIR-9: Risk Reduction Plan). With implementation of SCA-AIR-4, the project impact would be consistent with WOSP Impact Air-9 and no further analysis is required.

Impacts of the existing environment on the project are not required by CEQA and so are not analyzed in this CEQA document and related Mitigation Measures Air-9B and Air-9c are not applicable.⁵ (These mitigation measures have also been replaced by requirements under SCA-AIR-5, listed below.) Independent of conclusions of the Addendum, the following SCAs related to air quality and future site users would be applicable: SCA-AIR-5: Exposure to Air Pollution (Toxic Air Contaminants) (#25).

⁵ Supreme Court of California, 2018. *California Building Industry Association v Bay Area Air Quality Management District* No S213478. December 17.

C. Biological Resources

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|---|---|-------------------------------------|----------------------------------|----------------|--|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Special-Status Species, Wildlife Corridors, Riparian/Sensitive Habitat, Wetlands | LTS w/SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-BIO-1: Tree Removal During Breeding Season (#30) | LTS w/SCAs |
| b. Tree and Creek Protection | LTS w/SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-BIO-2: Tree Permit (#31) | LTS w/SCAs |

Discussion

Biological Resources

The project site is located within a developed area and is currently occupied by the West Oakland BART station plaza and associated surface parking. Wildlife and botanical resources present within the WOSP Plan Area, including the project site, are adapted to disturbed, urban conditions and would not be adversely affected by the implementation of the project.

The WOSP EIR determined that due to the absence of natural habitat in the Plan Area, special-status species and habitat as well as wildlife corridors and wetlands were not expected to be present within the Plan Area, with the exception of common birds, which are protected when nesting under the Migratory Bird Treaty Act.

Biological impacts related to disturbance of nesting birds and their movements (Impacts Bio-1 and Bio-4) were determined to be less-than-significant with implementation of SCA-BIO-1: Tree Removal During Breeding Season (#30). (The WOSP EIR-identified SCA related to Bird Collision Reduction would not be applicable to this site as this project site is not immediately adjacent to a water body or park and does not include substantial green roofs.) With implementation of SCA-BIO-1, the project impact would be consistent with WOSP Impacts Bio-1 through Bio-4 and no further analysis is required with respect to special-status species, habitat, corridors, or wetlands.

Creek and Tree Protection

No creeks exist on the project site, and no off-site creeks would be affected by the project. There are no habitat conservation plans or natural community conservation plans applicable to the site. Construction of the project would require removal of existing landscaping trees at the project site. The WOSP EIR determined that through compliance with SCA-BIO-2: Tree Permit (#31) (which combines the tree removal and tree replacement SCAs identified in the WOSP EIR), tree removal for Plan Area projects would comply with the applicable City of Oakland Tree Protection Ordinance. With implementation of SCA-BIO-2, the project impact would be consistent with the WOSP Impact Bio-5 and no further analysis is required with respect to tree and creek protection.

D. Cultural Resources

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|--|---|-------------------------------------|----------------------------------|----------------|--|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Historical Resources | LTS w/SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | N/A | LTS |
| b. Archaeological, Paleontological, and Tribal Resources and Human Remains | LTS w/SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-CUL-1: Archaeological and Paleontological Resources – Discovery During Construction (#33) SCA-CUL-2: Archaeologically Sensitive Areas – Pre-Construction Measures (#34) SCA-CUL-3: Human Remains – Discovery During Construction (#35) | LTS w/SCAs |

Discussion

Historic Resources

The project site does not include and is not adjacent to any of the historically significant structures identified in the WOSP EIR and therefore identified SCAs related to historic preservation and vibration adjacent to historic structures are not applicable.

The WOSP EIR shows that the project site is near, but not within, the Oakland Point Area of Primary Importance (Oakland Point API), whose southern boundary is one half to one full block north of the project site across 7th Street. The WOSP EIR concludes that properties surrounding the Oakland Point API, other than some 7th Street commercial strip properties that abut the district (which does not include the project site), do not contribute to its historical significance. The WOSP EIR further concludes that proposed development elsewhere in the 7th Street Opportunity Area, including on the project site, would not cause a substantial adverse change in the significance of this API or of the individual historical resources within the API. The WOSP EIR determined that Areas of Secondary Importance (ASIs) did not qualify as significant historical resources under CEQA and therefore, that while the project site is adjacent across Chester Street to the South Prescott ASI to the west, there would be no potential for significant historical impacts on this area. Therefore, the project impact would be consistent with the WOSP Impacts CR-1 and CR-3 and no further analysis is required with respect to historic resources.

Archaeological, Paleontological, and Tribal Resources and Human Remains

With respect to archaeological, paleontological, and Native American resources and human remains, the WOSP EIR concluded that the Plan Area is located in an area of moderate to high potential for unrecorded historic-period archaeological and/or Native American resources. Compliance with the following SCAs, which are functionally equivalent to the SCAs that were in effect at the writing of the WOSP EIR, would ensure that any impacts related to discovery of unrecorded resources during construction at the project site are mitigated to a less-than-significant level: SCA-CUL-1: Archaeological and Paleontological Resources – Discovery During Construction (#33); SCA-CUL-2: Archaeologically Sensitive Areas – Pre-Construction Measures (#34); and SCA-CUL-3: Human Remains – Discovery During Construction (#35).

E. Geology, Soils, and Geohazards

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|------------------------------------|---|-------------------------------------|----------------------------------|----------------|--|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Seismic Hazards & Unstable Soil | LTS w/SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-GEO-1: Construction-Related Permit[s] (#37) SCA-GEO-2: Soils Report (#38) SCA-GEO-3: Seismic Hazards Zone (Landslide/Liquefaction) (#40) | LTS w/SCAs |
| b. Soil Erosion | LTS w/SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-GEO-4: State General Construction Permit (#50) SCA-HYD-1: Erosion and Sedimentation Control Plan for Construction (#49) | LTS w/SCAs |

Discussion

Seismic Hazards and Unstable Soil

The WOSP EIR noted that there are no Alquist-Priolo Earthquake Fault Zones within the Plan Area and therefore no significant impact related to fault rupture. The WOSP EIR further noted that the Plan Area, including the project site, is located within the greater San Francisco Bay Area, a seismically active region with risks of strong seismic ground shaking and seismic-related ground failure, particularly the potential for liquefaction at and around the project site. Further, construction activities that disturb soils could result in erosion or loss of topsoil.

The WOSP EIR concluded that compliance with SCAs, which include the current SCAs: SCA-GEO-1: Construction-Related Permit(s) (#37), SCA-GEO-2: Soils Report (#38), and SCA-GEO-3: Seismic Hazards Zone (Landslide/Liquefaction) (#40), would ensure that the project would not result in significant impacts related to seismic hazards and unstable soils. These SCAs are included in Attachment A. With implementation of SCA-GEO-1, SCA-GEO-2, and SCA-GEO-3, the project impact would be consistent with WOSP EIR Impacts GEO-1, GEO-2, and GEO-5 and no further analysis is required with respect to seismic hazards and unstable soils.

Soil Erosion

The WOSP EIR identified SCA-GEO-4: State General Construction Permit (#50) and SCA-HYD-1: Erosion and Sedimentation Control Plan for Construction (#49) to ensure that the project would not result in significant impacts related to soil erosion. These SCAs are included in Attachment A. With implementation of SCA-GEO-4 and SCA-HYD-1, the project impact would be consistent with WOSP EIR Impact GEO-4 and no further analysis is required with respect to erosion.

F. Greenhouse Gas Emissions and Climate Change

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|--|--|-------------------------------------|----------------------------------|----------------|-----------------|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. GHG Emissions | LTS (Stationary sources SU but not applicable to current project) | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| b. Consistency with Applicable GHG Plans | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |

Discussion

GHG Emissions

According to the City of Oakland’s thresholds of significance, which were also used in the WOSP EIR, a project would have a significant impact if it would produce total greenhouse gas (GHG) emissions of more than 1,100 metric tons of carbon dioxide equivalents (CO₂e) annually and more than 4.6 metric tons of CO₂e per service population annually. The service population includes both the residents and the employees of the project.

The WOSP EIR evaluated impacts related to GHG emissions from construction and operation of development under the WOSP. Future projects and development under the WOSP would be required to implement SCAs that would reduce GHG emissions during construction and operation of projects and, with the exception of new stationary sources of GHG, would be expected to meet applicable efficiency thresholds and result in less-than-significant impacts. The project does not include permitted stationary sources of GHG so these are not further discussed.

While the project is consistent with the WOSP EIR analysis and therefore would have a less-than-significant impact with regard to GHG emissions, Oakland requires quantification to determine applicability of SCAs. Full inputs and outputs of the GHG emissions analysis are included in the Greenhouse Gas Reduction Plan and summarized below.

Based on the GHG analysis shown in **Table 3**, the project’s estimated CO₂e emissions per service population would be 0.57 metric tons annually, which is below the efficiency threshold of 4.6. Because the project would be below one of the project-level significance thresholds, impacts related to GHG emissions would be less-than-significant. Therefore, the proposed project would not substantially increase the severity of significant impacts identified in the WOSP EIR, nor would it result in new significant impacts related to GHG and climate change that were not identified in the WOSP EIR.

The WOSP EIR did not identify any mitigation measures related to GHGs, and none are required for the proposed project.

Table 3. Summary of Project GHG Emissions

| Emission Source | CO2e (MT/year) | CO2e Efficiency (MT/year/SP)^a |
|---|-----------------------|---|
| Construction ^b | 21 | 0.00 |
| Operation – Area | 40 | 0.01 |
| Operation – Energy | 2,075 | 0.49 |
| Operation – Mobile ^c | 5,670 | 1.33 |
| Operation – Waste | 43 | 0.01 |
| Operation – Water | 240 | 0.06 |
| Total Projects Emissions^c | 2,419 | 0.57 |
| Thresholds of Significance | 1,100 | 4.6 |
| Threshold Exceeded?^d | YES | NO |

^a The service population of 4,261 residents and employees was used, see subsection K, Population and Housing for details.

^b In accordance with CEQA guidance from the City of Oakland, GHG emissions during construction are amortized over 40 years

^c In accordance with SB 375, the estimated GHG emissions from cars and light-duty trucks are excluded from the GHG analysis.

^d Project must exceed both thresholds to be considered a significant impact.

Source: Greenhouse Gas Reduction Plan for WOB TOD Project, December 2018.

Independent of the Addendum, because of the size of the project and exceedance of at least one threshold, the project would be required to implement SCA-GHG-1: GHG Reduction Plan (#42). Implementation of other SCAs would also reduce GHG emissions. These include but are not limited to SCA-TRANS-4: Transportation and Parking Demand Management (#79), SCA-UTIL-1: Construction and Demolition Waste Reduction and Recycling (#84), SCA-UTIL-4: Green Building Requirements (#87), SCA-UTIL-7: Recycled Water (#91), and SCA-UTIL-8: Water Efficient Landscape Ordinance (WELO) (#92).

Consistency with GHG Emissions and Policies

The City’s GHG quantitative thresholds were designed to ensure compliance with the State’s AB 32 GHG reduction goals, as set forth in the California Air Resources Board’s (CARB’s) Climate Change Scoping Plan. Since the GHG emissions from the project would be below the City’s efficiency threshold based on the service population (see above), it can be assumed that the proposed project is consistent, and not in fundamental conflict, with the AB 32 Scoping Plan. Moreover, the project site is located in a Priority Development Area designated by Plan Bay Area,⁶ the Sustainable Communities Strategy adopted for the purpose of achieving the GHG reduction target established by CARB for the region’s transportation and land use sector pursuant to the AB 32 Scoping Plan. As stated by Plan Bay Area, a Priority Development Area is a geographic area “where new development

⁶ Metropolitan Transportation Commission (MTC) and Association of Bay Area Governments (ABAG), 2017. Priority Development Areas (Plan Bay Area 2040), available at http://opendata.mtc.ca.gov/datasets/56ee3b41d6a242e5a5871b043ae84dc1_0.

will support the day-to-day needs of residents and workers in a pedestrian-friendly environment served by transit.” By focusing new development within a Priority Development Area, Plan Bay Area establishes a preferred development scenario, which will achieve the plan’s GHG reduction targets. Since the proposed project would be constructed within a Priority Development Area with land uses at a density and intensity higher than the minimum recommendation included in Plan Bay Area (i.e., >20 dwelling units per acre; 0.75 FAR), the proposed project would further, and not conflict with, Plan Bay Area’s GHG reduction targets.

The project is consistent with, and would not hinder, the GHG reduction goals set forth in the City of Oakland’s Energy and Climate Action Plan (ECAP) and the green planning policies of the General Plan because the proposed project would promote land use patterns and densities that help improve regional air quality conditions, as demonstrated by its compliance with Plan Bay Area’s preferred development scenario. The project would also be required to comply with the City’s Green Building Ordinance, which supports the goals, policies, and actions of the ECAP and General Plan.

As listed under GHG Emissions discussion above, implementation of the City’s SCAs would also reduce GHG emissions. Overall, the project would not conflict with applicable GHG plans, policies or regulations, and this impact would be less-than-significant, consistent with the conclusions of the WOSP EIR.

G. Hazards and Hazardous Materials

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|--|---|-------------------------------------|----------------------------------|----------------|---|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Hazardous Materials Use, Exposure, Storage & Disposal | LTS w/ SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-HAZ-1: Hazardous Materials Related to Construction (#43) SCA-HAZ-2: Hazardous Building Materials and Site Contamination (#44) SCA-HAZ-3: Fire Safety Phasing Plan (#46) | LTS w/ SCAs |
| b. Hazardous Materials within a ¼-mile of a School | LTS w/ SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | N/A | LTS |
| c. Emergency Access Routes | LTS w/ SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-GEN-1: Construction Management Plan (#13) | LTS w/ SCAs |

Discussion

The project site is not located near wildland areas or public or private airstrips. Therefore, there are no wildland fire risks or risk of airport hazards at the project site and these are not further discussed in this document.

Hazardous Materials

As noted in the WOSP EIR, the site is included in the DTSC Geotracker database as a site requiring evaluation though no known sources of contaminants or known contaminants of concern were identified.⁷ Construction activities would use, transport, and store on site hazardous materials, including fuels and other chemicals and disturb soils and/or groundwater that may contain contaminants. The WOSP EIR reported that hazards and hazardous materials impacts would be mitigated to less-than-significant levels with compliance with local, state, and federal regulations for treatment, remediation, and/or disposal of contaminated soil and/or groundwater and the City SCAs that were in effect at the time, which are functionally equivalent to the City's current SCAs, including SCA-HAZ-1: Hazardous Materials Related to Construction (#43), SCA-HAZ-2: Hazardous Building Materials and Site Contamination (#44), SCA-HAZ-3: Fire Safety Phasing Plan (#46). Impacts of the environment on the project are not required under CEQA and information/SCAs related to future site users or residents are included for informational purposes.

⁷ State Department of Toxic Substances Control, EnviroStor records, available at <https://www.envirostor.dtsc.ca.gov/public/>, including record ID # 70000133 for the project site.

Hazardous Materials Near Schools

Because the project would not include any industrial uses, the proposed project would not use substantial amounts of hazardous materials and the small amounts of “household hazardous waste”, which includes cleaning products, would be handled according to applicable regulations. While there are schools located within ¼ mile of the project site, the impact would be less-than-significant because the project would not handle significant amounts of hazardous materials during operations.

Emergency Access Routes

As noted in the WOSP EIR, 7th Street in the project area is an identified emergency evacuation route. The WOSP EIR noted that temporary localized disruption of evacuation routes could be possible but that the impact would be reduced to less-than-significant through implementation of functionally equivalent SCA-GEN-1: Construction Management Plan (#13).

H. Hydrology and Water Quality

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|---|---|-------------------------------------|----------------------------------|----------------|---|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Water Quality & Drainage | LTS w/ SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-HYD-1: Erosion and Sedimentation Control Plan for Construction (#49) SCA-HYD-2: State Construction General Permit (#50) SCA-HYD-3: NPDES C.3 Stormwater Requirements for Regulated Projects (#54) | LTS w/ SCAs |
| b. Use of Groundwater | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| c. Flooding & Substantial Risks from Flooding | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |

Discussion

Water Quality and Drainage

The majority of the site (212,865 square feet, which is 87.5% of the site) is currently covered with impervious surfaces. Implementation of the project would include landscaped areas that would reduce impervious surfaces on the project site (relative to the existing condition) by approximately 10,320 square feet. The project would be required to comply with Provision C.3 of the National Pollutant Discharge Elimination System (NPDES) Municipal Regional Permit (MRP). Consistent with conclusions of the WOSP EIR, because the project would adhere to national, state, and local regulations, as well as the City's SCAs, including functionally equivalent SCA-HYD-1: Erosion and Sedimentation Control Plan for Construction (#49), SCA-HYD-2: State Construction General Permit (#50), and SCA-HYD-3: NPDES C.3 Stormwater Requirements for Regulated Projects (#54), the potential for the proposed project to substantially alter drainage patterns, increase the flow of runoff, impact groundwater, or affect water quality would be less-than-significant.

Use of Groundwater

The WOSP EIR noted that the local water district, EBMUD, relies on surface water and does not use the groundwater basin for municipal water supply so the impact in regard to use of groundwater would be less-than-significant. Additionally, the WOSP noted that development is required to comply with C.3 provisions requiring recharge rates at development sites at least equivalent to pre-development rates.

Flooding

As noted in the WOSP EIR, the project site is not in an area subject to inundation in the event of dam failure, seiche, or mudflows. However, some areas, including a portion of the project site, could be subject to tsunami inundation in the event of an off-shore earthquake. The WOSP EIR determined that due to the rare occurrence of tsunamis, the distance from the shoreline, and the emergency alert system, the potential impacts related to tsunami inundation would be less-than-significant.

As noted in the WOSP EIR and confirmed on current flood maps,⁸ the project site is outside of the 100-year-flood hazard zone and would not have a significant impact related to flood hazards.

⁸ Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) #06001C0066H, effective 12/21/2018, available at <https://msc.fema.gov/portal/search>.

I. Land Use

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|---|---|-------------------------------------|----------------------------------|----------------|-----------------|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Division of an Existing Community | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| b. Conflict with Land Uses / Land Use Plans | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |

Discussion

Division of an Existing Community

Consistent with WOSP EIR findings, the project would not disrupt or divide a community, but instead would replace a surface lot with walkways and plaza areas lined with neighborhood-serving retail uses with increased activation as well as comfort and appearance of pedestrian connections through the site.

Conflict with Land Uses / Land Use Plans

As detailed in the consistency assessment in Section V, the project would be substantially consistent with the development density established by existing zoning, community plan, or General Plan policies and the State Affordable Housing Density Bonus Law, which requires that the City grant a density bonus if the project meets affordable housing requirements. Requested variations from base zoning, community plan or General Plan requirements are allowable under the applicable local and State regulations and would therefore not represent conflicts with applicable plans.

The WOSP EIR acknowledges that higher-density development would be allowed at the project site than in adjacent low-rise residential areas. The WOSP EIR further determined that the increased density was appropriate for the transit site and would not result in a substantial conflict with existing uses if building height transitions were considered at boundaries. The project proposes low-rise residential duplex units along the Chester Street boundary with the South Prescott neighborhood low-rise residential units consistent with this conclusion and would therefore be consistent with the less-than-significant conclusion in the WOSP EIR.

J. Noise

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|-------------------------------------|---|-------------------------------------|----------------------------------|----------------|---|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Construction Noise and Vibration | LTS w/ SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-NOI-1: Construction Days/Hours (#62) SCA-NOI-2: Construction Noise (#63) SCA-NOI-3: Extreme Construction Noise (#64) SCA-NOI-4: Project-Specific Construction Noise Reduction Measures (#65) SCA-NOI-5: Construction Noise Complaints (#66) | LTS w/ SCAs |
| b. Operational Noise and Vibration | LTS w/ SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-NOI-6: Operational Noise (#68) | LTS w/ SCAs |
| d. Noise Exposure / Compatibility | LTS w/ SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | N/A | N/A |

Discussion

Construction Noise and Vibration

Sensitive receptors are located across the street from the project site, which includes single-family homes approximately 60 feet away across Chester Street and 80 feet across 5th Street and multi-family structures approximately 100 feet away across 7th Street. The project site's proximity to sensitive receptors, and the type of construction equipment that would be used as part of the project, are similar to other projects in urban areas. Because the proposed project site and its vicinity are part of an established, urbanized area, periodic exposure to construction-related noise and vibration are existing conditions. The use of heavy construction equipment would occur at different locations across the site. Therefore, the duration and frequency of heavy construction equipment operation near sensitive receptors would be limited on any given day and would not be expected to last more than a few days at a time. The WOSP EIR concluded that the impacts related to construction noise and vibration would be less-than-significant with implementation of applicable SCAs which are functionally equivalent to the applicable SCA-NOI-1: Construction Days/Hours (#62), SCA-NOI-2: Construction Noise (#63), SCA-NOI-3: Extreme Construction Noise (#64), SCA-NOI-4: Project-Specific Construction Noise Reduction Measures (#65), SCA-NOI-5: Construction Noise Complaints (#66). With implementation of these SCAs, the project's impact would be less-than-significant and within Impacts Noise-1 and Noise-4 of the WOSP EIR.

Operational Noise and Vibration

The WOSP EIR concluded that increases in traffic noise from build-out of the Plan Area would be below threshold levels and would therefore represent a less-than-significant impact. Residential, office, and retail uses such as those proposed are not generally considered substantial sources of operational noise or vibration, though noise from rooftop equipment can exceed threshold levels if not appropriately shielded. The WOSP EIR concluded the impacts related to operational noise and vibration would be less-than-significant with compliance with relevant regulations and applicable SCAs functionally equivalent to SCA-NOI-6: Operational Noise (#68).

Additionally, a noise specialist assessed the potential for noise from the BART line and nearby 7th Street to reflect off the large surfaces of the project's proposed buildings. Even assuming that 100% of such noise were reflected, given the distance from receptors and way that noise is perceived, even under worst-case conditions, the reflected noise component would increase overall noise levels by only 0.3 dBA, which would not be a noticeable or measurable increase at receptors in nearby buildings. Therefore, the noise reflection would not result in significant noise impacts.⁹

Noise Exposure / Compatibility

Analysis of existing noise and vibration on the project is not required under CEQA and is not analyzed in this CEQA document. Independent of the Addendum, the project would comply with the following SCAs related to noise levels at future site users: SCA-NOI-7: Exposure to Community Noise (#67).

⁹ Personal correspondence with Michael Thill, Illingworth & Rodkin, Inc., 12/20/2018. BART produces a noise level of approximately 69 dBA Ldn at 50 feet and 7th Street a level of 72 dBA CNEL at 50 feet from centerline. Existing noise levels at sensitive receptors to the north of the project are approximately 72.6 dBA CNEL/Ldn. The reflected source would travel farther as it would bounce off the proposed buildings, and would be 61 dBA Ldn at sensitive receptors to the north. Calculating the combined noise level of existing and reflected noise, the noise level at sensitive receptors to the north would be 72.9 dBA CNEL/Ldn, an increase of 0.3 dBA.

K. Population & Housing

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|-------------------------------------|---|-------------------------------------|----------------------------------|----------------|-----------------|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Population Growth | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| b. Displacement of Housing & People | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |

Discussion

The project would not remove any existing housing nor displace people. In fact, the project would function to do the opposite; serving to combat displacement by providing much needed affordable housing (at least 152 units). The project would result in an estimated 2,287 permanent employees on site and approximately 1,974 new residents.^{10, 11} The WOSP EIR anticipated significant residential and employment growth, and as detailed in subsection M, Transportation and Circulation, the current proposal is within the overall development assumed in the WOSP EIR. Consistent with the WOSP EIR, environmental impacts related to population and housing would be less-than-significant.

¹⁰ Employee estimates are based on an office and retail employment density of 5 employees per 1,000 square feet.

¹¹ Residential estimates are based on a residential density of 2.59 persons per household per the State of California, Department of Finance, E-5 Population and Housing Estimates for Cities, Counties, and the State, 2011-2018, with 2010 Benchmark. Sacramento, California, January 2018.

L. PUBLIC SERVICES, PARKS, AND RECREATION FACILITIES

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|-----------------------|---|-------------------------------------|----------------------------------|----------------|---|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Public Services | LTS w/ SCA | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | SCA-GEN-1: Compliance with Other Requirements (#3) SCA-PUB-1: Capital Improvements Impact Fee (#74) SCA-HAZ-4: Fire Safety Phasing Plan (#46) | LTS w/ SCA |
| b. Parks & Recreation | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |

Discussion

The WOSP EIR concluded that while development of the Plan Area would increase demand for public services and recreation, it also includes improvements and would pay development fees to support services and the impacts in this regard would be less-than-significant or reduced to that level through implementation of applicable SCAs. The project would comply with the following SCAs related to public services, parks, and recreation: SCA-GEN-1: Compliance with Other Requirements (#3), SCA-PUB-1: Capital Improvements Impact Fee (#74), and SCA-HAZ-4: Fire Safety Phasing Plan (#46).

M. Transportation and Circulation

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|--|---|-------------------------------------|----------------------------------|----------------|--|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Conflict with Circulation Plans | LTS w/ SCAs | <input checked="" type="checkbox"/> | <input type="checkbox"/> | N/A | SCA-TRANS-4: Transportation and Parking Demand Management (#79) SCA-TRANS-5: Transportation Impact Fee (#80) SCA-GEN-1: Construction Management Plan (#13) | LTS w/ SCAs |
| b. Substantial Additional VMT ^a | LTS-SU | <input checked="" type="checkbox"/> | <input type="checkbox"/> | N/A | -- | LTS |
| c. Induce Traffic | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | | LTS |

^a As explained in the discussion below, LOS-based impact analysis has been replaced by VMT-based analysis. WOSP EIR findings were for LOS-based analysis.

Discussion

Transportation and circulation was analyzed in the WOSP EIR, which found Level of Service (LOS) at Intersection #13, Broadway and West Grand Avenue, LOS at Intersection #15, Adeline Street and 18th Street, and LOS at Intersection #24, Adeline Street and 5th Street impacts to be less than significant with implementation of mitigation measures or SCAs. Impacts to Intersection #1, 40th Street and Hollis Street, at PM hours, LOS at Intersection #2, 40th Street and San Pablo Avenue, LOS at Intersection #1, queue storage at Intersection #2, and LOS at Intersection #7, West Grand Avenue at Mandela Parkway, were found to be significant and unavoidable under the WOSP EIR. All other transportation and circulation impacts under the WOSP were found to have no impacts or less-than-significant impacts.

The 2010 Oakland Housing Element Update EIR and 2014 Addendum found significant and unavoidable impacts related to traffic delays. The remaining transportation and circulation impacts were found to have no impacts or less-than-significant impacts. In addition, the 1998 LUTE EIR found impacts to intersection operations to be less than significant with implementation of mitigation measures or SCAs. Impacts to roadway segments under the 1998 LUTE EIR were found to be significant and unavoidable. The remaining transportation and circulation impacts under the 1998 LUTE EIR were found to have no or less-than-significant impacts.

Conflicts with Circulation Plans

The project is consistent with applicable plans, ordinances, and policies, and would not cause a significant impact by conflicting with adopted plans, ordinances, or policies addressing the safety

and performance of the circulation system, including transit, roadways, bicycle lanes, and pedestrian paths (except for automobile level of service or other measures of vehicle delay).

The 1998 LUTE, as well as the City's Public Transit and Alternative Mode and Complete Streets policies, states a strong preference for encouraging the use of non-automobile transportation modes, such as transit, bicycling, and walking. The project would encourage the use of non-automobile transportation modes by locating a mixed-use project (residential, office, and retail) in an area that is becoming a more dense, walkable urban environment and is well-served by both local and regional transit. The project would further discourage driving in the project vicinity by eliminating 337 existing parking spaces at the existing West Oakland BART Station.

The project is consistent with both the City's 2017 Pedestrian Master Plan and the 2007 Bicycle Master Plan as it would not make major modifications to existing pedestrian or bicycle facilities in the surrounding areas and would not adversely affect installation of future facilities.

Further, the project is required to prepare and implement a Transportation and Parking Demand Management Plan (TDM Plan) because it would generate more than 50 peak hour trips (see separate Transportation and Parking Demand Management memorandum for more detail). The TDM Plan includes on-going operational strategies, as well as infrastructure improvements in the project vicinity, that encourage the use of non-automobile travel modes.

The major off-site infrastructure improvements included in the project consist of:

- New Class 4 bicycle lanes along both directions of 7th Street and Mandela Parkway adjacent to the project.
- Improved sidewalks and other pedestrian amenities along the project frontages and pedestrian safety and accessibility improvements along the corridor and at intersections.
- Enhanced bus facilities along the project frontage.

These improvements would not only benefit the project residents, workers, and visitors, but also residents, workers, and visitors in the areas surrounding the project site, including BART riders. In addition, these improvements are also consistent with the City's adopted plans, ordinances, and policies relating to safety and performance of the circulation system because they improve the pedestrian and bicycle environment in the vicinity of the project.

Overall, the project would not conflict with adopted plans, ordinances, or policies addressing the safety and performance of the circulation system. This is a less-than-significant impact; no mitigation measures are required.

In addition, the project is consistent with the WOSP EIR, which evaluated the impacts of developments in the West Oakland area, as described below.

WOSP EIR Traffic Analysis

The project site is located within the WOSP Area. The development evaluated in the WOSP EIR represents the reasonably foreseeable development expected to occur in the next 20 to 25 years in the WOSP Area. The WOSP and its EIR intend to provide flexibility in the location, amount, and type of development. Thus, as long as the trip generation for the overall WOSP Area remains below the

levels estimated in the WOSP EIR, the traffic impact analysis presented in the WOSP EIR continues to remain valid.

Since the certification of the WOSP EIR, 11 developments, including this project, have been proposed and are in some stage of the City’s approval process at this time. **Table 4** summarizes the trip generation for these developments. The 11 developments combined would generate about 1,305 AM peak hour and 1,452 PM peak hour trips. The combined trip generation is less than the total trip generation estimated in the WOSP EIR. Similarly, inclusive of the project, the 11 developments currently entitled and proposed within the WOSP Area are substantially less than the total cumulative development assumed within the WOSP Area by the WOSP EIR.

Table 4. Trip Generation for Development Projects within the WOSP Area

| Project Name | AM Peak Hour | PM Peak Hour |
|--|---------------------|---------------------|
| 2201 Filbert (Icehouse) ^a | 52 | 84 |
| 532 Union Street (The Union Project) ^b | 34 | 47 |
| 1708 Wood Street (Roadway Express) ^c | 50 | 58 |
| Mandela Parkway Hotel ^d | 135 | 141 |
| 914 West Grand Avenue ^e | 15 | 17 |
| 34 th and San Pablo Affordable Housing Development ^f | 38 | 41 |
| 1450 32 nd Street ^g | 12 | 15 |
| 1919 Market Street ^h | 34 | 41 |
| 801 Pine Street (The Phoenix) ⁱ | 84 | 97 |
| 500 Kirkham Street ^j | 384 | 399 |
| West Oakland BART Project ^k | 472 | 548 |
| Total Projects Trips | 1,310 | 1,488 |
| WOSP Estimated Trip Generation ^l | 5,537 | 6,698 |
| Percent Complete | 24% | 22% |

^a Source: West Grand Avenue & Market Street CEQA Analysis, August 20, 2015.

^b Source: 532 Union Street CEQA Analysis, July 15, 2016.

^c Source: 1708 Wood Street CEQA Analysis, June 20, 2016.

^d Source: 914 West Grand Avenue Project in Oakland – Transportation Impact Review, November 17, 2017.

^e Source: Mandela Hotel in Oakland – Transportation Assessment, November 29, 2017.

^f Source: 34th and San Pablo Project – Transportation Impact Review, October 20, 2017.

^g Source: 1450 32nd Street – Preliminary Transportation Impact Analysis, July 28, 2017.

^h Source: 1919 Market Street Project in Oakland – Preliminary Transportation Assessment, August 8, 2017.

ⁱ Source: 500 Kirkham Street – Planning-Related Non-CEQA Transportation Impact Review, January X, 2019

^j Source: The Phoenix – Transportation Assessment (Non-CEQA Memorandum), November 29, 2018

^k Source: West Oakland BART Project Planning-Related Non-CEQA Transportation Impact Review, January X, 2019.

^l Source: West Oakland Specific Plan Draft EIR, Table 4.10-4, May 2014.

Source: Fehr & Peers, 2019.

The project is located in the 7th Street Opportunity Area and is consistent with the assumptions used in the WOSP EIR for the 7th Street Opportunity Area. Since the project, combined with other currently proposed developments in the WOSP Area, would generate fewer automobile trips than assumed in the WOSP EIR, the project would not result in additional impacts on traffic operations at the intersections analyzed in the WOSP EIR. In addition, all the mitigation measures identified in the WOSP EIR are included in the citywide Transportation Impact Fee (TIF), implemented as SCA-TRANS-5: Transportation Impact Fee (#80). SCA-TRANS-4: Transportation and Parking Demand Management (#79) and SCA-GEN-1: Construction Management Plan (#13) would also be applicable to ensure consistency with applicable plans and regulations.

Substantial Additional VMT

On September 21, 2016, the City of Oakland's Planning Commission directed staff to update the CEQA Thresholds of Significance Guidelines related to transportation impacts in order to implement the directive from Senate Bill 743 to modify local environmental review processes by removing automobile delay, as described solely by level of service or similar measures of vehicular capacity or traffic congestion, as a significant impact on the environment pursuant to CEQA.¹² The Planning Commission direction aligns with draft proposed guidance from the Governor's Office of Planning and Research and the City's approach to transportation impact analysis, with adopted plans and policies related to transportation, which promote the reduction of greenhouse gas emissions, the development of multimodal transportation networks, and a diversity of land uses. Consistent with the Planning Commission direction and the Senate Bill 743 requirements, the City of Oakland published the revised Transportation Impact Review Guidelines on April 14, 2017 to guide the evaluation of the transportation impacts associated with land use development projects.

Many factors affect travel behavior, including density of development, diversity of land uses, design of the transportation network, access to regional destinations, distance to high-quality transit, development scale, demographics, and transportation demand management. Typically, low-density development that is located at a great distance from other land uses, in areas with poor access to non-single occupancy vehicle travel modes generate more vehicle travel compared to development located in urban areas, where a higher density of development, a mix of land uses, and non-single occupancy vehicle travel options are available.

Given these travel behavior factors, most of Oakland has lower VMT per capita and VMT per worker ratios than the nine-county San Francisco Bay Area region. Further, within the City of Oakland, some neighborhoods may have lower VMT ratios than others.

VMT Estimate

Neighborhoods within Oakland are expressed geographically in transportation analysis zones (TAZ), which are used in transportation planning models for transportation analysis and other planning purposes. The Metropolitan Transportation Commission (MTC) Travel Model includes 116 TAZs within Oakland that vary in size from a few city blocks in the downtown core, to multiple blocks in outer neighborhoods, to even larger geographic areas in lower-density neighborhoods.

¹² Steinberg, 2013. (Senate Bill SB 743)

The MTC Travel Model is a model that assigns all predicted trips within, across, or to/from the nine-county San Francisco Bay Area region onto the roadway network and the transit system by mode (single-driver and carpool vehicle, biking, walking, or transit) and transit carrier (bus, rail) for a particular scenario.

The travel behavior from MTC Travel Model is modeled based on the following inputs:

- Socioeconomic data developed by the Association of Bay Area Governments (ABAG).
- Population data created using the 2000 US Census and modified using the open source PopSyn software.
- Zonal accessibility measurements for destinations of interest.
- Travel characteristics and vehicle ownership rates derived from the 2000 Bay Area Travel Survey (BATS).
- Observed vehicle counts and transit boardings.

The daily VMT output from the MTC Travel Model for residential and office uses comes from a tour-based analysis. The tour-based analysis examines the entire chain of trips over the course of a day, not just trips to and from the project site. In this way, all of the VMT for an individual resident or employee is included; not just trips into and out of the person's home or workplace. For example, a resident leaves her apartment in the morning, stops for coffee, and then goes to the office. In the afternoon she heads out to lunch, and then returns to the office, with a stop at the drycleaners on the way. After work, she goes to the gym to work out, and then joins some friends at a restaurant for dinner before returning home. All the stops and trips within her day form her "tour". The tour-based approach would add up the total number of miles driven over the course of her tour and assign it as her daily VMT.

Based on the MTC Travel Model, the regional average daily VMT per capita is 15.0 under 2020 conditions and 13.8 under 2040 conditions. The regional average daily VMT per worker is 21.8 under 2020 conditions and 20.3 under 2040 conditions.

Thresholds of Significance for VMT

According to the City of Oakland Transportation Impact Review Guidelines (TIRG), the following are thresholds of significance related to substantial additional VMT:

- For residential projects, a project would cause substantial additional VMT if it exceeds existing regional household VMT per capita minus 15 percent.
- For office projects, a project would cause substantial additional VMT if it exceeds the existing regional VMT per worker minus 15 percent.
- For retail projects, a project would cause substantial additional VMT if it results in a net increase in total VMT.

Screening Criteria

VMT impacts would be less than significant for a project if any of the identified screening criteria outlined below are met:

1. Small Projects: The project generates fewer than 100 vehicle trips per day

2. Low-VMT Areas: The project meets map-based screening criteria by being located in an area that exhibits below threshold VMT, or 15 percent or more below the regional average
3. Near Transit Stations: The project is located in a Transit Priority Area or within a one-half mile of a Major Transit Corridor or Stop¹³ and satisfies the following:
 - Has a Floor Area Ratio (FAR) of more than 0.75.
 - Includes less parking for use by residents, customers, or employees of the project than other typical nearby uses, or less than required by the City (if parking minimums pertain to the site) or allowed without a conditional use permit (if minimums and/or maximums pertain to the site).
 - And is consistent with the applicable Sustainable Communities Strategy (as determined by the lead agency, with input from the MTC).

The project satisfies the Near Transit Stations (#3) criterion as described below.

Criterion #1: Small Projects

The project would generate more than 100 vehicle trips per day and therefore does not meet criterion #1.

Criterion #2: Low-VMT Area

Table 5 shows the estimated 2020 and 2040 VMT per capita and VMT per worker for TAZ 965, the TAZ in which the project is located, as well as the applicable VMT thresholds of 15 percent below the regional average. As shown in Table 5, the 2020 estimated average daily VMT per capita in the project TAZ is less than the regional averages minus 15 percent. However, the 2040 VMT per capita and both the 2020 and 2040 VMT per worker in TAZ 965 is greater than the regional average minus 15 percent.

Note that TAZ 965 has more than double the estimated VMT per capita and VMT per worker than other nearby TAZs. Although the West Oakland BART Station is located in TAZ 965, the MTC Model does not accurately reflect the proximity of the uses in the TAZ, especially the proposed project, to the BART Station because TAZ 965 is a relatively large TAZ (it is more than three or four times the size of the other nearby TAZs and includes the Port of Oakland to the West which is not very transit accessible.) The Model assumes that all the developments in the TAZ are uniformly distributed throughout the TAZ; even though many uses, such as the proposed project, are concentrated around the BART Station. Considering that the proposed project would consist of diverse uses with high densities adjacent to the BART station, it is expected that its VMT per capita and VMT per worker would be lower than the TAZ averages shown in Table 5. It is likely that the project would generate less VMT per capita and/or VMT per worker than the regional average minus 15 percent. However, since TAZ 965 does not meet the map-based screening criteria, it is conservatively assumed that the residential and office components of the project cannot be presumed to result in less than substantial additional VMT under the screening criterion.

¹³ "Major transit stop" is defined in CEQA Section 21064.3 as a rail transit station, a ferry terminal served by either a bus or rail transit service, or the intersection of two or more major bus routes with a frequency of service interval of 15 minutes or less during the morning and afternoon peak commute periods.

Table 5. Daily Vehicle Miles Traveled Summary

| Metric | Bay Area | | | | TAZ 965 | |
|---|------------------|----------------------------|------------------|----------------------------|-------------|-------------|
| | 2020 | | 2040 | | 2020 | 2040 |
| | Regional Average | Regional Average minus 15% | Regional Average | Regional Average minus 15% | | |
| Residential (VMT per Capita) ^a | 15.0 | 12.8 | 13.8 | 11.7 | 12.5 | 12.4 |
| Non-Residential (VMT per Worker) ^b | 21.8 | 18.5 | 20.3 | 17.3 | 32.0 | 28.1 |

Notes:

Bold indicates that the TAZ does not meet the screening criteria of VMT less than the regional average minus 15

^a MTC Model results at analytics.mtc.ca.gov/foswiki/Main/PlanBayAreaVmtPerCapita and accessed in December 2018.

^b MTC Model results at analytics.mtc.ca.gov/foswiki/Main/PlanBayAreaVmtPerWorker and accessed in December 2018.

Source: Fehr & Peers, 2018.

According to the City of Oakland TIRG, retail spaces less than 80,000 square-feet are considered local serving and are not expected to contribute to an increase in VMT. Therefore, it is presumed that the retail component of the project, which would consist of up to 75,000 square feet of ground level retail, would not result in substantial additional VMT and project impacts with respect to VMT would be less than significant.

Criterion #3: Near Transit Stations

The project would be located adjacent to the West Oakland BART Station and would be near frequent bus service at the West Oakland BART Station (Lines 14 and 62 with 15-minute headways during the peak periods). The project would satisfy Criterion #3 because it would meet the following three conditions for this criterion:

- The project would have a FAR greater than 0.75.
- The project would include 400 automobile parking spaces. The City of Oakland Planning Code requires the project to provide the following:
 - Section 17.116.060 requires a minimum of 0.5 space per dwelling unit and allows a maximum of 1.25 space per dwelling unit for multi-family residential developments in the S-15W zone. Section 17.116.110.C allows the residential parking minimums to be reduced by 50 percent because the project is located in a transit accessible area (30 percent) and it would provide on-site car-share spaces (20 percent). Thus, the residential component of the project is required to provide between 190 and 953 parking spaces.
 - Section 17.116.080 does not have any minimum parking for commercial activities, and allows a maximum of one space for each 300 square feet of floor area on the ground level and 500 square feet of floor area on other levels for commercial uses in the S-15W zone. Thus, the retail and office components of the project are required to provide between zero and 964 spaces.

Overall, the Code requires the project to provide a minimum of 190 and a maximum of 1,917 parking spaces. Thus, the 400 parking spaces provided by the project would be within the

parking supply allowed by the Planning Code for the project. Therefore, the project would not provide more parking for use by residents, customers, or employees than other typical nearby uses, nor would it provide more parking than required by City Code.

- The project is located within the West Oakland PDA as defined by Plan Bay Area, and is therefore consistent with the region's Sustainable Communities Strategy

VMT Screening Conclusion

As described above, VMT impacts would be less than significant for a project if any of the identified screening criteria outlined below are met: Small Projects, Low-VMT Areas, and Near Transit Stations. The project would satisfy the Near Transit Stations (#3) criterion and would have a less-than-significant impact on VMT.

Induce Automobile Travel

The project would not increase the automobile capacity of the roadway network surrounding the project site. Therefore, it would not increase the physical roadway capacity and would not add new roadways to the network, and would not induce additional automobile traffic. This is a less-than-significant impact; no mitigation measures are required.

Overall Conclusion

Consistent with the findings of the WOSP EIR, the project would not result in any significant impacts related to transportation or circulation. Further, based on an examination of the other Program EIRs, implementation of the project would not result in any increase in the severity of any previously identified impacts, nor would it result in new significant impacts related to transportation or circulation that were not previously identified in the WOSP EIR and Program EIRs.

N. Utilities and Service Systems

| Impacts Related To: | WOSP EIR Findings with Implementation of SCA or MMs (If Required) | PROJECT | | | | |
|---------------------------------------|---|-------------------------------------|----------------------------------|----------------|-----------------|-------------------------------|
| | | Relationship to WOSP EIR Findings | | Applicable MMs | Applicable SCAs | Project Level of Significance |
| | | Equal or Less Severity | Substantial Increase in Severity | | | |
| a. Wastewater & Stormwater Facilities | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| b. Water Supplies | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| c. Solid Waste Services | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |
| d. Energy | LTS | <input checked="" type="checkbox"/> | <input type="checkbox"/> | -- | -- | LTS |

Discussion

The Water Supply Assessment prepared by EBMUD for the WOSP EIR concluded that EBMUD has sufficient water supplies to meet current water demand and future water demand through 2035, including the increased water demand associated with development of the Plan Area during normal, single dry, and multiple dry years. The WOSP EIR determined that development of the Plan Area would have less-than-significant impacts related to stormwater and wastewater facilities, solid waste services, and energy. The WOSP EIR did not identify any mitigation measures related to utilities and service systems, and none would be required for the project.

Independent of the Addendum, the project would comply with the following SCAs: SCA-UTIL-1: Construction and Demolition Waste Reduction and Recycling (#84), SCA-UTIL-2: Underground Utilities (#85), SCA-UTIL-3: Recycling Collection and Storage Space (#86), SCA-UTIL-4: Green Building Requirements (#87), SCA-UTIL-5: Sanitary Sewer System (#89), SCA-UTIL-6: Storm Drain System (#90), SCA-UTIL-7: Recycled Water (#91), SCA-UTIL-8: Water Efficient Landscape Ordinance (WELO) (#92), and SCA-HYD-3: NPDES C.3 Stormwater Requirements for Regulated Projects (#54).

Acronyms and Terms

| | |
|-------------------|---|
| AC Transit | Alameda–Contra Costa Transit District |
| BART | Bay Area Rapid Transit |
| CEQA | California Environmental Quality Act |
| City | City of Oakland |
| EIR | Environmental Impact Report |
| FAR | floor area ratio |
| GHG | greenhouse gas |
| LUTE | Land Use and Transportation Element |
| NPDES | National Pollution Discharge Elimination System |
| PM _{2.5} | particulate matter, 2.5 micrometers or less |
| PM ₁₀ | particulate matter, 10 micrometers or less |
| SCA | Standard Condition of Approval |
| TAC | toxic air contaminant |
| VMT | vehicle miles traveled |
| WOSP | West Oakland Specific Plan |

Attachment A: City of Oakland Standard Conditions of Approval

The City of Oakland’s Uniformly Applied Development Standards adopted as Standard Conditions of Approval (Standard Conditions of Approval, or SCAs) were originally adopted by the City in 2008 (Ordinance No. 12899 C.M.S.) pursuant to Public Resources Code section 21083.3 and have been incrementally updated over time. The SCAs incorporate development policies and standards from various adopted plans, policies, and ordinances (such as the Oakland Planning and Municipal Codes, Oakland Creek Protection, Stormwater Water Management and Discharge Control Ordinance, Oakland Tree Protection Ordinance, Oakland Grading Regulations, National Pollutant Discharge Elimination System (NPDES) permit requirements, Housing Element-related mitigation measures, Green Building Ordinance, historic/Landmark status, California Building Code, and Uniform Fire Code, among others), which have been found to substantially mitigate environmental effects.

These SCAs are incorporated into projects as conditions of approval, regardless of the determination of a project’s environmental impacts. As applicable, the SCAs are adopted as requirements of an individual project when it is approved by the City, and are designed to, and will, avoid or substantially reduce a project’s environmental effects.

In reviewing project applications, the City determines which SCAs apply based upon the zoning district, community plan, site, surroundings, project proposal, and the type of permits/approvals required for the project. Depending on the specific characteristics of the project type and/or project site, the City will determine which SCAs apply to a specific project. Because these SCAs are mandatory City requirements imposed on a city-wide basis, environmental analyses assume that these SCAs will be imposed and implemented by the project sponsor, and are not imposed as mitigation measures under CEQA.

All SCAs identified in the Addendum—which is consistent with the measures and conditions presented in the City of Oakland General Plan, LUTE EIR—are included herein. To the extent that any SCA identified in the Addendum was inadvertently omitted, it is automatically incorporated herein by reference.

- The first column identifies the SCA applicable to that topic in the Addendum.
- The second column identifies the monitoring schedule or timing applicable to the project.
- The third column names the party responsible for monitoring the required action for the project.

In addition to the SCAs identified and discussed in the Addendum, other SCAs that are applicable to the project are included herein.

The project sponsor is responsible for compliance with any recommendations in approved technical reports and with all SCAs set forth herein at its sole cost and expense, unless otherwise expressly provided in a specific SCA, and subject to the review and approval of the City of Oakland. Overall monitoring and compliance with the SCAs will be the responsibility of the Planning and Zoning Division. Prior to the issuance of a demolition, grading, and/or construction permit, the project sponsor shall pay the applicable mitigation and monitoring fee to the City in accordance with the City’s Master Fee Schedule.

Note that the SCAs included in this document are referred to using an abbreviation for the environmental topic area and are numbered sequentially for each topic area—e.g., **SCA-AIR-1**, **SCA-AIR-2**. The SCA title and the SCA number that corresponds to the City’s current master SCA list are also provided—e.g., **SCA-AIR-1: Construction-Related Air Pollution (Dust and Equipment Emissions) (#19)**.

City of Oakland Standard SCAs Required for the Project

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---|---|---------------------------|
| GENERAL | | | |
| <p>SCA-AES-1: Construction Management Plan (#13) Prior to the issuance of the first construction-related permit, the project applicant and his/her general contractor shall submit a Construction Management Plan (CMP) for review and approval by the Bureau of Planning, Bureau of Building, and other relevant City departments such as the Fire Department, Department of Transportation, and the Public Works Department as directed. The CMP shall contain measures to minimize potential construction impacts including measures to comply with all construction-related Conditions of Approval (and mitigation measures if applicable) such as dust control, construction emissions, hazardous materials, construction days/hours, construction traffic control, waste reduction and recycling, stormwater pollution prevention, noise control, complaint management, and cultural resource management (see applicable Conditions below). The CMP shall provide project-specific information including descriptive procedures, approval documentation, and drawings (such as a site logistics plan, fire safety plan, construction phasing plan, proposed truck routes, traffic control plan, complaint management plan, construction worker parking plan, and litter/debris clean-up plan) that specify how potential construction impacts will be minimized and how each construction-related requirement will be satisfied throughout construction of the project.</p> | <p>Prior to the issuance of the first construction-related permit</p> | <p>Bureau of Planning, Bureau of Building, and other relevant City departments such as the Fire Department, Department of Transportation, and the Public Works Department as directed</p> | <p>Bureau of Building</p> |
| AESTHETICS, SHADOW, AND WIND | | | |
| <p>SCA-AES-1: Trash and Blight Removal (#16) The project applicant and his/her successors shall maintain the property free of blight, as defined in chapter 8.24 of the Oakland Municipal Code. For nonresidential and multi-family residential projects, the project applicant shall install and maintain trash receptacles near public entryways as needed to provide sufficient capacity for building users.</p> | <p>Ongoing</p> | <p>N/A</p> | <p>Bureau of Building</p> |
| <p>SCA-AES-2: Graffiti Control (#17) a. During construction and operation of the project, the project applicant shall incorporate best management practices reasonably related to the control of graffiti and/or the mitigation of the impacts of graffiti. Such best management practices may include, without limitation: i. Installation and maintenance of landscaping to discourage defacement of and/or protect likely graffiti-attracting surfaces. ii. Installation and maintenance of lighting to protect likely graffiti-attracting</p> | <p>Ongoing</p> | <p>N/A</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|---|---------------------------|---------------------------|
| <p>surfaces.</p> <ul style="list-style-type: none"> iii. Use of paint with anti-graffiti coating. iv. Incorporation of architectural or design elements or features to discourage graffiti defacement in accordance with the principles of Crime Prevention Through Environmental Design (CPTED). v. Other practices approved by the City to deter, protect, or reduce the potential for graffiti defacement. <p>b. The project applicant shall remove graffiti by appropriate means within seventy-two (72) hours. Appropriate means include:</p> <ul style="list-style-type: none"> i. Removal through scrubbing, washing, sanding, and/or scraping (or similar method) without damaging the surface and without discharging wash water or cleaning detergents into the City storm drain system. ii. Covering with new paint to match the color of the surrounding surface. iii. Replacing with new surfacing (with City permits if required). | | | |
| <p>SCA-AES-3: Landscape Plan (#18)</p> <p><i>a. Landscape Plan Required</i></p> <p>The project applicant shall submit a final Landscape Plan for City review and approval that is consistent with the approved Landscape Plan. The Landscape Plan shall be included with the set of drawings submitted for the construction-related permit and shall comply with the landscape requirements of chapter 17.124 of the Planning Code. Proposed plants shall be predominantly drought-tolerant. Specification of any street trees shall comply with the Master Street Tree List and Tree Planting Guidelines (which can be viewed at http://www2.oaklandnet.com/oakca1/groups/pwa/documents/report/oak042662.pdf and http://www2.oaklandnet.com/oakca1/groups/pwa/documents/form/oak025595.pdf, respectively), and with any applicable streetscape plan.</p> | <p>Prior to approval of construction-related permit</p> | <p>Bureau of Planning</p> | <p>N/A</p> |
| <p><i>b. Landscape Installation</i></p> <p>The project applicant shall implement the approved Landscape Plan unless a bond, cash deposit, letter of credit, or other equivalent instrument acceptable to the Director of City Planning, is provided. The financial instrument shall equal the greater of \$2,500 or the estimated cost of implementing the Landscape Plan based on a licensed contractor's bid.</p> | <p>Prior to building permit final</p> | <p>Bureau of Planning</p> | <p>Bureau of Building</p> |
| <p><i>c. Landscape Maintenance</i></p> <p>All required planting shall be permanently maintained in good growing condition and, whenever necessary, replaced with new plant materials to ensure continued compliance with applicable landscaping requirements. The property owner shall be responsible for</p> | <p>Ongoing</p> | <p>N/A</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|--|--------------------|---------------------------|
| maintaining planting in adjacent public rights-of-way. All required fences, walls, and irrigation systems shall be permanently maintained in good condition and, whenever necessary, repaired or replaced. | | | |
| <p>SCA-AES-4: Lighting (#19) Proposed new exterior lighting fixtures shall be adequately shielded to a point below the light bulb and reflector to prevent unnecessary glare onto adjacent properties.</p> | Prior to building permit final | N/A | Bureau of Building |
| <p>SCA-AES-5: Public Art for Private Development (#20) The project is subject to the City’s Public Art Requirements for Private Development, adopted by Ordinance No. 13275 C.M.S. (“Ordinance”). The public art contribution requirements are equivalent to one-half percent (0.5%) for the “residential” building development costs, and one percent (1.0%) for the “non-residential” building development costs. The contribution requirement can be met through: 1) the installation of freely accessible art at the site; 2) the installation of freely accessible art within one-quarter mile of the site; or 3) satisfaction of alternative compliance methods described in the Ordinance, including, but not limited to, payment of an in-lieu fee contribution. The applicant shall provide proof of full payment of the in-lieu contribution and/or provide plans, for review and approval by the Planning Director, showing the installation or improvements required by the Ordinance prior to issuance of a building permit. Proof of installation of artwork, or other alternative requirement, is required prior to the City’s issuance of a final certificate of occupancy for each phase of a project unless a separate, legal binding instrument is executed ensuring compliance within a timely manner subject to City approval.</p> | <p><i>Payment of in-lieu fees and/or plans showing fulfillment of public art requirement:</i> Prior to Issuance of Building permit. <i>Installation of art/cultural space:</i> Prior to Issuance of a Certificate of Occupancy</p> | Bureau of Planning | Bureau of Building |
| AIR QUALITY | | | |
| <p>SCA-AIR-1: Dust Controls – Construction Related (#21) The project applicant shall implement all of the following applicable air pollution control measures during construction of the project:</p> <ol style="list-style-type: none"> Water all exposed surfaces of active construction areas at least twice daily. Watering should be sufficient to prevent airborne dust from leaving the site. Increased watering frequency may be necessary whenever wind speeds exceed 15 miles per hour. Reclaimed water should be used whenever feasible. Cover all trucks hauling soil, sand, and other loose materials or require all trucks to maintain at least two feet of freeboard (i.e., the minimum required space between the top of the load and the top of the trailer). All visible mud or dirt track-out onto adjacent public roads shall be removed using | During construction | N/A | Bureau of Building |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|----------------------------|------------------|---------------------------|
| <p>wet power vacuum street sweepers at least once per day. The use of dry power sweeping is prohibited.</p> <p>e. All demolition activities (if any) shall be suspended when average wind speeds exceed 20 mph.</p> <p>f. All trucks and equipment, including tires, shall be washed off prior to leaving the site.</p> <p>g. Site accesses to a distance of 100 feet from the paved road shall be treated with a 6 to 12 inch compacted layer of wood chips, mulch, or gravel.</p> | | | |
| <p>SCA-AIR-2 : Criteria Air Pollutant Controls – Construction Related (#22)</p> <p>The project applicant shall implement all of the following applicable basic control measures for criteria air pollutants during construction of the project as applicable:</p> <p>a. Idling times on all diesel-fueled commercial vehicles over 10,000 lbs. shall be minimized either by shutting equipment off when not in use or reducing the maximum idling time to two minutes (as required by the California airborne toxics control measure Title 13, Section 2485, of the California Code of Regulations). Clear signage to this effect shall be provided for construction workers at all access points.</p> <p>b. Idling times on all diesel-fueled off-road vehicles over 25 horsepower shall be minimized either by shutting equipment off when not in use or reducing the maximum idling time to two minutes and fleet operators must develop a written policy as required by Title 23, Section 2449, of the California Code of Regulations (“California Air Resources Board Off-Road Diesel Regulations”).</p> <p>c. All construction equipment shall be maintained and properly tuned in accordance with the manufacturer’s specifications. All equipment shall be checked by a certified mechanic and determined to be running in proper condition prior to operation. Equipment check documentation should be kept at the construction site and be available for review by the City and the Bay Area Air Quality District as needed.</p> <p>d. Portable equipment shall be powered by grid electricity if available. If electricity is not available, propane or natural gas generators shall be used if feasible. Diesel engines shall only be used if grid electricity is not available and propane or natural gas generators cannot meet the electrical demand.</p> <p>e. Low VOC (i.e., ROG) coatings shall be used that comply with BAAQMD Regulation 8, Rule 3: Architectural Coatings.</p> <p>f. All equipment to be used on the construction site shall comply with the requirements of Title 13, Section 2449, of the California Code of Regulations (“California Air Resources Board Off-Road Diesel Regulations”) and upon request by the City (and the Air District if specifically requested), the project applicant shall provide written documentation that fleet requirements have been met.</p> | <p>During construction</p> | <p>N/A</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|---|---------------------------|---------------------------|
| <p>The project applicant shall implement all of the following applicable enhanced control measures for criteria air pollutants during construction of the project as applicable:</p> <p>g. Criteria Air Pollutant Reduction Measures</p> <p>The project applicant shall retain a qualified air quality consultant to identify criteria air pollutant reduction measures to reduce the project's average daily emissions below 54 pounds per day of ROG, NO_x, or PM_{2.5} or 82 pounds per day of PM₁₀. Quantified emissions and identified reduction measures shall be submitted to the City (and the Air District if specifically requested) for review and approval prior to the issuance of building permits and the approved criteria air pollutant reduction measures shall be implemented during construction.</p> <p>h. Construction Emissions Minimization Plan</p> <p>The project applicant shall prepare a Construction Emissions Minimization Plan (Emissions Plan) for all identified criteria air pollutant reduction measures. The Emissions Plan shall be submitted to the City (and the Air District if specifically requested) for review and approval prior to the issuance of building permits. The Emissions Plan shall include the following:</p> <p>i. An equipment inventory summarizing the type of off-road equipment required for each phase of construction, including the equipment manufacturer, equipment identification number, engine model year, engine certification (tier rating), horsepower, and engine serial number. For all Verified Diesel Emissions Control Strategies (VDECS), the equipment inventory shall also include the technology type, serial number, make, model, manufacturer, CARB verification number level, and installation date.</p> <p>ii. A Certification Statement that the Contractor agrees to comply fully with the Emissions Plan and acknowledges that a significant violation of the Emissions Plan shall constitute a material breach of contract.</p> | <p>Prior to issuance of a construction related permit</p> | <p>Bureau of Planning</p> | <p>Bureau of Building</p> |
| <p>SCA-AIR-3: Diesel Particulate Matter Controls-Construction Related (#23)</p> <p>a. <i>Diesel Particulate Matter Reduction Measures</i></p> <p>The project applicant shall implement appropriate measures during construction to reduce potential health risks to sensitive receptors due to exposure to diesel particulate matter (DPM) from construction emissions. The project applicant shall choose one of the following methods:</p> <p>i. The project applicant shall retain a qualified air quality consultant to prepare a Health Risk Assessment (HRA) in accordance with current guidance from the California Air Resources Board (CARB) and Office of Environmental Health and Hazard Assessment to determine the health risk to sensitive receptors exposed to</p> | <p>Prior to issuance of a construction related permit (i), during construction (ii)</p> | <p>Bureau of Planning</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---|---------------------------|---------------------------|
| <p>DPM from project construction emissions. The HRA shall be submitted to the City (and the Air District if specifically requested) for review and approval. If the HRA concludes that the health risk is at or below acceptable levels, then DPM reduction measures are not required. If the HRA concludes that the health risk exceeds acceptable levels, DPM reduction measures shall be identified to reduce the health risk to acceptable levels as set forth under subsection b below. Identified DPM reduction measures shall be submitted to the City for review and approval prior to the issuance of building permits and the approved DPM reduction measures shall be implemented during construction.</p> <p>-or-</p> <p>ii. All off-road diesel equipment shall be equipped with the most effective Verified Diesel Emission Control Strategies (VDECS) available for the engine type (Tier 4 engines automatically meet this requirement) as certified by CARB. The equipment shall be properly maintained and tuned in accordance with manufacturer specifications. This shall be verified through an equipment inventory submittal and Certification Statement that the Contractor agrees to compliance and acknowledges that a significant violation of this requirement shall constitute a material breach of contract.</p> | | | |
| <p>b. <i>Construction Emissions Minimization Plan (if required by a above)</i></p> <p>The project applicant shall prepare a Construction Emissions Minimization Plan (Emissions Plan) for all identified DPM reduction measures (if any). The Emissions Plan shall be submitted to the City (and the Bay Area Air Quality District if specifically requested) for review and approval prior to the issuance of building permits. The Emissions Plan shall include the following:</p> <p>i. An equipment inventory summarizing the type of off-road equipment required for each phase of construction, including the equipment manufacturer, equipment identification number, engine model year, engine certification (tier rating), horsepower, and engine serial number. For all VDECS, the equipment inventory shall also include the technology type, serial number, make, model, manufacturer, CARB verification number level, and installation date.</p> <p>ii. A Certification Statement that the Contractor agrees to comply fully with the Emissions Plan and acknowledges that a significant violation of the Emissions Plan shall constitute a material breach of contract.</p> | <p>Prior to issuance of a construction related permit</p> | <p>Bureau of Planning</p> | <p>Bureau of Building</p> |
| <p>SCA-AIR-4: Exposure to Air Pollution (Toxic Air Contaminants) (#24)</p> <p>a. <i>Health Risk Reduction Measures</i></p> <p>The project applicant shall incorporate appropriate measures into the project design</p> | <p>Prior to approval of construction-related permit</p> | <p>Bureau of Planning</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---------------------------------|---------------|------------------|---------------------------|
|---------------------------------|---------------|------------------|---------------------------|

in order to reduce the potential health risk due to exposure to toxic air contaminants. The project applicant shall choose one of the following methods:

i. The project applicant shall retain a qualified air quality consultant to prepare a Health Risk Assessment (HRA) in accordance with California Air Resources Board (CARB) and Office of Environmental Health and Hazard Assessment requirements to determine the health risk of exposure of project residents/occupants/users to air pollutants. The HRA shall be submitted to the City for review and approval. If the HRA concludes that the health risk is at or below acceptable levels, then health risk reduction measures are not required. If the HRA concludes that the health risk exceeds acceptable levels, health risk reduction measures shall be identified to reduce the health risk to acceptable levels. Identified risk reduction measures shall be submitted to the City for review and approval and be included on the project drawings submitted for the construction-related permit or on other documentation submitted to the City.

- or -

ii. The project applicant shall incorporate the following health risk reduction measures into the project. These features shall be submitted to the City for review and approval and be included on the project drawings submitted for the construction-related permit or on other documentation submitted to the City:

- Installation of air filtration to reduce cancer risks and Particulate Matter (PM) exposure for residents and other sensitive populations in the project that are in close proximity to sources of air pollution. Air filter devices shall be rated MERV-13 [insert MERV-16 for projects located in the West Oakland Specific Plan area] or higher. As part of implementing this measure, an ongoing maintenance plan for the building’s HVAC air filtration system shall be required.
- Where appropriate, install passive electrostatic filtering systems, especially those with low air velocities (i.e., 1 mph).
- Phasing of residential developments when proposed within 500 feet of freeways such that homes nearest the freeway are built last, if feasible.
- The project shall be designed to locate sensitive receptors as far away as feasible from the source(s) of air pollution. Operable windows, balconies, and building air intakes shall be located as far away from these sources as feasible. If near a distribution center, residents shall be located as far away as feasible from a loading dock or where trucks concentrate to deliver goods.
- Sensitive receptors shall be located on the upper floors of buildings, if feasible.

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|--|--------------------|---------------------------|
| <ul style="list-style-type: none"> • Planting trees and/or vegetation between sensitive receptors and pollution source, if feasible. Trees that are best suited to trapping PM shall be planted, including one or more of the following: Pine (<i>Pinus nigra</i> var. <i>maritima</i>), Cypress (<i>X Cupressocyparis leylandii</i>), Hybrid poplar (<i>Populus deltoids X trichocarpa</i>), and Redwood (<i>Sequoia sempervirens</i>). • Sensitive receptors shall be located as far away from truck activity areas, such as loading docks and delivery areas, as feasible. • Existing and new diesel generators shall meet CARB’s Tier 4 emission standards, if feasible. • Emissions from diesel trucks shall be reduced through implementing the following measures, if feasible: <ul style="list-style-type: none"> o Installing electrical hook-ups for diesel trucks at loading docks. o Requiring trucks to use Transportation Refrigeration Units (TRU) that meet Tier 4 emission standards. o Requiring truck-intensive projects to use advanced exhaust technology (e.g., hybrid) or alternative fuels. o Prohibiting trucks from idling for more than two minutes. o Establishing truck routes to avoid sensitive receptors in the project. A truck route program, along with truck calming, parking, and delivery restrictions, shall be implemented. | | | |
| <p><i>b. Maintenance of Health Risk Reduction Measures</i></p> <p>The project applicant shall maintain, repair, and/or replace installed health risk reduction measures, including but not limited to the HVAC system (if applicable), on an ongoing and as-needed basis. Prior to occupancy, the project applicant shall prepare and then distribute to the building manager/operator an operation and maintenance manual for the HVAC system and filter including the maintenance and replacement schedule for the filter.</p> | Ongoing | N/A | Bureau of Building |
| <p>SCA-AIR-4: Stationary Sources of Air Pollution (Toxic Air Contaminants) (#25)</p> <p>The project applicant shall incorporate appropriate measures into the project design in order to reduce the potential health risk due to on-site stationary sources of toxic air contaminants. The project applicant shall choose one of the following methods:</p> <p>a. The project applicant shall retain a qualified air quality consultant to prepare a Health Risk Assessment (HRA) in accordance with California Air Resources Board (CARB) and Office of Environmental Health and Hazard Assessment requirements to determine the health risk associated with proposed stationary sources of pollution in the project. The HRA shall be submitted to the City for review and approval. If the</p> | Prior to approval of construction-related permit | Bureau of Planning | Bureau of Building |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---------------|------------------|---------------------------|
| <p>HRA concludes that the health risk is at or below acceptable levels, then health risk reduction measures are not required. If the HRA concludes the health risk exceeds acceptable levels, health risk reduction measures shall be identified to reduce the health risk to acceptable levels. Identified risk reduction measures shall be submitted to the City for review and approval and be included on the project drawings submitted for the construction-related permit or on other documentation submitted to the City.</p> <p>- or -</p> <p>b. The project applicant shall incorporate the following health risk reduction measures into the project. These features shall be submitted to the City for review and approval and be included on the project drawings submitted for the construction-related permit or on other documentation submitted to the City:</p> <ul style="list-style-type: none"> i. Installation of non-diesel fueled generators, if feasible, or; ii. Installation of diesel generators with an EPA-certified Tier 4 engine or engines that are retrofitted with a CARB Level 3 Verified Diesel Emissions Control Strategy, if feasible. | | | |

BIOLOGICAL RESOURCES

| | | | |
|--|----------------------------------|---------------------------|---------------------------|
| <p>SCA-BIO-1: Tree Removal During Bird Breeding Season (#30)</p> <p>To the extent feasible, removal of any tree and/or other vegetation suitable for nesting of birds shall not occur during the bird breeding season of February 1 to August 15 (or during December 15 to August 15 for trees located in or near marsh, wetland, or aquatic habitats). If tree removal must occur during the bird breeding season, all trees to be removed shall be surveyed by a qualified biologist to verify the presence or absence of nesting raptors or other birds. Pre-removal surveys shall be conducted within 15 days prior to the start of work and shall be submitted to the City for review and approval. If the survey indicates the potential presence of nesting raptors or other birds, the biologist shall determine an appropriately sized buffer around the nest in which no work will be allowed until the young have successfully fledged. The size of the nest buffer will be determined by the biologist in consultation with the California Department of Fish and Wildlife, and will be based to a large extent on the nesting species and its sensitivity to disturbance. In general, buffer sizes of 200 feet for raptors and 50 feet for other birds should suffice to prevent disturbance to birds nesting in the urban environment, but these buffers may be increased or decreased, as appropriate, depending on the bird species and the level of disturbance anticipated near the nest.</p> | <p>Prior to removal of trees</p> | <p>Bureau of Building</p> | <p>Bureau of Building</p> |
|--|----------------------------------|---------------------------|---------------------------|

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|--|---|---------------------------|
| SCA-BIO-2: Tree Permit (#31) | | | |
| <p>a. <i>Tree Permit Required</i></p> <p>Pursuant to the City's Tree Protection Ordinance (OMC chapter 12.36), the project applicant shall obtain a tree permit and abide by the conditions of that permit.</p> | Prior to approval of construction-related permit | Permit approval by Public Works Department, Tree Division; evidence of approval submitted to Bureau of Building | Bureau of Building |
| <p>b. <i>Tree Protection During Construction</i></p> <p>Adequate protection shall be provided during the construction period for any trees which are to remain standing, including the following, plus any recommendations of an arborist:</p> | During construction | Public Works Department, Tree Division | Bureau of Building |
| <p>i. Before the start of any clearing, excavation, construction, or other work on the site, every protected tree deemed to be potentially endangered by said site work shall be securely fenced off at a distance from the base of the tree to be determined by the project's consulting arborist. Such fences shall remain in place for duration of all such work. All trees to be removed shall be clearly marked. A scheme shall be established for the removal and disposal of logs, brush, earth and other debris which will avoid injury to any protected tree.</p> | | | |
| <p>ii. Where proposed development or other site work is to encroach upon the protected perimeter of any protected tree, special measures shall be incorporated to allow the roots to breathe and obtain water and nutrients. Any excavation, cutting, filling, or compaction of the existing ground surface within the protected perimeter shall be minimized. No change in existing ground level shall occur within a distance to be determined by the project's consulting arborist from the base of any protected tree at any time. No burning or use of equipment with an open flame shall occur near or within the protected perimeter of any protected tree.</p> | | | |
| <p>iii. No storage or dumping of oil, gas, chemicals, or other substances that may be harmful to trees shall occur within the distance to be determined by the project's consulting arborist from the base of any protected trees, or any other location on the site from which such substances might enter the protected perimeter. No heavy construction equipment or construction materials shall be operated or stored within a distance from the base of any protected trees to be determined by the project's consulting arborist. Wires, ropes, or other devices shall not be</p> | | | |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|---------------------------------------|---|---------------------------|
| <p>attached to any protected tree, except as needed for support of the tree. No sign, other than a tag showing the botanical classification, shall be attached to any protected tree.</p> <p>iv. Periodically during construction, the leaves of protected trees shall be thoroughly sprayed with water to prevent buildup of dust and other pollution that would inhibit leaf transpiration.</p> <p>v. If any damage to a protected tree should occur during or as a result of work on the site, the project applicant shall immediately notify the Public Works Department and the project's consulting arborist shall make a recommendation to the City Tree Reviewer as to whether the damaged tree can be preserved. If, in the professional opinion of the Tree Reviewer, such tree cannot be preserved in a healthy state, the Tree Reviewer shall require replacement of any tree removed with another tree or trees on the same site deemed adequate by the Tree Reviewer to compensate for the loss of the tree that is removed.</p> <p>vi. All debris created as a result of any tree removal work shall be removed by the project applicant from the property within two weeks of debris creation, and such debris shall be properly disposed of by the project applicant in accordance with all applicable laws, ordinances, and regulations.</p> | | | |
| <p>c. <i>Tree Replacement Plantings</i></p> <p>Replacement plantings shall be required for tree removals for the purposes of erosion control, groundwater replenishment, visual screening, wildlife habitat, and preventing excessive loss of shade, in accordance with the following criteria:</p> <p>i. No tree replacement shall be required for the removal of nonnative species, for the removal of trees which is required for the benefit of remaining trees, or where insufficient planting area exists for a mature tree of the species being considered.</p> <p>ii. Replacement tree species shall consist of <i>Sequoia sempervirens</i> (Coast Redwood), <i>Quercus agrifolia</i> (Coast Live Oak), <i>Arbutus menziesii</i> (Madrone), <i>Aesculus californica</i> (California Buckeye), <i>Umbellularia californica</i> (California Bay Laurel), or other tree species acceptable to the Tree Division.</p> <p>iii. Replacement trees shall be at least twenty-four (24) inch box size, unless a smaller size is recommended by the arborist, except that three fifteen (15) gallon size trees may be substituted for each twenty-four (24) inch box size tree where appropriate.</p> <p>iv. Minimum planting areas must be available on site as follows:</p> <ul style="list-style-type: none"> • For <i>Sequoia sempervirens</i>, three hundred fifteen (315) square feet per tree; | <p>Prior to building permit final</p> | <p>Public Works Department, Tree Division</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---------------|------------------|---------------------------|
| <ul style="list-style-type: none"> • For other species listed, seven hundred (700) square feet per tree. v. In the event that replacement trees are required but cannot be planted due to site constraints, an in lieu fee in accordance with the City’s Master Fee Schedule may be substituted for required replacement plantings, with all such revenues applied toward tree planting in city parks, streets and medians. vi. The project applicant shall install the plantings and maintain the plantings until established. The Tree Reviewer of the Tree Division of the Public Works Department may require a landscape plan showing the replacement plantings and the method of irrigation. Any replacement plantings which fail to become established within one year of planting shall be replanted at the project applicant’s expense. | | | |

CULTURAL RESOURCES

| | | | |
|--|----------------------------|------------|---------------------------|
| <p>SCA-CUL-1: Archaeological and Paleontological Resources – Discovery During Construction (#33)</p> <p>Pursuant to CEQA Guidelines section 15064.5(f), in the event that any historic or prehistoric subsurface cultural resources are discovered during ground disturbing activities, all work within 50 feet of the resources shall be halted and the project applicant shall notify the City and consult with a qualified archaeologist or paleontologist, as applicable, to assess the significance of the find. In the case of discovery of paleontological resources, the assessment shall be done in accordance with the Society of Vertebrate Paleontology standards. If any find is determined to be significant, appropriate avoidance measures recommended by the consultant and approved by the City must be followed unless avoidance is determined unnecessary or infeasible by the City. Feasibility of avoidance shall be determined with consideration of factors such as the nature of the find, project design, costs, and other considerations. If avoidance is unnecessary or infeasible, other appropriate measures (e.g., data recovery, excavation) shall be instituted. Work may proceed on other parts of the project site while measures for the cultural resources are implemented.</p> <p>In the event of data recovery of archaeological resources, the project applicant shall submit an Archaeological Research Design and Treatment Plan (ARDTP) prepared by a qualified archaeologist for review and approval by the City. The ARDTP is required to identify how the proposed data recovery program would preserve the significant information the archaeological resource is expected to contain. The ARDTP shall identify the scientific/historic research questions applicable to the expected resource, the data classes the resource is expected to possess, and how the expected data classes would address the applicable research questions. The ARDTP shall include the analysis and specify the curation and storage methods. Data recovery, in general, shall be limited to</p> | <p>During construction</p> | <p>N/A</p> | <p>Bureau of Building</p> |
|--|----------------------------|------------|---------------------------|

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|--|---|---------------------------|
| <p>the portions of the archaeological resource that could be impacted by the proposed project. Destructive data recovery methods shall not be applied to portions of the archaeological resources if nondestructive methods are practicable. Because the intent of the ARDTP is to save as much of the archaeological resource as possible, including moving the resource, if feasible, preparation and implementation of the ARDTP would reduce the potential adverse impact to less than significant. The project applicant shall implement the ARDTP at his/her expense.</p> <p>In the event of excavation of paleontological resources, the project applicant shall submit an excavation plan prepared by a qualified paleontologist to the City for review and approval. All significant cultural materials recovered shall be subject to scientific analysis, professional museum curation, and/or a report prepared by a qualified paleontologist, as appropriate, according to current professional standards and at the expense of the project applicant.</p> | | | |
| <p>SCA-CUL-2: Archaeologically Sensitive Areas – Pre-Construction Measures (#34)</p> <p>The project applicant shall implement either Provision A (Intensive Pre-Construction Study) or Provision B (Construction ALERT Sheet) concerning archaeological resources.</p> <p><i>Provision A: Intensive Pre-Construction Study.</i></p> <p>The project applicant shall retain a qualified archaeologist to conduct a site-specific, intensive archaeological resources study for review and approval by the City prior to soil-disturbing activities occurring on the project site. The purpose of the site-specific, intensive archaeological resources study is to identify early the potential presence of history-period archaeological resources on the project site. At a minimum, the study shall include:</p> <ol style="list-style-type: none"> a. Subsurface presence/absence studies of the project site. Field studies may include, but are not limited to, auguring and other common methods used to identify the presence of archaeological resources. b. A report disseminating the results of this research. c. Recommendations for any additional measures that could be necessary to mitigate any adverse impacts to recorded and/or inadvertently discovered cultural resources. <p>If the results of the study indicate a high potential presence of historic-period archaeological resources on the project site, or a potential resource is discovered, the project applicant shall hire a qualified archaeologist to monitor any ground disturbing activities on the project site during construction and prepare an ALERT sheet pursuant to Provision B below that details what could potentially be found at the project site. Archaeological monitoring would include briefing construction personnel about the type of artifacts that may be present (as referenced in the ALERT sheet, required per Provision</p> | <p>Prior to approval of construction-related permit; during construction</p> | <p>Bureau of Building; Bureau of Planning</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|----------------------------|------------------|---------------------------|
| <p>B below) and the procedures to follow if any artifacts are encountered, field recording and sampling in accordance with the Secretary of Interior’s Standards and Guidelines for Archaeological Documentation, notifying the appropriate officials if human remains or cultural resources are discovered, and preparing a report to document negative findings after construction is completed if no archaeological resources are discovered during construction.</p> <p><i>Provision B: Construction ALERT Sheet.</i></p> <p>The project applicant shall prepare a construction “ALERT” sheet developed by a qualified archaeologist for review and approval by the City prior to soil-disturbing activities occurring on the project site. The ALERT sheet shall contain, at a minimum, visuals that depict each type of artifact that could be encountered on the project site. Training by the qualified archaeologist shall be provided to the project’s prime contractor, any project subcontractor firms (including demolition, excavation, grading, foundation, and pile driving), and utility firms involved in soil-disturbing activities within the project site.</p> <p>The ALERT sheet shall state, in addition to the basic archaeological resource protection measures contained in other standard conditions of approval, all work must stop and the City’s Environmental Review Officer contacted in the event of discovery of the following cultural materials: concentrations of shellfish remains; evidence of fire (ashes, charcoal, burnt earth, fire-cracked rocks); concentrations of bones; recognizable Native American artifacts (arrowheads, shell beads, stone mortars [bowls], humanly shaped rock); building foundation remains; trash pits, privies (outhouse holes); floor remains; wells; concentrations of bottles, broken dishes, shoes, buttons, cut animal bones, hardware, household items, barrels, etc.; thick layers of burned building debris (charcoal, nails, fused glass, burned plaster, burned dishes); wood structural remains (building, ship, wharf); clay roof/floor tiles; stone walls or footings; or gravestones. Prior to any soil-disturbing activities, each contractor shall be responsible for ensuring that the ALERT sheet is circulated to all field personnel, including machine operators, field crew, pile drivers, and supervisory personnel. The ALERT sheet shall also be posted in a visible location at the project site.</p> | | | |
| <p>SCA-CUL-3: Human Remains – Discovery during Construction (#35)</p> <p>Pursuant to CEQA Guidelines section 15064.5(e)(1), in the event that human skeletal remains are uncovered at the project site during construction activities, all work shall immediately halt and the project applicant shall notify the City and the Alameda County Coroner. If the County Coroner determines that an investigation of the cause of death is required or that the remains are Native American, all work shall cease within 50 feet of</p> | <p>During Construction</p> | <p>N/A</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---|--------------------|---------------------------|
| <p>the remains until appropriate arrangements are made. In the event that the remains are Native American, the City shall contact the California Native American Heritage Commission (NAHC), pursuant to subdivision (c) of section 7050.5 of the California Health and Safety Code. If the agencies determine that avoidance is not feasible, then an alternative plan shall be prepared with specific steps and timeframe required to resume construction activities. Monitoring, data recovery, determination of significance, and avoidance measures (if applicable) shall be completed expeditiously and at the expense of the project applicant.</p> | | | |
| GEOLOGY AND SOILS | | | |
| <p>SCA-GEO-1: Construction-Related Permit(s) (#37) The project applicant shall obtain all required construction-related permits/approvals from the City. The project shall comply with all standards, requirements and conditions contained in construction-related codes, including but not limited to the Oakland Building Code and the Oakland Grading Regulations, to ensure structural integrity and safe construction.</p> | Prior to approval of construction-related permit | Bureau of Building | Bureau of Building |
| <p>SCA-GEO-2: Soils Report (#38) The project applicant shall submit a soils report prepared by a registered geotechnical engineer for City review and approval. The soils report shall contain, at a minimum, field test results and observations regarding the nature, distribution and strength of existing soils, and recommendations for appropriate grading practices and project design. The project applicant shall implement the recommendations contained in the approved report during project design and construction.</p> | Prior to approval of construction-related permit | Bureau of Building | Bureau of Building |
| <p>SCA-GEO-3: Seismic Hazards Zone (Landslide/Liquefaction) (#40) The project applicant shall submit a site-specific geotechnical report, consistent with California Geological Survey Special Publication 117 (as amended), prepared by a registered geotechnical engineer for City review and approval containing at a minimum a description of the geological and geotechnical conditions at the site, an evaluation of site-specific seismic hazards based on geological and geotechnical conditions, and recommended measures to reduce potential impacts related to liquefaction and/or slope stability hazards. The project applicant shall implement the recommendations contained in the approved report during project design and construction.</p> | Prior to approval of construction-related permit | Bureau of Building | Bureau of Building |
| GREENHOUSE GAS EMISSIONS | | | |
| <p>SCA-GHG-1: Greenhouse Gas (GHG) Reduction Plan (#42) a. Greenhouse Gas (GHG) Reduction Plan Required The project applicant shall retain a qualified air quality consultant to develop a</p> | Prior to approval of construction-related permit. | Bureau of Planning | N/A |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---------------|------------------|---------------------------|
| <p>Greenhouse Gas (GHG) Reduction Plan for City review and approval and shall implement the approved GHG Reduction Plan.</p> <p>The goal of the GHG Reduction Plan shall be to increase energy efficiency and reduce GHG emissions to below at least one of the Bay Area Quality Management District's (BAAQMD's) CEQA Thresholds of Significance (1,100 metric tons of CO₂e per year or 4.6 metric tons of CO₂e per year per service population) AND to reduce GHG emissions by 36 percent below the project's 2005 "business-as-usual" baseline GHG emissions(as explained below) to help implement the City's Energy and Climate Action Plan (adopted in 2012) which calls for reducing GHG emissions by 36 percent below 2005 levels. The GHG Reduction Plan shall include, at a minimum, (a) a detailed GHG emissions inventory for the project under a "business-as-usual" scenario with no consideration of project design features, or other energy efficiencies, (b) an "adjusted" baseline GHG emissions inventory for the project, taking into consideration energy efficiencies included as part of the project (including the City's Standard Conditions of Approval, proposed mitigation measures, project design features, and other City requirements), and additional GHG reduction measures available to further reduce GHG emissions, and (c) requirements for ongoing monitoring and reporting to demonstrate that the additional GHG reduction measures are being implemented. If the project is to be constructed in phases, the GHG Reduction Plan shall provide GHG emission scenarios by phase. Potential GHG reduction measures to be considered include, but are not be limited to, measures recommended in BAAQMD's latest CEQA Air Quality Guidelines, the California Air Resources Board Scoping Plan (December 2008, as may be revised), the California Air Pollution Control Officers Association (CAPCOA) Quantifying Greenhouse Gas Mitigation Measures (August 2010, as may be revised), the California Attorney General's website, and Reference Guides on Leadership in Energy and Environmental Design (LEED) published by the U.S. Green Building Council.</p> <p>The types of allowable GHG reduction measures include the following (listed in order of City preference): (1) physical design features; (2) operational features; and (3) the payment of fees to fund GHG-reducing programs (i.e., the purchase of "carbon credits") as explained below.</p> <p>The allowable locations of the GHG reduction measures include the following (listed in order of City preference): (1) the project site; (2) off-site within the City of Oakland; (3) off-site within the San Francisco Bay Area Air Basin; (4) off-site within the State of California; then (5) elsewhere in the United States.</p> <p>As with preferred locations for the implementation of all GHG reductions measures,</p> | | | |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|---------------------|--------------------|---------------------------|
| <p>the preference for carbon credit purchases include those that can be achieved as follows (listed in order of City preference): (1) within the City of Oakland; (2) within the San Francisco Bay Area Air Basin; (3) within the State of California; then (4) elsewhere in the United States. The cost of carbon credit purchases shall be based on current market value at the time purchased and shall be based on the project's operational emissions estimated in the GHG Reduction Plan or subsequent approved emissions inventory, which may result in emissions that are higher or lower than those estimated in the GHG Reduction Plan.</p> <p>For physical GHG reduction measures to be incorporated into the design of the project, the measures shall be included on the drawings submitted for construction-related permits.</p> | | | |
| <p>b. GHG Reduction Plan Implementation During Construction</p> <p>The project applicant shall implement the GHG Reduction Plan during construction of the project. For physical GHG reduction measures to be incorporated into the design of the project, the measures shall be implemented during construction. For physical GHG reduction measures to be incorporated into off-site projects, the project applicant shall obtain all necessary permits/approvals and the measures shall be included on drawings and submitted to the City Planning Director or his/her designee for review and approval. These off-site improvements shall be installed prior to completion of the subject project (or prior to completion of the project phase for phased projects). For GHG reduction measures involving the purchase of carbon credits, evidence of the payment/purchase shall be submitted to the City for review and approval prior to completion of the project (or prior to completion of the project phase, for phased projects).</p> | During construction | Bureau of Planning | Bureau of Building |
| <p>c. GHG Reduction Plan Implementation After Construction</p> <p>The project applicant shall implement the GHG Reduction Plan after construction of the project (or at the completion of the project phase for phased projects). For operational GHG reduction measures to be incorporated into the project or off-site projects, the measures shall be implemented on an indefinite and ongoing basis.</p> <p>The project applicant shall satisfy the following requirements for ongoing monitoring and reporting to demonstrate that the additional GHG reduction measures are being implemented. The GHG Reduction Plan requires regular periodic evaluation over the life of the project (generally estimated to be at least 40 years) to determine how the Plan is achieving required GHG emissions reductions over time, as well as the efficacy of the specific additional GHG reduction measures identified in the Plan. Annual Report. Implementation of the GHG reduction measures and related requirements shall be ensured through compliance with Conditions of Approval</p> | Ongoing | Bureau of Planning | Bureau of Planning |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|----------------------|-------------------------|-----------------------------------|
| <p>adopted for the project. Generally, starting two years after the City issues the first Certificate of Occupancy for the project, the project applicant shall prepare each year of the useful life of the project an Annual GHG Emissions Reduction Report (“Annual Report”), for review and approval by the City Planning Director or his/her designee. The Annual Report shall be submitted to an independent reviewer of the City’s choosing, to be paid for by the project applicant.</p> <p>The Annual Report shall summarize the project’s implementation of GHG reduction measures over the preceding year, intended upcoming changes, compliance with the conditions of the Plan, and include a brief summary of the previous year’s Annual Report results (starting the second year). The Annual Report shall include a comparison of annual project emissions to the baseline emissions reported in the GHG Plan.</p> <p>The GHG Reduction Plan shall be considered fully attained when project emissions are less than either applicable numeric BAAQMD CEQA Thresholds AND GHG emissions are 36 percent below the project’s 2005 “business-as-usual” baseline GHG emissions, as confirmed by the City through an established monitoring program. Monitoring and reporting activities will continue at the City’s discretion, as discussed below.</p> <p>Corrective Procedure. If the third Annual Report, or any report thereafter, indicates that, in spite of the implementation of the GHG Reduction Plan, the project is not achieving the GHG reduction goal, the project applicant shall prepare a report for City review and approval, which proposes additional or revised GHG measures to better achieve the GHG emissions reduction goals, including without limitation, a discussion on the feasibility and effectiveness of the menu of other additional measures (“Corrective GHG Action Plan”). The project applicant shall then implement the approved Corrective GHG Action Plan.</p> <p>If, one year after the Corrective GHG Action Plan is implemented, the required GHG emissions reduction target is still not being achieved, or if the project applicant fails to submit a report at the times described above, or if the reports do not meet City requirements outlined above, the City may, in addition to its other remedies, (a) assess the project applicant a financial penalty based upon actual percentage reduction in GHG emissions as compared to the percent reduction in GHG emissions established in the GHG Reduction Plan; or (b) refer the matter to the City Planning Commission for scheduling of a compliance hearing to determine whether the project’s approvals should be revoked, altered or additional conditions of approval imposed.</p> <p>The penalty as described in (a) above shall be determined by the City Planning</p> | | | |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|----------------------|-------------------------|-----------------------------------|
| <p>Director or his/her designee and be commensurate with the percentage GHG emissions reduction not achieved (compared to the applicable numeric significance thresholds) or required percentage reduction from the “adjusted” baseline.</p> <p>In determining whether a financial penalty or other remedy is appropriate, the City shall not impose a penalty if the project applicant has made a good faith effort to comply with the GHG Reduction Plan.</p> <p>The City would only have the ability to impose a monetary penalty after a reasonable cure period and in accordance with the enforcement process outlined in Planning Code Chapter 17.152. If a financial penalty is imposed, such penalty sums shall be used by the City solely toward the implementation of the GHG Reduction Plan.</p> <p>Timeline Discretion and Summary. The City shall have the discretion to reasonably modify the timing of reporting, with reasonable notice and opportunity to comment by the applicant, to coincide with other related monitoring and reporting required for the project.</p> | | | |

HAZARDS AND HAZARDOUS MATERIALS

| | | | |
|---|----------------------------|------------|---------------------------|
| <p>SCA-HAZ-1: Hazardous Materials Related to Construction (#43)</p> <p>The project applicant shall ensure that Best Management Practices (BMPs) are implemented by the contractor during construction to minimize potential negative effects on groundwater, soils, and human health. These shall include, at a minimum, the following:</p> <ol style="list-style-type: none"> a. Follow manufacture’s recommendations for use, storage, and disposal of chemical products used in construction; b. Avoid overtopping construction equipment fuel gas tanks; c. During routine maintenance of construction equipment, properly contain and remove grease and oils; d. Properly dispose of discarded containers of fuels and other chemicals; e. Implement lead-safe work practices and comply with all local, regional, state, and federal requirements concerning lead (for more information refer to the Alameda County Lead Poisoning Prevention Program); and f. If soil, groundwater, or other environmental medium with suspected contamination is encountered unexpectedly during construction activities (e.g., identified by odor or visual staining, or if any underground storage tanks, abandoned drums or other hazardous materials or wastes are encountered), the project applicant shall cease work in the vicinity of the suspect material, the area shall be secured as necessary, and the applicant shall take all appropriate measures to protect human health and | <p>During construction</p> | <p>N/A</p> | <p>Bureau of Building</p> |
|---|----------------------------|------------|---------------------------|

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|--|---|---|
| <p>the environment. Appropriate measures shall include notifying the City and applicable regulatory agency(ies) and implementation of the actions described in the City's Standard Conditions of Approval, as necessary, to identify the nature and extent of contamination. Work shall not resume in the area(s) affected until the measures have been implemented under the oversight of the City or regulatory agency, as appropriate.</p> | | | |
| <p>SCA-HAZ-2: Hazardous Building Materials and Site Contamination (#44)</p> | | | |
| <p>a. <i>Hazardous Building Materials Assessment</i> The project applicant shall submit a comprehensive assessment report to the Bureau of Building, signed by a qualified environmental professional, documenting the presence or lack thereof of asbestos-containing materials (ACMs), lead-based paint, polychlorinated biphenyls (PCBs), and any other building materials or stored materials classified as hazardous materials by State or federal law. If lead-based paint, ACMs, PCBs, or any other building materials or stored materials classified as hazardous materials are present, the project applicant shall submit specifications prepared and signed by a qualified environmental professional, for the stabilization and/or removal of the identified hazardous materials in accordance with all applicable laws and regulations. The project applicant shall implement the approved recommendations and submit to the City evidence of approval for any proposed remedial action and required clearances by the applicable local, state, or federal regulatory agency.</p> | <p>Prior to approval of demolition, grading, or building permits</p> | <p>Bureau of Building</p> | <p>Bureau of Building</p> |
| <p>b. <i>Environmental Site Assessment Required</i> The project applicant shall submit a Phase I Environmental Site Assessment report, and Phase II Environmental Site Assessment report if warranted by the Phase I report, for the project site for review and approval by the City. The report(s) shall be prepared by a qualified environmental assessment professional and include recommendations for remedial action, as appropriate, for hazardous materials. The project applicant shall implement the approved recommendations and submit to the City evidence of approval for any proposed remedial action and required clearances by the applicable local, state, or federal regulatory agency.</p> | <p>Prior to approval of construction-related permit</p> | <p>Applicable regulatory agency with jurisdiction</p> | <p>Applicable regulatory agency with jurisdiction</p> |
| <p>c. <i>Health and Safety Plan Required</i> The project applicant shall submit a Health and Safety Plan for the review and approval by the City in order to protect project construction workers from risks associated with hazardous materials. The project applicant shall implement the approved Plan.</p> | <p>Prior to approval of construction-related permit</p> | <p>Bureau of Building</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---|-------------------------|---------------------------|
| <p>d. <i>Best Management Practices (BMPs) Required for Contaminated Sites</i> The project applicant shall ensure that Best Management Practices (BMPs) are implemented by the contractor during construction to minimize potential soil and groundwater hazards. These shall include the following:</p> <ul style="list-style-type: none"> i. Soil generated by construction activities shall be stockpiled on-site in a secure and safe manner. All contaminated soils determined to be hazardous or non-hazardous waste must be adequately profiled (sampled) prior to acceptable reuse or disposal at an appropriate off-site facility. Specific sampling and handling and transport procedures for reuse or disposal shall be in accordance with applicable local, state, and federal requirements. ii. Groundwater pumped from the subsurface shall be contained on-site in a secure and safe manner, prior to treatment and disposal, to ensure environmental and health issues are resolved pursuant to applicable laws and policies. Engineering controls shall be utilized, which include impermeable barriers to prohibit groundwater and vapor intrusion into the building. | Prior to approval of demolition, grading, or building permits | Bureau of Building | Bureau of Building |
| <p>SCA-HAZ-2: Fire Safety Phasing Plan (#46) The project applicant shall submit a Fire Safety Phasing Plan for City review and approval, and shall implement the approved Plan. The Fire Safety Phasing Plan shall include all of the fire safety features incorporated into each phase of the project and the schedule for implementation of the features.</p> | Prior to approval of construction-related permit | Oakland Fire Department | Bureau of Building |
| HYDROLOGY AND WATER QUALITY | | | |
| <p>SCA-HYDRO-1: Erosion and Sedimentation Control Plan for Construction (#49) a. <i>Erosion and Sedimentation Control Plan Required</i> The project applicant shall submit an Erosion and Sedimentation Control Plan to the City for review and approval. The Erosion and Sedimentation Control Plan shall include all necessary measures to be taken to prevent excessive stormwater runoff or carrying by stormwater runoff of solid materials on to lands of adjacent property owners, public streets, or to creeks as a result of conditions created by grading and/or construction operations. The Plan shall include, but not be limited to, such measures as short-term erosion control planting, waterproof slope covering, check dams, interceptor ditches, benches, storm drains, dissipation structures, diversion dikes, retarding berms and barriers, devices to trap, store and filter out sediment, and stormwater retention basins. Off-site work by the project applicant may be necessary. The project applicant shall obtain permission or easements necessary for off-site work. There shall be a clear notation that the plan is subject to changes as changing conditions occur. Calculations of anticipated stormwater runoff and</p> | Prior to approval of construction-related permit | Bureau of Building | N/A |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|--|---|-------------------------------------|
| <p>sediment volumes shall be included, if required by the City. The Plan shall specify that, after construction is complete, the project applicant shall ensure that the storm drain system shall be inspected and that the project applicant shall clear the system of any debris or sediment.</p> <p>b. <i>Erosion and Sedimentation Control During Construction</i> The project applicant shall implement the approved Erosion and Sedimentation Control Plan. No grading shall occur during the wet weather season (October 15 through April 15) unless specifically authorized in writing by the Bureau of Building.</p> | During construction | N/A | Bureau of Building |
| <p>SCA-HYDRO-2: State Construction General Permit (#50) The project applicant shall comply with the requirements of the Construction General Permit issued by the State Water Resources Control Board (SWRCB). The project applicant shall submit a Notice of Intent (NOI), Stormwater Pollution Prevention Plan (SWPPP), and other required Permit Registration Documents to SWRCB. The project applicant shall submit evidence of compliance with Permit requirements to the City.</p> | Prior to approval of construction-related permit | State Water Resources Control Board; evidence of compliance submitted to Bureau of Building | State Water Resources Control Board |
| <p>SCA-HYDRO-2: Site Design Measures to Reduce Stormwater Runoff (#52) Pursuant to Provision C.3 of the Municipal Regional Stormwater Permit issued under the National Pollutant Discharge Elimination System (NPDES), the project applicant is encouraged to incorporate appropriate site design measures into the project to reduce the amount of stormwater runoff. These measures may include, but are not limited to, the following:</p> <ol style="list-style-type: none"> Minimize impervious surfaces, especially directly connected impervious surfaces and surface parking areas; Utilize permeable paving in place of impervious paving where appropriate; Cluster structures; Direct roof runoff to vegetated areas; Preserve quality open space; and Establish vegetated buffer areas. | Ongoing | N/A | N/A |
| <p>SCA-HYDRO-3: NPDES C.3 Stormwater Requirements for Regulated Projects (#54) a. <i>Post-Construction Stormwater Management Plan Required</i> The project applicant shall comply with the requirements of Provision C.3 of the Municipal Regional Stormwater Permit issued under the National Pollutant Discharge Elimination System (NPDES). The project applicant shall submit a Post-Construction Stormwater Management Plan to the City for review and approval with</p> | Prior to approval of construction-related permit | Bureau of Planning; Bureau of Building | Bureau of Building |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---------------------------------------|---------------------------|---------------------------|
| <p>the project drawings submitted for site improvements, and shall implement the approved Plan during construction. The Post-Construction Stormwater Management Plan shall include and identify the following:</p> <ul style="list-style-type: none"> i. Location and size of new and replaced impervious surface; ii. Directional surface flow of stormwater runoff; iii. Location of proposed on-site storm drain lines; iv. Site design measures to reduce the amount of impervious surface area; v. Source control measures to limit stormwater pollution; vi. Stormwater treatment measures to remove pollutants from stormwater runoff, including the method used to hydraulically size the treatment measures; and vii. Hydromodification management measures, if required by Provision C.3, so that post-project stormwater runoff flow and duration match pre-project runoff. <p><i>b. Maintenance Agreement Required</i></p> <p>The project applicant shall enter into a maintenance agreement with the City, based on the Standard City of Oakland Stormwater Treatment Measures Maintenance Agreement, in accordance with Provision C.3, which provides, in part, for the following:</p> <ul style="list-style-type: none"> i. The project applicant accepting responsibility for the adequate installation/construction, operation, maintenance, inspection, and reporting of any on-site stormwater treatment measures being incorporated into the project until the responsibility is legally transferred to another entity; and ii. Legal access to the on-site stormwater treatment measures for representatives of the City, the local vector control district, and staff of the Regional Water Quality Control Board, San Francisco Region, for the purpose of verifying the implementation, operation, and maintenance of the on-site stormwater treatment measures and to take corrective action if necessary. <p>The maintenance agreement shall be recorded at the County Recorder's Office at the applicant's expense.</p> | <p>Prior to building permit final</p> | <p>Bureau of Building</p> | <p>Bureau of Building</p> |
| NOISE | | | |
| <p>SCA-NOS-1: Construction Days/Hours (#62)</p> <p>The project applicant shall comply with the following restrictions concerning construction days and hours:</p> <ul style="list-style-type: none"> a. Construction activities are limited to between 7:00 a.m. and 7:00 p.m. Monday through Friday, except that pier drilling and/or other extreme noise generating activities greater than 90 dBA shall be limited to between 8:00 a.m. and 4:00 p.m. | <p>During Construction</p> | <p>N/A</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|---------------------|------------------|---------------------------|
| <p>b. Construction activities are limited to between 9:00 a.m. and 5:00 p.m. on Saturday. In residential zones and within 300 feet of a residential zone, construction activities are allowed from 9:00 a.m. to 5:00 p.m. only within the interior of the building with the doors and windows closed. No pier drilling or other extreme noise generating activities greater than 90 dBA are allowed on Saturday.</p> <p>c. No construction is allowed on Sunday or federal holidays.</p> <p>Construction activities include, but are not limited to, truck idling, moving equipment (including trucks, elevators, etc.) or materials, deliveries, and construction meetings held on-site in a non-enclosed area.</p> <p>Any construction activity proposed outside of the above days and hours for special activities (such as concrete pouring which may require more continuous amounts of time) shall be evaluated on a case-by-case basis by the City, with criteria including the urgency/emergency nature of the work, the proximity of residential or other sensitive uses, and a consideration of nearby residents'/occupants' preferences. The project applicant shall notify property owners and occupants located within 300 feet at least 14 calendar days prior to construction activity proposed outside of the above days/hours. When submitting a request to the City to allow construction activity outside of the above days/hours, the project applicant shall submit information concerning the type and duration of proposed construction activity and the draft public notice for City review and approval prior to distribution of the public notice.</p> | | | |
| <p>SCA-NOS-2: Construction Noise (#63)</p> <p>The project applicant shall implement noise reduction measures to reduce noise impacts due to construction. Noise reduction measures include, but are not limited to, the following:</p> <p>a. Equipment and trucks used for project construction shall utilize the best available noise control techniques (e.g., improved mufflers, equipment redesign, use of intake silencers, ducts, engine enclosures and acoustically-attenuating shields or shrouds) wherever feasible.</p> <p>b. Except as provided herein, impact tools (e.g., jack hammers, pavement breakers, and rock drills) used for project construction shall be hydraulically or electrically powered to avoid noise associated with compressed air exhaust from pneumatically powered tools. However, where use of pneumatic tools is unavoidable, an exhaust muffler on the compressed air exhaust shall be used; this muffler can lower noise levels from the exhaust by up to about 10 dBA. External jackets on the tools themselves shall be used, if such jackets are commercially available, and this could achieve a reduction of 5 dBA. Quieter procedures shall be used, such as drills rather than impact equipment, whenever such procedures are available and consistent with</p> | During Construction | N/A | Bureau of Building |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|--------------------------|---------------------------|---------------------------|
| <p>construction procedures.</p> <p>c. Applicant shall use temporary power poles instead of generators where feasible.</p> <p>d. Stationary noise sources shall be located as far from adjacent properties as possible, and they shall be muffled and enclosed within temporary sheds, incorporate insulation barriers, or use other measures as determined by the City to provide equivalent noise reduction.</p> <p>e. The noisiest phases of construction shall be limited to less than 10 days at a time. Exceptions may be allowed if the City determines an extension is necessary and all available noise reduction controls are implemented.</p> | | | |
| <p>SCA-NOS-3: Extreme Construction Noise (#64)</p> <p><i>a. Construction Noise Management Plan Required</i></p> <p>Prior to any extreme noise generating construction activities (e.g., pier drilling, pile driving and other activities generating greater than 90 dBA), the project applicant shall submit a Construction Noise Management Plan prepared by a qualified acoustical consultant for City review and approval that contains a set of site-specific noise attenuation measures to further reduce construction impacts associated with extreme noise generating activities. The project applicant shall implement the approved Plan during construction. Potential attenuation measures include, but are not limited to, the following:</p> <p>i. Erect temporary plywood noise barriers around the construction site, particularly along on sites adjacent to residential buildings;</p> <p>ii. Implement “quiet” pile driving technology (such as pre-drilling of piles, the use of more than one pile driver to shorten the total pile driving duration), where feasible, in consideration of geotechnical and structural requirements and conditions;</p> <p>iii. Utilize noise control blankets on the building structure as the building is erected to reduce noise emission from the site;</p> <p>iv. Evaluate the feasibility of noise control at the receivers by temporarily improving the noise reduction capability of adjacent buildings by the use of sound blankets for example and implement such measure if such measures are feasible and would noticeably reduce noise impacts; and</p> <p>v. Monitor the effectiveness of noise attenuation measures by taking noise measurements.</p> <p><i>b. Public Notification Required</i></p> <p>The project applicant shall notify property owners and occupants located within 300 feet of the construction activities at least 14 calendar days prior to commencing extreme noise generating activities. Prior to providing the notice, the project applicant shall</p> | <p>Prior to Approval</p> | <p>Bureau of Building</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|---|---------------------------|---------------------------|
| <p>submit to the City for review and approval the proposed type and duration of extreme noise generating activities and the proposed public notice. The public notice shall provide the estimated start and end dates of the extreme noise generating activities and describe noise attenuation measures to be implemented.</p> | | | |
| <p>SCA-NOS-4: Construction Noise Complaints (#66) The project applicant shall submit to the City for review and approval a set of procedures for responding to and tracking complaints received pertaining to construction noise, and shall implement the procedures during construction. At a minimum, the procedures shall include:</p> <ol style="list-style-type: none"> a. Designation of an on-site construction complaint and enforcement manager for the project; b. A large on-site sign near the public right-of-way containing permitted construction days/hours, complaint procedures, and phone numbers for the project complaint manager and City Code Enforcement unit; c. Protocols for receiving, responding to, and tracking received complaints; and d. Maintenance of a complaint log that records received complaints and how complaints were addressed, which shall be submitted to the City for review upon the City's request. | <p>Prior to Approval of Construction-Related Permit</p> | <p>Bureau of Building</p> | <p>Bureau of Building</p> |
| <p>SCA-NOS-5: Exposure to Community Noise (#67) The project applicant shall submit a Noise Reduction Plan prepared by a qualified acoustical engineer for City review and approval that contains noise reduction measures (e.g., sound-rated window, wall, and door assemblies) to achieve an acceptable interior noise level in accordance with the land use compatibility guidelines of the Noise Element of the Oakland General Plan. The applicant shall implement the approved Plan during construction. To the maximum extent practicable, interior noise levels shall not exceed the following:</p> <ol style="list-style-type: none"> a. 45 dBA: Residential activities, civic activities, hotels b. 50 dBA: Administrative offices; group assembly activities c. 55 dBA: Commercial activities d. 65 dBA: Industrial activities | <p>Prior to approval of construction-related permit</p> | <p>Bureau of Planning</p> | <p>Bureau of Building</p> |
| <p>SCA-NOS-6: Operational Noise (#68) Noise levels from the project site after completion of the project (i.e., during project operation) shall comply with the performance standards of chapter 17.120 of the Oakland Planning Code and chapter 8.18 of the Oakland Municipal Code. If noise levels exceed these standards, the activity causing the noise shall be abated until appropriate noise reduction measures have been installed and compliance verified by the City.</p> | <p>Ongoing</p> | <p>N/A</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---|---|---------------------------|
| <p>SCA-TRANS-2: Bicycle Parking (#77) The project applicant shall comply with the City of Oakland Bicycle Parking Requirements (chapter 17.118 of the Oakland Planning Code). The project drawings submitted for construction-related permits shall demonstrate compliance with the requirements.</p> | <p>Prior to approval of construction-related permit</p> | <p>Bureau of Planning</p> | <p>Bureau of Building</p> |
| <p>SCA-TRANS-3: Transportation Improvements (#78) The project applicant shall implement the recommended on- and off-site transportation-related improvements contained within the Transportation Impact Review for the project (e.g., signal timing adjustments, restriping, signalization, traffic control devices, roadway reconfigurations, transportation demand management measures, and transit, pedestrian, and bicyclist amenities). The project applicant is responsible for funding and installing the improvements, and shall obtain all necessary permits and approvals from the City and/or other applicable regulatory agencies such as, but not limited to, Caltrans (for improvements related to Caltrans facilities) and the California Public Utilities Commission (for improvements related to railroad crossings), prior to installing the improvements. To implement this measure for intersection modifications, the project applicant shall submit Plans, Specifications, and Estimates (PS&E) to the City for review and approval. All elements shall be designed to applicable City standards in effect at the time of construction and all new or upgraded signals shall include these enhancements as required by the City. All other facilities supporting vehicle travel and alternative modes through the intersection shall be brought up to both City standards and ADA standards (according to Federal and State Access Board guidelines) at the time of construction. Current City Standards call for, among other items, the elements listed below:</p> <ul style="list-style-type: none"> a. 2070L Type Controller with cabinet accessory b. GPS communication (clock) c. Accessible pedestrian crosswalks according to Federal and State Access Board guidelines with signals (audible and tactile) d. Countdown pedestrian head module switch out e. City Standard ADA wheelchair ramps f. Video detection on existing (or new, if required) g. Mast arm poles, full activation (where applicable) | <p>Prior to building permit final or as otherwise specified</p> | <p>Bureau of Building; Department of Transportation</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|---|---------------------------|---------------------------|
| <ul style="list-style-type: none"> h. Polara Push buttons (full activation) i. Bicycle detection (full activation) j. Pull boxes k. Signal interconnect and communication with trenching (where applicable), or through existing conduit (where applicable), 600 feet maximum l. Conduit replacement contingency m. Fiber switch n. PTZ camera (where applicable) o. Transit Signal Priority (TSP) equipment consistent with other signals along corridor p. Signal timing plans for the signals in the coordination group q. Bi-directional curb ramps (where feasible, and if project is on a street corner) r. Upgrade ramps on receiving curb (where feasible, and if project is on a street corner) | | | |
| <p>SCA-TRANS-4: Transportation and Parking Demand Management (#79)</p> <ul style="list-style-type: none"> a. Transportation and Parking Demand Management (TDM) Plan Required The project applicant shall submit a Transportation and Parking Demand Management (TDM) Plan for review and approval by the City. <ul style="list-style-type: none"> i. The goals of the TDM Plan shall be the following: <ul style="list-style-type: none"> • Reduce vehicle traffic and parking demand generated by the project to the maximum extent practicable. • Achieve the following project vehicle trip reductions (VTR): <ul style="list-style-type: none"> o Projects generating 50-99 net new a.m. or p.m. peak hour vehicle trips: 10 percent VTR o Projects generating 100 or more net new a.m. or p.m. peak hour vehicle trips: 20 percent VTR • Increase pedestrian, bicycle, transit, and carpool/vanpool modes of travel. All four modes of travel shall be considered, as appropriate. • Enhance the City's transportation system, consistent with City policies and programs. ii. The TDM Plan should include the following: <ul style="list-style-type: none"> • Baseline existing conditions of parking and curbside regulations within the surrounding neighborhood that could affect the effectiveness of TDM strategies, including inventory of parking spaces and occupancy if applicable. • Proposed TDM strategies to achieve VTR goals (see below). iii. For employers with 100 or more employees at the subject site, the TDM Plan | <p>Prior to approval of planning application.</p> | <p>Bureau of Planning</p> | <p>per TDM Plan</p> |

Standard Conditions of Approval

When Required

Initial Approval

**Monitoring/
Inspection**

shall also comply with the requirements of Oakland Municipal Code Chapter 10.68 Employer-Based Trip Reduction Program.

- iv. The following TDM strategies must be incorporated into a TDM Plan based on a project location or other characteristics. When required, these mandatory strategies should be identified as a credit toward a project’s VTR.

| Improvement | Required by code or when... |
|---|---|
| Bus boarding bulbs or islands | <ul style="list-style-type: none"> • A bus boarding bulb or island does not already exist and a bus stop is located along the project frontage; and/or • A bus stop along the project frontage serves a route with 15 minutes or better peak hour service and has a shared bus-bike lane curb |
| Bus shelter | <ul style="list-style-type: none"> • A stop with no shelter is located within the project frontage, or • The project is located within 0.10 miles of a flag stop with 25 or more boardings per day |
| Concrete bus pad | <ul style="list-style-type: none"> • A bus stop is located along the project frontage and a concrete bus pad does not already exist |
| Curb extensions or bulb-outs | <ul style="list-style-type: none"> • Identified as an improvement within site analysis |
| Implementation of a corridor-level bikeway improvement | <ul style="list-style-type: none"> • A buffered Class II or Class IV bikeway facility is in a local or county adopted plan within 0.10 miles of the project location; and • The project would generate 500 or more daily bicycle trips |
| Implementation of a corridor-level transit capital improvement | <ul style="list-style-type: none"> • A high-quality transit facility is in a local or county adopted plan within 0.25 miles of the project location; and • The project would generate 400 or more peak period transit trips |
| Installation of amenities such as lighting; pedestrian-oriented green infrastructure, trees, or other greening landscape; and trash receptacles per the Pedestrian Master Plan and any | <ul style="list-style-type: none"> • Always required |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|--|------------------|---------------------------|
| applicable streetscape plan. | | | |
| Installation of safety improvements identified in the Pedestrian Master Plan (such as crosswalk striping, curb ramps, count down signals, bulb outs, etc.) | <ul style="list-style-type: none"> When improvements are identified in the Pedestrian Master Plan along project frontage or at an adjacent intersection | | |
| In-street bicycle corral | <ul style="list-style-type: none"> A project includes more than 10,000 square feet of ground floor retail, is located along a Tier 1 bikeway, and on-street vehicle parking is provided along the project frontages. | | |
| Intersection improvements¹⁴ | <ul style="list-style-type: none"> Identified as an improvement within site analysis | | |
| New sidewalk, curb ramps, curb and gutter meeting current City and ADA standards | <ul style="list-style-type: none"> Always required | | |
| No monthly permits and establish minimum price floor for public parking¹⁵ | <ul style="list-style-type: none"> If proposed parking ratio exceeds 1:1000 sf. (commercial) | | |
| Parking garage is designed with retrofit capability | <ul style="list-style-type: none"> Optional if proposed parking ratio exceeds 1:1.25 (residential) or 1:1000 sf. (commercial) | | |
| Parking space reserved for car share | <ul style="list-style-type: none"> If a project is providing parking and a project is located within downtown. One car share space reserved for buildings between 50 – 200 units, then one car share space per 200 units. | | |
| Paving, lane striping or restriping (vehicle and bicycle), and signs to midpoint of street section | <ul style="list-style-type: none"> Typically required | | |
| Pedestrian crossing improvements | <ul style="list-style-type: none"> Identified as an improvement within site analysis | | |
| Pedestrian-supportive signal changes¹⁶ | <ul style="list-style-type: none"> Identified as an improvement within | | |

¹⁴ Including but not limited to visibility improvements, shortening corner radii, pedestrian safety islands, accounting for pedestrian desire lines.

¹⁵ May also provide a cash incentive or transit pass alternative to a free parking space in commercial properties.

| Standard Conditions of Approval | | When Required | Initial Approval | Monitoring/ Inspection |
|---|---|---------------|------------------|---------------------------|
| | operations analysis | | | |
| Real-time transit information system | <ul style="list-style-type: none"> A project frontage block includes a bus stop or BART station and is along a Tier 1 transit route with 2 or more routes or peak period frequency of 15 minutes or better | | | |
| Relocating bus stops to far side | <ul style="list-style-type: none"> A project is located within 0.10 mile of any active bus stop that is currently near-side | | | |
| Signal upgrades¹⁷ | <ul style="list-style-type: none"> Project size exceeds 100 residential units, 80,000 sf. of retail, or 100,000 sf. of commercial; and Project frontage abuts an intersection with signal infrastructure older than 15 years | | | |
| Transit queue jumps | <ul style="list-style-type: none"> Identified as a needed improvement within operations analysis of a project with frontage along a Tier 1 transit route with 2 or more routes or peak period frequency of 15 minutes or better | | | |
| Transit Operations | <ul style="list-style-type: none"> The project applicant shall, if feasible, contribute its fair share to AC Transit service enhancements to meet access goals outlined in the City of Oakland West Oakland Specific Plan and AC Transit's ACgo expanded service plan and improve connections to local goods and services. Alternatively, the project applicant may explore and propose other TDM measure(s), including those already set forth in the TDM plan, in lieu of this fair share contribution. The City may approve the substitute TDM measure(s) if the City, in its discretion, deems the measure(s) more feasible and reasonably related and roughly proportional to the impacts of the development. | | | |

¹⁶ Including but not limited to reducing signal cycle lengths to less than 90 seconds to avoid pedestrian crossings against the signal, providing a leading pedestrian interval, provide a "scramble" signal phase where appropriate.

¹⁷ Including typical traffic lights, pedestrian signals, bike actuated signals, transit-only signals

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|--|------------------|---------------------------|
| Trenching and placement of conduit for providing traffic signal interconnect | <ul style="list-style-type: none"> • Project size exceeds 100 units, 80,000 sf. of retail, or 100,000 sf. of commercial; and • Project frontage block is identified for signal interconnect improvements as part of a planned ITS improvement; and • A major transit improvement is identified within operations analysis requiring traffic signal interconnect | | |
| Unbundled parking | <ul style="list-style-type: none"> • If proposed parking ratio exceeds 1:1.25 (residential) | | |

- v. Other TDM strategies to consider include, but are not limited to, the following:
- Inclusion of additional long-term and short-term bicycle parking that meets the design standards set forth in chapter five of the Bicycle Master Plan and the Bicycle Parking Ordinance (chapter 17.117 of the Oakland Planning Code), and shower and locker facilities in commercial developments that exceed the requirement.
 - Construction of and/or access to bikeways per the Bicycle Master Plan; construction of priority bikeways, on-site signage and bike lane striping.
 - Installation of safety elements per the Pedestrian Master Plan (such as crosswalk striping, curb ramps, count down signals, bulb outs, etc.) to encourage convenient and safe crossing at arterials, in addition to safety elements required to address safety impacts of the project.
 - Installation of amenities such as lighting, street trees, and trash receptacles per the Pedestrian Master Plan, the Master Street Tree List and Tree Planting Guidelines (which can be viewed at <http://www2.oaklandnet.com/oakca1/groups/pwa/documents/report/oak042662.pdf> and <http://www2.oaklandnet.com/oakca1/groups/pwa/documents/form/oak025595.pdf>, respectively) and any applicable streetscape plan.
 - Construction and development of transit stops/shelters, pedestrian access, way finding signage, and lighting around transit stops per transit agency plans or negotiated improvements.
 - Direct on-site sales of transit passes purchased and sold at a bulk group rate (through programs such as AC Transit Easy Pass or a similar program through another transit agency).

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---------------|------------------|---------------------------|
| <ul style="list-style-type: none"> • Provision of a transit subsidy to employees or residents, determined by the project applicant and subject to review by the City, if employees or residents use transit or commute by other alternative modes. • Provision of an ongoing contribution to transit service to the area between the project and nearest mass transit station prioritized as follows: 1) Contribution to AC Transit bus service; 2) Contribution to an existing area shuttle service; and 3) Establishment of new shuttle service. The amount of contribution (for any of the above scenarios) would be based upon the cost of establishing new shuttle service (Scenario 3). • Guaranteed ride home program for employees, either through 511.org or through separate program. • Pre-tax commuter benefits (commuter checks) for employees. • Free designated parking spaces for on-site car-sharing program (such as City Car Share, Zip Car, etc.) and/or car-share membership for employees or tenants. • On-site carpooling and/or vanpool program that includes preferential (discounted or free) parking for carpools and vanpools. • Distribution of information concerning alternative transportation options. • Parking spaces sold/leased separately for residential units. Charge employees for parking, or provide a cash incentive or transit pass alternative to a free parking space in commercial properties. • Parking management strategies including attendant/valet parking and shared parking spaces. • Requiring tenants to provide opportunities and the ability to work off-site. • Allow employees or residents to adjust their work schedule in order to complete the basic work requirement of five eight-hour workdays by adjusting their schedule to reduce vehicle trips to the worksite (e.g., working four, ten-hour days; allowing employees to work from home two days per week). • Provide or require tenants to provide employees with staggered work hours involving a shift in the set work hours of all employees at the workplace or flexible work hours involving individually determined work hours. | | | |
| <p>The TDM Plan shall indicate the estimated VTR for each strategy, based on published research or guidelines where feasible. For TDM Plans containing ongoing operational VTR strategies, the Plan shall include an ongoing monitoring and enforcement program to ensure the Plan is implemented on an ongoing basis during project operation. If an</p> | | | |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|---|---|---|
| <p>annual compliance report is required, as explained below, the TDM Plan shall also specify the topics to be addressed in the annual report.</p> <p>b. <i>TDM Implementation – Physical Improvements</i> For VTR strategies involving physical improvements, the project applicant shall obtain the necessary permits/approvals from the City and install the improvements prior to the completion of the project.</p> <p>c. <i>TDM Implementation – Operational Strategies</i> For projects that generate 100 or more net new a.m. or p.m. peak hour vehicle trips and contain ongoing operational VTR strategies, the project applicant shall submit an annual compliance report for the first five years following completion of the project (or completion of each phase for phased projects) for review and approval by the City. The annual report shall document the status and effectiveness of the TDM program, including the actual VTR achieved by the project during operation. If deemed necessary, the City may elect to have a peer review consultant, paid for by the project applicant, review the annual report. If timely reports are not submitted and/or the annual reports indicate that the project applicant has failed to implement the TDM Plan, the project will be considered in violation of the Conditions of Approval and the City may initiate enforcement action as provided for in these Conditions of Approval. The project shall not be considered in violation of this Condition if the TDM Plan is implemented but the VTR goal is not achieved.</p> | <p>Prior to building permit final</p> <p>Ongoing</p> | <p>Bureau of Building</p> <p>Department of Transportation</p> | <p>Bureau of Building</p> <p>Department of Transportation</p> |
| <p>SCA-TRANS-5: Transportation Impact Fee (#80) The project applicant shall comply with the requirements of the City of Oakland Transportation Impact Fee Ordinance (chapter 15.74 of the Oakland Municipal Code).</p> | <p>Prior to issuance of building permit</p> | <p>Bureau of Building</p> | <p>N/A</p> |
| <p>SCA-TRANS-6: Plug-In Electric Vehicle (PEV) Charging Infrastructure (#83)</p> <p>a. <i>PEV-Ready Parking Spaces</i> The applicant shall submit, for review and approval of the Building Official and the Zoning Manager, plans that show the location of parking spaces equipped with full electrical circuits designated for future PEV charging (i.e. “PEV-Ready”) per the requirements of Chapter 15.04 of the Oakland Municipal Code. Building electrical plans shall indicate sufficient electrical capacity to supply the required PEV-Ready parking spaces.</p> <p>b. <i>PEV-Capable Parking Spaces</i> The applicant shall submit, for review and approval of the Building Official, plans that show the location of inaccessible conduit to supply PEV-capable parking spaces per the requirements of Chapter 15.04 of the Oakland Municipal Code. Building electrical plans shall indicate sufficient electrical capacity to supply the required PEV-capable parking spaces.</p> | <p>Prior to Issuance of Building Permit</p> <p>Prior to Issuance of Building Permit</p> | <p>Bureau of Building</p> <p>Bureau of Building</p> | <p>Bureau of Building</p> <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|--|--|--|
| UTILITIES AND SERVICE SYSTEMS | | | |
| <p>SCA-UTIL-1: Construction and Demolition Waste Reduction and Recycling (#84) The project applicant shall comply with the City of Oakland Construction and Demolition Waste Reduction and Recycling Ordinance (chapter 15.34 of the Oakland Municipal Code) by submitting a Construction and Demolition Waste Reduction and Recycling Plan (WRRP) for City review and approval, and shall implement the approved WRRP. Projects subject to these requirements include all new construction, renovations/alterations/modifications with construction values of \$50,000 or more (except R-3 type construction), and all demolition (including soft demolition) except demolition of type R-3 construction. The WRRP must specify the methods by which the project will divert construction and demolition debris waste from landfill disposal in accordance with current City requirements. The WRRP may be submitted electronically at www.greenhalosystems.com or manually at the City's Green Building Resource Center. Current standards, FAQs, and forms are available on the City's website and in the Green Building Resource Center.</p> | Prior to Approval of Construction-Related Permit | Public Works Department, Environmental Services Division | Public Works Department, Environmental Services Division |
| <p>SCA-UTIL-2: Underground Utilities (#85) The project applicant shall place underground all new utilities serving the project and under the control of the project applicant and the City, including all new gas, electric, cable, and telephone facilities, fire alarm conduits, street light wiring, and other wiring, conduits, and similar facilities. The new facilities shall be placed underground along the project's street frontage and from the project structures to the point of service. Utilities under the control of other agencies, such as PG&E, shall be placed underground if feasible. All utilities shall be installed in accordance with standard specifications of the serving utilities.</p> | During Construction | N/A | Bureau of Building |
| <p>SCA-UTIL-3: Recycling Collection and Storage Space (#86) The project applicant shall comply with the City of Oakland Recycling Space Allocation Ordinance (chapter 17.118 of the Oakland Planning Code). The project drawings submitted for construction-related permits shall contain recycling collection and storage areas in compliance with the Ordinance. For residential projects, at least two cubic feet of storage and collection space per residential unit is required, with a minimum of ten cubic feet. For nonresidential projects, at least two cubic feet of storage and collection space per 1,000 sf of building floor area is required, with a minimum of ten cubic feet.</p> | Prior to Approval of Construction-Related Permit | Bureau of Planning | Bureau of Building |
| <p>SCA-UTIL-4: Green Building Requirements (#87) <i>a. Compliance with Green Building Requirements During Plan-Check</i> The project applicant shall comply with the requirements of the California Green Building Standards (CALGreen) mandatory measures and the applicable requirements of</p> | Prior to approval of construction-related permit | Bureau of Building | N/A |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|----------------------------|------------------|---------------------------|
| <p>the City of Oakland Green Building Ordinance (chapter 18.02 of the Oakland Municipal Code).</p> <p>The following information shall be submitted to the City for review and approval with the application for a building permit:</p> <ul style="list-style-type: none"> • Documentation showing compliance with Title 24 of the current version of the California Building Energy Efficiency Standards. • Completed copy of the final green building checklist approved during the review of the Planning and Zoning permit. • Copy of the Unreasonable Hardship Exemption, if granted, during the review of the Planning and Zoning permit. • Permit plans that show, in general notes, detailed design drawings, and specifications as necessary, compliance with the items listed in subsection (ii) below. • Copy of the signed statement by the Green Building Certifier approved during the review of the Planning and Zoning permit that the project complied with the requirements of the Green Building Ordinance. • Signed statement by the Green Building Certifier that the project still complies with the requirements of the Green Building Ordinance, unless an Unreasonable Hardship Exemption was granted during the review of the Planning and Zoning permit. • Other documentation as deemed necessary by the City to demonstrate compliance with the Green Building Ordinance. <p>The set of plans in subsection (i) shall demonstrate compliance with the following:</p> <ul style="list-style-type: none"> • CALGreen mandatory measures. • Green building point level/certification requirement per the appropriate checklist approved during the Planning entitlement process. • All green building points identified on the checklist approved during review of the Planning and Zoning permit, unless a Request for Revision Plan-check application is submitted and approved by the Bureau of Planning that shows the previously approved points that will be eliminated or substituted. • The required green building point minimums in the appropriate credit categories. | | | |
| <p><i>b. Compliance with Green Building Requirements During Construction</i></p> <p>The project applicant shall comply with the applicable requirements of CALGreen and the Oakland Green Building Ordinance during construction of the project.</p> <p>The following information shall be submitted to the City for review and approval:</p> <p>i. Completed copies of the green building checklists approved during the review of the Planning and Zoning permit and during the review of the building permit.</p> | <p>During construction</p> | <p>N/A</p> | <p>Bureau of Building</p> |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|---|--|---|---------------------------|
| <p>ii. Signed statement(s) by the Green Building Certifier during all relevant phases of construction that the project complies with the requirements of the Green Building Ordinance.</p> <p>iii. Other documentation as deemed necessary by the City to demonstrate compliance with the Green Building Ordinance.</p> <p>c. <i>Compliance with Green Building Requirements After Construction</i> Prior to the final Building Permit, the Green Building Certifier shall submit the appropriate documentation to City staff and attain the minimum required point level.</p> | Prior to Final Approval | Bureau of Planning | Bureau of Building |
| <p>SCA-UTIL-5: Sanitary Sewer System (#89) The project applicant shall prepare and submit a Sanitary Sewer Impact Analysis to the City for review and approval in accordance with the City of Oakland Sanitary Sewer Design Guidelines. The Impact Analysis shall include an estimate of pre-project and post-project wastewater flow from the project site. In the event that the Impact Analysis indicates that the net increase in project wastewater flow exceeds City-projected increases in wastewater flow in the sanitary sewer system, the project applicant shall pay the Sanitary Sewer Impact Fee in accordance with the City’s Master Fee Schedule for funding improvements to the sanitary sewer system.</p> | Prior to Approval of Construction-Related Permit | Public Works Department, Department of Engineering and Construction | N/A |
| <p>SCA-UTIL-6: Storm Drain System (#90) The project storm drainage system shall be designed in accordance with the City of Oakland’s Storm Drainage Design Guidelines. To the maximum extent practicable, peak stormwater runoff from the project site shall be reduced by at least 25 percent compared to the pre-project condition.</p> | Prior to Approval of Construction-Related Permit | Bureau of Building | Bureau of Building |
| <p>SCA-UTIL-7: Water Efficient Landscape Ordinance (WELO) (#92) The project applicant shall comply with California’s Water Efficient Landscape Ordinance (WELO) in order to reduce landscape water usage. For any landscape project with an aggregate (total noncontiguous) landscape area equal to 2,500 sq. ft. or less. The project applicant may implement either the Prescriptive Measures or the Performance Measures, of, and in accordance with the California’s Model Water Efficient Landscape Ordinance. For any landscape project with an aggregate (total noncontiguous) landscape area over 2,500 sq. ft., the project applicant shall implement the Performance Measures in accordance with the WELO.</p> <p>Prescriptive Measures: Prior to construction, the project applicant shall submit documentation showing compliance with Appendix D of California’s Model Water Efficient Landscape Ordinance (see website below starting on page 23): http://www.water.ca.gov/wateruseefficiency/landscapeordinance/docs/Title%202023%20ex</p> | Prior to approval of construction-related permit | Bureau of Planning | Bureau of Building |

| Standard Conditions of Approval | When Required | Initial Approval | Monitoring/ Inspection |
|--|---------------|------------------|---------------------------|
| <p>tract%20-%20Official%20CCR%20pages.pdf</p> <p>Performance Measures: Prior to construction, the project applicant shall prepare and submit a Landscape Documentation Package for review and approval, which includes the following</p> <ul style="list-style-type: none"> a. Project Information: <ul style="list-style-type: none"> i. Date, ii. Applicant and property owner name, iii. Project address, iv. Total landscape area, v. Project type (new, rehabilitated, cemetery, or home owner installed), vi. Water supply type and water purveyor, vii. Checklist of documents in the package, and viii. Applicant signature and date with the statement: "I agree to comply with the requirements of the water efficient landscape ordinance and submit a complete Landscape Documentation Package." b. Water Efficient Landscape Worksheet <ul style="list-style-type: none"> i. Hydrozone Information Table ii. Water Budget Calculations with Maximum Applied Water Allowance (MAWA) and Estimated Total Water Use c. Soil Management Report d. Landscape Design Plan e. Irrigation Design Plan, and f. Grading Plan <p>Upon installation of the landscaping and irrigation systems, the Project applicant shall submit a Certificate of Completion and landscape and irrigation maintenance schedule for review and approval by the City. The Certificate of Compliance shall also be submitted to the local water purveyor and property owner or his or her designee.</p> <p>For the specific requirements within the Water Efficient Landscape Worksheet, Soil Management Report, Landscape Design Plan, Irrigation Design Plan and Grading Plan, see the link below.</p> <p>http://www.water.ca.gov/wateruseefficiency/landscapeordinance/docs/Title%202023%20tract%20-%20Official%20CCR%20pages.pdf</p> | | | |



MEMORANDUM

Date: January 29, 2019
To: Rebecca Auld, Lamphier-Gregory
From: Sam Tabibnia and Jordan Brooks, Fehr & Peers
Subject: **West Oakland BART TOD – Transportation Assessment (non-CEQA)**

OK18-0294

This memorandum summarizes the non-CEQA transportation assessment that Fehr & Peers completed for the proposed West Oakland BART TOD project in Oakland. This document provides a brief description of the project, an estimate of project trip generation, a review of the project site plan and surrounding areas for access and circulation for various modes, an intersection operations analysis, and a collision analysis. This memorandum also includes recommendations that improve multi-modal access, circulation, and safety.

PROJECT DESCRIPTION

The proposed project would be located adjacent to the West Oakland BART station, bounded by 7th Street to the north, Mandela Parkway to the east, 5th Street to the south, and Chester Street to the west. Based on the project site plan dated January 11, 2019, the project would consist of the following:

- 762 multi-family dwelling units
- approximately 382,000 square feet of office space
- approximately 75,000 square feet of ground-level commercial space

The project would also include 400 automobile parking spaces, with six dedicated carshare spaces, in a garage accessible via a driveway on Chester Street.



The project site is currently occupied by surface parking lots that provide 413 automobile parking spaces for the West Oakland BART station. These spaces for BART riders would be eliminated by the project and would not be replaced.

TRIP GENERATION AND INTERSECTION COUNTS

Automobile Trip Generation

Trip generation is the process of estimating the number of vehicles that would likely access the project on any given day. **Table 1** summarizes the trip generation for the proposed project. Trip generation data published by the Institute of Transportation Engineers (ITE) in the *Trip Generation Manual (10th Edition)* was used as a starting point to estimate the vehicle trip generation.

ITE's *Trip Generation Manual (10th Edition)* is primarily based on data collected at single-use suburban sites where the automobile is often the only travel mode. However, the project site is located in a moderately dense area with streets generally laid out in a grid and sidewalks on most streets. It is located near some existing neighborhood-serving retail and industrial uses, and several projects are proposed in the area that would increase residential and employment densities and provide neighborhood-serving retail uses. Additionally, the project is located within two miles of Downtown Oakland, a dense employment center. Thus, many trips generated by the project may be walking, bicycling, or transit trips.

Since the project borders the West Oakland BART station, this analysis reduces the ITE-based trip generation by about 47 percent to account for non-automobile trips. This reduction is consistent with the City of Oakland's TIRG and is based on US Census commute data for Alameda County from the 2014 5-Year Estimates of the American Community Survey (ACS), which shows that the non-automobile mode share for areas less than 0.5 miles from a BART Station is about 47 percent.

In addition, pass-by adjustments were applied for the retail use. Pass-by trips are trips attracted to the site from adjacent roadways as an interim stop on the way to their ultimate destination. These vehicles would be on the roadway network regardless of the project, so pass-by trips result in changed travel patterns but do not add new vehicle trips to the roadway network. According to the *ITE Trip Generation Handbook (2nd Edition)*, the average weekday PM peak hour pass-by reduction is 34 percent for retail uses (ITE land use category 820). Since AM peak hour and daily pass-by reductions are not available, a pass-by reduction was not applied for the AM peak hour, and a 17-percent reduction (half the PM peak hour pass-by reduction) was applied to daily trips.



The estimated trip generation presented in Table 1 is conservative and likely overestimates the actual trip generation of the project in that it does not account for the following:

- The proposed project would eliminate about 413 surface parking spaces currently used for BART parking. Considering that many streets near the BART station have restricted parking, such as residential parking permit (RPP) which limits on-street parking to two-hours by non-local residents and that many streets and other off-street public parking facilities in the vicinity operate at or near capacity during most weekdays, it is likely that many of the current BART riders that park at the West Oakland BART Station surface parking lot would either shift to other modes, drive to other stations, or not use BART. Thus, it is likely that the elimination of the existing surface lot would reduce the number of BART riders who currently drive to and from the West Oakland BART Station. However, in order to present a conservative analysis, this analysis does not eliminate any trips associated with these existing BART parking spaces, and assumes that all of the BART riders who currently drive to the station would continue to drive and park in nearby surface lots or on-street.
- At least 20 percent of the residential units in the proposed project would be affordable. Although research on the transportation impacts of affordable housing in California shows that for any given location and housing type, lower income residents generate fewer automobile trips than residents of a typical multifamily development, this analysis does not reduce the trip generation for these units.¹

As summarized in Table 1, the net new automobile trip generation for the proposed development is approximately 6,300 daily, 472 AM peak hour, and 548 PM peak hour automobile trips.

¹ Howell, A., Currans, K., Norton, G., & Clifton, K. (2018). Transportation impacts of affordable housing: Informing development review with travel behavior analysis. *Journal of Transport and Land Use*, 11(1). doi:10.5198/jtlu.2018.1129, <https://www.jtlu.org/index.php/jtlu/article/download/1129/986>



TABLE 1
WEST OAKLAND BART TOD PROJECT AUTOMOBILE TRIP GENERATION

| Land Use | ITE Code | Size ¹ | Daily Trips | Weekday AM Peak Hour | | | Weekday PM Peak Hour | | |
|--|------------------|-------------------|--------------|----------------------|------------|------------|----------------------|------------|------------|
| | | | | In | Out | Total | In | Out | Total |
| High-Rise Apartment | 222 ² | 500 DU | 2,230 | 37 | 118 | 155 | 110 | 70 | 180 |
| Mid-Rise Apartment | 221 ³ | 240 DU | 1,310 | 23 | 64 | 87 | 65 | 41 | 106 |
| Duplex | 220 ⁴ | 22 DU | 130 | 3 | 9 | 12 | 10 | 6 | 16 |
| Office | 710 ⁵ | 382.5 KSF | 3,900 | 382 | 62 | 444 | 70 | 370 | 440 |
| Retail | 820 ⁶ | 75.0 KSF | 4,950 | 118 | 72 | 190 | 211 | 229 | 440 |
| ITE Trip Generation Subtotal | | | 12,520 | 563 | 325 | 888 | 466 | 716 | 1,182 |
| <i>Non-Auto Mode Reduction⁷</i> | | | -5,870 | -264 | -152 | -416 | -219 | -336 | -554 |
| <i>Retail Pass-By Reduction⁸</i> | | | -350 | 0 | 0 | 0 | -38 | -41 | -80 |
| <i>Existing Land Use Reduction⁹</i> | | | -0 | -0 | -0 | -0 | -0 | -0 | -0 |
| Net New Project Trips | | | 6,300 | 299 | 173 | 472 | 209 | 339 | 548 |

Notes:

1. DU = Dwelling Units; KSF = 1,000 square feet.
2. ITE *Trip Generation (10th Edition)* land use category 222 (High-Rise Apartment, General Urban/Suburban):
 Daily: $T = 4.45 * X$
 AM Peak Hour: $T = 0.31 * X$ (24% in, 76% out)
 PM Peak Hour: $T = 0.36 * X$ (61% in, 39% out)
3. ITE *Trip Generation (10th Edition)* land use category 221 (Mid-Rise Apartment, General Urban/Suburban):
 Daily: $T = 5.44 * X$
 AM Peak Hour: $T = 0.36 * X$ (26% in, 74% out)
 PM Peak Hour: $T = 0.44 * X$ (61% in, 39% out)
4. ITE *Trip Generation (10th Edition)* land use category 220 (Low-Rise Apartment, General Urban/Suburban):
 Daily: $T = 7.56 * X - 40.86$
 AM Peak Hour: $\text{Ln}(T) = 0.95 * \text{Ln}(X) - 0.51$ (23% in, 77% out)
 PM Peak Hour: $\text{Ln}(T) = 0.89 * \text{Ln}(X) - 0.02$ (63% in, 37% out)
5. ITE *Trip Generation (10th Edition)* land use category 710 (General Office Building, General Urban/Suburban):
 Daily: $\text{Ln}(T) = 0.97 * \text{Ln}(X) + 2.5$
 AM Peak Hour: $T = 1.16 * X$ (86% in, 14% out)
 PM Peak Hour: $T = 1.15 * X$ (16% in, 84% out)
6. ITE *Trip Generation (10th Edition)* land use category 820 (Shopping Center, General Urban/Suburban):
 Daily: $\text{Ln}(T) = 0.68 * \text{Ln}(X) + 5.57$
 AM Peak Hour: $T = 0.5 * X + 151.78$ (62% in, 38% out)
 PM Peak Hour: $\text{Ln}(T) = 0.74 * \text{Ln}(X) + 2.89$ (48% in, 52% out)
7. Reduction of 47% assumed, based on City of Oakland *Transportation Impact Review Guidelines*, using Census data for urban environments less than 0.5 miles from a BART station.



8. Based on *ITE Trip Generation Handbook (2nd Edition)*, the average PM peak hour pass-by rate for land use category 820 is 34%. A reduction was not applied to the AM peak hour, and a 17% reduction was applied for daily trips.
9. The West Oakland BART TOD project would eliminate 413 surface parking spaces currently used for BART parking. To present a conservative analysis, the project was assumed to not eliminate any trips associated with those parking spaces, because some or all of the BART riders who currently drive to the station would continue to drive and park in nearby surface lots or on-street.

Source: Fehr & Peers, 2019.

Non-Vehicular Trip Generation

Consistent with the City of Oakland TIRG, **Table 2** presents the estimates of project trip generation for all travel modes for the project site. The automobile trip generation shown in Table 2 does not account for pass-by reductions.

TABLE 2
WEST OAKLAND BART TOD PROJECT TRIP GENERATION BY TRAVEL MODE

| Mode | Mode Share Adjustment Factors ¹ | Daily | AM Peak Hour | PM Peak Hour |
|--------------------|--|---------------|--------------|--------------|
| Automobile | 53.1% | 6,650 | 472 | 628 |
| Transit | 29.7% | 3,720 | 264 | 351 |
| Bike | 5.1% | 640 | 45 | 60 |
| Walk | 10.5% | 1,310 | 93 | 124 |
| Total Trips | | 12,320 | 874 | 1,163 |

Notes:

1. Based on *City of Oakland Transportation Impact Study Guidelines* assuming project site is in an urban environment less than 0.5 miles from a BART station.

Source: Fehr & Peers, 2019.

Trip Distribution and Study Intersection Selection

The trip distribution and assignment process is used to estimate how the trips generated by the project would be distributed across the roadway network. Trip distribution and assignment for the project were developed based on the locations of complementary land uses, existing travel patterns, the street network in the area, and the results of the Alameda County Transportation Commission (CTC) travel demand model. **Table 3** shows the resulting trip distribution.



TABLE 3
WEST OAKLAND BART TOD PROJECT
VEHICLE DISTRIBUTION

| Zone | Distribution |
|---------------------|---------------------|
| To/From West | 21% |
| To/From East | 24% |
| To/From North | 17% |
| To/From South | 6% |
| To/From I-880 South | 20% |
| To/From I-880 North | 12% |
| Total | 100% |

Sources: Fehr & Peers, 2019.

Trips generated by the proposed project, as shown in Table 1, were assigned to the roadway network according to the trip distribution shown on Table 3.

According to the City of Oakland's TIRG, the criteria for selecting study intersections include:

- All intersection(s) of streets adjacent to project site;
- All signalized intersection(s), all-way stop-controlled intersection(s) or roundabouts where 100 or more peak hour trips are added by the project;
- All signalized intersection(s) with 50 or more project-related peak hour trips and existing LOS D-E-F; and
- Side-street stop-controlled intersection(s) where 50 or more peak hour trips are added by the project to any individual movement other than the major-street through movement.

This analysis evaluates the following intersections due to being adjacent to the project site:

1. 7th Street/Chester Street
2. 7th Street/Center Street
3. 7th Street/Mandela Parkway
4. 5th Street/Chester Street
5. 5th Street/Center Street
6. 5th Street/Mandela Parkway

Automobile turning movements, pedestrian counts, and bicycle counts were collected at these intersections during the AM and PM peak commuting hours (7:00 AM to 9:00 AM and 4:00 PM to 6:00 PM) on December 12, 2018, a typical weekday with local schools in normal session, moderate



weather, and no observed traffic incidents. **Figure 1** shows the peak hour intersection volumes, and **Appendix A** provides the raw traffic counts.

SITE ACCESS AND CIRCULATION ANALYSIS

Fehr & Peers reviewed the project site plan dated January 11, 2019 and the existing street network adjacent to the project site to evaluate safety, access, and circulation for all travel modes.

Automobile Access and Circulation

Currently, the project site is occupied by parking facilities for the West Oakland BART Station, which would be demolished by the project. Access to the existing site is provided by driveways on Mandela Parkway, Chester Street, and 5th Street. These driveways would be eliminated by the project. The proposed project would include a 400-space parking garage which would be accessed through a driveway on Chester Street. Each project building would also provide a loading dock for two trucks. The loading dock for Buildings T1 and T4 would be on Mandela Parkway and the loading dock for Building T3 would be on 5th Street. Based on the project site plan, the garage driveway and/or the loading docks may not provide adequate sight distance between exiting vehicles and pedestrians on the adjacent sidewalk.

Recommendation 1: While not required to address a CEQA impact, the following should be considered as part of the final design for the project:

- Review the final site plans for the project to ensure that the garage driveway on Chester Street and the loading docks for each project building would provide adequate sight distance between vehicles exiting the garage and pedestrians on the adjacent sidewalk.

The project would eliminate the existing merge on westbound 7th Street just west of Mandela Parkway in order to accommodate a Class 4 cycletrack along this segment of 7th Street. Thus the existing shared right/through lane on westbound 7th Street at Mandela Parkway would need to be converted to a right-turn lane.

With the addition of the traffic generated by the proposed project, it is expected that the 7th Street/Chester Street intersection would meet the Manual on Uniform Traffic Control Devices (MUTCD) Peak Hour Signal Warrant, and the intersection may need to be signalized. Signal warrant analysis



is used to determine whether conditions warrant the installation of a new traffic signal. However, meeting one or more signal warrants does not mean that the intersection must be signalized.

Recommendation 2: While not required to address a CEQA impact, the following should be considered as part of the final design for the project:

- Implement the following at the 7th Street/Mandela Parkway intersection:
 - Convert the existing through/right-turn lane on the westbound 7th Street approach to a right-turn/bus only lane, and remove the merge lane on westbound 7th Street west of the intersection
 - Modify the signal timings at the intersection to provide a bus only phase for the westbound approach, and reduce the signal cycle length to 90 seconds
- After the completion of the first phase of the project, conduct a signal warrant analysis at the 7th Street/Chester Street intersection to determine if and when the intersection should be signalized. If signalization is warranted, the project shall signalize the intersection with protected left-turn phasing for the east/west 7th Street approaches. In addition and as determined by the City of Oakland staff, the signal may be interconnected with existing adjacent signals along 7th Street. If signalization is not warranted, the project shall conduct an analysis to determine if other control devices, such as all-way stop controls, or rectangular rapid flash beacon (RRFB) should be installed at the intersection. The project shall implement the recommended improvement at the intersection as approved by the City of Oakland.

Bicycle Access and Bicycle Parking

Currently, Class 2 bicycle lanes are provided along the project frontage on 7th Street and on Mandela Parkway. The 7th Street bicycle lanes connect Peralta Street to the west and about 140 feet west of Mandela Parkway to the east, where they convert to Class 3 bicycle routes with shared-lane markings and continue to Union Street. The bicycle lanes on Mandela Parkway connect 3rd Street in the south and Horton Street in the north. The City's 2007 Bicycle Master Plan proposes Class 2 bicycle lanes on 7th Street between Wood and Union Streets.

The project would include the following modifications that would benefit bicyclists in the project vicinity:



- Raised one-way Class 4 separated bikeways on both sides of 7th Street between Chester Street and Mandela Parkway.
- One-way Class 4 separated bikeways on both sides of Mandela Parkway between 7th and 5th Streets.
- A bike station on the east side of the existing BART station under the BART tracks and adjacent to a mid-block crossing on Mandela Parkway. The bike station is estimated to accommodate at least 500 bicycles, and would provide a repair station.

The nearest Ford GoBike bikeshare station is located adjacent to the site on 7th Street just east of Center Street within the street right-of-way. The project would remove this station to accommodate a bus stop on eastbound 7th Street east of Center Street, but the site plan does not indicate where the bikeshare station would be relocated.

Recommendation 3: While not required to address a CEQA impact, the following should be considered as part of the final design for the project:

- Ensure that the Ford GoBike station currently located in-street on 7th Street just east of Center Street is relocated on the BART Station Plaza to provide close and convenient access to the West Oakland BART station and the bicycle facilities adjacent to the project site.

Chapter 17.117 of the Oakland Municipal Code requires long-term and short-term bicycle parking for new buildings. Long-term bicycle parking includes lockers or locked enclosures, and short-term bicycle parking includes bicycle racks. The Code requires one long-term space for every four multi-family dwelling units and one short-term space for every 20 multi-family dwelling units. The Code does not require any bicycle parking for duplexes. For office uses, the Code requires one long-term space for every 10,000 square feet of floor area and one short-term space for every 20,000 square feet of floor area. For retail uses, the Code requires one long-term space for every 12,000 square feet of floor area and one short-term space for every 5,000 square feet of floor area.

Table 4 presents the bicycle parking requirements for the proposed project. The project would be required to provide at least 229 long-term bicycle parking spaces and 71 short-term spaces.



**TABLE 4
 BICYCLE PARKING REQUIREMENTS**

| Land Use | Size ¹ | Long-Term | | Short-Term | |
|--------------------------------|-------------------|------------------------------|------------|------------------------------|------------|
| | | Spaces per Unit ² | Spaces | Spaces per Unit ² | Spaces |
| Multi-family Residential | 740 DU | 1:4 DU | 185 | 1:20 DU | 37 |
| Duplex | 22 DU | None Required | 0 | None Required | 0 |
| Office | 382.5 KSF | 1:10 KSF | 38 | 1:20 KSF | 19 |
| Retail | 75.0 KSF | 1:12 KSF | 6 | 1:5 KSF | 15 |
| Total Required Bicycle Spaces | | | 229 | | 71 |
| Total Bicycle Parking Provided | | | 252 | | 94 |
| Bicycle Parking Met? | | | Yes | | Yes |

Notes:

1. DU = dwelling unit, KSF = 1,000 square feet
2. Based on Oakland Municipal Code Sections 17.117.090 and 17.117.110

Source: Fehr & Peers, 2019.

The project would provide 252 long-term bicycle parking spaces, which would consist of bike rooms for 150 bicycles in the T1 building (northeast corner of the site), 70 bicycles in the T3 building (southwest corner of the site), and 32 bicycles in the T4 building (southeast corner of the site). Thus, the project would exceed the minimum requirements for long-term bicycle parking.

The project would provide 94 short-term bicycle parking spaces. The short-term spaces would consist of bicycle racks for 34 bicycles along the 5th Street frontage, 40 bicycles along the 7th Street frontage, and 20 bicycles on the pedestrian plaza between 5th Street and the BART station. Thus, the project would exceed the minimum requirements for short-term bicycle parking.

In addition, the bike station at the BART Station would also be available to project residents, workers, and visitors.

Pedestrian Access and Circulation

Most streets in the vicinity of the project site provide sidewalks on both sides of the street, except for the south side of 5th Street between Center Street and Mandela Parkway. The project site currently provides 10-foot sidewalks along the project frontage on Mandela Parkway, 5th Street,



and Chester Street. Along the project site's 7th Street frontage, a 30-foot sidewalk is provided between Chester and Center Streets, and a 20-foot sidewalk is provided between Center Street and Mandela Parkway. The City of Oakland's 2017 Pedestrian Master Plan does not list any planned improvements along the project frontages.

Pedestrian facilities at the intersections adjacent to the site include:

- The 7th Street/Chester Street intersection is stop-controlled on both the northbound and southbound Chester Street approaches and provides directional curb ramps with truncated domes on all four corners. The intersection provides curb extensions at the northwest and northeast corners and provides colored crosswalks for all four approaches.
- The 7th Street/Center Street intersection is a signalized T-intersection that provides directional curb ramps with truncated domes on all corners and approaches. The intersection provides curb extensions at the northwest and northeast corners and provides colored crosswalks, and pedestrian countdown signal heads and push buttons for all three approaches. The signal currently provides continuous green phase for the east/west 7th Street approaches, unless vehicles are detected on the southbound Center Street approach or pedestrians activate the push buttons to cross 7th Street.
- The 7th Street/Mandela Parkway intersection is a signalized intersection that provides directional curb ramps with truncated domes on all four corners. The intersection provides curb extensions at the northwest and northeast corners and provides colored crosswalks, and pedestrian countdown signal heads and push buttons for all four approaches.
- The 5th Street/Chester Street intersection is stop-controlled on both the northbound and southbound Chester Street approaches and provides diagonal curb ramps on the northeast, southeast and southwest corners and a directional curb ramp leading across 5th Street on the northwest corner. None of the curb ramps provide truncated domes, and no marked crosswalks are provided on any approach.
- The 5th Street/Center Street intersection is a T-intersection and stop-controlled on the northbound Center Street approach. The intersection provides diagonal curb ramps at both corners. Neither of the curb ramps provide truncated domes, and no marked crosswalks are provided on any approach. Currently, on-street parking is allowed along the north side of the intersection, blocking pedestrian crossings of 5th Street.
- The 5th Street/Mandela Parkway intersection is a signalized intersection that provides diagonal curb ramps with substandard truncated domes on all four corners. The intersection provides a curb extension across the 5th Street approach at the southeast corner and provides marked crosswalks, and pedestrian countdown signal heads and push buttons for all four approaches.



The project would provide pedestrian access to the BART Station from all the four streets bordering the project site, including a north-south pedestrian plaza aligned with Center Street that would provide direct access to the BART station entrance. The site would also provide internal walkways along the south side of the elevated BART tracks that would connect to Chester Street and Mandela Parkway. Each project building would have a lobby that would be accessed from the adjacent street and/or the internal site plazas. The project would include the following modifications that would benefit pedestrian access and circulation in the areas surrounding the project site:

- The project proposes a 19-foot sidewalk along the project frontage on 5th Street, between Chester Street and Mandela Parkway. The sidewalk would have a minimum eight-foot pedestrian through zone, and the sidewalk width would accommodate the needs of pedestrians, bus passengers, and curbside passenger loading.
- The project proposes a sidewalk along the project frontage on 7th Street with a minimum eight-foot pedestrian through zone between Chester Street and Mandela Parkway. The sidewalk would provide adequate width to accommodate the high level of pedestrians with pedestrian amenities such as seating, real-time bus arrival information, trash receptacles, and pedestrian-lighting.
- The project proposes an 11 to 15-foot sidewalk along the project frontage on Chester Street and a 15-foot sidewalk along Mandela Parkway between 5th and 7th Street. All sidewalks would have a minimum eight-foot pedestrian through zone.
- As part of implementing a Class 4 cycletrack along westbound 7th Street, the project would eliminate the second receiving lane west of Mandela Parkway and shorten the pedestrian crossing distance for the west crosswalk at the 7th Street/Mandela Parkway intersection.
- The sidewalks along the project frontage and the internal pedestrian plazas would provide pedestrian-scale lighting and street trees/plantings.
- At the intersections of 5th Street with Chester Street, Center Street and Mandela Parkway, the project would provide high-visibility crosswalks and directional ramps along all approaches.
- At the 5th Street/Center Street intersection, project would provide curb extensions (bulb-outs) at all four intersection corners.
- High-visibility, mid-block pedestrian crossing would be provided on Mandela Parkway between 5th and 7th Streets to align with the east-west pedestrian path within the project site. The mid-block crossing would also allow access between the bike station and the northbound Class 4 cycletrack on Mandela Parkway.



In addition, Recommendation 2 would either signalize or implement other modifications at the 7th Street/Chester Street intersection which would improve pedestrian crossings across 7th Street. The following recommendations are provided to further enhance pedestrian access for the project site:

Recommendation 4: While not required to address a CEQA impact, the following should be considered as part of the final design for the project:

- Explore the feasibility of (and implement, if feasible) installing curb extensions (bulb-outs) and directional curb ramps with truncated domes at the following locations:
 - Southwest corner of the 7th Street/Chester Street intersection.
 - All four corners of the 5th Street/Mandela Parkway intersection and curb extensions (bulb-outs) across the 5th Street approaches of the southwest and northeast corners.
- Provide all-way stop control at the 5th Street/Center Street and 5th Street/Chester Street intersection.
- If reviewed and approved by BART and Oakland Fire Department, provide rolled curb instead of curb cuts for emergency vehicle access points on Chester Street and Mandela Parkway.
- Install a pedestrian scramble at the 7th Street/Center Street intersection.
- Install improvement measures at the proposed mid-block crossing on Mandela Parkway, such as raised crosswalk, RRFB, or other measures as approved by the City of Oakland.

Recommendation 5: While not required to address a CEQA impact, the following should be considered as part of the final design for the project:

- Coordinate with the City of Oakland and the appropriate property owners to determine the feasibility of and if deemed feasible, complete the sidewalk gap on the south side of 5th Street just east of Center Street.

Transit Access

Transit service providers in the vicinity of the proposed project include BART and AC Transit.



BART provides regional rail service throughout the East Bay and across the San Francisco Bay. The proposed project is located adjacent to the West Oakland BART station. The project would eliminate the majority of the existing parking spaces used by BART rider. The project would continue to provide and enhance pedestrian and bicycle access for the BART station as described above.

Currently, the BART station is served by Lines 14, 29, 36, and 62. All bus routes are currently accommodated within the BART station and described in **Table 5**. In addition, 7th Street also accommodates bus stops for Lines 29 and 62, as well as intercity buses (Mega Bus and Bolt), and other shuttle services.

**TABLE 5
 AC TRANSIT ROUTES AND HEADWAYS**

| Line | Description | Layover at West Oakland BART | Weekday Hours of Operation | Weekday Headways ¹ | Weekend Hours of Operation | Weekend Headways ¹ |
|------|--|------------------------------|----------------------------|-------------------------------|----------------------------|-------------------------------|
| 14 | Fruitvale BART to West Oakland BART via 14th Street | 10-20 min | 5:00 AM – 11:00 PM | 15 min | 6:30 AM – 11:15 PM | 30 min |
| 29 | Emeryville Public Market to Lakeshore via Peralta Street and 10th Street | n/a | 6:00 AM – 10:45 PM | 20 (30) min | 6:00 AM – 10:45 PM | 30 min |
| 36 | UC Berkeley to West Oakland BART via Adeline Street | 10-20 min | 6:00 AM – 12:45 AM | 30 min | 6:00 AM – 12:45 AM | 30 min |
| 62 | Fruitvale BART to West Oakland BART via 7th Street | 10-20 min | 5:45 AM – 12:45 AM | 15 (20) min | 6:15 AM – 12:45 AM | 20 (30) min |

Notes:

1. Headways in parentheses show off-peak headways if different from peak headways.

Source: AC Transit and Fehr & Peers, 2019.

The proposed project would not be able to accommodate the bus stops within the project site and proposes the following modifications:

- The project would provide a bus stop/layover zone along the project frontage on 5th Street just west of Mandela Parkway. The bus zone would be at least 170 feet long and a concrete



bus pad would also be installed in the roadway. The bus stop and layover for AC Transit Lines 36 and 62 could be relocated to this location.

- The existing bus stop on eastbound 7th Street west of Mandel Parkway would be retained and extended for an approximate length of 270 feet. This stop could serve AC Transit Lines 29, 36, and 62 and could serve as both a stop and layover space for AC Transit Line 14. The bus stop would be located on a 10-foot bus island that separates the Class 4 cycletrack along this segment of 7th Street. A new bus stop would be installed on westbound 7th Street just west of Center Street that could serve AC Transit Line 29. The bus stop would be about 130 feet long. The bus stop would be located on a 10-foot bus island that separates the Class 4 cycletrack along this segment of 7th Street.
- The sidewalks along project frontage on 5th and 7th Street would have adequate width and would accommodate a high level of passenger amenities, including shelters with seating, maps and other information, and real-time bus arrival information; trash receptacles; and lighting. In addition, the roadway pavement would be upgraded to provide concrete pads for the bus stops.
- To facilitate buses turning from northbound Chester Street to eastbound 7th Street, Chester Street is redesigned so that buses are positioned closer to the center line of Chester Street, which would improve current conditions for buses. Due to the tight turning radius of the corner, buses cannot make the turn from Chester Street to 7th Street when positioned close to the curb on northbound Chester Street.

Recommendation 6: While not required to address a CEQA impact, the following should be considered as part of the final design for the project:

- Consider designating a bus stop for intercity coaches (e.g., Megabus and Bolt) and other shuttles on 7th Street between Henry and Chester Streets.

Off-street Automobile Parking Requirements

The *City of Oakland Municipal Code* sets minimum and maximum parking requirements. According to Section 17.116.060, the residential component of the project has minimum required parking of 0.5 spaces per unit and maximum allowable parking of 1.25 spaces per unit. According to Section 17.116.110, this parking requirement can be reduced by 30 percent for projects within a Transit Accessible Area² and by 20 percent for projects that provide on-site carshare spaces at the level

² "Transit Accessible Area" means the area within one-half mile of a: (1) BART Station; (2) BRT Station; (3) designated rapid bus line; or (4) transit stop served by a frequency of service interval of fifteen (15) minutes or less during the morning and afternoon peak commute periods. (Section 17.09.040)



described in Section 17.116.105. For projects with 600 to 800 residential units, Section 17.116.105 requires four carshare spaces.

For the retail and office components of the project, Section 17.116.090 does not require any parking to be provided, maximum allowable parking of 1.0 spaces for each 300 square feet of ground floor area and 1.0 spaces per 500 square feet of above ground floor area.

Table 6 presents the off-street automobile parking requirements for the proposed project, per City of Oakland Municipal Code. Because the project is located within one-half mile of a BART station and provides six on-site carshare spaces, residential parking requirements are reduced by a total of 50 percent. Overall, the project is required to provide a minimum of 191 spaces, with a maximum of 1,968 spaces allowed. The proposed project would include 400 off-street parking spaces, more than the minimum requirement and less than the maximum allowed by City Code. Consistent with Code Section 17.116.310, all parking spaces would be leased separately from the rent of the dwelling units.

**TABLE 6
 AUTOMOBILE PARKING CODE REQUIREMENTS**

| Land Use | Size ¹ | Required Off-Street Parking Supply | | Provided Off-Street Parking Supply | Within Range? |
|--------------------------|-------------------|------------------------------------|--------------|------------------------------------|---------------|
| | | Minimum | Maximum | | |
| Residential ² | 762 DU | 191 | 953 | | |
| Office ³ | 382.5 DU | 0 | 765 | | |
| Retail ³ | 75.0 KSF | 0 | 250 | | |
| Total | | 191 | 1,968 | 400 | Yes |

Notes:

1. DU = Dwelling Unit, KSF = 1,000 square feet
2. The City of Oakland off-street parking requirement for two-family and multi-family residential in the S-15W zone is a minimum of 0.5 spaces per unit, with a maximum of 1.25 spaces per unit (Section 17.116.060). The minimum is reduced to 0.25 spaces per unit for this project due to its location in a Transit Accessible Area and because it provides at least four carshare space for a project between 600 and 800 multifamily units (Section 17.116.110).
3. The City of Oakland does not have a minimum off-street parking requirement for Commercial Activities in the S-15W zone and allows a maximum of 1.0 spaces per 300 square feet of ground floor area and 1.0 spaces per 500 feet of above ground floor area.

Source: Fehr & Peers, 2019.



On-Street Parking and Curb Use

Most streets currently provide unrestricted parking along both sides of the street in the vicinity of the project site except the following:

- On-street parking is currently prohibited along the project frontage on 7th Street and the east side of Mandela Parkway between 5th and 7th Streets.
- On-street parking along the north side of 7th Street between Mandela Parkway and Center Street is limited to two-hours from 8:00 AM to 6:00 PM Monday through Saturday
- On-Street parking on south side of 5th Street between Chester and Center Street, on the west side Chester Street between 5th and 7th Street and many of the residential streets to the south, west, and north of the site is controlled by residential parking permit (RPP), where vehicles without RPP are restricted to a two-hour time limit between 8:00 AM and 6:00 PM Monday through Saturday except for those with a residential parking permit.

The project site currently contains surface parking lots providing 413 parking spaces for BART riders. About 80 feet of white curb for passenger loading/unloading and about 20 feet of blue curb for accessible loading/unloading is provided on an internal drive aisle adjacent to the BART station entrance. The project would eliminate the internal loading zones and surface parking lots. The project would relocate the passenger loading zones to the streets along the project frontage, which can be used for both BART riders and project residents, workers, and visitors. The project proposes the following uses for the curbs in the project vicinity:

- The following would be designated for passenger loading and unloading:
 - Approximately 100 feet of linear curb along the north side of 5th street east of Center Street and about 200 feet west of Center Street
 - Approximately 250 feet of linear curb along eastbound 7th Street between Chester and Center Streets, with about 50 feet of curb on eastbound 7th Street just west of Center Street designated as a blue accessible loading zone
- Parking would be prohibited at the following locations:
 - On both sides of Mandela Parkway between 5th and 7th Street
 - On the east side of Chester Street between 5th and 7th Streets and on the west side of Chester Street for about 100 feet south of 7th Street.



The proposed space for passenger loading is much greater than the approximately 100 feet of linear white curb currently available at the station. The West Oakland station has one of the highest shares of pick-up/drop-off access modes, and that condition is likely to continue in the future considering the removal of parking and the station's location within the BART system and its proximity to I-880.

INTERSECTION OPERATIONS

Intersection operations under Existing Conditions and Existing Plus Project conditions were analyzed for the six study intersections. The traffic volumes, intersection lane configurations, and traffic controls presented on **Figure 1** form the basis for the intersection level of service (LOS) analysis under Existing Conditions.³ The project trip assignment was added to the Existing Conditions peak hour traffic volumes to estimate the Existing plus Project peak hour traffic volumes, as shown on **Figure 2**.

The Existing Plus Project analysis also accounts for the modifications to the streets as proposed by the project or as recommended in this memorandum. The main modifications that would affect intersection operations include:

- 7th Street/Mandela Parkway intersection:
 - Convert the existing through/right-turn lane on the westbound 7th Street approach to a right-turn/bus only lane, and remove the merge lane on westbound 7th Street west of the intersection
 - Modify the signal timings at the intersection to provide a bus only phase for the westbound approach, and reduce the signal cycle length to 90 seconds
- 7th Street/Center Street intersection:
 - Modify signal timings at the intersection to provide a pedestrian scramble phase.
- 7th Street/Chester Street intersection:
 - Convert intersection from side-street stop-controlled to signalized operations with protected left-turn phasing for the east/west 7th Street approaches.

³ The operations of roadway facilities are typically described with the term level of service (LOS), a qualitative description of traffic flow based on factors such as speed, travel time, delay, and freedom to maneuver. Six levels are defined from LOS A, which reflects free-flow conditions where there is very little interaction between vehicles, to LOS F, where the vehicle demand exceeds the capacity and high levels of vehicle delay result. LOS E represents "at-capacity" operations. When traffic volumes exceed the intersection capacity, stop-and-go conditions result and a vehicle may wait through multiple signal cycles before passing through the intersection; these operations are designated as LOS F.



- 5th Street/Chester Street and 5th Street/Center Street:
 - Convert intersections from side-street stop-controlled to all-way stop-controlled.

Table 7 summarizes the results of the intersection operations analysis under Existing Conditions and Existing Plus Project conditions. **Appendix B** provides the detailed intersection LOS calculation worksheets.

**TABLE 7
 EXISTING AND EXISTING PLUS PROJECT CONDITIONS
 STUDY INTERSECTION LOS SUMMARY**

| Intersection | Traffic Control ¹ | Peak Hour | Existing | | Existing Plus Project | |
|--|----------------------------------|-----------|------------------------------|------------------|------------------------------|------------------|
| | | | Delay ² (seconds) | LOS ² | Delay ² (seconds) | LOS ² |
| 1. 7th Street/Chester Street | SSSC/ Signalized ⁴ | AM | 10 (23) | A (C) | 26 | C |
| | | PM | 8 (29) | A (D) | 27 | C |
| 2. 7th Street/Center Street ³ | Signalized | AM | 3 | A | 3 | A |
| | | PM | 4 | A | 3 | A |
| 3. 7th Street/Mandela Parkway | Signalized | AM | 33 | C | 29 | C |
| | | PM | 34 | C | 28 | C |
| 4. 5th Street/Chester Street | SSSC/ AWSC ⁵ | AM | 4 (10) | A (A) | 8 | A |
| | | PM | 4 (11) | A (B) | 5 | A |
| 5. 5th Street/Center Street | SSSC/ AWSC ⁵ | AM | 1 (9) | A (A) | 9 | A |
| | | PM | 1 (10) | A (A) | 9 | A |
| 6. 5th Street/Mandela Parkway | Signalized | AM | 8 | A | 9 | A |
| | | PM | 9 | A | 9 | A |

1. SSSC = Side-Street Stop-Controlled; AWSC = All-Way Stop-Controlled
2. Average intersection delay and LOS based on the 2010 HCM method except where noted. Average delay is reported for signalized intersections. Average and worst-approach delays, respectively, are reported for side-street stop controlled intersections.
3. Average intersection delay and LOS based on HCM 2000 because the intersection cannot be accurately evaluated in the 2010 HCM.
4. Side-street stop-controlled under Existing conditions; signalized under Existing Plus Project conditions.
5. Side-street stop-controlled under Existing conditions; all-way stop-controlled under Existing Plus Project conditions.

Source: Fehr & Peers, 2019.

All study intersections operate at LOS D or better under both Existing Conditions and Existing Plus Project conditions. Note that the northbound approach at the 7th Street/Chester Street intersection would operate at LOS F during both the AM and PM peak hours under Existing Plus Project conditions if the intersection remains side-street stop-controlled. The 7th Street/Chester Street



intersection would meet the MUTCD Peak Hour Signal Warrant under Existing Plus Project conditions. The intersection would operate at LOS C during both AM and PM peak hours with a signalized intersection.

COLLISION ANALYSIS

A five-year history (January 1, 2013 to December 31, 2017) of collision data in the study area was obtained from the Statewide Integrated Traffic Records System (SWITRS) and evaluated for this collision analysis. **Table 8** summarizes the collision data by type and location, and **Table 9** summarizes the collision data by severity and location.

As shown in Table 8, 24 collisions were reported adjacent to the project site during this five-year period. The most common collision type was broadside (25 percent), and the most frequent primary collision factor violation category was vehicles making an improper turn (33 percent). Pedestrians were involved in three (13 percent) and bicyclists were also involved in three (13 percent) of the reported collisions. Of the 24 reported collisions, 12 (50 percent) resulted in injuries, and none resulted in fatalities, as shown in Table 9.

The Highway Safety Manual (HSM, Predictive Method - Volume 2, Part C) provides a methodology to predict the number of collisions for intersections and street segments based on roadway and intersection characteristics like vehicle and pedestrian volumes, number of lanes, signal phasing, on-street parking, and number of driveways. **Table 10** presents the predicted collision frequencies for the six study intersections and six study segments using the HSM Predictive Method for Urban and Suburban Arterials and compares predicted collision frequencies to reported collision frequencies. **Appendix C** provides detailed predicted collision frequency calculation sheets based on the HSM methodology. Intersections or roadway segments with collision frequency greater than the predicted frequency should have their collision trends and potential roadway or intersection modifications evaluated in greater detail.



**TABLE 8
 SUMMARY OF COLLISIONS BY TYPE**

| Location | Head-on | Sideswipe | Rear-End | Broadside | Hit Object | Pedestrian-Involved | Bicycle-Involved | Total |
|--|----------|-----------|----------|-----------|------------|---------------------|------------------|-----------|
| Intersection | | | | | | | | |
| 7th Street/Chester Street | 0 | 1 | 1 | 1 | 0 | 0 | 0 | 3 |
| 7th Street/Center Street | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 1 |
| 7th Street/Mandela Parkway | 0 | 3 | 1 | 0 | 0 | 2 | 2 | 8 |
| 5th Street/Chester Street | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5th Street/Center Street | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5th Street/Mandela Parkway | 0 | 0 | 0 | 1 | 1 | 1 | 0 | 3 |
| Roadway Segment | | | | | | | | |
| 7th Street between Chester Street and Center Street | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 |
| 7th Street between Center Street and Mandela Parkway | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5th Street between Chester Street and Center Street | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5th Street between Center Street and Mandela Parkway | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 |
| Chester Street between 7th Street and 5th Street | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| Mandela Parkway between 7th Street and 5th Street | 1 | 1 | 1 | 3 | 0 | 0 | 0 | 6 |
| Total | 1 | 5 | 4 | 6 | 2 | 3 | 3 | 24 |

Notes:

1. Based on SWITRS five-year collision data reported from January 1, 2013 to December 31, 2017.
 Source: SWITRS, Fehr & Peers, 2019.



**TABLE 9
 SUMMARY OF COLLISION SEVERITY**

| Location | Property Damage Only | Injury Collisions | Fatality Collisions | Total | Person-Injuries | | | |
|--|----------------------|-------------------|---------------------|-----------|-----------------|----------|-------------------|-----------|
| | | | | | Bike | Ped | Driver/ Passenger | Total |
| Intersection | | | | | | | | |
| 7th Street/Chester Street | 2 | 1 | 0 | 3 | 0 | 0 | 1 | 1 |
| 7th Street/Center Street | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 |
| 7th Street/Mandela Parkway | 2 | 6 | 0 | 8 | 2 | 2 | 3 | 7 |
| 5th Street/Chester Street | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5th Street/Center Street | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5th Street/Mandela Parkway | 2 | 1 | 0 | 3 | 0 | 1 | 0 | 1 |
| Roadway Segment | | | | | | | | |
| 7th Street between Chester Street and Center Street | 0 | 1 | 0 | 1 | 0 | 0 | 3 | 3 |
| 7th Street between Center Street and Mandela Parkway | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5th Street between Chester Street and Center Street | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5th Street between Center Street and Mandela Parkway | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 |
| Chester Street between 7th Street and 5th Street | 0 | 1 | 0 | 1 | 1 | 0 | 0 | 1 |
| Mandela Parkway between 7th Street and 5th Street | 4 | 2 | 0 | 6 | 0 | 0 | 2 | 2 |
| Total | 12 | 12 | 0 | 24 | 3 | 3 | 9 | 15 |

Notes:

1. Based on SWITRS five-year collision data reported from January 1, 2013 to December 31, 2017.
 Source: SWITRS, Fehr & Peers, 2019.



**TABLE 10
 PREDICTED AND ACTUAL COLLISION FREQUENCIES**

| Location | Predicted Collision Frequency ¹ (per year) | Actual Collision Frequency ² (per year) | Difference | Higher Than Predicted? |
|--|--|---|------------|------------------------|
| Intersection | | | | |
| 7th Street/Chester Street | 0.8 | 0.6 | -0.2 | No |
| 7th Street/Center Street | 0.6 | 0.2 | -0.4 | No |
| 7th Street/Mandela Parkway | 2.0 | 1.6 | -0.4 | No |
| 5th Street/Chester Street | 0.4 | 0.0 | -0.4 | No |
| 5th Street/Center Street | 0.2 | 0.0 | -0.2 | No |
| 5th Street/Mandela Parkway | 1.3 | 0.6 | -0.7 | No |
| Roadway Segment | | | | |
| 7th Street between Chester Street and Center Street | 0.3 | 0.2 | -0.1 | No |
| 7th Street between Center Street and Mandela Parkway | 0.2 | 0.0 | -0.2 | No |
| 5th Street between Chester Street and Center Street | 0.1 | 0.0 | -0.1 | No |
| 5th Street between Center Street and Mandela Parkway | 0.6 | 0.2 | -0.4 | No |
| Chester Street between 7th Street and 5th Street | 0.1 | 0.0 | -0.1 | No |
| Mandela Parkway between 7th Street and 5th Street | 0.4 | 1.2 | 0.8 | Yes |

Notes:

1. Based on the Highway Safety Manual Predictive Method (Volume 2, Part C)
2. Based on five-year collision data reported from January 1, 2013 to December 31, 2017.

Source: Fehr & Peers, 2019



As shown in Table 10, all study locations had a lower reported collision frequency than predicted by the HSM, except for Mandela Parkway between 7th Street and 5th Street. The collisions along this segment mostly occurred near the BART station driveway on the west side of the street. Sight distance between the vehicles exiting the BART driveway and vehicles traveling northbound on Mandela Parkway is limited due to on-street parking on the west side street. Half of the collisions along this street segment were broadside collisions, which is consistent with the limited sight distance at the BART driveway. The project would eliminate the BART station driveway, and on-street parking, which would improve safety along this segment of Mandela Parkway. Thus, no additional modifications related to roadway safety beyond the ones provided in this memorandum are recommended.

CONCLUSION

Per the site plan review, the project would have adequate automobile, bicycle, pedestrian, and transit access and circulation with the inclusion of **Recommendations 1** through **6**.

Please contact Sam Tabibnia (s.tabibnia@fehrandpeers.com or 510-835-1943) with questions or comments.

ATTACHMENTS


Figure 1 - Existing Conditions Peak Hour Intersection Traffic Volumes, Lane Configurations and Traffic Controls

Figure 2 - Existing Plus Project Peak Hour Intersection Traffic Volumes, Lane Configurations and Traffic Controls

Appendix A – Traffic Counts

Appendix B – Intersection Analysis Worksheets

Appendix C – Predicted Crash Frequency Calculation Sheets



XX (YY) AM (PM) Peak Hour Traffic Volumes Signalized Intersection Stop Sign
 Project Site Study Intersection






OK18-0294_X_Volumes



| 1. Chester Street/7th Street | 2. Center Street/7th Street | 3. Mandela Pkwy/7th Street |
|--|--|--|
| <p>5 (5) 20 (13) 4 (10)</p> <p>17 (28) 136 (201) 91 (80)</p> <p>7 (8) 136 (315) 56 (64)</p> <p>63 (45) 38 (26) 138 (117)</p> | <p>19 (30) 16 (20)</p> <p>32 (34) 255 (255)</p> <p>17 (20) 266 (424)</p> | <p>36 (37) 283 (234) 73 (132)</p> <p>80 (106) 220 (201) 183 (146)</p> <p>65 (72) 197 (319) 23 (34)</p> <p>23 (37) 116 (196) 70 (117)</p> |
| 4. Chester Street/5th Street | 5. Center Street/5th Street | 6. Mandela Pkwy/5th Street |
| <p>13 (11) 4 (5) 38 (35)</p> <p>40 (58) 29 (54) 5 (22)</p> <p>2 (7) 38 (29) 0 (4)</p> <p>0 (2) 3 (7) 13 (10)</p> | <p>120 (154) 9 (21)</p> <p>153 (134) 4 (6)</p> <p>2 (6) 24 (14)</p> | <p>22 (49) 38 (108) 86 (45)</p> <p>59 (102) 122 (122) 20 (38)</p> <p>47 (67) 122 (109) 45 (36)</p> <p>9 (32) 35 (102) 17 (46)</p> |

Figure 1

Existing Peak Hour Intersection Traffic Volumes, Lane Configurations and Traffic Controls



XX (YY) AM (PM) Peak Hour Traffic Volumes  Signalized Intersection  Stop Sign

 Project Site  Study Intersection



OK18-0294_X_Volumes




Figure 2

Existing with Project Peak Hour Intersection Traffic Volumes, Lane Configurations and Traffic Controls

APPENDIX A
TRAFFIC COUNTS



National Data & Surveying Services

Intersection Turning Movement Count

Location: Chester St & 7th St
 City: Oakland
 Control: 2-Way Stop(NB/SB)

Project ID: 18-08661-001
 Date: 12/12/2018

Total

| NS/EW Streets: | Chester St | | | | Chester St | | | | 7th St | | | | 7th St | | | | TOTAL |
|-------------------------|----------------------------|--------|--------|-------|------------|--------|--------|-------|-----------|--------|--------|-------|-----------|--------|-------|-------|--------------|
| | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| AM | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 1 | 0 | 0 | 1 | 1 | 0 | 0 | TOTAL |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 7:00 AM | 11 | 6 | 16 | 0 | 2 | 4 | 0 | 0 | 0 | 29 | 12 | 0 | 13 | 41 | 4 | 0 | 138 |
| 7:15 AM | 19 | 4 | 26 | 0 | 2 | 4 | 3 | 0 | 0 | 30 | 13 | 0 | 16 | 24 | 0 | 0 | 141 |
| 7:30 AM | 9 | 13 | 31 | 2 | 2 | 7 | 1 | 0 | 0 | 35 | 11 | 0 | 20 | 30 | 5 | 1 | 167 |
| 7:45 AM | 17 | 7 | 41 | 0 | 2 | 2 | 0 | 0 | 0 | 28 | 10 | 0 | 19 | 29 | 6 | 0 | 161 |
| 8:00 AM | 17 | 6 | 27 | 0 | 0 | 4 | 0 | 0 | 2 | 36 | 13 | 2 | 24 | 33 | 5 | 0 | 169 |
| 8:15 AM | 18 | 18 | 32 | 0 | 0 | 8 | 2 | 0 | 1 | 33 | 19 | 0 | 20 | 37 | 2 | 1 | 191 |
| 8:30 AM | 11 | 7 | 38 | 0 | 2 | 6 | 3 | 0 | 2 | 39 | 14 | 0 | 27 | 37 | 4 | 0 | 190 |
| 8:45 AM | 12 | 12 | 33 | 1 | 1 | 8 | 1 | 0 | 0 | 28 | 4 | 0 | 12 | 29 | 3 | 0 | 144 |
| TOTAL VOLUMES : | 114 | 73 | 244 | 3 | 11 | 43 | 10 | 0 | 5 | 258 | 96 | 2 | 151 | 260 | 29 | 2 | 1301 |
| APPROACH %'s : | 26.27% | 16.82% | 56.22% | 0.69% | 17.19% | 67.19% | 15.63% | 0.00% | 1.39% | 71.47% | 26.59% | 0.55% | 34.16% | 58.82% | 6.56% | 0.45% | |
| PEAK HR : | 07:45 AM - 08:45 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 63 | 38 | 138 | 0 | 4 | 20 | 5 | 0 | 5 | 136 | 56 | 2 | 90 | 136 | 17 | 1 | 711 |
| PEAK HR FACTOR : | 0.875 | 0.528 | 0.841 | 0.000 | 0.500 | 0.625 | 0.417 | 0.000 | 0.625 | 0.872 | 0.737 | 0.250 | 0.833 | 0.919 | 0.708 | 0.250 | 0.931 |
| | 0.879 | | | | 0.659 | | | | 0.905 | | | | 0.897 | | | | |

| NS/EW Streets: | Chester St | | | | Chester St | | | | 7th St | | | | 7th St | | | | TOTAL |
|-------------------------|----------------------------|--------|--------|-------|------------|--------|--------|-------|-----------|--------|--------|-------|-----------|--------|-------|-------|--------------|
| | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| PM | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 1 | 0 | 0 | 1 | 1 | 0 | 0 | TOTAL |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 4:00 PM | 9 | 3 | 14 | 0 | 1 | 4 | 2 | 0 | 0 | 54 | 6 | 0 | 8 | 37 | 6 | 1 | 145 |
| 4:15 PM | 8 | 4 | 27 | 0 | 2 | 6 | 1 | 0 | 4 | 64 | 10 | 0 | 10 | 29 | 3 | 0 | 168 |
| 4:30 PM | 8 | 7 | 21 | 0 | 2 | 1 | 1 | 0 | 4 | 75 | 18 | 0 | 8 | 45 | 5 | 1 | 196 |
| 4:45 PM | 10 | 10 | 24 | 0 | 2 | 3 | 3 | 0 | 4 | 87 | 12 | 0 | 10 | 43 | 3 | 0 | 211 |
| 5:00 PM | 6 | 7 | 25 | 0 | 1 | 1 | 2 | 0 | 2 | 86 | 16 | 0 | 21 | 46 | 6 | 0 | 219 |
| 5:15 PM | 16 | 8 | 34 | 0 | 2 | 3 | 1 | 0 | 2 | 73 | 17 | 0 | 20 | 58 | 3 | 1 | 238 |
| 5:30 PM | 9 | 8 | 30 | 0 | 4 | 4 | 1 | 0 | 2 | 77 | 16 | 0 | 19 | 49 | 7 | 0 | 226 |
| 5:45 PM | 14 | 3 | 28 | 0 | 3 | 5 | 1 | 0 | 2 | 79 | 15 | 0 | 18 | 48 | 12 | 1 | 229 |
| TOTAL VOLUMES : | 80 | 50 | 203 | 0 | 17 | 27 | 12 | 0 | 20 | 595 | 110 | 0 | 114 | 355 | 45 | 4 | 1632 |
| APPROACH %'s : | 24.02% | 15.02% | 60.96% | 0.00% | 30.36% | 48.21% | 21.43% | 0.00% | 2.76% | 82.07% | 15.17% | 0.00% | 22.01% | 68.53% | 8.69% | 0.77% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 45 | 26 | 117 | 0 | 10 | 13 | 5 | 0 | 8 | 315 | 64 | 0 | 78 | 201 | 28 | 2 | 912 |
| PEAK HR FACTOR : | 0.703 | 0.813 | 0.860 | 0.000 | 0.625 | 0.650 | 0.625 | 0.000 | 1.000 | 0.916 | 0.941 | 0.000 | 0.929 | 0.866 | 0.583 | 0.500 | 0.958 |
| | 0.810 | | | | 0.778 | | | | 0.930 | | | | 0.942 | | | | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Chester St & 7th St
City: Oakland
Control: 2-Way Stop(NB/SB)

Project ID: 18-08661-001
Date: 12/12/2018

Bikes

| NS/EW Streets: | Chester St | | | | Chester St | | | | 7th St | | | | 7th St | | | | |
|-------------------------|---------------------|--------|--------|-------|------------|--------|--------|-------|-----------|--------|--------|-------|-----------|--------|--------|-------|--------------|
| AM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 7:00 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 2 |
| 7:15 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 1 | 0 | 0 | 3 |
| 7:30 AM | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 1 | 1 | 0 | 6 |
| 7:45 AM | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 3 |
| 8:00 AM | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 3 |
| 8:15 AM | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 1 | 0 | 0 | 4 |
| 8:30 AM | 1 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 6 |
| 8:45 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 2 | 0 | 0 | 0 | 0 | 0 | 4 |
| TOTAL VOLUMES : | 1 | 0 | 0 | 0 | 2 | 5 | 0 | 0 | 0 | 12 | 6 | 0 | 0 | 4 | 1 | 0 | 31 |
| APPROACH %'s : | 100.00% | 0.00% | 0.00% | 0.00% | 28.57% | 71.43% | 0.00% | 0.00% | 0.00% | 66.67% | 33.33% | 0.00% | 0.00% | 80.00% | 20.00% | 0.00% | |
| PEAK HR : | 07:45 AM - 08:45 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 1 | 0 | 0 | 0 | 1 | 4 | 0 | 0 | 0 | 5 | 4 | 0 | 0 | 1 | 0 | 0 | 16 |
| PEAK HR FACTOR : | 0.250 | 0.000 | 0.000 | 0.000 | 0.250 | 1.000 | 0.000 | 0.000 | 0.000 | 0.625 | 1.000 | 0.000 | 0.000 | 0.250 | 0.000 | 0.000 | 0.667 |
| | 0.250 | | | | 0.625 | | | | 0.750 | | | | 0.250 | | | | |
| PM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 4:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 3 | 2 | 0 | 7 |
| 4:15 PM | 1 | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 6 |
| 4:30 PM | 1 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 2 | 0 | 0 | 6 |
| 4:45 PM | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 1 | 0 | 5 |
| 5:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 0 | 1 | 2 | 2 | 0 | 7 |
| 5:15 PM | 3 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 3 | 0 | 0 | 12 |
| 5:30 PM | 2 | 0 | 1 | 0 | 1 | 0 | 0 | 0 | 0 | 1 | 2 | 0 | 1 | 4 | 0 | 0 | 12 |
| 5:45 PM | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 1 | 0 | 0 | 3 | 0 | 0 | 8 |
| TOTAL VOLUMES : | 7 | 2 | 9 | 0 | 1 | 0 | 2 | 0 | 1 | 7 | 5 | 0 | 3 | 21 | 5 | 0 | 63 |
| APPROACH %'s : | 38.89% | 11.11% | 50.00% | 0.00% | 33.33% | 0.00% | 66.67% | 0.00% | 7.69% | 53.85% | 38.46% | 0.00% | 10.34% | 72.41% | 17.24% | 0.00% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 5 | 0 | 7 | 0 | 1 | 0 | 1 | 0 | 1 | 4 | 4 | 0 | 2 | 12 | 2 | 0 | 39 |
| PEAK HR FACTOR : | 0.42 | 0.000 | 0.438 | 0.000 | 0.250 | 0.000 | 0.250 | 0.000 | 0.250 | 0.500 | 0.500 | 0.000 | 0.500 | 0.750 | 0.250 | 0.000 | 0.813 |
| | 0.429 | | | | 0.500 | | | | 0.750 | | | | 0.800 | | | | |

National Data & Surveying Services

Location: **City: Oakland**
 Project ID: **108561-001**
 Date: **12/12/2018**

Intersection Turning Movement Count

Pedestrians (Crosswalks)

| NS/EW Streets: | Chester St | | Chester St | | 7th St | | 7th St | | |
|-------------------------|----------------------------|----------|------------|----------|----------|-----------|----------|----------|--------------|
| AM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 7:00 AM | 5 | 1 | 19 | 3 | 2 | 9 | 0 | 3 | 42 |
| 7:15 AM | 6 | 2 | 21 | 3 | 1 | 19 | 0 | 0 | 52 |
| 7:30 AM | 3 | 2 | 24 | 3 | 2 | 19 | 0 | 3 | 56 |
| 7:45 AM | 5 | 3 | 18 | 1 | 2 | 18 | 1 | 3 | 51 |
| 8:00 AM | 6 | 3 | 22 | 3 | 1 | 31 | 1 | 4 | 71 |
| 8:15 AM | 3 | 2 | 22 | 1 | 1 | 17 | 0 | 2 | 48 |
| 8:30 AM | 3 | 0 | 21 | 0 | 3 | 22 | 1 | 5 | 55 |
| 8:45 AM | 4 | 2 | 26 | 5 | 2 | 13 | 1 | 4 | 57 |
| TOTAL VOLUMES : | EB 35 | WB 15 | EB 173 | WB 19 | NB 14 | SB 148 | NB 4 | SB 24 | TOTAL 432 |
| APPROACH %'s : | 70.00% | 30.00% | 90.10% | 9.90% | 8.64% | 91.36% | 14.29% | 85.71% | |
| PEAK HR : | 07:45 AM - 08:45 AM | | | | | | | | TOTAL |
| PEAK HR VOL : | 17 | 8 | 83 | 5 | 7 | 88 | 3 | 14 | 225 |
| PEAK HR FACTOR : | 0.708 | 0.667 | 0.943 | 0.417 | 0.583 | 0.710 | 0.750 | 0.700 | 0.792 |
| | 0.694 | | 0.880 | | 0.742 | | 0.708 | | |

| PM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
|-------------------------|----------------------------|----------|-----------|-----------|-----------|----------|----------|---------|--------------|
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 4:00 PM | 2 | 9 | 4 | 6 | 8 | 2 | 4 | 0 | 35 |
| 4:15 PM | 5 | 8 | 7 | 9 | 10 | 4 | 0 | 0 | 43 |
| 4:30 PM | 0 | 10 | 7 | 18 | 14 | 0 | 3 | 0 | 52 |
| 4:45 PM | 5 | 8 | 9 | 16 | 7 | 3 | 4 | 3 | 55 |
| 5:00 PM | 4 | 10 | 2 | 14 | 19 | 3 | 3 | 0 | 55 |
| 5:15 PM | 5 | 12 | 6 | 21 | 22 | 2 | 2 | 2 | 72 |
| 5:30 PM | 2 | 11 | 13 | 20 | 14 | 9 | 2 | 0 | 71 |
| 5:45 PM | 8 | 15 | 4 | 13 | 14 | 5 | 1 | 0 | 60 |
| TOTAL VOLUMES : | EB 31 | WB 83 | EB 52 | WB 117 | NB 108 | SB 28 | NB 19 | SB 5 | TOTAL 443 |
| APPROACH %'s : | 27.19% | 72.81% | 30.77% | 69.23% | 79.41% | 20.59% | 79.17% | 20.83% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | TOTAL |
| PEAK HR VOL : | 19 | 48 | 25 | 68 | 69 | 19 | 8 | 2 | 258 |
| PEAK HR FACTOR : | 0.594 | 0.800 | 0.481 | 0.810 | 0.784 | 0.528 | 0.667 | 0.250 | 0.896 |
| | 0.728 | | 0.705 | | 0.917 | | 0.625 | | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Center St & 7th St
 City: Oakland
 Control: Signalized

Project ID: 18-08661-002
 Date: 12/12/2018

Total

| NS/EW Streets: | Center St | | | | Center St | | | | 7th St | | | | 7th St | | | | TOTAL |
|-------------------------|----------------------------|-------|-------|-------|------------|-------|--------|-------|-----------|--------|-------|-------|-----------|--------|--------|-------|-------|
| | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| AM | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 7:00 AM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 2 | 42 | 0 | 0 | 0 | 46 | 3 | 0 | 96 |
| 7:15 AM | 0 | 0 | 0 | 0 | 6 | 0 | 4 | 0 | 2 | 58 | 0 | 0 | 0 | 41 | 7 | 0 | 118 |
| 7:30 AM | 0 | 0 | 0 | 0 | 7 | 0 | 5 | 0 | 6 | 58 | 0 | 0 | 0 | 59 | 9 | 0 | 144 |
| 7:45 AM | 0 | 0 | 0 | 0 | 2 | 0 | 3 | 0 | 3 | 73 | 0 | 0 | 0 | 58 | 3 | 0 | 142 |
| 8:00 AM | 0 | 0 | 0 | 0 | 5 | 0 | 6 | 0 | 3 | 61 | 0 | 1 | 0 | 64 | 15 | 0 | 155 |
| 8:15 AM | 0 | 0 | 0 | 0 | 4 | 0 | 7 | 0 | 5 | 59 | 0 | 0 | 0 | 59 | 10 | 0 | 144 |
| 8:30 AM | 0 | 0 | 0 | 0 | 5 | 0 | 3 | 0 | 5 | 73 | 0 | 0 | 0 | 74 | 4 | 0 | 164 |
| 8:45 AM | 0 | 0 | 0 | 0 | 5 | 0 | 4 | 0 | 1 | 62 | 0 | 0 | 0 | 50 | 10 | 0 | 132 |
| TOTAL VOLUMES : | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| APPROACH %'s : | 0 | 0 | 0 | 0 | 34 | 0 | 35 | 0 | 27 | 486 | 0 | 1 | 0 | 451 | 61 | 0 | 1095 |
| | | | | | 49.28% | 0.00% | 50.72% | 0.00% | 5.25% | 94.55% | 0.00% | 0.19% | 0.00% | 88.09% | 11.91% | 0.00% | |
| PEAK HR : | 07:45 AM - 08:45 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 0 | 0 | 0 | 16 | 0 | 19 | 0 | 16 | 266 | 0 | 1 | 0 | 255 | 32 | 0 | 605 |
| PEAK HR FACTOR : | 0.000 | 0.000 | 0.000 | 0.000 | 0.800 | 0.000 | 0.679 | 0.000 | 0.800 | 0.911 | 0.000 | 0.250 | 0.000 | 0.861 | 0.533 | 0.000 | 0.922 |
| | | | | | 0.795 | | | | 0.907 | | | | 0.908 | | | | |

| NS/EW Streets: | Center St | | | | Center St | | | | 7th St | | | | 7th St | | | | TOTAL |
|-------------------------|----------------------------|-------|-------|-------|------------|-------|--------|-------|-----------|--------|-------|-------|-----------|--------|--------|-------|-------|
| | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| PM | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 4:00 PM | 0 | 0 | 0 | 0 | 7 | 0 | 6 | 0 | 3 | 67 | 0 | 0 | 0 | 40 | 13 | 0 | 136 |
| 4:15 PM | 0 | 0 | 0 | 0 | 6 | 0 | 5 | 0 | 2 | 101 | 0 | 0 | 0 | 36 | 11 | 1 | 162 |
| 4:30 PM | 0 | 0 | 0 | 0 | 6 | 0 | 3 | 0 | 1 | 99 | 0 | 0 | 0 | 49 | 12 | 0 | 170 |
| 4:45 PM | 0 | 0 | 0 | 0 | 5 | 0 | 4 | 0 | 6 | 101 | 0 | 1 | 0 | 48 | 10 | 0 | 175 |
| 5:00 PM | 0 | 0 | 0 | 0 | 7 | 0 | 8 | 0 | 6 | 114 | 0 | 0 | 0 | 61 | 7 | 1 | 204 |
| 5:15 PM | 0 | 0 | 0 | 0 | 6 | 0 | 10 | 0 | 3 | 102 | 0 | 0 | 0 | 68 | 11 | 0 | 200 |
| 5:30 PM | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 | 6 | 101 | 0 | 0 | 0 | 64 | 8 | 0 | 190 |
| 5:45 PM | 0 | 0 | 0 | 0 | 4 | 0 | 4 | 0 | 3 | 107 | 0 | 2 | 0 | 61 | 8 | 0 | 189 |
| TOTAL VOLUMES : | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| APPROACH %'s : | 0 | 0 | 0 | 0 | 44 | 0 | 48 | 0 | 30 | 792 | 0 | 3 | 0 | 427 | 80 | 2 | 1426 |
| | | | | | 47.83% | 0.00% | 52.17% | 0.00% | 3.64% | 96.00% | 0.00% | 0.36% | 0.00% | 83.89% | 15.72% | 0.39% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 0 | 0 | 0 | 20 | 0 | 30 | 0 | 18 | 424 | 0 | 2 | 0 | 254 | 34 | 1 | 783 |
| PEAK HR FACTOR : | 0.000 | 0.000 | 0.000 | 0.000 | 0.714 | 0.000 | 0.750 | 0.000 | 0.750 | 0.930 | 0.000 | 0.250 | 0.000 | 0.934 | 0.773 | 0.250 | 0.960 |
| | | | | | 0.781 | | | | 0.925 | | | | 0.915 | | | | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Center St & 7th St
City: Oakland
Control: Signalized

Project ID: 18-08661-002
Date: 12/12/2018

Bikes

| NS/EW Streets: | Center St | | | | Center St | | | | 7th St | | | | 7th St | | | | |
|-------------------------|----------------------------|--------|--------|-------|------------|---------|--------|-------|-----------|--------|--------|-------|-----------|--------|-------|-------|--------------|
| AM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 7:00 AM | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 1 | 0 | 3 | 2 | 0 | 0 | 10 |
| 7:15 AM | 0 | 6 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 2 | 0 | 0 | 12 |
| 7:30 AM | 0 | 1 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 8 | 0 | 0 | 0 | 15 |
| 7:45 AM | 0 | 0 | 1 | 0 | 0 | 7 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 10 |
| 8:00 AM | 0 | 10 | 2 | 0 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 11 | 1 | 0 | 0 | 29 |
| 8:15 AM | 0 | 2 | 1 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 0 | 0 | 14 |
| 8:30 AM | 0 | 5 | 6 | 0 | 0 | 6 | 0 | 0 | 0 | 1 | 0 | 0 | 7 | 0 | 0 | 0 | 25 |
| 8:45 AM | 0 | 1 | 1 | 0 | 0 | 4 | 0 | 0 | 0 | 1 | 0 | 0 | 10 | 0 | 0 | 0 | 17 |
| TOTAL VOLUMES : | 0 | 25 | 15 | 0 | 0 | 31 | 0 | 0 | 0 | 5 | 1 | 0 | 49 | 6 | 0 | 0 | 132 |
| APPROACH %'s : | 0.00% | 62.50% | 37.50% | 0.00% | 0.00% | 100.00% | 0.00% | 0.00% | 0.00% | 83.33% | 16.67% | 0.00% | 89.09% | 10.91% | 0.00% | 0.00% | |
| PEAK HR : | 07:45 AM - 08:45 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 17 | 10 | 0 | 0 | 21 | 0 | 0 | 0 | 2 | 0 | 0 | 26 | 2 | 0 | 0 | 78 |
| PEAK HR FACTOR : | 0.000 | 0.425 | 0.417 | 0.000 | 0.000 | 0.750 | 0.000 | 0.000 | 0.000 | 0.500 | 0.000 | 0.000 | 0.591 | 0.500 | 0.000 | 0.000 | 0.672 |
| | 0.563 | | | | 0.750 | | | | 0.500 | | | | 0.583 | | | | |
| PM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 4:00 PM | 2 | 1 | 2 | 0 | 0 | 1 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 8 |
| 4:15 PM | 0 | 1 | 4 | 0 | 0 | 1 | 0 | 0 | 0 | 2 | 0 | 0 | 2 | 1 | 0 | 0 | 11 |
| 4:30 PM | 2 | 1 | 5 | 0 | 0 | 4 | 1 | 0 | 0 | 1 | 0 | 0 | 2 | 0 | 0 | 0 | 16 |
| 4:45 PM | 1 | 3 | 8 | 0 | 0 | 4 | 1 | 0 | 0 | 0 | 0 | 0 | 3 | 1 | 0 | 0 | 21 |
| 5:00 PM | 1 | 1 | 8 | 0 | 1 | 2 | 0 | 0 | 0 | 1 | 0 | 0 | 6 | 1 | 0 | 1 | 22 |
| 5:15 PM | 1 | 2 | 9 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 5 | 4 | 0 | 0 | 23 |
| 5:30 PM | 0 | 4 | 3 | 0 | 0 | 1 | 0 | 0 | 0 | 2 | 0 | 0 | 7 | 2 | 1 | 0 | 20 |
| 5:45 PM | 0 | 6 | 6 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 3 | 0 | 0 | 21 |
| TOTAL VOLUMES : | 7 | 19 | 45 | 0 | 1 | 17 | 2 | 0 | 1 | 8 | 0 | 0 | 28 | 12 | 1 | 1 | 142 |
| APPROACH %'s : | 9.86% | 26.76% | 63.38% | 0.00% | 5.00% | 85.00% | 10.00% | 0.00% | 11.11% | 88.89% | 0.00% | 0.00% | 66.67% | 28.57% | 2.38% | 2.38% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 2 | 13 | 26 | 0 | 1 | 7 | 0 | 0 | 0 | 4 | 0 | 0 | 21 | 10 | 1 | 1 | 86 |
| PEAK HR FACTOR : | 0.50 | 0.542 | 0.722 | 0.000 | 0.250 | 0.583 | 0.000 | 0.000 | 0.000 | 0.500 | 0.000 | 0.000 | 0.750 | 0.625 | 0.250 | 0.250 | 0.935 |
| | 0.854 | | | | 0.667 | | | | 0.500 | | | | 0.825 | | | | |

National Data & Surveying Services

Location: Center St & 7th St **Project ID:** 1108561-007
City: Oakland **Date:** 12/12/2018

Pedestrians (Crosswalks)

| NS/EW Streets: | Center St | | Center St | | 7th St | | 7th St | | |
|------------------|---------------------|----------|-----------|---------|----------|-----------|----------|-----------|--------------|
| AM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 7:00 AM | 4 | 1 | 0 | 0 | 1 | 7 | 7 | 14 | 34 |
| 7:15 AM | 5 | 5 | 0 | 0 | 5 | 10 | 19 | 32 | 76 |
| 7:30 AM | 3 | 1 | 0 | 0 | 3 | 17 | 15 | 26 | 65 |
| 7:45 AM | 2 | 3 | 0 | 0 | 4 | 12 | 8 | 22 | 51 |
| 8:00 AM | 1 | 1 | 0 | 0 | 6 | 17 | 5 | 29 | 59 |
| 8:15 AM | 2 | 2 | 0 | 0 | 4 | 17 | 11 | 33 | 69 |
| 8:30 AM | 2 | 2 | 0 | 0 | 5 | 17 | 1 | 25 | 52 |
| 8:45 AM | 3 | 3 | 0 | 0 | 2 | 16 | 5 | 19 | 48 |
| TOTAL VOLUMES : | EB 22 | WB 18 | EB 0 | WB 0 | NB 30 | SB 113 | NB 71 | SB 200 | TOTAL 454 |
| APPROACH %'s : | 55.00% | 45.00% | | | 20.98% | 79.02% | 26.20% | 73.80% | |
| PEAK HR : | 07:45 AM - 08:45 AM | | | | | | | | TOTAL |
| PEAK HR VOL : | 7 | 8 | 0 | 0 | 19 | 63 | 25 | 109 | 231 |
| PEAK HR FACTOR : | 0.875 | 0.667 | | | 0.792 | 0.926 | 0.568 | 0.826 | 0.837 |
| | 0.750 | | | | 0.891 | | 0.761 | | |

| PM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
|------------------|---------------------|----------|-----------|---------|----------|----------|-----------|----------|--------------|
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 4:00 PM | 7 | 3 | 0 | 0 | 7 | 4 | 17 | 7 | 45 |
| 4:15 PM | 4 | 10 | 0 | 0 | 11 | 0 | 26 | 4 | 55 |
| 4:30 PM | 9 | 5 | 0 | 0 | 8 | 4 | 32 | 11 | 69 |
| 4:45 PM | 8 | 2 | 0 | 0 | 8 | 8 | 32 | 10 | 68 |
| 5:00 PM | 9 | 5 | 0 | 0 | 8 | 4 | 32 | 18 | 76 |
| 5:15 PM | 10 | 4 | 0 | 0 | 16 | 5 | 29 | 9 | 73 |
| 5:30 PM | 6 | 7 | 0 | 0 | 15 | 6 | 15 | 9 | 58 |
| 5:45 PM | 9 | 5 | 0 | 0 | 26 | 2 | 42 | 10 | 94 |
| TOTAL VOLUMES : | EB 62 | WB 41 | EB 0 | WB 0 | NB 99 | SB 33 | NB 225 | SB 78 | TOTAL 538 |
| APPROACH %'s : | 60.19% | 39.81% | | | 75.00% | 25.00% | 74.26% | 25.74% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | TOTAL |
| PEAK HR VOL : | 34 | 21 | 0 | 0 | 65 | 17 | 118 | 46 | 301 |
| PEAK HR FACTOR : | 0.850 | 0.750 | | | 0.625 | 0.708 | 0.702 | 0.639 | 0.801 |
| | 0.982 | | | | 0.732 | | 0.788 | | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Mandela Pkwy & 7th St
 City: Oakland
 Control: Signalized

Project ID: 18-08661-003
 Date: 12/12/2018

Bikes

| NS/EW Streets: | Mandela Pkwy | | | | | Mandela Pkwy | | | | | 7th St | | | | | 7th St | | | | | NORTHBOUND2 | | | | | | TOTAL | | | | | | |
|-------------------------|----------------------------|--------|-------|-------|-------|--------------|--------|--------|-------|-------|-----------|--------|--------|-------|-------|-----------|--------|--------|-------|-------|-------------|-------|-------|-------|---------|-------|-------|---|---|---|---|---|-------|
| | NORTHBOUND | | | | | SOUTHBOUND | | | | | EASTBOUND | | | | | WESTBOUND | | | | | NORTHBOUND2 | | | | | | | | | | | | |
| AM | 0 | 1 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | TOTAL |
| | NL | NT | NR | NU | NU2 | SL | ST | SR | SU | ST2 | EL | ET | ER | EU | ER2 | WL | WT | WR | WU | WL2 | N2L | N2U | N2L2 | N2T2 | N2R2 | N2U2 | TOTAL | | | | | | |
| 7:00 AM | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 9 |
| 7:15 AM | 0 | 1 | 0 | 0 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 |
| 7:30 AM | 1 | 0 | 0 | 0 | 0 | 0 | 5 | 8 | 0 | 0 | 0 | 5 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 22 |
| 7:45 AM | 0 | 1 | 0 | 0 | 0 | 0 | 3 | 4 | 0 | 0 | 0 | 3 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13 |
| 8:00 AM | 0 | 0 | 0 | 0 | 0 | 0 | 9 | 12 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 3 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 27 |
| 8:15 AM | 0 | 1 | 0 | 0 | 0 | 0 | 10 | 6 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 21 |
| 8:30 AM | 0 | 0 | 0 | 0 | 0 | 0 | 9 | 8 | 0 | 0 | 4 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 22 |
| 8:45 AM | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 8 | 0 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 21 |
| TOTAL VOLUMES : | NL | NT | NR | NU | NU2 | SL | ST | SR | SU | ST2 | EL | ET | ER | EU | ER2 | WL | WT | WR | WU | WL2 | N2L | N2U | N2L2 | N2T2 | N2R2 | N2U2 | TOTAL | | | | | | |
| APPROACH %'s : | 25.00% | 75.00% | 0.00% | 0.00% | 0.00% | 0.00% | 48.51% | 51.49% | 0.00% | 0.00% | 71.43% | 17.86% | 10.71% | 0.00% | 0.00% | 10.00% | 70.00% | 20.00% | 0.00% | 0.00% | 0 | 0 | 0 | 0 | 0 | 0 | 143 | | | | | | |
| PEAK HR : | 07:45 AM - 08:45 AM | | | | | | | | | | | | | | | | | | | | TOTAL | | | | | | | | | | | | |
| PEAK HR VOL : | 0 | 2 | 0 | 0 | 0 | 0 | 31 | 30 | 0 | 0 | 10 | 3 | 0 | 0 | 0 | 0 | 5 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 83 | | | | | | |
| PEAK HR FACTOR : | 0.000 | 0.500 | 0.000 | 0.000 | 0.000 | 0.000 | 0.775 | 0.625 | 0.000 | 0.000 | 0.625 | 0.375 | 0.000 | 0.000 | 0.000 | 0.000 | 0.417 | 0.250 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.769 | | | | | | |
| | | | | | 0.500 | | | | | 0.726 | | | | | 0.650 | | | | | 0.350 | | | | | | | | | | | | | |
| PM | 0 | 1 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | TOTAL | | | | | | |
| | NL | NT | NR | NU | NU2 | SL | ST | SR | SU | ST2 | EL | ET | ER | EU | ER2 | WL | WT | WR | WU | WL2 | N2L | N2U | N2L2 | N2T2 | N2R2 | N2U2 | TOTAL | | | | | | |
| 4:00 PM | 0 | 1 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | | | | | | |
| 4:15 PM | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 3 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 13 | | | | | | |
| 4:30 PM | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 6 | 1 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 17 | | | | | | |
| 4:45 PM | 0 | 2 | 0 | 0 | 0 | 0 | 2 | 4 | 0 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 16 | | | | | | |
| 5:00 PM | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 10 | 1 | 0 | 0 | 0 | 0 | 5 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 24 | | | | | | |
| 5:15 PM | 1 | 8 | 1 | 0 | 0 | 0 | 1 | 5 | 0 | 0 | 7 | 1 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 27 | | | | | | |
| 5:30 PM | 1 | 7 | 0 | 0 | 0 | 0 | 3 | 6 | 0 | 0 | 5 | 2 | 0 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 27 | | | | | | |
| 5:45 PM | 0 | 10 | 1 | 0 | 0 | 0 | 1 | 4 | 0 | 0 | 5 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 22 | | | | | | |
| TOTAL VOLUMES : | NL | NT | NR | NU | NU2 | SL | ST | SR | SU | ST2 | EL | ET | ER | EU | ER2 | WL | WT | WR | WU | WL2 | N2L | N2U | N2L2 | N2T2 | N2R2 | N2U2 | TOTAL | | | | | | |
| APPROACH %'s : | 4.44% | 91.11% | 4.44% | 0.00% | 0.00% | 0.00% | 24.24% | 75.76% | 0.00% | 0.00% | 83.33% | 16.67% | 0.00% | 0.00% | 0.00% | 6.25% | 81.25% | 12.50% | 0.00% | 0.00% | 0.00% | 0.00% | 0.00% | 0.00% | 100.00% | 0.00% | 149 | | | | | | |
| PEAK HR : | 04:45 PM - 05:45 PM | | | | | | | | | | | | | | | | | | | | TOTAL | | | | | | | | | | | | |
| PEAK HR VOL : | 2 | 20 | 1 | 0 | 0 | 0 | 6 | 18 | 0 | 0 | 28 | 4 | 0 | 0 | 0 | 1 | 11 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 94 | | | | | | |
| PEAK HR FACTOR : | 0.50 | 0.625 | 0.250 | 0.000 | 0.000 | 0.000 | 0.500 | 0.750 | 0.000 | 0.000 | 0.700 | 0.500 | 0.000 | 0.000 | 0.000 | 0.250 | 0.550 | 0.250 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.250 | 0.000 | 0.870 | | | | | | |
| | | | | | 0.575 | | | | | 0.667 | | | | | 0.727 | | | | | 0.500 | | | | | 0.250 | | | | | | | | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Mandela Pkwy & 7th St
City: Oakland

Project ID: 18-0611-03
Date: 12/12/2018

Pedestrians (Crosswalks)

| NS/EW Streets: | Mandela Pkwy | | Mandela Pkwy | | 7th St | | 7th St | | | | |
|-------------------------|----------------------------|----|--------------|--------|----------|----|----------|----|-------------|--------|-------|
| AM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | SOUTH LEG 2 | | TOTAL |
| | EB | WB | EB | WB | NB | SB | NB | SB | EB | WB | |
| 7:00 AM | 0 | 0 | 2 | 5 | 0 | 0 | 0 | 0 | 2 | 5 | 14 |
| 7:15 AM | 0 | 0 | 4 | 17 | 0 | 0 | 0 | 0 | 4 | 17 | 42 |
| 7:30 AM | 0 | 0 | 5 | 15 | 0 | 0 | 0 | 0 | 5 | 15 | 40 |
| 7:45 AM | 0 | 0 | 6 | 23 | 0 | 0 | 0 | 0 | 6 | 23 | 58 |
| 8:00 AM | 0 | 0 | 3 | 7 | 0 | 0 | 0 | 0 | 3 | 7 | 20 |
| 8:15 AM | 0 | 0 | 3 | 24 | 0 | 0 | 0 | 0 | 3 | 24 | 54 |
| 8:30 AM | 0 | 0 | 1 | 12 | 0 | 0 | 0 | 0 | 1 | 12 | 26 |
| 8:45 AM | 0 | 0 | 3 | 17 | 0 | 0 | 0 | 0 | 3 | 17 | 40 |
| TOTAL VOLUMES : | EB | WB | EB | WB | NB | SB | NB | SB | EB | WB | TOTAL |
| APPROACH %'s : | 0 | 0 | 27 | 120 | 0 | 0 | 0 | 0 | 27 | 120 | 294 |
| | | | 18.37% | 81.63% | | | | | 18.37% | 81.63% | |
| PEAK HR : | 07:45 AM - 08:45 AM | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 0 | 13 | 66 | 0 | 0 | 0 | 0 | 13 | 66 | 158 |
| PEAK HR FACTOR : | | | 0.542 | 0.688 | | | | | 0.542 | 0.688 | 0.681 |
| | | | 0.681 | | | | | | 0.681 | | |

| PM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | SOUTH LEG 2 | | TOTAL |
|-------------------------|----------------------------|----|-----------|--------|----------|----|----------|----|-------------|--------|-------|
| | EB | WB | EB | WB | NB | SB | NB | SB | EB | WB | |
| 4:00 PM | 0 | 0 | 7 | 1 | 0 | 0 | 0 | 0 | 7 | 1 | 16 |
| 4:15 PM | 0 | 0 | 10 | 1 | 0 | 0 | 0 | 0 | 10 | 1 | 22 |
| 4:30 PM | 0 | 0 | 13 | 5 | 0 | 0 | 0 | 0 | 13 | 5 | 36 |
| 4:45 PM | 0 | 0 | 10 | 5 | 0 | 0 | 0 | 0 | 10 | 5 | 30 |
| 5:00 PM | 0 | 0 | 14 | 1 | 0 | 0 | 0 | 0 | 14 | 1 | 30 |
| 5:15 PM | 0 | 0 | 18 | 5 | 0 | 0 | 0 | 0 | 18 | 5 | 46 |
| 5:30 PM | 0 | 0 | 29 | 1 | 0 | 0 | 0 | 0 | 29 | 1 | 60 |
| 5:45 PM | 0 | 0 | 14 | 2 | 0 | 0 | 0 | 0 | 14 | 2 | 32 |
| TOTAL VOLUMES : | EB | WB | EB | WB | NB | SB | NB | SB | EB | WB | TOTAL |
| APPROACH %'s : | 0 | 0 | 115 | 21 | 0 | 0 | 0 | 0 | 115 | 21 | 272 |
| | | | 84.56% | 15.44% | | | | | 84.56% | 15.44% | |
| PEAK HR : | 04:45 PM - 05:45 PM | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 0 | 71 | 12 | 0 | 0 | 0 | 0 | 71 | 12 | 166 |
| PEAK HR FACTOR : | | | 0.612 | 0.600 | | | | | 0.612 | 0.600 | 0.692 |
| | | | 0.692 | | | | | | 0.692 | | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Chester St & 5th St
 City: Oakland
 Control: 2-Way Stop(NB/SB)

Project ID: 18-08661-004
 Date: 12/12/2018

Total

| NS/EW Streets: | Chester St | | | | Chester St | | | | 5th St | | | | 5th St | | | | |
|-------------------------|----------------------------|--------|--------|-------|------------|--------|--------|-------|-----------|--------|-------|-------|-----------|--------|--------|-------|--------------|
| AM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | TOTAL |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 7:00 AM | 0 | 1 | 0 | 0 | 10 | 3 | 0 | 0 | 1 | 5 | 1 | 0 | 1 | 2 | 5 | 0 | 29 |
| 7:15 AM | 0 | 1 | 2 | 0 | 8 | 1 | 2 | 0 | 1 | 14 | 0 | 0 | 1 | 7 | 6 | 0 | 43 |
| 7:30 AM | 0 | 1 | 2 | 0 | 9 | 3 | 1 | 0 | 0 | 10 | 0 | 0 | 4 | 4 | 10 | 0 | 44 |
| 7:45 AM | 1 | 0 | 2 | 0 | 5 | 2 | 0 | 0 | 1 | 10 | 0 | 0 | 2 | 6 | 6 | 0 | 35 |
| 8:00 AM | 0 | 1 | 3 | 0 | 7 | 1 | 0 | 0 | 0 | 11 | 0 | 0 | 0 | 5 | 8 | 0 | 36 |
| 8:15 AM | 0 | 0 | 4 | 0 | 9 | 0 | 4 | 0 | 2 | 9 | 0 | 0 | 4 | 5 | 12 | 0 | 49 |
| 8:30 AM | 0 | 2 | 1 | 0 | 10 | 3 | 6 | 0 | 0 | 11 | 0 | 0 | 0 | 12 | 7 | 0 | 52 |
| 8:45 AM | 0 | 0 | 5 | 0 | 12 | 0 | 3 | 0 | 0 | 7 | 0 | 0 | 1 | 7 | 13 | 0 | 48 |
| TOTAL VOLUMES : | 1 | 6 | 19 | 0 | 70 | 13 | 16 | 0 | 5 | 77 | 1 | 0 | 13 | 48 | 67 | 0 | 336 |
| APPROACH %'s : | 3.85% | 23.08% | 73.08% | 0.00% | 70.71% | 13.13% | 16.16% | 0.00% | 6.02% | 92.77% | 1.20% | 0.00% | 10.16% | 37.50% | 52.34% | 0.00% | |
| PEAK HR : | 08:00 AM - 09:00 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 3 | 13 | 0 | 38 | 4 | 13 | 0 | 2 | 38 | 0 | 0 | 5 | 29 | 40 | 0 | 185 |
| PEAK HR FACTOR : | 0.000 | 0.375 | 0.650 | 0.000 | 0.792 | 0.333 | 0.542 | 0.000 | 0.250 | 0.864 | 0.000 | 0.000 | 0.313 | 0.604 | 0.769 | 0.000 | 0.889 |
| | 0.800 | | | | 0.724 | | | | 0.909 | | | | 0.881 | | | | |
| PM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | TOTAL |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 4:00 PM | 0 | 3 | 1 | 0 | 1 | 0 | 2 | 0 | 2 | 8 | 2 | 0 | 3 | 8 | 7 | 0 | 37 |
| 4:15 PM | 2 | 3 | 1 | 0 | 7 | 1 | 0 | 0 | 1 | 8 | 0 | 0 | 1 | 4 | 5 | 0 | 33 |
| 4:30 PM | 0 | 3 | 3 | 0 | 6 | 2 | 1 | 0 | 3 | 13 | 0 | 0 | 1 | 7 | 9 | 0 | 48 |
| 4:45 PM | 0 | 2 | 2 | 0 | 7 | 2 | 2 | 0 | 1 | 7 | 0 | 0 | 3 | 8 | 7 | 0 | 41 |
| 5:00 PM | 1 | 0 | 1 | 0 | 9 | 0 | 0 | 0 | 1 | 5 | 2 | 0 | 4 | 14 | 17 | 1 | 55 |
| 5:15 PM | 0 | 3 | 3 | 0 | 9 | 1 | 5 | 0 | 3 | 6 | 1 | 0 | 2 | 12 | 9 | 1 | 55 |
| 5:30 PM | 0 | 1 | 3 | 0 | 10 | 1 | 4 | 0 | 1 | 10 | 1 | 0 | 7 | 10 | 18 | 2 | 68 |
| 5:45 PM | 1 | 3 | 3 | 0 | 7 | 3 | 2 | 0 | 1 | 8 | 0 | 1 | 4 | 18 | 14 | 1 | 66 |
| TOTAL VOLUMES : | 4 | 18 | 17 | 0 | 56 | 10 | 16 | 0 | 13 | 65 | 6 | 1 | 25 | 81 | 86 | 5 | 403 |
| APPROACH %'s : | 10.26% | 46.15% | 43.59% | 0.00% | 68.29% | 12.20% | 19.51% | 0.00% | 15.29% | 76.47% | 7.06% | 1.18% | 12.69% | 41.12% | 43.65% | 2.54% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 2 | 7 | 10 | 0 | 35 | 5 | 11 | 0 | 6 | 29 | 4 | 1 | 17 | 54 | 58 | 5 | 244 |
| PEAK HR FACTOR : | 0.500 | 0.583 | 0.833 | 0.000 | 0.875 | 0.417 | 0.550 | 0.000 | 0.500 | 0.725 | 0.500 | 0.250 | 0.607 | 0.750 | 0.806 | 0.625 | 0.897 |
| | 0.679 | | | | 0.850 | | | | 0.833 | | | | 0.905 | | | | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Chester St & 5th St
City: Oakland
Control: 2-Way Stop(NB/SB)

Project ID: 18-08661-004
Date: 12/12/2018

Bikes

| NS/EW Streets: | Chester St | | | | Chester St | | | | 5th St | | | | 5th St | | | | |
|-------------------------|---------------------|--------|-------|-------|------------|-------|--------|-------|-----------|--------|--------|-------|-----------|---------|-------|-------|-------|
| AM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 7:00 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:15 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 7:30 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 7:45 AM | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 8:00 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8:15 AM | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 8:30 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8:45 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| TOTAL VOLUMES : | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 5 |
| APPROACH %'s : | 50.00% | 50.00% | 0.00% | 0.00% | | | | | 66.67% | 33.33% | 0.00% | 0.00% | | | | | |
| PEAK HR : | 08:00 AM - 09:00 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 2 |
| PEAK HR FACTOR : | 0.000 | 0.250 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.250 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.500 |
| | 0.250 | | | | | | | | 0.250 | | | | | | | | |
| PM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 4:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 4:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 4:45 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 4 |
| 5:00 PM | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 2 |
| 5:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 5:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 2 |
| 5:45 PM | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| TOTAL VOLUMES : | 0 | 0 | 0 | 0 | 2 | 0 | 1 | 0 | 2 | 4 | 1 | 0 | 0 | 2 | 0 | 0 | 12 |
| APPROACH %'s : | | | | | 66.67% | 0.00% | 33.33% | 0.00% | 28.57% | 57.14% | 14.29% | 0.00% | 0.00% | 100.00% | 0.00% | 0.00% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 2 | 1 | 0 | 0 | 1 | 0 | 0 | 6 |
| PEAK HR FACTOR : | 0.00 | 0.000 | 0.000 | 0.000 | 0.500 | 0.000 | 0.000 | 0.000 | 0.000 | 0.500 | 0.250 | 0.000 | 0.000 | 0.250 | 0.000 | 0.000 | 0.750 |
| | | | | | 0.500 | | | | 0.750 | | | | 0.250 | | | | |

National Data & Surveying Services

Location: **City of Oakland** Project ID: **1108561-004** Date: **12/12/2018**
Intersection Turning Movement Count

Pedestrians (Crosswalks)

| NS/EW Streets: | Chester St | | Chester St | | 5th St | | 5th St | | |
|-------------------------|----------------------------|---------|------------|---------|----------|---------|----------|---------|-------------|
| AM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 7:00 AM | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 7:15 AM | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 |
| 7:30 AM | 3 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 4 |
| 7:45 AM | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 |
| 8:00 AM | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 9 |
| 8:15 AM | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 |
| 8:30 AM | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 11 |
| 8:45 AM | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 |
| TOTAL VOLUMES : | EB 42 | WB 1 | EB 0 | WB 0 | NB 0 | SB 0 | NB 0 | SB 0 | TOTAL 43 |
| APPROACH %'s : | 97.67% | 2.33% | | | | | | | |
| PEAK HR : | 08:00 AM - 09:00 AM | | | | | | | | TOTAL |
| PEAK HR VOL : | 31 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 31 |
| PEAK HR FACTOR : | 0.705 | 0.705 | | | | | | | 0.705 |

| PM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
|-------------------------|----------------------------|----------|-----------|----------|----------|----------|----------|----------|--------------|
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 4:00 PM | 0 | 6 | 0 | 0 | 2 | 1 | 0 | 5 | 14 |
| 4:15 PM | 0 | 3 | 1 | 1 | 1 | 1 | 0 | 1 | 8 |
| 4:30 PM | 1 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 5 |
| 4:45 PM | 1 | 1 | 0 | 1 | 0 | 2 | 0 | 0 | 5 |
| 5:00 PM | 2 | 5 | 0 | 1 | 0 | 0 | 1 | 3 | 12 |
| 5:15 PM | 2 | 4 | 0 | 4 | 0 | 4 | 2 | 1 | 17 |
| 5:30 PM | 4 | 4 | 0 | 0 | 2 | 2 | 2 | 3 | 17 |
| 5:45 PM | 3 | 7 | 0 | 6 | 2 | 5 | 3 | 4 | 30 |
| TOTAL VOLUMES : | EB 13 | WB 34 | EB 1 | WB 13 | NB 7 | SB 15 | NB 8 | SB 17 | TOTAL 108 |
| APPROACH %'s : | 27.66% | 72.34% | 7.14% | 92.86% | 31.82% | 68.18% | 32.00% | 68.00% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | TOTAL |
| PEAK HR VOL : | 11 | 20 | 0 | 11 | 4 | 11 | 8 | 11 | 76 |
| PEAK HR FACTOR : | 0.688 | 0.714 | | 0.458 | 0.500 | 0.550 | 0.667 | 0.688 | 0.633 |
| | | 0.775 | | 0.458 | | 0.536 | | 0.679 | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Center St & 5th St
 City: Oakland
 Control: 1-Way Stop(NB)

Project ID: 18-08661-005
 Date: 12/12/2018

Total

| NS/EW Streets: | Center St | | | | Center St | | | | 5th St | | | | 5th St | | | | TOTAL |
|-------------------------|----------------------------|-------|--------|-------|------------|-------|-------|-------|-----------|--------|-------|-------|-----------|--------|-------|-------|-------|
| | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| AM | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | TOTAL |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 7:00 AM | 1 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 23 | 1 | 0 | 3 | 18 | 0 | 2 | 49 |
| 7:15 AM | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 30 | 3 | 0 | 2 | 22 | 0 | 2 | 63 |
| 7:30 AM | 1 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 25 | 4 | 0 | 2 | 29 | 0 | 0 | 64 |
| 7:45 AM | 0 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 30 | 1 | 0 | 4 | 28 | 0 | 0 | 70 |
| 8:00 AM | 0 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 29 | 0 | 0 | 2 | 17 | 0 | 0 | 53 |
| 8:15 AM | 1 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 47 | 1 | 0 | 2 | 34 | 0 | 2 | 92 |
| 8:30 AM | 1 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 37 | 2 | 0 | 2 | 34 | 0 | 0 | 81 |
| 8:45 AM | 0 | 0 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 39 | 1 | 1 | 1 | 35 | 0 | 0 | 86 |
| TOTAL VOLUMES : | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| APPROACH %'s : | 4 | 0 | 39 | 0 | 0 | 0 | 0 | 0 | 0 | 260 | 13 | 1 | 18 | 217 | 0 | 6 | 558 |
| | 9.30% | 0.00% | 90.70% | 0.00% | | | | | 0.00% | 94.89% | 4.74% | 0.36% | 7.47% | 90.04% | 0.00% | 2.49% | |
| PEAK HR : | 08:00 AM - 09:00 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 2 | 0 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 152 | 4 | 1 | 7 | 120 | 0 | 2 | 312 |
| PEAK HR FACTOR : | 0.500 | 0.000 | 0.667 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.809 | 0.500 | 0.250 | 0.875 | 0.857 | 0.000 | 0.250 | 0.848 |
| | 0.722 | | | | | | | | 0.818 | | | | 0.849 | | | | |

| NS/EW Streets: | Center St | | | | Center St | | | | 5th St | | | | 5th St | | | | TOTAL |
|-------------------------|----------------------------|-------|--------|-------|------------|-------|-------|-------|-----------|--------|-------|-------|-----------|--------|-------|-------|-------|
| | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| PM | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | TOTAL |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 4:00 PM | 2 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 18 | 0 | 0 | 5 | 18 | 0 | 0 | 50 |
| 4:15 PM | 0 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 21 | 0 | 0 | 3 | 13 | 0 | 0 | 44 |
| 4:30 PM | 1 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 33 | 1 | 0 | 5 | 23 | 0 | 1 | 70 |
| 4:45 PM | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 24 | 0 | 0 | 6 | 28 | 0 | 0 | 62 |
| 5:00 PM | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 29 | 1 | 0 | 1 | 40 | 0 | 0 | 73 |
| 5:15 PM | 2 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 27 | 1 | 0 | 6 | 34 | 0 | 2 | 78 |
| 5:30 PM | 2 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 43 | 1 | 0 | 3 | 36 | 0 | 3 | 94 |
| 5:45 PM | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 35 | 3 | 0 | 6 | 44 | 0 | 0 | 90 |
| TOTAL VOLUMES : | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| APPROACH %'s : | 9 | 0 | 38 | 0 | 0 | 0 | 0 | 0 | 0 | 230 | 7 | 0 | 35 | 236 | 0 | 6 | 561 |
| | 19.15% | 0.00% | 80.85% | 0.00% | | | | | 0.00% | 97.05% | 2.95% | 0.00% | 12.64% | 85.20% | 0.00% | 2.17% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 6 | 0 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 134 | 6 | 0 | 16 | 154 | 0 | 5 | 335 |
| PEAK HR FACTOR : | 0.750 | 0.000 | 0.583 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.779 | 0.500 | 0.000 | 0.667 | 0.875 | 0.000 | 0.417 | 0.891 |
| | 0.625 | | | | | | | | 0.795 | | | | 0.875 | | | | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Center St & 5th St
City: Oakland
Control: 1-Way Stop(NB)

Project ID: 18-08661-005
Date: 12/12/2018

Bikes

| NS/EW Streets: | Center St | | | | Center St | | | | 5th St | | | | 5th St | | | | |
|-------------------------|----------------------------|-------|---------|-------|------------|-------|-------|-------|-----------|---------|--------|-------|-----------|---------|-------|-------|--------------|
| AM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 7:00 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7:15 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 |
| 7:30 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 7:45 AM | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 8:00 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8:15 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 8:30 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 2 |
| 8:45 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| TOTAL VOLUMES : | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 1 | 2 | 0 | 0 | 7 |
| APPROACH %'s : | 0.00% | 0.00% | 100.00% | 0.00% | | | | | 0.00% | 100.00% | 0.00% | 0.00% | 33.33% | 66.67% | 0.00% | 0.00% | |
| PEAK HR : | 08:00 AM - 09:00 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 2 | 0 | 0 | 4 |
| PEAK HR FACTOR : | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.500 | 0.000 | 0.000 | 0.000 | 0.250 | 0.000 | 0.000 | 0.500 |
| | | | | | | | | | | 0.500 | | | | 0.250 | | | |
| PM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 4:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 4:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 1 |
| 4:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 |
| 4:45 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 5:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 |
| 5:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 5:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 2 |
| 5:45 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| TOTAL VOLUMES : | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 1 | 0 | 0 | 3 | 0 | 0 | 9 |
| APPROACH %'s : | | | | | | | | | 0.00% | 83.33% | 16.67% | 0.00% | 0.00% | 100.00% | 0.00% | 0.00% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 0 | 2 | 0 | 0 | 5 |
| PEAK HR FACTOR : | 0.00 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.750 | 0.000 | 0.000 | 0.000 | 0.500 | 0.000 | 0.000 | 0.625 |
| | | | | | | | | | | 0.750 | | | | 0.500 | | | |

National Data & Surveying Services

Location: Center St & 5th St **Project ID:** 1108561-007
City: Oakland **Date:** 12/12/2018

Pedestrians (Crosswalks)

| NS/EW Streets: | Center St | | Center St | | 5th St | | 5th St | | |
|-------------------------|----------------------------|----|-----------|-------|----------|--------|----------|--------|--------------|
| AM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 7:00 AM | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 1 | 3 |
| 7:15 AM | 0 | 0 | 2 | 0 | 3 | 0 | 0 | 0 | 5 |
| 7:30 AM | 0 | 0 | 0 | 0 | 1 | 0 | 3 | 0 | 4 |
| 7:45 AM | 0 | 0 | 0 | 0 | 1 | 0 | 3 | 0 | 4 |
| 8:00 AM | 0 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 2 |
| 8:15 AM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 3 |
| 8:30 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| 8:45 AM | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 2 | 4 |
| TOTAL VOLUMES : | 0 | 0 | 3 | 0 | 6 | 1 | 12 | 4 | 26 |
| APPROACH %'s : | | | 100.00% | 0.00% | 85.71% | 14.29% | 75.00% | 25.00% | |
| PEAK HR : | 08:00 AM - 09:00 AM | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 0 | 0 | 0 | 1 | 0 | 6 | 3 | 10 |
| PEAK HR FACTOR : | | | | | 0.250 | 0 | 0.500 | 0.375 | 0.625 |
| | | | | | | 0.250 | | 0.563 | |

| PM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
|-------------------------|----------------------------|----|-----------|--------|----------|--------|----------|--------|--------------|
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 4:00 PM | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 2 |
| 4:15 PM | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 1 | 2 |
| 4:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4:45 PM | 0 | 0 | 1 | 0 | 0 | 0 | 4 | 2 | 7 |
| 5:00 PM | 0 | 0 | 0 | 0 | 1 | 1 | 0 | 1 | 3 |
| 5:15 PM | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 3 | 5 |
| 5:30 PM | 0 | 0 | 0 | 1 | 0 | 0 | 2 | 1 | 4 |
| 5:45 PM | 0 | 0 | 0 | 0 | 1 | 0 | 2 | 0 | 3 |
| TOTAL VOLUMES : | 0 | 0 | 3 | 2 | 2 | 2 | 8 | 9 | 26 |
| APPROACH %'s : | | | 60.00% | 40.00% | 50.00% | 50.00% | 47.06% | 52.94% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | TOTAL |
| PEAK HR VOL : | 0 | 0 | 2 | 1 | 2 | 1 | 4 | 5 | 15 |
| PEAK HR FACTOR : | | | 0.250 | 0.250 | 0.500 | 0.250 | 0.500 | 0.417 | 0.750 |
| | | | | 0.375 | | 0.375 | | 0.750 | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Mandela Pkwy & 5th St
 City: Oakland
 Control: Signalized

Project ID: 18-08661-006
 Date: 12/12/2018

Total

| NS/EW Streets: | Mandela Pkwy | | | | Mandela Pkwy | | | | 5th St | | | | 5th St | | | | TOTAL |
|-------------------------|----------------------------|--------|--------|-------|--------------|--------|--------|-------|-----------|--------|--------|-------|-----------|--------|--------|-------|--------------|
| | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| AM | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | TOTAL |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 7:00 AM | 3 | 6 | 6 | 0 | 22 | 8 | 5 | 0 | 6 | 23 | 3 | 0 | 3 | 23 | 10 | 0 | 118 |
| 7:15 AM | 0 | 9 | 3 | 0 | 23 | 4 | 6 | 0 | 7 | 31 | 5 | 0 | 10 | 22 | 21 | 0 | 141 |
| 7:30 AM | 2 | 6 | 2 | 0 | 20 | 11 | 10 | 0 | 3 | 28 | 3 | 0 | 10 | 29 | 19 | 0 | 143 |
| 7:45 AM | 3 | 4 | 8 | 0 | 17 | 12 | 8 | 0 | 6 | 31 | 7 | 0 | 1 | 23 | 19 | 0 | 139 |
| 8:00 AM | 1 | 7 | 3 | 0 | 23 | 7 | 4 | 0 | 8 | 26 | 9 | 0 | 3 | 19 | 13 | 0 | 123 |
| 8:15 AM | 4 | 10 | 4 | 0 | 17 | 11 | 9 | 0 | 11 | 41 | 10 | 0 | 8 | 35 | 13 | 1 | 174 |
| 8:30 AM | 3 | 12 | 7 | 0 | 30 | 10 | 7 | 0 | 13 | 31 | 8 | 0 | 5 | 36 | 17 | 0 | 179 |
| 8:45 AM | 1 | 6 | 3 | 0 | 16 | 10 | 2 | 0 | 15 | 24 | 18 | 0 | 3 | 32 | 16 | 0 | 146 |
| TOTAL VOLUMES : | 17 | 60 | 36 | 0 | 168 | 73 | 51 | 0 | 69 | 235 | 63 | 0 | 43 | 219 | 128 | 1 | 1163 |
| APPROACH %'s : | 15.04% | 53.10% | 31.86% | 0.00% | 57.53% | 25.00% | 17.47% | 0.00% | 18.80% | 64.03% | 17.17% | 0.00% | 11.00% | 56.01% | 32.74% | 0.26% | |
| PEAK HR : | 08:00 AM - 09:00 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 9 | 35 | 17 | 0 | 86 | 38 | 22 | 0 | 47 | 122 | 45 | 0 | 19 | 122 | 59 | 1 | 622 |
| PEAK HR FACTOR : | 0.563 | 0.729 | 0.607 | 0.000 | 0.717 | 0.864 | 0.611 | 0.000 | 0.783 | 0.744 | 0.625 | 0.000 | 0.594 | 0.847 | 0.868 | 0.250 | 0.869 |
| | 0.693 | | | | 0.777 | | | | 0.863 | | | | 0.866 | | | | |

| NS/EW Streets: | Mandela Pkwy | | | | Mandela Pkwy | | | | 5th St | | | | 5th St | | | | TOTAL |
|-------------------------|----------------------------|--------|--------|-------|--------------|--------|--------|-------|-----------|--------|--------|-------|-----------|--------|--------|-------|--------------|
| | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| PM | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | TOTAL |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | |
| 4:00 PM | 2 | 12 | 4 | 0 | 11 | 12 | 9 | 1 | 13 | 14 | 7 | 0 | 1 | 17 | 9 | 0 | 112 |
| 4:15 PM | 0 | 19 | 4 | 0 | 9 | 15 | 4 | 0 | 10 | 29 | 7 | 0 | 6 | 19 | 18 | 0 | 140 |
| 4:30 PM | 8 | 17 | 10 | 0 | 16 | 19 | 10 | 0 | 15 | 24 | 7 | 0 | 9 | 22 | 28 | 0 | 185 |
| 4:45 PM | 6 | 16 | 16 | 0 | 11 | 18 | 6 | 0 | 9 | 20 | 3 | 0 | 4 | 26 | 27 | 0 | 162 |
| 5:00 PM | 13 | 31 | 20 | 0 | 11 | 15 | 12 | 0 | 8 | 25 | 11 | 0 | 9 | 31 | 31 | 0 | 217 |
| 5:15 PM | 3 | 28 | 16 | 0 | 13 | 25 | 13 | 0 | 21 | 24 | 9 | 0 | 4 | 37 | 26 | 0 | 219 |
| 5:30 PM | 7 | 18 | 6 | 0 | 10 | 35 | 12 | 0 | 19 | 37 | 13 | 0 | 13 | 23 | 23 | 0 | 216 |
| 5:45 PM | 9 | 25 | 4 | 0 | 11 | 33 | 12 | 0 | 19 | 23 | 3 | 0 | 12 | 31 | 22 | 0 | 204 |
| TOTAL VOLUMES : | 48 | 166 | 80 | 0 | 92 | 172 | 78 | 1 | 114 | 196 | 60 | 0 | 58 | 206 | 184 | 0 | 1455 |
| APPROACH %'s : | 16.33% | 56.46% | 27.21% | 0.00% | 26.82% | 50.15% | 22.74% | 0.29% | 30.81% | 52.97% | 16.22% | 0.00% | 12.95% | 45.98% | 41.07% | 0.00% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 32 | 102 | 46 | 0 | 45 | 108 | 49 | 0 | 67 | 109 | 36 | 0 | 38 | 122 | 102 | 0 | 856 |
| PEAK HR FACTOR : | 0.615 | 0.823 | 0.575 | 0.000 | 0.865 | 0.771 | 0.942 | 0.000 | 0.798 | 0.736 | 0.692 | 0.000 | 0.731 | 0.824 | 0.823 | 0.000 | 0.977 |
| | 0.703 | | | | 0.886 | | | | 0.768 | | | | 0.923 | | | | |

National Data & Surveying Services

Intersection Turning Movement Count

Location: Mandela Pkwy & 5th St
City: Oakland
Control: Signalized

Project ID: 18-08661-006
Date: 12/12/2018

Bikes

| NS/EW Streets: | Mandela Pkwy | | | | Mandela Pkwy | | | | 5th St | | | | 5th St | | | | |
|-------------------------|----------------------------|--------|-------|-------|--------------|--------|-------|-------|-----------|--------|--------|-------|-----------|--------|---------|-------|-------|
| AM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 7:00 AM | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 7:15 AM | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 3 |
| 7:30 AM | 0 | 1 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 4 |
| 7:45 AM | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 3 |
| 8:00 AM | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 6 |
| 8:15 AM | 0 | 2 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 8 |
| 8:30 AM | 2 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 5 |
| 8:45 AM | 0 | 1 | 0 | 0 | 0 | 1 | 1 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 4 |
| TOTAL VOLUMES : | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| APPROACH %'s : | 2 | 5 | 0 | 0 | 0 | 17 | 1 | 0 | 0 | 3 | 2 | 0 | 0 | 1 | 3 | 0 | 34 |
| | 28.57% | 71.43% | 0.00% | 0.00% | 0.00% | 94.44% | 5.56% | 0.00% | 0.00% | 60.00% | 40.00% | 0.00% | 0.00% | 25.00% | 75.00% | 0.00% | |
| PEAK HR : | 08:00 AM - 09:00 AM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 2 | 3 | 0 | 0 | 0 | 11 | 1 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 3 | 0 | 23 |
| PEAK HR FACTOR : | 0.250 | 0.375 | 0.000 | 0.000 | 0.000 | 0.550 | 0.250 | 0.000 | 0.000 | 0.250 | 0.250 | 0.000 | 0.000 | 0.000 | 0.375 | 0.000 | 0.719 |
| | 0.625 | | | | 0.600 | | | | 0.375 | | | | 0.375 | | | | |
| PM | NORTHBOUND | | | | SOUTHBOUND | | | | EASTBOUND | | | | WESTBOUND | | | | |
| | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| 4:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| 4:15 PM | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 |
| 4:30 PM | 2 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 |
| 4:45 PM | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 |
| 5:00 PM | 1 | 2 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 |
| 5:15 PM | 2 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 1 | 0 | 9 |
| 5:30 PM | 1 | 3 | 0 | 0 | 2 | 4 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 11 |
| 5:45 PM | 0 | 2 | 0 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 6 |
| TOTAL VOLUMES : | NL | NT | NR | NU | SL | ST | SR | SU | EL | ET | ER | EU | WL | WT | WR | WU | TOTAL |
| APPROACH %'s : | 6 | 13 | 0 | 0 | 3 | 11 | 0 | 0 | 2 | 1 | 3 | 0 | 0 | 0 | 1 | 0 | 40 |
| | 31.58% | 68.42% | 0.00% | 0.00% | 21.43% | 78.57% | 0.00% | 0.00% | 33.33% | 16.67% | 50.00% | 0.00% | 0.00% | 0.00% | 100.00% | 0.00% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | | | | | | | | | TOTAL |
| PEAK HR VOL : | 4 | 11 | 0 | 0 | 3 | 7 | 0 | 0 | 0 | 1 | 3 | 0 | 0 | 0 | 1 | 0 | 30 |
| PEAK HR FACTOR : | 0.50 | 0.688 | 0.000 | 0.000 | 0.375 | 0.438 | 0.000 | 0.000 | 0.000 | 0.250 | 0.375 | 0.000 | 0.000 | 0.000 | 0.250 | 0.000 | 0.682 |
| | 0.625 | | | | 0.417 | | | | 0.500 | | | | 0.250 | | | | |

National Data & Surveying Services

Intersection Turning Movement Count
Location: Mandela Pkwy & 5th St Project ID: 18561-006 Date: 12/12/2018
City: Oakland

Pedestrians (Crosswalks)

| NS/EW Streets: | Mandela Pkwy | | Mandela Pkwy | | 5th St | | 5th St | | |
|-------------------------|----------------------------|-----------|--------------|-----------|-----------|---------|-----------|----------|--------------|
| AM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 7:00 AM | 2 | 9 | 0 | 5 | 7 | 2 | 6 | 2 | 33 |
| 7:15 AM | 0 | 7 | 0 | 14 | 8 | 2 | 13 | 2 | 46 |
| 7:30 AM | 1 | 7 | 0 | 18 | 7 | 0 | 20 | 1 | 54 |
| 7:45 AM | 2 | 19 | 1 | 22 | 16 | 2 | 20 | 8 | 90 |
| 8:00 AM | 0 | 23 | 1 | 25 | 18 | 0 | 24 | 5 | 96 |
| 8:15 AM | 3 | 28 | 0 | 24 | 24 | 3 | 24 | 0 | 106 |
| 8:30 AM | 0 | 28 | 0 | 19 | 28 | 0 | 19 | 1 | 95 |
| 8:45 AM | 0 | 29 | 1 | 21 | 28 | 0 | 20 | 5 | 104 |
| TOTAL VOLUMES : | EB 8 | WB 150 | EB 3 | WB 148 | NB 136 | SB 9 | NB 146 | SB 24 | TOTAL 624 |
| APPROACH %'s : | 5.06% | 94.94% | 1.99% | 98.01% | 93.79% | 6.21% | 85.88% | 14.12% | |
| PEAK HR : | 08:00 AM - 09:00 AM | | | | | | | | TOTAL |
| PEAK HR VOL : | 3 | 108 | 2 | 89 | 98 | 3 | 87 | 11 | 401 |
| PEAK HR FACTOR : | 0.250 | 0.931 | 0.500 | 0.890 | 0.875 | 0.250 | 0.906 | 0.550 | 0.946 |
| | 0.895 | | 0.875 | | 0.902 | | 0.845 | | |

| PM | NORTH LEG | | SOUTH LEG | | EAST LEG | | WEST LEG | | TOTAL |
|-------------------------|----------------------------|----------|-----------|---------|----------|-----------|----------|----------|--------------|
| | EB | WB | EB | WB | NB | SB | NB | SB | |
| 4:00 PM | 6 | 0 | 7 | 0 | 0 | 8 | 1 | 4 | 26 |
| 4:15 PM | 15 | 3 | 8 | 1 | 1 | 12 | 6 | 8 | 54 |
| 4:30 PM | 21 | 1 | 18 | 0 | 2 | 20 | 3 | 15 | 80 |
| 4:45 PM | 15 | 1 | 12 | 1 | 0 | 13 | 3 | 13 | 58 |
| 5:00 PM | 26 | 1 | 4 | 2 | 1 | 21 | 5 | 5 | 65 |
| 5:15 PM | 14 | 2 | 8 | 1 | 2 | 18 | 6 | 9 | 60 |
| 5:30 PM | 25 | 5 | 17 | 4 | 1 | 18 | 2 | 20 | 92 |
| 5:45 PM | 17 | 6 | 10 | 0 | 3 | 20 | 1 | 11 | 68 |
| TOTAL VOLUMES : | EB 139 | WB 19 | EB 84 | WB 9 | NB 10 | SB 130 | NB 27 | SB 85 | TOTAL 503 |
| APPROACH %'s : | 87.97% | 12.03% | 90.32% | 9.68% | 7.14% | 92.86% | 24.11% | 75.89% | |
| PEAK HR : | 05:00 PM - 06:00 PM | | | | | | | | TOTAL |
| PEAK HR VOL : | 82 | 14 | 39 | 7 | 7 | 77 | 14 | 45 | 285 |
| PEAK HR FACTOR : | 0.788 | 0.583 | 0.574 | 0.438 | 0.583 | 0.917 | 0.583 | 0.563 | 0.774 |
| | 0.800 | | 0.548 | | 0.913 | | 0.670 | | |

APPENDIX B
INTERSECTION OPERATIONS
WORKSHEETS



| Intersection | | | | | | | | | | | | |
|--------------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 9.7 | | | | | | | | | | | |
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↖ | ↗ | | ↖ | ↗ | | | ↕ | | | ↕ | |
| Traffic Vol, veh/h | 7 | 136 | 56 | 91 | 136 | 17 | 63 | 38 | 138 | 4 | 20 | 5 |
| Future Vol, veh/h | 7 | 136 | 56 | 91 | 136 | 17 | 63 | 38 | 138 | 4 | 20 | 5 |
| Conflicting Peds, #/hr | 67 | 0 | 93 | 93 | 0 | 67 | 10 | 0 | 88 | 88 | 0 | 10 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | 60 | - | - | 55 | - | - | - | - | - | - | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 7 | 136 | 56 | 91 | 136 | 17 | 63 | 38 | 138 | 4 | 20 | 5 |

| Major/Minor | Major1 | | | Major2 | | | Minor1 | | | Minor2 | | |
|----------------------|--------|---|---|--------|---|---|--------|-------|-------|--------|-------|-------|
| Conflicting Flow All | 220 | 0 | 0 | 285 | 0 | 0 | 620 | 673 | 345 | 748 | 693 | 222 |
| Stage 1 | - | - | - | - | - | - | 271 | 271 | - | 394 | 394 | - |
| Stage 2 | - | - | - | - | - | - | 349 | 402 | - | 354 | 299 | - |
| Critical Hdwy | 4.13 | - | - | 4.13 | - | - | 7.13 | 6.53 | 6.23 | 7.13 | 6.53 | 6.23 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 6.13 | 5.53 | - | 6.13 | 5.53 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 6.13 | 5.53 | - | 6.13 | 5.53 | - |
| Follow-up Hdwy | 2.227 | - | - | 2.227 | - | - | 3.527 | 4.027 | 3.327 | 3.527 | 4.027 | 3.327 |
| Pot Cap-1 Maneuver | 1343 | - | - | 1271 | - | - | 399 | 375 | 696 | 327 | 366 | 815 |
| Stage 1 | - | - | - | - | - | - | 733 | 683 | - | 629 | 603 | - |
| Stage 2 | - | - | - | - | - | - | 665 | 599 | - | 661 | 664 | - |
| Platoon blocked, % | - | - | - | - | - | - | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | 1332 | - | - | 1178 | - | - | 322 | 300 | 595 | 186 | 293 | 763 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 322 | 300 | - | 186 | 293 | - |
| Stage 1 | - | - | - | - | - | - | 673 | 627 | - | 591 | 525 | - |
| Stage 2 | - | - | - | - | - | - | 581 | 522 | - | 440 | 609 | - |


| Approach | EB | WB | NB | SB |
|----------------------|-----|-----|------|------|
| HCM Control Delay, s | 0.3 | 3.1 | 23.3 | 18.2 |
| HCM LOS | | | C | C |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 |
|-----------------------|-------|-------|-----|-----|-------|-----|-----|-------|
| Capacity (veh/h) | 431 | 1332 | - | - | 1178 | - | - | 301 |
| HCM Lane V/C Ratio | 0.555 | 0.005 | - | - | 0.077 | - | - | 0.096 |
| HCM Control Delay (s) | 23.3 | 7.7 | - | - | 8.3 | - | - | 18.2 |
| HCM Lane LOS | C | A | - | - | A | - | - | C |
| HCM 95th %tile Q(veh) | 3.3 | 0 | - | - | 0.3 | - | - | 0.3 |

HCM Signalized Intersection Capacity Analysis

2: 7th Street & Center Street

01/11/2019



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|-------|------|-------|------|
| Lane Configurations | ↶ | ↷ | ↷ | | ↶ | ↶ |
| Traffic Volume (vph) | 17 | 266 | 255 | 32 | 16 | 19 |
| Future Volume (vph) | 17 | 266 | 255 | 32 | 16 | 19 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.0 | 5.0 | 5.0 | | 3.0 | |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | | 1.00 | |
| Frpb, ped/bikes | 1.00 | 1.00 | 0.99 | | 0.90 | |
| Flpb, ped/bikes | 0.94 | 1.00 | 1.00 | | 1.00 | |
| Frt | 1.00 | 1.00 | 0.98 | | 0.93 | |
| Flt Protected | 0.95 | 1.00 | 1.00 | | 0.98 | |
| Satd. Flow (prot) | 1656 | 1845 | 1796 | | 1501 | |
| Flt Permitted | 0.58 | 1.00 | 1.00 | | 0.98 | |
| Satd. Flow (perm) | 1018 | 1845 | 1796 | | 1501 | |
| Peak-hour factor, PHF | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj. Flow (vph) | 17 | 266 | 255 | 32 | 16 | 19 |
| RTOR Reduction (vph) | 0 | 0 | 5 | 0 | 17 | 0 |
| Lane Group Flow (vph) | 17 | 266 | 282 | 0 | 18 | 0 |
| Confl. Peds. (#/hr) | 55 | | | 55 | 82 | 164 |
| Confl. Bikes (#/hr) | | | | 10 | | 7 |
| Turn Type | Perm | NA | NA | | Prot | |
| Protected Phases | | 6 | 2 | | 4 | |
| Permitted Phases | 6 | | | | | |
| Actuated Green, G (s) | 24.4 | 24.4 | 24.4 | | 3.4 | |
| Effective Green, g (s) | 24.4 | 24.4 | 24.4 | | 3.4 | |
| Actuated g/C Ratio | 0.68 | 0.68 | 0.68 | | 0.09 | |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | | 3.0 | |
| Vehicle Extension (s) | 2.0 | 2.0 | 2.0 | | 2.0 | |
| Lane Grp Cap (vph) | 693 | 1257 | 1224 | | 142 | |
| v/s Ratio Prot | | 0.14 | c0.16 | | c0.01 | |
| v/s Ratio Perm | 0.02 | | | | | |
| v/c Ratio | 0.02 | 0.21 | 0.23 | | 0.13 | |
| Uniform Delay, d1 | 1.8 | 2.1 | 2.2 | | 14.8 | |
| Progression Factor | 1.00 | 1.00 | 1.00 | | 1.00 | |
| Incremental Delay, d2 | 0.0 | 0.0 | 0.0 | | 0.1 | |
| Delay (s) | 1.9 | 2.2 | 2.2 | | 15.0 | |
| Level of Service | A | A | A | | B | |
| Approach Delay (s) | | 2.1 | 2.2 | | 15.0 | |
| Approach LOS | | A | A | | B | |

Intersection Summary

| | | | |
|-----------------------------------|-------|---------------------------|-----|
| HCM 2000 Control Delay | 2.9 | HCM 2000 Level of Service | A |
| HCM 2000 Volume to Capacity ratio | 0.22 | | |
| Actuated Cycle Length (s) | 35.8 | Sum of lost time (s) | 8.0 |
| Intersection Capacity Utilization | 40.0% | ICU Level of Service | A |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM 2010 Signalized Intersection Summary
 3: Mandela Pkwy & 7th Street

01/11/2019



| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-------------------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Lane Configurations | ↔ | ↕ | | ↔ | ↕ | | | ↕ | | ↔ | ↕ | |
| Traffic Volume (veh/h) | 65 | 197 | 23 | 183 | 220 | 80 | 23 | 116 | 70 | 73 | 283 | 36 |
| Future Volume (veh/h) | 65 | 197 | 23 | 183 | 220 | 80 | 23 | 116 | 70 | 73 | 283 | 36 |
| Number | 1 | 6 | 16 | 5 | 2 | 12 | 3 | 8 | 18 | 7 | 4 | 14 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 1.00 | | 0.94 | 1.00 | | 0.90 | 1.00 | | 0.97 | 1.00 | | 0.98 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1845 | 1845 | 1900 | 1845 | 1845 | 1900 | 1900 | 1845 | 1900 | 1845 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 65 | 197 | 23 | 183 | 220 | 80 | 23 | 116 | 70 | 73 | 283 | 36 |
| Adj No. of Lanes | 1 | 2 | 0 | 1 | 2 | 0 | 0 | 1 | 0 | 1 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 139 | 1721 | 198 | 214 | 1438 | 498 | 49 | 156 | 83 | 190 | 353 | 45 |
| Arrive On Green | 0.08 | 0.55 | 0.55 | 0.12 | 0.58 | 0.58 | 0.22 | 0.22 | 0.22 | 0.22 | 0.22 | 0.22 |
| Sat Flow, veh/h | 1757 | 3146 | 361 | 1757 | 2479 | 859 | 42 | 709 | 378 | 1181 | 1601 | 204 |
| Grp Volume(v), veh/h | 65 | 108 | 112 | 183 | 152 | 148 | 209 | 0 | 0 | 73 | 0 | 319 |
| Grp Sat Flow(s),veh/h/ln | 1757 | 1752 | 1755 | 1757 | 1752 | 1585 | 1129 | 0 | 0 | 1181 | 0 | 1804 |
| Q Serve(g_s), s | 3.5 | 3.0 | 3.1 | 10.2 | 4.0 | 4.3 | 2.4 | 0.0 | 0.0 | 0.0 | 0.0 | 16.7 |
| Cycle Q Clear(g_c), s | 3.5 | 3.0 | 3.1 | 10.2 | 4.0 | 4.3 | 19.2 | 0.0 | 0.0 | 15.5 | 0.0 | 16.7 |
| Prop In Lane | 1.00 | | 0.21 | 1.00 | | 0.54 | 0.11 | | 0.33 | 1.00 | | 0.11 |
| Lane Grp Cap(c), veh/h | 139 | 959 | 960 | 214 | 1016 | 919 | 289 | 0 | 0 | 190 | 0 | 398 |
| V/C Ratio(X) | 0.47 | 0.11 | 0.12 | 0.85 | 0.15 | 0.16 | 0.72 | 0.00 | 0.00 | 0.38 | 0.00 | 0.80 |
| Avail Cap(c_a), veh/h | 139 | 959 | 960 | 264 | 1016 | 919 | 336 | 0 | 0 | 225 | 0 | 451 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 1.00 |
| Uniform Delay (d), s/veh | 44.0 | 10.9 | 10.9 | 43.0 | 9.7 | 9.7 | 35.6 | 0.0 | 0.0 | 36.4 | 0.0 | 36.9 |
| Incr Delay (d2), s/veh | 0.9 | 0.2 | 0.2 | 17.0 | 0.3 | 0.4 | 4.8 | 0.0 | 0.0 | 0.5 | 0.0 | 7.7 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln | 1.8 | 1.5 | 1.6 | 5.9 | 2.0 | 2.0 | 6.0 | 0.0 | 0.0 | 1.9 | 0.0 | 9.2 |
| LnGrp Delay(d),s/veh | 44.9 | 11.2 | 11.2 | 60.1 | 10.0 | 10.1 | 40.4 | 0.0 | 0.0 | 36.9 | 0.0 | 44.6 |
| LnGrp LOS | D | B | B | E | A | B | D | | | D | | D |
| Approach Vol, veh/h | | 285 | | | 483 | | | 209 | | | 392 | |
| Approach Delay, s/veh | | 18.9 | | | 29.0 | | | 40.4 | | | 43.2 | |
| Approach LOS | | B | | | C | | | D | | | D | |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | 1 | 2 | | 4 | 5 | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | 1.9 | 62.0 | | 26.1 | 15.2 | 58.7 | | 26.1 | | | | |
| Change Period (Y+Rc), s | 4.0 | * 4 | | 4.0 | 3.0 | 4.0 | | 4.0 | | | | |
| Max Green Setting (Gmax), s | 60.0 | * 58 | | 25.0 | 15.0 | 49.0 | | 25.0 | | | | |
| Max Q Clear Time (g_c+1/5), s | 11.5 | 6.3 | | 18.7 | 12.2 | 5.1 | | 21.2 | | | | |
| Green Ext Time (p_c), s | 0.0 | 1.3 | | 1.3 | 0.1 | 0.9 | | 0.9 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | 32.7 | | | | | | | | | |
| HCM 2010 LOS | | | C | | | | | | | | | |
| Notes | | | | | | | | | | | | |

| Intersection | | | | | | | | | | | | |
|--------------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 4 | | | | | | | | | | | |
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↕ | | | ↕ | | | ↕ | | | ↕ | |
| Traffic Vol, veh/h | 2 | 38 | 0 | 5 | 29 | 40 | 0 | 3 | 13 | 38 | 4 | 13 |
| Future Vol, veh/h | 2 | 38 | 0 | 5 | 29 | 40 | 0 | 3 | 13 | 38 | 4 | 13 |
| Conflicting Peds, #/hr | 31 | 0 | 11 | 11 | 0 | 31 | 19 | 0 | 15 | 15 | 0 | 19 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | - | - | - | - | - | - | - | - | - | - | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 2 | 38 | 0 | 5 | 29 | 40 | 0 | 3 | 13 | 38 | 4 | 13 |

| Major/Minor | Major1 | | | Major2 | | | Minor1 | | | Minor2 | | |
|----------------------|--------|---|---|--------|---|---|--------|-------|-------|--------|-------|-------|
| Conflicting Flow All | 100 | 0 | 0 | 49 | 0 | 0 | 140 | 163 | 64 | 155 | 143 | 99 |
| Stage 1 | - | - | - | - | - | - | 53 | 53 | - | 90 | 90 | - |
| Stage 2 | - | - | - | - | - | - | 87 | 110 | - | 65 | 53 | - |
| Critical Hdwy | 4.13 | - | - | 4.13 | - | - | 7.13 | 6.53 | 6.23 | 7.13 | 6.53 | 6.23 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 6.13 | 5.53 | - | 6.13 | 5.53 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 6.13 | 5.53 | - | 6.13 | 5.53 | - |
| Follow-up Hdwy | 2.227 | - | - | 2.227 | - | - | 3.527 | 4.027 | 3.327 | 3.527 | 4.027 | 3.327 |
| Pot Cap-1 Maneuver | 1486 | - | - | 1551 | - | - | 828 | 728 | 998 | 809 | 746 | 954 |
| Stage 1 | - | - | - | - | - | - | 957 | 849 | - | 915 | 818 | - |
| Stage 2 | - | - | - | - | - | - | 918 | 802 | - | 943 | 849 | - |
| Platoon blocked, % | | - | - | | - | - | | | | | | |
| Mov Cap-1 Maneuver | 1462 | - | - | 1532 | - | - | 790 | 700 | 976 | 763 | 717 | 915 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 790 | 700 | - | 763 | 717 | - |
| Stage 1 | - | - | - | - | - | - | 947 | 840 | - | 890 | 794 | - |
| Stage 2 | - | - | - | - | - | - | 883 | 779 | - | 915 | 840 | - |

| Approach | EB | | | WB | | | NB | | | SB | | |
|----------------------|-----|--|--|-----|--|--|----|--|--|-----|--|--|
| HCM Control Delay, s | 0.4 | | | 0.5 | | | 9 | | | 9.9 | | |
| HCM LOS | | | | | | | A | | | A | | |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 |
|-----------------------|-------|-------|-----|-----|-------|-----|-----|-------|
| Capacity (veh/h) | 909 | 1462 | - | - | 1532 | - | - | 790 |
| HCM Lane V/C Ratio | 0.018 | 0.001 | - | - | 0.003 | - | - | 0.07 |
| HCM Control Delay (s) | 9 | 7.5 | 0 | - | 7.4 | 0 | - | 9.9 |
| HCM Lane LOS | A | A | A | - | A | A | - | A |
| HCM 95th %tile Q(veh) | 0.1 | 0 | - | - | 0 | - | - | 0.2 |

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 1 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | | | | | | |
| Traffic Vol, veh/h | 153 | 4 | 9 | 120 | 2 | 24 |
| Future Vol, veh/h | 153 | 4 | 9 | 120 | 2 | 24 |
| Conflicting Peds, #/hr | 0 | 3 | 3 | 0 | 9 | 3 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 153 | 4 | 9 | 120 | 2 | 24 |

















| Major/Minor | Major1 | Major2 | Minor1 | | |
|----------------------|--------|--------|--------|---|-------|
| Conflicting Flow All | 0 | 0 | 160 | 0 | 305 |
| Stage 1 | - | - | - | - | 158 |
| Stage 2 | - | - | - | - | 147 |
| Critical Hdwy | - | - | 4.13 | - | 6.43 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.43 |
| Critical Hdwy Stg 2 | - | - | - | - | 5.43 |
| Follow-up Hdwy | - | - | 2.227 | - | 3.527 |
| Pot Cap-1 Maneuver | - | - | 1413 | - | 685 |
| Stage 1 | - | - | - | - | 868 |
| Stage 2 | - | - | - | - | 878 |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 1409 | - | 673 |
| Mov Cap-2 Maneuver | - | - | - | - | 673 |
| Stage 1 | - | - | - | - | 866 |
| Stage 2 | - | - | - | - | 865 |

| Approach | EB | WB | NB |
|----------------------|----|-----|-----|
| HCM Control Delay, s | 0 | 0.5 | 9.3 |
| HCM LOS | | | A |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 857 | - | - | 1409 | - |
| HCM Lane V/C Ratio | 0.03 | - | - | 0.006 | - |
| HCM Control Delay (s) | 9.3 | - | - | 7.6 | 0 |
| HCM Lane LOS | A | - | - | A | A |
| HCM 95th %tile Q(veh) | 0.1 | - | - | 0 | - |

HCM 2010 Signalized Intersection Summary
 6: Mandela Pkwy & 5th Street

01/11/2019

| |  |  |  |  |  |  |  |  |  |  |  |  |
|------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | |  | | |  | | |  | | |  | |
| Traffic Volume (veh/h) | 47 | 122 | 45 | 20 | 122 | 59 | 9 | 35 | 17 | 86 | 38 | 22 |
| Future Volume (veh/h) | 47 | 122 | 45 | 20 | 122 | 59 | 9 | 35 | 17 | 86 | 38 | 22 |
| Number | 7 | 4 | 14 | 3 | 8 | 18 | 5 | 2 | 12 | 1 | 6 | 16 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 0.92 | | 0.87 | 0.92 | | 0.88 | 0.91 | | 0.87 | 0.90 | | 0.87 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 47 | 122 | 45 | 20 | 122 | 59 | 9 | 35 | 17 | 86 | 38 | 22 |
| Adj No. of Lanes | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 193 | 432 | 138 | 122 | 456 | 201 | 143 | 414 | 177 | 422 | 176 | 81 |
| Arrive On Green | 0.42 | 0.42 | 0.42 | 0.42 | 0.42 | 0.42 | 0.39 | 0.39 | 0.39 | 0.39 | 0.39 | 0.39 |
| Sat Flow, veh/h | 210 | 1038 | 332 | 64 | 1097 | 482 | 111 | 1059 | 452 | 726 | 449 | 209 |
| Grp Volume(v), veh/h | 214 | 0 | 0 | 201 | 0 | 0 | 61 | 0 | 0 | 146 | 0 | 0 |
| Grp Sat Flow(s),veh/h/ln | 1580 | 0 | 0 | 1643 | 0 | 0 | 1623 | 0 | 0 | 1385 | 0 | 0 |
| Q Serve(g_s), s | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.2 | 0.0 | 0.0 |
| Cycle Q Clear(g_c), s | 3.4 | 0.0 | 0.0 | 3.3 | 0.0 | 0.0 | 1.0 | 0.0 | 0.0 | 2.6 | 0.0 | 0.0 |
| Prop In Lane | 0.22 | | 0.21 | 0.10 | | 0.29 | 0.15 | | 0.28 | 0.59 | | 0.15 |
| Lane Grp Cap(c), veh/h | 763 | 0 | 0 | 779 | 0 | 0 | 734 | 0 | 0 | 679 | 0 | 0 |
| V/C Ratio(X) | 0.28 | 0.00 | 0.00 | 0.26 | 0.00 | 0.00 | 0.08 | 0.00 | 0.00 | 0.21 | 0.00 | 0.00 |
| Avail Cap(c_a), veh/h | 1047 | 0 | 0 | 1078 | 0 | 0 | 1258 | 0 | 0 | 1131 | 0 | 0 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 |
| Uniform Delay (d), s/veh | 8.1 | 0.0 | 0.0 | 8.0 | 0.0 | 0.0 | 8.0 | 0.0 | 0.0 | 8.4 | 0.0 | 0.0 |
| Incr Delay (d2), s/veh | 0.1 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln | 1.6 | 0.0 | 0.0 | 1.5 | 0.0 | 0.0 | 0.4 | 0.0 | 0.0 | 1.1 | 0.0 | 0.0 |
| LnGrp Delay(d),s/veh | 8.1 | 0.0 | 0.0 | 8.1 | 0.0 | 0.0 | 8.0 | 0.0 | 0.0 | 8.5 | 0.0 | 0.0 |
| LnGrp LOS | A | | | A | | | A | | | A | | |
| Approach Vol, veh/h | | 214 | | | 201 | | | 61 | | | 146 | |
| Approach Delay, s/veh | | 8.1 | | | 8.1 | | | 8.0 | | | 8.5 | |
| Approach LOS | | A | | | A | | | A | | | A | |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | | 2 | | 4 | | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | | 20.1 | | 21.2 | | 20.1 | | 21.2 | | | | |
| Change Period (Y+Rc), s | | 4.0 | | 4.0 | | 4.0 | | 4.0 | | | | |
| Max Green Setting (Gmax), s | | 30.0 | | 25.0 | | 30.0 | | 25.0 | | | | |
| Max Q Clear Time (g_c+I1), s | | 3.0 | | 5.4 | | 4.6 | | 5.3 | | | | |
| Green Ext Time (p_c), s | | 0.8 | | 1.8 | | 0.8 | | 1.8 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | 8.2 | | | | | | | | | |
| HCM 2010 LOS | | | A | | | | | | | | | |

| Intersection | | | | | | | | | | | | |
|--------------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 7.7 | | | | | | | | | | | |
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↖ | ↗ | | ↖ | ↗ | | | ↕ | | | ↕ | |
| Traffic Vol, veh/h | 8 | 315 | 64 | 80 | 201 | 28 | 45 | 26 | 117 | 10 | 13 | 5 |
| Future Vol, veh/h | 8 | 315 | 64 | 80 | 201 | 28 | 45 | 26 | 117 | 10 | 13 | 5 |
| Conflicting Peds, #/hr | 67 | 0 | 93 | 93 | 0 | 67 | 10 | 0 | 88 | 88 | 0 | 10 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | 60 | - | - | 55 | - | - | - | - | - | - | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 8 | 315 | 64 | 80 | 201 | 28 | 45 | 26 | 117 | 10 | 13 | 5 |

| Major/Minor | Major1 | | | Major2 | | | Minor1 | | | Minor2 | | |
|----------------------|--------|---|---|--------|---|---|--------|-------|-------|--------|-------|-------|
| Conflicting Flow All | 296 | 0 | 0 | 472 | 0 | 0 | 850 | 912 | 528 | 965 | 930 | 292 |
| Stage 1 | - | - | - | - | - | - | 456 | 456 | - | 442 | 442 | - |
| Stage 2 | - | - | - | - | - | - | 394 | 456 | - | 523 | 488 | - |
| Critical Hdwy | 4.13 | - | - | 4.13 | - | - | 7.13 | 6.53 | 6.23 | 7.13 | 6.53 | 6.23 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 6.13 | 5.53 | - | 6.13 | 5.53 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 6.13 | 5.53 | - | 6.13 | 5.53 | - |
| Follow-up Hdwy | 2.227 | - | - | 2.227 | - | - | 3.527 | 4.027 | 3.327 | 3.527 | 4.027 | 3.327 |
| Pot Cap-1 Maneuver | 1260 | - | - | 1085 | - | - | 279 | 273 | 548 | 233 | 266 | 745 |
| Stage 1 | - | - | - | - | - | - | 582 | 566 | - | 592 | 575 | - |
| Stage 2 | - | - | - | - | - | - | 629 | 566 | - | 535 | 548 | - |
| Platoon blocked, % | - | - | - | - | - | - | - | - | - | - | - | - |
| Mov Cap-1 Maneuver | 1250 | - | - | 1005 | - | - | 226 | 217 | 468 | 130 | 212 | 698 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 226 | 217 | - | 130 | 212 | - |
| Stage 1 | - | - | - | - | - | - | 533 | 519 | - | 555 | 500 | - |
| Stage 2 | - | - | - | - | - | - | 555 | 492 | - | 351 | 502 | - |


| Approach | EB | | | WB | | | NB | | | SB | | |
|----------------------|-----|--|--|-----|--|--|------|--|--|------|--|--|
| HCM Control Delay, s | 0.2 | | | 2.3 | | | 29.4 | | | 26.8 | | |
| HCM LOS | | | | | | | D | | | D | | |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 |
|-----------------------|-------|-------|-----|-----|------|-----|-----|-------|
| Capacity (veh/h) | 330 | 1250 | - | - | 1005 | - | - | 193 |
| HCM Lane V/C Ratio | 0.57 | 0.006 | - | - | 0.08 | - | - | 0.145 |
| HCM Control Delay (s) | 29.4 | 7.9 | - | - | 8.9 | - | - | 26.8 |
| HCM Lane LOS | D | A | - | - | A | - | - | D |
| HCM 95th %tile Q(veh) | 3.3 | 0 | - | - | 0.3 | - | - | 0.5 |

HCM Signalized Intersection Capacity Analysis

2: 7th Street & Center Street

01/11/2019



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|-------|------|------|-------|------|
| Lane Configurations | ↶ | ↷ | ↷ | | ↶ | ↶ |
| Traffic Volume (vph) | 20 | 424 | 255 | 34 | 20 | 30 |
| Future Volume (vph) | 20 | 424 | 255 | 34 | 20 | 30 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.0 | 5.0 | 5.0 | | 3.0 | |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | | 1.00 | |
| Frbp, ped/bikes | 1.00 | 1.00 | 0.99 | | 0.88 | |
| Flpb, ped/bikes | 0.94 | 1.00 | 1.00 | | 1.00 | |
| Frt | 1.00 | 1.00 | 0.98 | | 0.92 | |
| Flt Protected | 0.95 | 1.00 | 1.00 | | 0.98 | |
| Satd. Flow (prot) | 1648 | 1845 | 1791 | | 1468 | |
| Flt Permitted | 0.58 | 1.00 | 1.00 | | 0.98 | |
| Satd. Flow (perm) | 1011 | 1845 | 1791 | | 1468 | |
| Peak-hour factor, PHF | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj. Flow (vph) | 20 | 424 | 255 | 34 | 20 | 30 |
| RTOR Reduction (vph) | 0 | 0 | 6 | 0 | 26 | 0 |
| Lane Group Flow (vph) | 20 | 424 | 283 | 0 | 24 | 0 |
| Confl. Peds. (#/hr) | 55 | | | 55 | 82 | 164 |
| Confl. Bikes (#/hr) | | | | 10 | | 7 |
| Turn Type | Perm | NA | NA | | Prot | |
| Protected Phases | | 6 | 2 | | 4 | |
| Permitted Phases | 6 | | | | | |
| Actuated Green, G (s) | 26.2 | 26.2 | 26.2 | | 4.7 | |
| Effective Green, g (s) | 26.2 | 26.2 | 26.2 | | 4.7 | |
| Actuated g/C Ratio | 0.67 | 0.67 | 0.67 | | 0.12 | |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | | 3.0 | |
| Vehicle Extension (s) | 2.0 | 2.0 | 2.0 | | 2.0 | |
| Lane Grp Cap (vph) | 680 | 1242 | 1206 | | 177 | |
| v/s Ratio Prot | | c0.23 | 0.16 | | c0.02 | |
| v/s Ratio Perm | 0.02 | | | | | |
| v/c Ratio | 0.03 | 0.34 | 0.24 | | 0.13 | |
| Uniform Delay, d1 | 2.1 | 2.7 | 2.5 | | 15.3 | |
| Progression Factor | 1.00 | 1.00 | 1.00 | | 1.00 | |
| Incremental Delay, d2 | 0.0 | 0.1 | 0.0 | | 0.1 | |
| Delay (s) | 2.1 | 2.8 | 2.5 | | 15.4 | |
| Level of Service | A | A | A | | B | |
| Approach Delay (s) | | 2.7 | 2.5 | | 15.4 | |
| Approach LOS | | A | A | | B | |

Intersection Summary

| | | | |
|-----------------------------------|-------|---------------------------|-----|
| HCM 2000 Control Delay | 3.5 | HCM 2000 Level of Service | A |
| HCM 2000 Volume to Capacity ratio | 0.31 | | |
| Actuated Cycle Length (s) | 38.9 | Sum of lost time (s) | 8.0 |
| Intersection Capacity Utilization | 46.4% | ICU Level of Service | A |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM 2010 Signalized Intersection Summary
 3: Mandela Pkwy & 7th Street

01/11/2019



| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------|------|------|------|-------|------|------|------|------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (veh/h) | 72 | 319 | 34 | 146 | 201 | 106 | 37 | 196 | 117 | 132 | 234 | 37 |
| Future Volume (veh/h) | 72 | 319 | 34 | 146 | 201 | 106 | 37 | 196 | 117 | 132 | 234 | 37 |
| Number | 1 | 6 | 16 | 5 | 2 | 12 | 3 | 8 | 18 | 7 | 4 | 14 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 1.00 | | 0.94 | 1.00 | | 0.88 | 1.00 | | 0.97 | 1.00 | | 0.98 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1845 | 1845 | 1900 | 1845 | 1845 | 1900 | 1900 | 1845 | 1900 | 1845 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 72 | 319 | 34 | 146 | 201 | 106 | 37 | 196 | 117 | 132 | 234 | 37 |
| Adj No. of Lanes | 1 | 2 | 0 | 1 | 2 | 0 | 0 | 1 | 0 | 1 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 196 | 1626 | 172 | 137 | 1017 | 498 | 72 | 267 | 148 | 251 | 447 | 71 |
| Arrive On Green | 0.11 | 0.51 | 0.51 | 0.08 | 0.47 | 0.47 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 |
| Sat Flow, veh/h | 1757 | 3177 | 335 | 1757 | 2179 | 1067 | 96 | 926 | 513 | 1052 | 1551 | 245 |
| Grp Volume(v), veh/h | 72 | 174 | 179 | 146 | 159 | 148 | 350 | 0 | 0 | 132 | 0 | 271 |
| Grp Sat Flow(s),veh/h/ln | 1757 | 1752 | 1760 | 1757 | 1752 | 1493 | 1536 | 0 | 0 | 1052 | 0 | 1796 |
| Q Serve(g_s), s | 3.4 | 4.9 | 5.0 | 7.0 | 4.8 | 5.3 | 8.0 | 0.0 | 0.0 | 2.9 | 0.0 | 11.4 |
| Cycle Q Clear(g_c), s | 3.4 | 4.9 | 5.0 | 7.0 | 4.8 | 5.3 | 19.3 | 0.0 | 0.0 | 22.2 | 0.0 | 11.4 |
| Prop In Lane | 1.00 | | 0.19 | 1.00 | | 0.71 | 0.11 | | 0.33 | 1.00 | | 0.14 |
| Lane Grp Cap(c), veh/h | 196 | 897 | 901 | 137 | 818 | 697 | 487 | 0 | 0 | 251 | 0 | 518 |
| V/C Ratio(X) | 0.37 | 0.19 | 0.20 | 1.07 | 0.19 | 0.21 | 0.72 | 0.00 | 0.00 | 0.53 | 0.00 | 0.52 |
| Avail Cap(c_a), veh/h | 196 | 897 | 901 | 137 | 818 | 697 | 578 | 0 | 0 | 310 | 0 | 619 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.97 | 0.00 | 0.00 | 1.00 | 0.00 | 1.00 |
| Uniform Delay (d), s/veh | 37.0 | 11.9 | 11.9 | 41.5 | 14.1 | 14.2 | 29.5 | 0.0 | 0.0 | 32.1 | 0.0 | 26.9 |
| Incr Delay (d2), s/veh | 0.4 | 0.5 | 0.5 | 96.5 | 0.5 | 0.7 | 2.5 | 0.0 | 0.0 | 0.6 | 0.0 | 0.3 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln | 1.7 | 2.4 | 2.5 | 7.0 | 2.4 | 2.3 | 8.4 | 0.0 | 0.0 | 3.2 | 0.0 | 5.7 |
| LnGrp Delay(d),s/veh | 37.4 | 12.4 | 12.4 | 138.0 | 14.6 | 14.9 | 31.9 | 0.0 | 0.0 | 32.8 | 0.0 | 27.2 |
| LnGrp LOS | D | B | B | F | B | B | C | | | C | | C |
| Approach Vol, veh/h | | 425 | | | 453 | | | 350 | | | 403 | |
| Approach Delay, s/veh | | 16.7 | | | 54.5 | | | 31.9 | | | 29.0 | |
| Approach LOS | | B | | | D | | | C | | | C | |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | 1 | 2 | | 4 | 5 | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | 4.1 | 46.0 | | 29.9 | 10.0 | 50.1 | | 29.9 | | | | |
| Change Period (Y+Rc), s | 4.0 | * 4 | | 4.0 | 3.0 | 4.0 | | 4.0 | | | | |
| Max Green Setting (Gmax), s | 42 | | | 31.0 | 7.0 | 41.0 | | 31.0 | | | | |
| Max Q Clear Time (g_c+1), s | 11.4 | 7.3 | | 24.2 | 9.0 | 7.0 | | 21.3 | | | | |
| Green Ext Time (p_c), s | 0.1 | 1.3 | | 1.8 | 0.0 | 1.5 | | 2.1 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | | 33.5 | | | | | | | | |
| HCM 2010 LOS | | | | C | | | | | | | | |
| Notes | | | | | | | | | | | | |

Intersection

Int Delay, s/veh 3.8

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|--------------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Lane Configurations | | ↕ | | | ↕ | | | ↕ | | | ↕ | |
| Traffic Vol, veh/h | 7 | 29 | 4 | 22 | 54 | 58 | 2 | 7 | 10 | 35 | 5 | 11 |
| Future Vol, veh/h | 7 | 29 | 4 | 22 | 54 | 58 | 2 | 7 | 10 | 35 | 5 | 11 |
| Conflicting Peds, #/hr | 31 | 0 | 11 | 11 | 0 | 31 | 19 | 0 | 15 | 15 | 0 | 19 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | - | - | - | - | - | - | - | - | - | - | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 7 | 29 | 4 | 22 | 54 | 58 | 2 | 7 | 10 | 35 | 5 | 11 |

| Major/Minor | Major1 | Major2 | Minor1 | Minor2 |
|----------------------|--------|--------|--------|--------|
| Conflicting Flow All | 143 | 0 | 0 | 44 |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Critical Hdwy | 4.13 | - | - | 4.13 |
| Critical Hdwy Stg 1 | - | - | - | - |
| Critical Hdwy Stg 2 | - | - | - | - |
| Follow-up Hdwy | 2.227 | - | - | 2.227 |
| Pot Cap-1 Maneuver | 1434 | - | - | 1558 |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |
| Platoon blocked, % | - | - | - | - |
| Mov Cap-1 Maneuver | 1411 | - | - | 1539 |
| Mov Cap-2 Maneuver | - | - | - | - |
| Stage 1 | - | - | - | - |
| Stage 2 | - | - | - | - |

| Approach | EB | WB | NB | SB |
|----------------------|-----|-----|-----|------|
| HCM Control Delay, s | 1.3 | 1.2 | 9.7 | 10.5 |
| HCM LOS | | | A | B |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 |
|-----------------------|-------|-------|-----|-----|-------|-----|-----|-------|
| Capacity (veh/h) | 783 | 1411 | - | - | 1539 | - | - | 706 |
| HCM Lane V/C Ratio | 0.024 | 0.005 | - | - | 0.014 | - | - | 0.072 |
| HCM Control Delay (s) | 9.7 | 7.6 | 0 | - | 7.4 | 0 | - | 10.5 |
| HCM Lane LOS | A | A | A | - | A | A | - | B |
| HCM 95th %tile Q(veh) | 0.1 | 0 | - | - | 0 | - | - | 0.2 |

| Intersection | | | | | | |
|--------------------------|------|------|------|------|------|------|
| Int Delay, s/veh | 1 | | | | | |
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | | | | | | |
| Traffic Vol, veh/h | 134 | 6 | 21 | 154 | 6 | 14 |
| Future Vol, veh/h | 134 | 6 | 21 | 154 | 6 | 14 |
| Conflicting Peds, #/hr | 0 | 3 | 3 | 0 | 9 | 3 |
| Sign Control | Free | Free | Free | Free | Stop | Stop |
| RT Channelized | - | None | - | None | - | None |
| Storage Length | - | - | - | - | 0 | - |
| Veh in Median Storage, # | 0 | - | - | 0 | 0 | - |
| Grade, % | 0 | - | - | 0 | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 134 | 6 | 21 | 154 | 6 | 14 |

















| Major/Minor | Major1 | Major2 | Minor1 | | |
|----------------------|--------|--------|--------|---|-------|
| Conflicting Flow All | 0 | 0 | 143 | 0 | 345 |
| Stage 1 | - | - | - | - | 140 |
| Stage 2 | - | - | - | - | 205 |
| Critical Hdwy | - | - | 4.13 | - | 6.43 |
| Critical Hdwy Stg 1 | - | - | - | - | 5.43 |
| Critical Hdwy Stg 2 | - | - | - | - | 5.43 |
| Follow-up Hdwy | - | - | 2.227 | - | 3.527 |
| Pot Cap-1 Maneuver | - | - | 1434 | - | 650 |
| Stage 1 | - | - | - | - | 884 |
| Stage 2 | - | - | - | - | 827 |
| Platoon blocked, % | - | - | - | - | - |
| Mov Cap-1 Maneuver | - | - | 1430 | - | 633 |
| Mov Cap-2 Maneuver | - | - | - | - | 633 |
| Stage 1 | - | - | - | - | 882 |
| Stage 2 | - | - | - | - | 808 |

| Approach | EB | WB | NB |
|----------------------|----|-----|-----|
| HCM Control Delay, s | 0 | 0.9 | 9.6 |
| HCM LOS | | | A |

| Minor Lane/Major Mvmt | NBLn1 | EBT | EBR | WBL | WBT |
|-----------------------|-------|-----|-----|-------|-----|
| Capacity (veh/h) | 797 | - | - | 1430 | - |
| HCM Lane V/C Ratio | 0.025 | - | - | 0.015 | - |
| HCM Control Delay (s) | 9.6 | - | - | 7.6 | 0 |
| HCM Lane LOS | A | - | - | A | A |
| HCM 95th %tile Q(veh) | 0.1 | - | - | 0 | - |

HCM 2010 Signalized Intersection Summary
 6: Mandela Pkwy & 5th Street



















01/11/2019

| |  |  |  |  |  |  |  |  |  |  |  |  |
|------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | |  | | |  | | |  | | |  | |
| Traffic Volume (veh/h) | 67 | 109 | 36 | 38 | 122 | 102 | 32 | 102 | 46 | 45 | 108 | 49 |
| Future Volume (veh/h) | 67 | 109 | 36 | 38 | 122 | 102 | 32 | 102 | 46 | 45 | 108 | 49 |
| Number | 7 | 4 | 14 | 3 | 8 | 18 | 5 | 2 | 12 | 1 | 6 | 16 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 0.93 | | 0.87 | 0.92 | | 0.89 | 0.92 | | 0.87 | 0.92 | | 0.87 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 67 | 109 | 36 | 38 | 122 | 102 | 32 | 102 | 46 | 45 | 108 | 49 |
| Adj No. of Lanes | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 258 | 381 | 108 | 145 | 356 | 258 | 159 | 406 | 159 | 186 | 383 | 149 |
| Arrive On Green | 0.42 | 0.42 | 0.42 | 0.42 | 0.42 | 0.42 | 0.39 | 0.39 | 0.39 | 0.39 | 0.39 | 0.39 |
| Sat Flow, veh/h | 347 | 904 | 256 | 113 | 846 | 612 | 150 | 1042 | 409 | 211 | 982 | 382 |
| Grp Volume(v), veh/h | 212 | 0 | 0 | 262 | 0 | 0 | 180 | 0 | 0 | 202 | 0 | 0 |
| Grp Sat Flow(s),veh/h/ln | 1508 | 0 | 0 | 1571 | 0 | 0 | 1600 | 0 | 0 | 1575 | 0 | 0 |
| Q Serve(g_s), s | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Cycle Q Clear(g_c), s | 3.4 | 0.0 | 0.0 | 4.7 | 0.0 | 0.0 | 3.1 | 0.0 | 0.0 | 3.5 | 0.0 | 0.0 |
| Prop In Lane | 0.32 | | 0.17 | 0.15 | | 0.39 | 0.18 | | 0.26 | 0.22 | | 0.24 |
| Lane Grp Cap(c), veh/h | 747 | 0 | 0 | 759 | 0 | 0 | 724 | 0 | 0 | 718 | 0 | 0 |
| V/C Ratio(X) | 0.28 | 0.00 | 0.00 | 0.35 | 0.00 | 0.00 | 0.25 | 0.00 | 0.00 | 0.28 | 0.00 | 0.00 |
| Avail Cap(c_a), veh/h | 988 | 0 | 0 | 1015 | 0 | 0 | 1211 | 0 | 0 | 1197 | 0 | 0 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 |
| Uniform Delay (d), s/veh | 8.1 | 0.0 | 0.0 | 8.4 | 0.0 | 0.0 | 8.8 | 0.0 | 0.0 | 8.9 | 0.0 | 0.0 |
| Incr Delay (d2), s/veh | 0.1 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln | 1.6 | 0.0 | 0.0 | 2.1 | 0.0 | 0.0 | 1.4 | 0.0 | 0.0 | 1.6 | 0.0 | 0.0 |
| LnGrp Delay(d),s/veh | 8.2 | 0.0 | 0.0 | 8.5 | 0.0 | 0.0 | 8.9 | 0.0 | 0.0 | 9.0 | 0.0 | 0.0 |
| LnGrp LOS | A | | | A | | | A | | | A | | |
| Approach Vol, veh/h | | 212 | | | 262 | | | 180 | | | 202 | |
| Approach Delay, s/veh | | 8.2 | | | 8.5 | | | 8.9 | | | 9.0 | |
| Approach LOS | | A | | | A | | | A | | | A | |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | | 2 | | 4 | | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | | 20.5 | | 21.8 | | 20.5 | | 21.8 | | | | |
| Change Period (Y+Rc), s | | 4.0 | | 4.0 | | 4.0 | | 4.0 | | | | |
| Max Green Setting (Gmax), s | | 30.0 | | 25.0 | | 30.0 | | 25.0 | | | | |
| Max Q Clear Time (g_c+I1), s | | 5.1 | | 5.4 | | 5.5 | | 6.7 | | | | |
| Green Ext Time (p_c), s | | 1.6 | | 2.2 | | 1.6 | | 2.2 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | 8.6 | | | | | | | | | |
| HCM 2010 LOS | | | A | | | | | | | | | |

HCM 2010 Signalized Intersection Summary

1: Chester Street & 7th Street


01/11/2019

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations |  |  | |  |  | | |  | | |  | |
| Traffic Volume (veh/h) | 7 | 136 | 118 | 209 | 136 | 17 | 97 | 41 | 217 | 4 | 24 | 5 |
| Future Volume (veh/h) | 7 | 136 | 118 | 209 | 136 | 17 | 97 | 41 | 217 | 4 | 24 | 5 |
| Number | 1 | 6 | 16 | 5 | 2 | 12 | 3 | 8 | 18 | 7 | 4 | 14 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 1.00 | | 0.80 | 1.00 | | 0.88 | 0.87 | | 0.86 | 0.98 | | 0.86 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1845 | 1845 | 1900 | 1845 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 7 | 136 | 118 | 209 | 136 | 17 | 97 | 41 | 217 | 4 | 24 | 5 |
| Adj No. of Lanes | 1 | 1 | 0 | 1 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 13 | 208 | 181 | 452 | 802 | 100 | 159 | 74 | 263 | 90 | 425 | 82 |
| Arrive On Green | 0.01 | 0.26 | 0.26 | 0.26 | 0.51 | 0.51 | 0.31 | 0.31 | 0.31 | 0.31 | 0.31 | 0.31 |
| Sat Flow, veh/h | 1757 | 809 | 702 | 1757 | 1581 | 198 | 298 | 235 | 837 | 102 | 1354 | 260 |
| Grp Volume(v), veh/h | 7 | 0 | 254 | 209 | 0 | 153 | 355 | 0 | 0 | 33 | 0 | 0 |
| Grp Sat Flow(s),veh/h/ln | 1757 | 0 | 1512 | 1757 | 0 | 1779 | 1370 | 0 | 0 | 1716 | 0 | 0 |
| Q Serve(g_s), s | 0.3 | 0.0 | 10.5 | 7.0 | 0.0 | 3.2 | 12.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Cycle Q Clear(g_c), s | 0.3 | 0.0 | 10.5 | 7.0 | 0.0 | 3.2 | 16.6 | 0.0 | 0.0 | 0.9 | 0.0 | 0.0 |
| Prop In Lane | 1.00 | | 0.46 | 1.00 | | 0.11 | 0.27 | | 0.61 | 0.12 | | 0.15 |
| Lane Grp Cap(c), veh/h | 13 | 0 | 389 | 452 | 0 | 902 | 496 | 0 | 0 | 597 | 0 | 0 |
| V/C Ratio(X) | 0.55 | 0.00 | 0.65 | 0.46 | 0.00 | 0.17 | 0.72 | 0.00 | 0.00 | 0.06 | 0.00 | 0.00 |
| Avail Cap(c_a), veh/h | 100 | 0 | 389 | 452 | 0 | 902 | 496 | 0 | 0 | 597 | 0 | 0 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 0.00 | 1.00 | 0.97 | 0.00 | 0.97 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 |
| Uniform Delay (d), s/veh | 34.6 | 0.0 | 23.2 | 21.9 | 0.0 | 9.3 | 22.0 | 0.0 | 0.0 | 16.8 | 0.0 | 0.0 |
| Incr Delay (d2), s/veh | 12.9 | 0.0 | 8.3 | 0.3 | 0.0 | 0.4 | 8.6 | 0.0 | 0.0 | 0.2 | 0.0 | 0.0 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln | 0.2 | 0.0 | 5.3 | 3.4 | 0.0 | 1.7 | 7.5 | 0.0 | 0.0 | 0.5 | 0.0 | 0.0 |
| LnGrp Delay(d),s/veh | 47.5 | 0.0 | 31.5 | 22.2 | 0.0 | 9.7 | 30.5 | 0.0 | 0.0 | 17.0 | 0.0 | 0.0 |
| LnGrp LOS | D | | C | C | | A | C | | | B | | |
| Approach Vol, veh/h | | 261 | | | 362 | | | 355 | | | | 33 |
| Approach Delay, s/veh | | 31.9 | | | 16.9 | | | 30.5 | | | | 17.0 |
| Approach LOS | | C | | | B | | | C | | | | B |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | 1 | 2 | | 4 | 5 | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | 4.5 | 39.5 | | 26.0 | 22.0 | 22.0 | | 26.0 | | | | |
| Change Period (Y+Rc), s | 4.0 | 4.0 | | 4.0 | 4.0 | 4.0 | | 4.0 | | | | |
| Max Green Setting (Gmax), s | 4.0 | 32.0 | | 22.0 | 18.0 | 18.0 | | 22.0 | | | | |
| Max Q Clear Time (g_c+1), s | 2.3 | 5.2 | | 2.9 | 9.0 | 12.5 | | 18.6 | | | | |
| Green Ext Time (p_c), s | 0.0 | 0.8 | | 1.9 | 0.6 | 0.5 | | 0.7 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | 25.6 | | | | | | | | | |
| HCM 2010 LOS | | | C | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis

2: 7th Street & Center Street

01/11/2019



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|-------|------|-------|------|
| Lane Configurations | ↙ | ↑ | ↘ | | ↙ | ↘ |
| Traffic Volume (vph) | 20 | 342 | 369 | 32 | 16 | 23 |
| Future Volume (vph) | 20 | 342 | 369 | 32 | 16 | 23 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.0 | 5.0 | 5.0 | | 3.0 | |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | | 1.00 | |
| Frbp, ped/bikes | 1.00 | 1.00 | 0.99 | | 0.88 | |
| Flpb, ped/bikes | 0.95 | 1.00 | 1.00 | | 1.00 | |
| Frt | 1.00 | 1.00 | 0.99 | | 0.92 | |
| Flt Protected | 0.95 | 1.00 | 1.00 | | 0.98 | |
| Satd. Flow (prot) | 1659 | 1845 | 1808 | | 1465 | |
| Flt Permitted | 0.53 | 1.00 | 1.00 | | 0.98 | |
| Satd. Flow (perm) | 918 | 1845 | 1808 | | 1465 | |
| Peak-hour factor, PHF | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj. Flow (vph) | 20 | 342 | 369 | 32 | 16 | 23 |
| RTOR Reduction (vph) | 0 | 0 | 2 | 0 | 20 | 0 |
| Lane Group Flow (vph) | 20 | 342 | 399 | 0 | 19 | 0 |
| Confl. Peds. (#/hr) | 55 | | | 55 | 82 | 164 |
| Confl. Bikes (#/hr) | | | | 10 | | 7 |
| Turn Type | Perm | NA | NA | | Prot | |
| Protected Phases | | 6 | 2 | | 4 | |
| Permitted Phases | 6 | | | | | |
| Actuated Green, G (s) | 28.1 | 28.1 | 28.1 | | 4.7 | |
| Effective Green, g (s) | 28.1 | 28.1 | 28.1 | | 4.7 | |
| Actuated g/C Ratio | 0.69 | 0.69 | 0.69 | | 0.12 | |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | | 3.0 | |
| Vehicle Extension (s) | 2.0 | 2.0 | 2.0 | | 2.0 | |
| Lane Grp Cap (vph) | 632 | 1270 | 1245 | | 168 | |
| v/s Ratio Prot | | 0.19 | c0.22 | | c0.01 | |
| v/s Ratio Perm | 0.02 | | | | | |
| v/c Ratio | 0.03 | 0.27 | 0.32 | | 0.11 | |
| Uniform Delay, d1 | 2.0 | 2.4 | 2.5 | | 16.2 | |
| Progression Factor | 1.00 | 1.00 | 1.00 | | 1.00 | |
| Incremental Delay, d2 | 0.0 | 0.0 | 0.1 | | 0.1 | |
| Delay (s) | 2.0 | 2.5 | 2.6 | | 16.3 | |
| Level of Service | A | A | A | | B | |
| Approach Delay (s) | | 2.4 | 2.6 | | 16.3 | |
| Approach LOS | | A | A | | B | |





















Intersection Summary

| | | | |
|-----------------------------------|-------|---------------------------|------|
| HCM 2000 Control Delay | 3.2 | HCM 2000 Level of Service | A |
| HCM 2000 Volume to Capacity ratio | 0.31 | | |
| Actuated Cycle Length (s) | 40.8 | Sum of lost time (s) | 10.0 |
| Intersection Capacity Utilization | 45.8% | ICU Level of Service | A |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM 2010 Signalized Intersection Summary
 3: Mandela Pkwy & 7th Street

01/11/2019

| |  |  |  |  |  |  |  |  |  |  |  |  |
|------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations |  |  | |  |  |  | |  | |  |  | |
| Traffic Volume (veh/h) | 78 | 260 | 23 | 183 | 313 | 80 | 23 | 116 | 70 | 73 | 283 | 58 |
| Future Volume (veh/h) | 78 | 260 | 23 | 183 | 313 | 80 | 23 | 116 | 70 | 73 | 283 | 58 |
| Number | 1 | 6 | 16 | 5 | 2 | 12 | 3 | 8 | 18 | 7 | 4 | 14 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 1.00 | | 0.93 | 1.00 | | 0.87 | 1.00 | | 0.95 | 1.00 | | 0.98 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1845 | 1845 | 1900 | 1845 | 1845 | 1845 | 1900 | 1845 | 1900 | 1845 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 78 | 260 | 23 | 183 | 313 | 80 | 23 | 116 | 70 | 73 | 283 | 58 |
| Adj No. of Lanes | 1 | 1 | 0 | 1 | 1 | 1 | 0 | 1 | 0 | 1 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 310 | 769 | 68 | 218 | 738 | 545 | 54 | 167 | 89 | 220 | 348 | 71 |
| Arrive On Green | 0.18 | 0.46 | 0.46 | 0.12 | 0.40 | 0.40 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 | 0.23 |
| Sat Flow, veh/h | 1757 | 1660 | 147 | 1757 | 1845 | 1363 | 40 | 713 | 379 | 1181 | 1481 | 304 |
| Grp Volume(v), veh/h | 78 | 0 | 283 | 183 | 313 | 80 | 209 | 0 | 0 | 73 | 0 | 341 |
| Grp Sat Flow(s),veh/h/ln | 1757 | 0 | 1806 | 1757 | 1845 | 1363 | 1132 | 0 | 0 | 1181 | 0 | 1785 |
| Q Serve(g_s), s | 3.4 | 0.0 | 9.0 | 9.2 | 11.0 | 3.4 | 1.1 | 0.0 | 0.0 | 0.0 | 0.0 | 16.3 |
| Cycle Q Clear(g_c), s | 3.4 | 0.0 | 9.0 | 9.2 | 11.0 | 3.4 | 17.4 | 0.0 | 0.0 | 12.6 | 0.0 | 16.3 |
| Prop In Lane | 1.00 | | 0.08 | 1.00 | | 1.00 | 0.11 | | 0.33 | 1.00 | | 0.17 |
| Lane Grp Cap(c), veh/h | 310 | 0 | 837 | 218 | 738 | 545 | 310 | 0 | 0 | 220 | 0 | 419 |
| V/C Ratio(X) | 0.25 | 0.00 | 0.34 | 0.84 | 0.42 | 0.15 | 0.67 | 0.00 | 0.00 | 0.33 | 0.00 | 0.81 |
| Avail Cap(c_a), veh/h | 310 | 0 | 837 | 332 | 738 | 545 | 448 | 0 | 0 | 323 | 0 | 575 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 0.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 1.00 |
| Uniform Delay (d), s/veh | 31.9 | 0.0 | 15.4 | 38.5 | 19.5 | 17.2 | 30.4 | 0.0 | 0.0 | 31.2 | 0.0 | 32.6 |
| Incr Delay (d2), s/veh | 0.2 | 0.0 | 1.1 | 6.9 | 1.8 | 0.6 | 1.0 | 0.0 | 0.0 | 0.3 | 0.0 | 4.5 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln | 1.7 | 0.0 | 4.7 | 4.8 | 5.9 | 1.4 | 5.1 | 0.0 | 0.0 | 1.7 | 0.0 | 8.5 |
| LnGrp Delay(d),s/veh | 32.1 | 0.0 | 16.5 | 45.4 | 21.3 | 17.8 | 31.3 | 0.0 | 0.0 | 31.5 | 0.0 | 37.1 |
| LnGrp LOS | C | | B | D | C | B | C | | | C | | D |
| Approach Vol, veh/h | | 361 | | | 576 | | | 209 | | | 414 | |
| Approach Delay, s/veh | | 19.8 | | | 28.5 | | | 31.3 | | | 36.1 | |
| Approach LOS | | B | | | C | | | C | | | D | |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | 1 | 2 | | 4 | 5 | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | 19.9 | 40.0 | | 30.1 | 14.2 | 45.7 | | 30.1 | | | | |
| Change Period (Y+Rc), s | 4.0 | * 4 | | 9.0 | 3.0 | 4.0 | | 9.0 | | | | |
| Max Green Setting (Gmax), s | 9.0 | * 36 | | 29.0 | 17.0 | 28.0 | | 29.0 | | | | |
| Max Q Clear Time (g_c+I1), s | 5.4 | 13.0 | | 18.3 | 11.2 | 11.0 | | 19.4 | | | | |
| Green Ext Time (p_c), s | 0.1 | 1.4 | | 1.8 | 0.1 | 1.1 | | 1.7 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | 28.9 | | | | | | | | | |
| HCM 2010 LOS | | | C | | | | | | | | | |
| Notes | | | | | | | | | | | | |

| Intersection | |
|---------------------------|-----|
| Intersection Delay, s/veh | 7.8 |
| Intersection LOS | A |

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|---------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Lane Configurations | | ↕ | | | ↕ | | | ↕ | | | ↕ | |
| Traffic Vol, veh/h | 2 | 38 | 0 | 5 | 29 | 152 | 0 | 3 | 13 | 92 | 4 | 13 |
| Future Vol, veh/h | 2 | 38 | 0 | 5 | 29 | 152 | 0 | 3 | 13 | 92 | 4 | 13 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 2 | 38 | 0 | 5 | 29 | 152 | 0 | 3 | 13 | 92 | 4 | 13 |
| Number of Lanes | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 |

| Approach | EB | WB | NB | SB |
|----------------------------|-----|-----|-----|-----|
| Opposing Approach | WB | EB | SB | NB |
| Opposing Lanes | 1 | 1 | 1 | 1 |
| Conflicting Approach Left | SB | NB | EB | WB |
| Conflicting Lanes Left | 1 | 1 | 1 | 1 |
| Conflicting Approach Right | NB | SB | WB | EB |
| Conflicting Lanes Right | 1 | 1 | 1 | 1 |
| HCM Control Delay | 7.7 | 7.7 | 7.1 | 8.2 |
| HCM LOS | A | A | A | A |

| Lane | NBLn1 | EBLn1 | WBLn1 | SBLn1 |
|------------------------|-------|-------|-------|-------|
| Vol Left, % | 0% | 5% | 3% | 84% |
| Vol Thru, % | 19% | 95% | 16% | 4% |
| Vol Right, % | 81% | 0% | 82% | 12% |
| Sign Control | Stop | Stop | Stop | Stop |
| Traffic Vol by Lane | 16 | 40 | 186 | 109 |
| LT Vol | 0 | 2 | 5 | 92 |
| Through Vol | 3 | 38 | 29 | 4 |
| RT Vol | 13 | 0 | 152 | 13 |
| Lane Flow Rate | 16 | 40 | 186 | 109 |
| Geometry Grp | 1 | 1 | 1 | 1 |
| Degree of Util (X) | 0.018 | 0.049 | 0.192 | 0.135 |
| Departure Headway (Hd) | 4.053 | 4.433 | 3.713 | 4.452 |
| Convergence, Y/N | Yes | Yes | Yes | Yes |
| Cap | 888 | 813 | 949 | 796 |
| Service Time | 2.055 | 2.433 | 1.807 | 2.532 |
| HCM Lane V/C Ratio | 0.018 | 0.049 | 0.196 | 0.137 |
| HCM Control Delay | 7.1 | 7.7 | 7.7 | 8.2 |
| HCM Lane LOS | A | A | A | A |
| HCM 95th-tile Q | 0.1 | 0.2 | 0.7 | 0.5 |

| Intersection | |
|---------------------------|-----|
| Intersection Delay, s/veh | 8.7 |
| Intersection LOS | A |

















| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
|---------------------|------|------|------|------|------|------|
| Lane Configurations | | | | | | |
| Traffic Vol, veh/h | 207 | 4 | 9 | 232 | 2 | 24 |
| Future Vol, veh/h | 207 | 4 | 9 | 232 | 2 | 24 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 207 | 4 | 9 | 232 | 2 | 24 |
| Number of Lanes | 1 | 0 | 0 | 1 | 1 | 0 |

| Approach | EB | WB | NB |
|----------------------------|-----|-----|-----|
| Opposing Approach | WB | EB | |
| Opposing Lanes | 1 | 1 | 0 |
| Conflicting Approach Left | | NB | EB |
| Conflicting Lanes Left | 0 | 1 | 1 |
| Conflicting Approach Right | NB | | WB |
| Conflicting Lanes Right | 1 | 0 | 1 |
| HCM Control Delay | 8.6 | 8.9 | 7.5 |
| HCM LOS | A | A | A |

| Lane | NBLn1 | EBLn1 | WBLn1 |
|------------------------|-------|-------|-------|
| Vol Left, % | 8% | 0% | 4% |
| Vol Thru, % | 0% | 98% | 96% |
| Vol Right, % | 92% | 2% | 0% |
| Sign Control | Stop | Stop | Stop |
| Traffic Vol by Lane | 26 | 211 | 241 |
| LT Vol | 2 | 0 | 9 |
| Through Vol | 0 | 207 | 232 |
| RT Vol | 24 | 4 | 0 |
| Lane Flow Rate | 26 | 211 | 241 |
| Geometry Grp | 1 | 1 | 1 |
| Degree of Util (X) | 0.032 | 0.244 | 0.279 |
| Departure Headway (Hd) | 4.383 | 4.165 | 4.162 |
| Convergence, Y/N | Yes | Yes | Yes |
| Cap | 822 | 852 | 856 |
| Service Time | 2.383 | 2.239 | 2.228 |
| HCM Lane V/C Ratio | 0.032 | 0.248 | 0.282 |
| HCM Control Delay | 7.5 | 8.6 | 8.9 |
| HCM Lane LOS | A | A | A |
| HCM 95th-tile Q | 0.1 | 1 | 1.1 |



















HCM 2010 Signalized Intersection Summary
 6: Mandela Pkwy & 5th Street

01/11/2019

| |  |  |  |  |  |  |  |  |  |  |  |  |
|------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | |  | | |  | | |  | | |  | |
| Traffic Volume (veh/h) | 47 | 173 | 47 | 20 | 231 | 59 | 12 | 35 | 17 | 86 | 38 | 22 |
| Future Volume (veh/h) | 47 | 173 | 47 | 20 | 231 | 59 | 12 | 35 | 17 | 86 | 38 | 22 |
| Number | 7 | 4 | 14 | 3 | 8 | 18 | 5 | 2 | 12 | 1 | 6 | 16 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 0.94 | | 0.87 | 0.93 | | 0.89 | 0.91 | | 0.86 | 0.90 | | 0.87 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 47 | 173 | 47 | 20 | 231 | 59 | 12 | 35 | 17 | 86 | 38 | 22 |
| Adj No. of Lanes | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 165 | 503 | 122 | 109 | 572 | 139 | 164 | 389 | 164 | 414 | 172 | 80 |
| Arrive On Green | 0.43 | 0.43 | 0.43 | 0.43 | 0.43 | 0.43 | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 | 0.38 |
| Sat Flow, veh/h | 154 | 1177 | 284 | 43 | 1339 | 325 | 164 | 1013 | 426 | 726 | 448 | 208 |
| Grp Volume(v), veh/h | 267 | 0 | 0 | 310 | 0 | 0 | 64 | 0 | 0 | 146 | 0 | 0 |
| Grp Sat Flow(s),veh/h/ln | 1616 | 0 | 0 | 1707 | 0 | 0 | 1603 | 0 | 0 | 1382 | 0 | 0 |
| Q Serve(g_s), s | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.3 | 0.0 | 0.0 |
| Cycle Q Clear(g_c), s | 4.4 | 0.0 | 0.0 | 5.3 | 0.0 | 0.0 | 1.0 | 0.0 | 0.0 | 2.7 | 0.0 | 0.0 |
| Prop In Lane | 0.18 | | 0.18 | 0.06 | | 0.19 | 0.19 | | 0.27 | 0.59 | | 0.15 |
| Lane Grp Cap(c), veh/h | 790 | 0 | 0 | 820 | 0 | 0 | 717 | 0 | 0 | 666 | 0 | 0 |
| V/C Ratio(X) | 0.34 | 0.00 | 0.00 | 0.38 | 0.00 | 0.00 | 0.09 | 0.00 | 0.00 | 0.22 | 0.00 | 0.00 |
| Avail Cap(c_a), veh/h | 1036 | 0 | 0 | 1087 | 0 | 0 | 1212 | 0 | 0 | 1100 | 0 | 0 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 |
| Uniform Delay (d), s/veh | 8.2 | 0.0 | 0.0 | 8.5 | 0.0 | 0.0 | 8.4 | 0.0 | 0.0 | 8.8 | 0.0 | 0.0 |
| Incr Delay (d2), s/veh | 0.1 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln | 2.1 | 0.0 | 0.0 | 2.5 | 0.0 | 0.0 | 0.5 | 0.0 | 0.0 | 1.1 | 0.0 | 0.0 |
| LnGrp Delay(d),s/veh | 8.3 | 0.0 | 0.0 | 8.6 | 0.0 | 0.0 | 8.4 | 0.0 | 0.0 | 8.9 | 0.0 | 0.0 |
| LnGrp LOS | A | | | A | | | A | | | A | | |
| Approach Vol, veh/h | | 267 | | | 310 | | | 64 | | | 146 | |
| Approach Delay, s/veh | | 8.3 | | | 8.6 | | | 8.4 | | | 8.9 | |
| Approach LOS | | A | | | A | | | A | | | A | |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | | 2 | | 4 | | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | | 20.3 | | 22.2 | | 20.3 | | 22.2 | | | | |
| Change Period (Y+Rc), s | | 4.0 | | 4.0 | | 4.0 | | 4.0 | | | | |
| Max Green Setting (Gmax), s | | 30.0 | | 25.0 | | 30.0 | | 25.0 | | | | |
| Max Q Clear Time (g_c+I1), s | | 3.0 | | 6.4 | | 4.7 | | 7.3 | | | | |
| Green Ext Time (p_c), s | | 0.8 | | 2.6 | | 0.8 | | 2.5 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | 8.5 | | | | | | | | | |
| HCM 2010 LOS | | | A | | | | | | | | | |

HCM 2010 Signalized Intersection Summary
 1: Chester Street & 7th Street

West Oakland BART TIA
 Existing Plus Project PM Peak Conditions

| |  |  |  |  |  |  |  |  |  |  |  |  |
|------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations |  |  | |  |  | | |  | | |  | |
| Traffic Volume (veh/h) | 8 | 315 | 106 | 160 | 201 | 28 | 108 | 30 | 271 | 10 | 16 | 5 |
| Future Volume (veh/h) | 8 | 315 | 106 | 160 | 201 | 28 | 108 | 30 | 271 | 10 | 16 | 5 |
| Number | 1 | 6 | 16 | 5 | 2 | 12 | 3 | 8 | 18 | 7 | 4 | 14 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 1.00 | | 0.84 | 1.00 | | 0.88 | 0.87 | | 0.87 | 1.00 | | 0.87 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1845 | 1845 | 1900 | 1845 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 8 | 315 | 106 | 160 | 201 | 28 | 108 | 30 | 271 | 10 | 16 | 5 |
| Adj No. of Lanes | 1 | 1 | 0 | 1 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 14 | 430 | 145 | 276 | 765 | 107 | 162 | 54 | 297 | 173 | 254 | 69 |
| Arrive On Green | 0.01 | 0.34 | 0.34 | 0.16 | 0.49 | 0.49 | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 |
| Sat Flow, veh/h | 1757 | 1255 | 422 | 1757 | 1555 | 217 | 294 | 166 | 903 | 318 | 773 | 210 |
| Grp Volume(v), veh/h | 8 | 0 | 421 | 160 | 0 | 229 | 409 | 0 | 0 | 31 | 0 | 0 |
| Grp Sat Flow(s),veh/h/ln | 1757 | 0 | 1678 | 1757 | 0 | 1771 | 1362 | 0 | 0 | 1302 | 0 | 0 |
| Q Serve(g_s), s | 0.3 | 0.0 | 15.4 | 5.9 | 0.0 | 5.3 | 16.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Cycle Q Clear(g_c), s | 0.3 | 0.0 | 15.4 | 5.9 | 0.0 | 5.3 | 20.1 | 0.0 | 0.0 | 0.9 | 0.0 | 0.0 |
| Prop In Lane | 1.00 | | 0.25 | 1.00 | | 0.12 | 0.26 | | 0.66 | 0.32 | | 0.16 |
| Lane Grp Cap(c), veh/h | 14 | 0 | 575 | 276 | 0 | 871 | 513 | 0 | 0 | 496 | 0 | 0 |
| V/C Ratio(X) | 0.55 | 0.00 | 0.73 | 0.58 | 0.00 | 0.26 | 0.80 | 0.00 | 0.00 | 0.06 | 0.00 | 0.00 |
| Avail Cap(c_a), veh/h | 100 | 0 | 575 | 276 | 0 | 871 | 513 | 0 | 0 | 496 | 0 | 0 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 0.00 | 1.00 | 0.98 | 0.00 | 0.98 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 |
| Uniform Delay (d), s/veh | 34.6 | 0.0 | 20.2 | 27.4 | 0.0 | 10.4 | 22.4 | 0.0 | 0.0 | 16.1 | 0.0 | 0.0 |
| Incr Delay (d2), s/veh | 11.7 | 0.0 | 8.0 | 2.0 | 0.0 | 0.7 | 12.2 | 0.0 | 0.0 | 0.2 | 0.0 | 0.0 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln | 0.2 | 0.0 | 8.4 | 3.0 | 0.0 | 2.7 | 9.2 | 0.0 | 0.0 | 0.4 | 0.0 | 0.0 |
| LnGrp Delay(d),s/veh | 46.3 | 0.0 | 28.2 | 29.3 | 0.0 | 11.1 | 34.6 | 0.0 | 0.0 | 16.3 | 0.0 | 0.0 |
| LnGrp LOS | D | | C | C | | B | C | | | B | | |
| Approach Vol, veh/h | | 429 | | | 389 | | | 409 | | | | 31 |
| Approach Delay, s/veh | | 28.5 | | | 18.6 | | | 34.6 | | | | 16.3 |
| Approach LOS | | C | | | B | | | C | | | | B |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | 1 | 2 | | 4 | 5 | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | 4.6 | 38.4 | | 27.0 | 15.0 | 28.0 | | 27.0 | | | | |
| Change Period (Y+Rc), s | 4.0 | 4.0 | | 4.0 | 4.0 | 4.0 | | 4.0 | | | | |
| Max Green Setting (Gmax), s | 4.0 | 31.0 | | 23.0 | 11.0 | 24.0 | | 23.0 | | | | |
| Max Q Clear Time (g_c+I1), s | 2.3 | 7.3 | | 2.9 | 7.9 | 17.4 | | 22.1 | | | | |
| Green Ext Time (p_c), s | 0.0 | 1.1 | | 2.3 | 0.2 | 1.1 | | 0.2 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | | 27.1 | | | | | | | | |
| HCM 2010 LOS | | | | C | | | | | | | | |

HCM Signalized Intersection Capacity Analysis

2: 7th Street & Center Street

West Oakland BART TIA
Existing Plus Project PM Peak Conditions



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|-----------------------------------|------|-------|-------|------|---------------------------|------|
| Lane Configurations | | | | | | |
| Traffic Volume (vph) | 24 | 574 | 337 | 34 | 20 | 33 |
| Future Volume (vph) | 24 | 574 | 337 | 34 | 20 | 33 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.0 | 5.0 | 5.0 | | 3.0 | |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | | 1.00 | |
| Frpb, ped/bikes | 1.00 | 1.00 | 0.99 | | 0.85 | |
| Flpb, ped/bikes | 0.93 | 1.00 | 1.00 | | 1.00 | |
| Frt | 1.00 | 1.00 | 0.99 | | 0.92 | |
| Flt Protected | 0.95 | 1.00 | 1.00 | | 0.98 | |
| Satd. Flow (prot) | 1631 | 1845 | 1799 | | 1407 | |
| Flt Permitted | 0.54 | 1.00 | 1.00 | | 0.98 | |
| Satd. Flow (perm) | 928 | 1845 | 1799 | | 1407 | |
| Peak-hour factor, PHF | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj. Flow (vph) | 24 | 574 | 337 | 34 | 20 | 33 |
| RTOR Reduction (vph) | 0 | 0 | 2 | 0 | 29 | 0 |
| Lane Group Flow (vph) | 24 | 574 | 369 | 0 | 24 | 0 |
| Confl. Peds. (#/hr) | 55 | | | 55 | 82 | 164 |
| Confl. Bikes (#/hr) | | | | 10 | | 7 |
| Turn Type | Perm | NA | NA | | Prot | |
| Protected Phases | | 6 | 2 | | 4 | |
| Permitted Phases | 6 | | | | | |
| Actuated Green, G (s) | 37.4 | 37.4 | 37.4 | | 5.4 | |
| Effective Green, g (s) | 37.4 | 37.4 | 37.4 | | 5.4 | |
| Actuated g/C Ratio | 0.74 | 0.74 | 0.74 | | 0.11 | |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | | 3.0 | |
| Vehicle Extension (s) | 2.0 | 2.0 | 2.0 | | 2.0 | |
| Lane Grp Cap (vph) | 683 | 1358 | 1324 | | 149 | |
| v/s Ratio Prot | | c0.31 | 0.21 | | c0.02 | |
| v/s Ratio Perm | 0.03 | | | | | |
| v/c Ratio | 0.04 | 0.42 | 0.28 | | 0.16 | |
| Uniform Delay, d1 | 1.8 | 2.6 | 2.2 | | 20.6 | |
| Progression Factor | 1.00 | 1.00 | 1.00 | | 1.00 | |
| Incremental Delay, d2 | 0.0 | 0.1 | 0.0 | | 0.2 | |
| Delay (s) | 1.8 | 2.6 | 2.3 | | 20.8 | |
| Level of Service | A | A | A | | C | |
| Approach Delay (s) | | 2.6 | 2.3 | | 20.8 | |
| Approach LOS | | A | A | | C | |
| Intersection Summary | | | | | | |
| HCM 2000 Control Delay | | | 3.4 | | HCM 2000 Level of Service | A |
| HCM 2000 Volume to Capacity ratio | | | 0.41 | | | |
| Actuated Cycle Length (s) | | | 50.8 | | Sum of lost time (s) | 10.0 |
| Intersection Capacity Utilization | | | 54.3% | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | |
| c Critical Lane Group | | | | | | |

HCM 2010 Signalized Intersection Summary
 3: Mandela Pkwy & 7th Street

West Oakland BART TIA
 Existing Plus Project PM Peak Conditions



| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Traffic Volume (veh/h) | 95 | 445 | 34 | 146 | 263 | 106 | 37 | 196 | 117 | 132 | 234 | 51 |
| Future Volume (veh/h) | 95 | 445 | 34 | 146 | 263 | 106 | 37 | 196 | 117 | 132 | 234 | 51 |
| Number | 1 | 6 | 16 | 5 | 2 | 12 | 3 | 8 | 18 | 7 | 4 | 14 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 1.00 | | 0.93 | 1.00 | | 0.87 | 1.00 | | 0.95 | 1.00 | | 0.98 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1845 | 1845 | 1900 | 1845 | 1845 | 1845 | 1900 | 1845 | 1900 | 1845 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 95 | 445 | 34 | 146 | 263 | 106 | 37 | 196 | 117 | 132 | 234 | 51 |
| Adj No. of Lanes | 1 | 1 | 0 | 1 | 1 | 1 | 0 | 1 | 0 | 1 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 209 | 720 | 55 | 179 | 738 | 545 | 71 | 262 | 145 | 245 | 427 | 93 |
| Arrive On Green | 0.12 | 0.43 | 0.43 | 0.10 | 0.40 | 0.40 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 |
| Sat Flow, veh/h | 1757 | 1682 | 129 | 1757 | 1845 | 1363 | 91 | 899 | 497 | 1052 | 1463 | 319 |
| Grp Volume(v), veh/h | 95 | 0 | 479 | 146 | 263 | 106 | 350 | 0 | 0 | 132 | 0 | 285 |
| Grp Sat Flow(s),veh/h/ln | 1757 | 0 | 1810 | 1757 | 1845 | 1363 | 1487 | 0 | 0 | 1052 | 0 | 1782 |
| Q Serve(g_s), s | 4.5 | 0.0 | 18.5 | 7.3 | 9.0 | 4.6 | 8.1 | 0.0 | 0.0 | 2.8 | 0.0 | 12.1 |
| Cycle Q Clear(g_c), s | 4.5 | 0.0 | 18.5 | 7.3 | 9.0 | 4.6 | 20.2 | 0.0 | 0.0 | 23.0 | 0.0 | 12.1 |
| Prop In Lane | 1.00 | | 0.07 | 1.00 | | 1.00 | 0.11 | | 0.33 | 1.00 | | 0.18 |
| Lane Grp Cap(c), veh/h | 209 | 0 | 775 | 179 | 738 | 545 | 478 | 0 | 0 | 245 | 0 | 520 |
| V/C Ratio(X) | 0.45 | 0.00 | 0.62 | 0.81 | 0.36 | 0.19 | 0.73 | 0.00 | 0.00 | 0.54 | 0.00 | 0.55 |
| Avail Cap(c_a), veh/h | 209 | 0 | 775 | 332 | 738 | 545 | 527 | 0 | 0 | 277 | 0 | 574 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 0.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.97 | 0.00 | 0.00 | 1.00 | 0.00 | 1.00 |
| Uniform Delay (d), s/veh | 36.9 | 0.0 | 20.0 | 39.6 | 18.9 | 17.6 | 29.4 | 0.0 | 0.0 | 32.2 | 0.0 | 26.9 |
| Incr Delay (d2), s/veh | 0.6 | 0.0 | 3.7 | 3.4 | 1.3 | 0.8 | 3.7 | 0.0 | 0.0 | 0.7 | 0.0 | 0.3 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln | 2.2 | 0.0 | 10.0 | 3.7 | 4.8 | 1.8 | 8.6 | 0.0 | 0.0 | 3.2 | 0.0 | 6.0 |
| LnGrp Delay(d),s/veh | 37.5 | 0.0 | 23.7 | 43.0 | 20.2 | 18.4 | 33.1 | 0.0 | 0.0 | 32.9 | 0.0 | 27.2 |
| LnGrp LOS | D | | C | D | C | B | C | | | C | | C |
| Approach Vol, veh/h | | 574 | | | 515 | | | 350 | | | 417 | |
| Approach Delay, s/veh | | 26.0 | | | 26.3 | | | 33.1 | | | 29.0 | |
| Approach LOS | | C | | | C | | | C | | | C | |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | 1 | 2 | | 4 | 5 | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | 4.7 | 40.0 | | 35.3 | 12.2 | 42.5 | | 35.3 | | | | |
| Change Period (Y+Rc), s | 4.0 | * 4 | | 9.0 | 3.0 | 4.0 | | 9.0 | | | | |
| Max Green Setting (Gmax), s | 36 | * 36 | | 29.0 | 17.0 | 28.0 | | 29.0 | | | | |
| Max Q Clear Time (g_c+I), s | 10.5 | 11.0 | | 25.0 | 9.3 | 20.5 | | 22.2 | | | | |
| Green Ext Time (p_c), s | 0.1 | 1.2 | | 1.2 | 0.1 | 1.4 | | 1.8 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | 28.1 | | | | | | | | | |
| HCM 2010 LOS | | | C | | | | | | | | | |
| Notes | | | | | | | | | | | | |

| Intersection | | | | | | | | | | | | |
|--------------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Int Delay, s/veh | 5.4 | | | | | | | | | | | |
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↕ | | | ↕ | | | ↕ | | | ↕ | |
| Traffic Vol, veh/h | 7 | 29 | 4 | 22 | 54 | 134 | 2 | 7 | 10 | 135 | 5 | 11 |
| Future Vol, veh/h | 7 | 29 | 4 | 22 | 54 | 134 | 2 | 7 | 10 | 135 | 5 | 11 |
| Conflicting Peds, #/hr | 31 | 0 | 11 | 11 | 0 | 31 | 19 | 0 | 15 | 15 | 0 | 19 |
| Sign Control | Free | Free | Free | Free | Free | Free | Stop | Stop | Stop | Stop | Stop | Stop |
| RT Channelized | - | - | None | - | - | None | - | - | None | - | - | None |
| Storage Length | - | - | - | - | - | - | - | - | - | - | - | - |
| Veh in Median Storage, # | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Grade, % | - | 0 | - | - | 0 | - | - | 0 | - | - | 0 | - |
| Peak Hour Factor | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 | 100 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 7 | 29 | 4 | 22 | 54 | 134 | 2 | 7 | 10 | 135 | 5 | 11 |

| Major/Minor | Major1 | | | Major2 | | | Minor1 | | | Minor2 | | |
|----------------------|--------|---|---|--------|---|---|--------|-------|-------|--------|-------|-------|
| Conflicting Flow All | 219 | 0 | 0 | 44 | 0 | 0 | 248 | 319 | 57 | 265 | 254 | 171 |
| Stage 1 | - | - | - | - | - | - | 56 | 56 | - | 196 | 196 | - |
| Stage 2 | - | - | - | - | - | - | 192 | 263 | - | 69 | 58 | - |
| Critical Hdwy | 4.13 | - | - | 4.13 | - | - | 7.13 | 6.53 | 6.23 | 7.13 | 6.53 | 6.23 |
| Critical Hdwy Stg 1 | - | - | - | - | - | - | 6.13 | 5.53 | - | 6.13 | 5.53 | - |
| Critical Hdwy Stg 2 | - | - | - | - | - | - | 6.13 | 5.53 | - | 6.13 | 5.53 | - |
| Follow-up Hdwy | 2.227 | - | - | 2.227 | - | - | 3.527 | 4.027 | 3.327 | 3.527 | 4.027 | 3.327 |
| Pot Cap-1 Maneuver | 1344 | - | - | 1558 | - | - | 704 | 596 | 1006 | 686 | 648 | 870 |
| Stage 1 | - | - | - | - | - | - | 954 | 846 | - | 803 | 737 | - |
| Stage 2 | - | - | - | - | - | - | 807 | 689 | - | 939 | 845 | - |
| Platoon blocked, % | | - | - | | - | - | | | | | | |
| Mov Cap-1 Maneuver | 1323 | - | - | 1539 | - | - | 662 | 563 | 984 | 637 | 612 | 834 |
| Mov Cap-2 Maneuver | - | - | - | - | - | - | 662 | 563 | - | 637 | 612 | - |
| Stage 1 | - | - | - | - | - | - | 941 | 834 | - | 778 | 706 | - |
| Stage 2 | - | - | - | - | - | - | 766 | 660 | - | 906 | 833 | - |

| Approach | EB | | | WB | | | NB | | | SB | | |
|----------------------|-----|--|--|-----|--|--|----|--|--|------|--|--|
| HCM Control Delay, s | 1.4 | | | 0.8 | | | 10 | | | 12.3 | | |
| HCM LOS | | | | | | | B | | | B | | |

| Minor Lane/Major Mvmt | NBLn1 | EBL | EBT | EBR | WBL | WBT | WBR | SBLn1 |
|-----------------------|-------|-------|-----|-----|-------|-----|-----|-------|
| Capacity (veh/h) | 742 | 1323 | - | - | 1539 | - | - | 647 |
| HCM Lane V/C Ratio | 0.026 | 0.005 | - | - | 0.014 | - | - | 0.233 |
| HCM Control Delay (s) | 10 | 7.7 | 0 | - | 7.4 | 0 | - | 12.3 |
| HCM Lane LOS | B | A | A | - | A | A | - | B |
| HCM 95th %tile Q(veh) | 0.1 | 0 | - | - | 0 | - | - | 0.9 |

| Intersection | |
|---------------------------|-----|
| Intersection Delay, s/veh | 8.9 |
| Intersection LOS | A |

| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
|---------------------|------|------|------|------|------|------|
| Lane Configurations | ↻ | | | ↻ | ↻ | |
| Traffic Vol, veh/h | 234 | 6 | 21 | 230 | 6 | 14 |
| Future Vol, veh/h | 234 | 6 | 21 | 230 | 6 | 14 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Heavy Vehicles, % | 3 | 3 | 3 | 3 | 3 | 3 |
| Mvmt Flow | 234 | 6 | 21 | 230 | 6 | 14 |
| Number of Lanes | 1 | 0 | 0 | 1 | 1 | 0 |

| Approach | EB | WB | NB |
|----------------------------|-----|----|-----|
| Opposing Approach | WB | EB | |
| Opposing Lanes | 1 | 1 | 0 |
| Conflicting Approach Left | | NB | EB |
| Conflicting Lanes Left | 0 | 1 | 1 |
| Conflicting Approach Right | NB | | WB |
| Conflicting Lanes Right | 1 | 0 | 1 |
| HCM Control Delay | 8.8 | 9 | 7.8 |
| HCM LOS | A | A | A |

| Lane | NBLn1 | EBLn1 | WBLn1 |
|------------------------|-------|-------|-------|
| Vol Left, % | 30% | 0% | 8% |
| Vol Thru, % | 0% | 97% | 92% |
| Vol Right, % | 70% | 3% | 0% |
| Sign Control | Stop | Stop | Stop |
| Traffic Vol by Lane | 20 | 240 | 251 |
| LT Vol | 6 | 0 | 21 |
| Through Vol | 0 | 234 | 230 |
| RT Vol | 14 | 6 | 0 |
| Lane Flow Rate | 20 | 240 | 251 |
| Geometry Grp | 1 | 1 | 1 |
| Degree of Util (X) | 0.026 | 0.277 | 0.292 |
| Departure Headway (Hd) | 4.644 | 4.159 | 4.182 |
| Convergence, Y/N | Yes | Yes | Yes |
| Cap | 775 | 854 | 851 |
| Service Time | 2.644 | 2.234 | 2.253 |
| HCM Lane V/C Ratio | 0.026 | 0.281 | 0.295 |
| HCM Control Delay | 7.8 | 8.8 | 9 |
| HCM Lane LOS | A | A | A |
| HCM 95th-tile Q | 0.1 | 1.1 | 1.2 |

HCM 2010 Signalized Intersection Summary
6: Mandela Pkwy & 5th Street

West Oakland BART TIA
Existing Plus Project PM Peak Conditions



| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Lane Configurations | | ↕ | | | ↕ | | | ↕ | | | ↕ | |
| Traffic Volume (veh/h) | 67 | 206 | 39 | 38 | 196 | 102 | 34 | 102 | 46 | 45 | 108 | 49 |
| Future Volume (veh/h) | 67 | 206 | 39 | 38 | 196 | 102 | 34 | 102 | 46 | 45 | 108 | 49 |
| Number | 7 | 4 | 14 | 3 | 8 | 18 | 5 | 2 | 12 | 1 | 6 | 16 |
| Initial Q (Qb), veh | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Ped-Bike Adj(A_pbT) | 0.94 | | 0.87 | 0.93 | | 0.89 | 0.92 | | 0.86 | 0.92 | | 0.87 |
| Parking Bus, Adj | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Adj Sat Flow, veh/h/ln | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 | 1900 | 1845 | 1900 |
| Adj Flow Rate, veh/h | 67 | 206 | 39 | 38 | 196 | 102 | 34 | 102 | 46 | 45 | 108 | 49 |
| Adj No. of Lanes | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 | 0 | 1 | 0 |
| Peak Hour Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Percent Heavy Veh, % | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 | 3 |
| Cap, veh/h | 191 | 511 | 86 | 132 | 445 | 211 | 161 | 396 | 155 | 183 | 377 | 147 |
| Arrive On Green | 0.43 | 0.43 | 0.43 | 0.43 | 0.43 | 0.43 | 0.39 | 0.39 | 0.39 | 0.39 | 0.39 | 0.39 |
| Sat Flow, veh/h | 210 | 1188 | 200 | 91 | 1034 | 491 | 162 | 1028 | 403 | 212 | 980 | 382 |
| Grp Volume(v), veh/h | 312 | 0 | 0 | 336 | 0 | 0 | 182 | 0 | 0 | 202 | 0 | 0 |
| Grp Sat Flow(s),veh/h/ln1597 | 0 | 0 | 0 | 1616 | 0 | 0 | 1593 | 0 | 0 | 1573 | 0 | 0 |
| Q Serve(g_s), s | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Cycle Q Clear(g_c), s | 5.3 | 0.0 | 0.0 | 6.2 | 0.0 | 0.0 | 3.2 | 0.0 | 0.0 | 3.6 | 0.0 | 0.0 |
| Prop In Lane | 0.21 | | 0.12 | 0.11 | | 0.30 | 0.19 | | 0.25 | 0.22 | | 0.24 |
| Lane Grp Cap(c), veh/h | 788 | 0 | 0 | 788 | 0 | 0 | 712 | 0 | 0 | 707 | 0 | 0 |
| V/C Ratio(X) | 0.40 | 0.00 | 0.00 | 0.43 | 0.00 | 0.00 | 0.26 | 0.00 | 0.00 | 0.29 | 0.00 | 0.00 |
| Avail Cap(c_a), veh/h | 1009 | 0 | 0 | 1016 | 0 | 0 | 1179 | 0 | 0 | 1168 | 0 | 0 |
| HCM Platoon Ratio | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Upstream Filter(I) | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 |
| Uniform Delay (d), s/veh | 8.5 | 0.0 | 0.0 | 8.8 | 0.0 | 0.0 | 9.2 | 0.0 | 0.0 | 9.3 | 0.0 | 0.0 |
| Incr Delay (d2), s/veh | 0.1 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 | 0.1 | 0.0 | 0.0 |
| Initial Q Delay(d3),s/veh | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| %ile BackOfQ(50%),veh/ln2.5 | 0.0 | 0.0 | 0.0 | 2.8 | 0.0 | 0.0 | 1.5 | 0.0 | 0.0 | 1.7 | 0.0 | 0.0 |
| LnGrp Delay(d),s/veh | 8.7 | 0.0 | 0.0 | 8.9 | 0.0 | 0.0 | 9.3 | 0.0 | 0.0 | 9.4 | 0.0 | 0.0 |
| LnGrp LOS | A | | | A | | | A | | | A | | |
| Approach Vol, veh/h | | 312 | | | 336 | | | 182 | | | 202 | |
| Approach Delay, s/veh | | 8.7 | | | 8.9 | | | 9.3 | | | 9.4 | |
| Approach LOS | | A | | | A | | | A | | | A | |
| Timer | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | | | | |
| Assigned Phs | | 2 | | 4 | | 6 | | 8 | | | | |
| Phs Duration (G+Y+Rc), s | | 20.7 | | 22.6 | | 20.7 | | 22.6 | | | | |
| Change Period (Y+Rc), s | | 4.0 | | 4.0 | | 4.0 | | 4.0 | | | | |
| Max Green Setting (Gmax), s | | 30.0 | | 25.0 | | 30.0 | | 25.0 | | | | |
| Max Q Clear Time (g_c+I1), s | | 5.2 | | 7.3 | | 5.6 | | 8.2 | | | | |
| Green Ext Time (p_c), s | | 1.6 | | 3.0 | | 1.6 | | 2.9 | | | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM 2010 Ctrl Delay | | | | 9.0 | | | | | | | | |
| HCM 2010 LOS | | | | A | | | | | | | | |

**APPENDIX C
PREDICTED CRASH
FREQUENCY
CALCULATION**



| Worksheet 1A -- General Information and Input Data for Urban and Suburban Roadway Segments | | | |
|--|--|----------------------|--|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | 7th Street |
| Agency or Company | Fehr & Peers | Roadway Section | Between Chester Street and Center Street |
| Date Performed | 01/02/19 | Jurisdiction | Oakland, CA |
| | | Analysis Year | 2019 |
| Input Data | | Base Conditions | Site Conditions |
| Roadway type (2U, 3T, 4U, 4D, ST) | | -- | 3T |
| Length of segment, L (mi) | | -- | 0.06 |
| AADT (veh/day) | AADT _{MAX} = 32,900 (veh/day) | -- | 7,415 |
| Type of on-street parking (none/parallel/angle) | | None | Parallel (Comm/Ind) |
| Proportion of curb length with on-street parking | | -- | 0.34 |
| Median width (ft) - for divided only | | 15 | Not Present |
| Lighting (present / not present) | | Not Present | Present |
| Auto speed enforcement (present / not present) | | Not Present | Not Present |
| Major commercial driveways (number) | | -- | 0 |
| Minor commercial driveways (number) | | -- | 3 |
| Major industrial / institutional driveways (number) | | -- | 0 |
| Minor industrial / institutional driveways (number) | | -- | 0 |
| Major residential driveways (number) | | -- | 0 |
| Minor residential driveways (number) | | -- | 0 |
| Other driveways (number) | | -- | 0 |
| Speed Category | | -- | Posted Speed 30 mph or Lower |
| Roadside fixed object density (fixed objects / mi) | | 0 | 132 |
| Offset to roadside fixed objects (ft) [If greater than 30 or Not Present, input 30] | | 30 | 14 |
| Calibration Factor, Cr | | 1.00 | 1.00 |

| Worksheet 1B -- Crash Modification Factors for Urban and Suburban Roadway Segments | | | | | |
|--|--------------------------------|----------------------|---------------------|-------------------------------------|---------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| CMF for On-Street Parking | CMF for Roadside Fixed Objects | CMF for Median Width | CMF for Lighting | CMF for Automated Speed Enforcement | Combined CMF |
| <i>CMF 1r</i> | <i>CMF 2r</i> | <i>CMF 3r</i> | <i>CMF 4r</i> | <i>CMF 5r</i> | <i>CMF comb</i> |
| from Equation 12-32 | from Equation 12-33 | from Table 12-22 | from Equation 12-34 | from Section 12.7.1 | (1)*(2)*(3)*(4)*(5) |
| 1.36 | 1.28 | 1.00 | 0.93 | 1.00 | 1.63 |

| Worksheet 1C -- Multiple-Vehicle Nondriveway Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|------------------|------|-----------------------------|---------------------------|--|----------------------------|---------------|------------------------|-----------------------------|
| (1) | (2) | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
| Crash Severity Level | SPF Coefficients | | Overdispersion Parameter, k | Initial N _{brmv} | Proportion of Total Crashes | Adjusted N _{brmv} | Combined CMFs | Calibration Factor, Cr | Predicted N _{brmv} |
| | a | b | | | | | | | |
| Total | -12.40 | 1.41 | 0.66 | 0.073 | 1.000 | 0.073 | 1.63 | 1.00 | 0.119 |
| Fatal and Injury (FI) | -16.45 | 1.69 | 0.59 | 0.015 | $\frac{(4)_{FI}}{(4)_{FI} + (4)_{PDO}}$ 0.216 | 0.016 | 1.63 | 1.00 | 0.026 |
| Property Damage Only (PDO) | -11.95 | 1.33 | 0.59 | 0.056 | $\frac{(5)_{TOTAL} - (5)_{FI}}{0.784}$ | 0.057 | 1.63 | 1.00 | 0.093 |

| Worksheet 1D -- Multiple-Vehicle Nondriveway Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brmv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brmv (PDO)} (crashes/year) | (6) Predicted N _{brmv (TOTAL)} (crashes/year) |
| | from Table 12-4 | (9) _{FI} from Worksheet 1C | from Table 12-4 | (9) _{PDO} from Worksheet 1C | (9) _{TOTAL} from Worksheet 1C |
| Total | 1.000 | 0.026 | 1.000 | 0.093 | 0.119 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Rear-end collision | 0.845 | 0.022 | 0.842 | 0.078 | 0.100 |
| Head-on collision | 0.034 | 0.001 | 0.020 | 0.002 | 0.003 |
| Angle collision | 0.069 | 0.002 | 0.020 | 0.002 | 0.004 |
| Sideswipe, same direction | 0.001 | 0.000 | 0.078 | 0.007 | 0.007 |
| Sideswipe, opposite direction | 0.017 | 0.000 | 0.020 | 0.002 | 0.002 |
| Other multiple-vehicle collision | 0.034 | 0.001 | 0.020 | 0.002 | 0.003 |

| Worksheet 1E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|-------------------------|------|------------------------------------|----------------------------------|--|-----------------------------------|---|-------------------------------|------------------------------------|
| (1) Crash Severity Level | (2) SPF Coefficients | | (3) Overdispersion Parameter, k | (4) Initial N _{brsv} | (5) Proportion of Total Crashes | (6) Adjusted N _{brsv} | (7) Combined CMFs (6) from Worksheet 1B | (8) Calibration Factor, Cr | (9) Predicted N _{brsv} |
| | from Table 12-5 | | from Table 12-5 | from Equation 12-13 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | | | | | | | |
| Total | -5.74 | 0.54 | 1.37 | 0.024 | 1.000 | 0.024 | 1.63 | 1.00 | 0.040 |
| Fatal and Injury (FI) | -6.37 | 0.47 | 1.06 | 0.007 | (4) _{FI} /((4) _{FI} +(4) _{PDO}) 0.293 | 0.007 | 1.63 | 1.00 | 0.012 |
| Property Damage Only (PDO) | -6.29 | 0.56 | 1.93 | 0.017 | (5) _{TOTAL} -(5) _{FI} 0.707 | 0.017 | 1.63 | 1.00 | 0.028 |

| Worksheet 1F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brsv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brsv (PDO)} (crashes/year) | (6) Predicted N _{brsv (TOTAL)} (crashes/year) |
| | from Table 12-6 | (9) _{FI} from Worksheet 1E | from Table 12-6 | (9) _{PDO} from Worksheet 1E | (9) _{TOTAL} from Worksheet 1E |
| Total | 1.000 | 0.012 | 1.000 | 0.028 | 0.040 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with animal | 0.001 | 0.000 | 0.001 | 0.000 | 0.000 |
| Collision with fixed object | 0.688 | 0.008 | 0.963 | 0.027 | 0.035 |
| Collision with other object | 0.001 | 0.000 | 0.001 | 0.000 | 0.000 |
| Other single-vehicle collision | 0.310 | 0.004 | 0.035 | 0.001 | 0.005 |

| Worksheet 1G -- Multiple-Vehicle Driveway-Related Collisions by Driveway Type for Urban and Suburban Roadway Segments | | | | | |
|---|----------------------------|--------------------------------------|---|---|-------------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Driveway Type | Number of driveways, n_j | Crashes per driveway per year, N_j | Coefficient for traffic adjustment, t | Initial N_{brdwy} | Overdispersion parameter, k |
| | | from Table 12-7 | from Table 12-7 | Equation 12-16 $n_j * N_j * (AADT/15,000)^t$ | from Table 12-7 |
| Major commercial | 0 | 0.102 | 1.000 | 0.000 | -- |
| Minor commercial | 3 | 0.032 | 1.000 | 0.047 | |
| Major industrial/institutional | 0 | 0.110 | 1.000 | 0.000 | |
| Minor industrial/institutional | 0 | 0.015 | 1.000 | 0.000 | |
| Major residential | 0 | 0.053 | 1.000 | 0.000 | |
| Minor residential | 0 | 0.010 | 1.000 | 0.000 | |
| Other | 0 | 0.016 | 1.000 | 0.000 | |
| Total | -- | -- | -- | 0.047 | 1.10 |

| Worksheet 1H -- Multiple-Vehicle Driveway-Related Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | |
|--|--|---|----------------------------|-----------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Initial N_{brdwy} | Proportion of total crashes (f_{dwy}) | Adjusted N_{brdwy} | Combined CMFs | Calibration factor, C_r | Predicted N_{brdwy} |
| | (5) _{TOTAL} from Worksheet 1G | from Table 12-7 | (2) _{TOTAL} * (3) | (6) from Worksheet 1B | | (4)*(5)*(6) |
| Total | 0.047 | 1.000 | 0.047 | 1.63 | 1.00 | 0.078 |
| Fatal and injury (FI) | -- | 0.243 | 0.012 | 1.63 | 1.00 | 0.019 |
| Property damage only (PDO) | -- | 0.757 | 0.036 | 1.63 | 1.00 | 0.059 |

| Worksheet 1I -- Vehicle-Pedestrian Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|---|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{pedr} | Calibration factor, C_r | Predicted N_{pedr} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-8 | | (5)*(6)*(7) |
| Total | 0.119 | 0.040 | 0.078 | 0.236 | 0.041 | 1.00 | 0.010 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.010 |

| Worksheet 1J -- Vehicle-Bicycle Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|--|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{biker} | Calibration factor, C_r | Predicted N_{biker} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-9 | | (5)*(6)*(7) |
| Total | 0.119 | 0.040 | 0.078 | 0.236 | 0.027 | 1.00 | 0.006 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.006 |

| Worksheet 1K -- Crash Severity Distribution for Urban and Suburban Roadway Segments | | | |
|--|---|--|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J | (5) from Worksheet 1D and 1F; and (7) from Worksheet 1H | (6) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 1D) | 0.022 | 0.078 | 0.100 |
| Head-on collisions (from Worksheet 1D) | 0.001 | 0.002 | 0.003 |
| Angle collisions (from Worksheet 1D) | 0.002 | 0.002 | 0.004 |
| Sideswipe, same direction (from Worksheet 1D) | 0.000 | 0.007 | 0.007 |
| Sideswipe, opposite direction (from Worksheet 1D) | 0.000 | 0.002 | 0.002 |
| Driveway-related collisions (from Worksheet 1H) | 0.019 | 0.059 | 0.078 |
| Other multiple-vehicle collision (from Worksheet 1D) | 0.001 | 0.002 | 0.003 |
| Subtotal | 0.044 | 0.152 | 0.196 |
| SINGLE-VEHICLE | | | |
| Collision with animal (from Worksheet 1F) | 0.000 | 0.000 | 0.000 |
| Collision with fixed object (from Worksheet 1F) | 0.008 | 0.027 | 0.035 |
| Collision with other object (from Worksheet 1F) | 0.000 | 0.000 | 0.000 |
| Other single-vehicle collision (from Worksheet 1F) | 0.004 | 0.001 | 0.005 |
| Collision with pedestrian (from Worksheet 1I) | 0.010 | 0.000 | 0.010 |
| Collision with bicycle (from Worksheet 1J) | 0.006 | 0.000 | 0.006 |
| Subtotal | 0.028 | 0.028 | 0.056 |
| Total | 0.072 | 0.180 | 0.252 |

| Worksheet 1L -- Summary Results for Urban and Suburban Roadway Segments | | | |
|--|--|--------------------------------|------------------------------|
| (1) | (2) | (3) | (4) |
| Crash Severity Level | Predicted average crash frequency, $N_{\text{predicted rs}}$ (crashes/year) | Roadway segment length, L (mi) | Crash rate (crashes/mi/year) |
| | (Total) from Worksheet 1K | | (2) / (3) |
| Total | 0.252 | 0.06 | 4.1 |
| Fatal and injury (FI) | 0.1 | 0.06 | 1.2 |
| Property damage only (PDO) | 0.2 | 0.06 | 2.9 |

| Worksheet 1A -- General Information and Input Data for Urban and Suburban Roadway Segments | | | |
|--|--|----------------------|---|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | 7th Street |
| Agency or Company | Fehr & Peers | Roadway Section | Between Center Street and Mandela Parkway |
| Date Performed | 01/02/19 | Jurisdiction | Oakland, CA |
| | | Analysis Year | 2019 |
| Input Data | | Base Conditions | Site Conditions |
| Roadway type (2U, 3T, 4U, 4D, ST) | | -- | 3T |
| Length of segment, L (mi) | | -- | 0.08 |
| AADT (veh/day) | AADT _{MAX} = 32,900 (veh/day) | -- | 7,170 |
| Type of on-street parking (none/parallel/angle) | | None | Parallel (Comm/Ind) |
| Proportion of curb length with on-street parking | | -- | 0.35 |
| Median width (ft) - for divided only | | 15 | Not Present |
| Lighting (present / not present) | | Not Present | Present |
| Auto speed enforcement (present / not present) | | Not Present | Not Present |
| Major commercial driveways (number) | | -- | 0 |
| Minor commercial driveways (number) | | -- | 0 |
| Major industrial / institutional driveways (number) | | -- | 0 |
| Minor industrial / institutional driveways (number) | | -- | 0 |
| Major residential driveways (number) | | -- | 0 |
| Minor residential driveways (number) | | -- | 0 |
| Other driveways (number) | | -- | 0 |
| Speed Category | | -- | Posted Speed 30 mph or Lower |
| Roadside fixed object density (fixed objects / mi) | | 0 | 151 |
| Offset to roadside fixed objects (ft) [If greater than 30 or Not Present, input 30] | | 30 | 19 |
| Calibration Factor, Cr | | 1.00 | 1.00 |

| Worksheet 1B -- Crash Modification Factors for Urban and Suburban Roadway Segments | | | | | |
|--|--------------------------------|----------------------|---------------------|-------------------------------------|---------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| CMF for On-Street Parking | CMF for Roadside Fixed Objects | CMF for Median Width | CMF for Lighting | CMF for Automated Speed Enforcement | Combined CMF |
| <i>CMF 1r</i> | <i>CMF 2r</i> | <i>CMF 3r</i> | <i>CMF 4r</i> | <i>CMF 5r</i> | <i>CMF comb</i> |
| from Equation 12-32 | from Equation 12-33 | from Table 12-22 | from Equation 12-34 | from Section 12.7.1 | (1)*(2)*(3)*(4)*(5) |
| 1.37 | 1.27 | 1.00 | 0.93 | 1.00 | 1.62 |

| Worksheet 1C -- Multiple-Vehicle Nondriveway Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|------------------|-----------------|-----------------------------|---------------------------|--|----------------------------|---------------|------------------------|-----------------------------|
| (1) | (2) | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
| Crash Severity Level | SPF Coefficients | | Overdispersion Parameter, k | Initial N _{brmv} | Proportion of Total Crashes | Adjusted N _{brmv} | Combined CMFs | Calibration Factor, Cr | Predicted N _{brmv} |
| | from Table 12-3 | from Table 12-3 | | | | | | | |
| | a | b | | | | | | | |
| Total | -12.40 | 1.41 | 0.66 | 0.085 | 1.000 | 0.085 | 1.62 | 1.00 | 0.138 |
| Fatal and Injury (FI) | -16.45 | 1.69 | 0.59 | 0.018 | $\frac{(4)_{FI}}{(4)_{FI} + (4)_{PDO}}$ 0.213 | 0.018 | 1.62 | 1.00 | 0.030 |
| Property Damage Only (PDO) | -11.95 | 1.33 | 0.59 | 0.066 | $\frac{(5)_{TOTAL} - (5)_{FI}}{0.787}$ | 0.067 | 1.62 | 1.00 | 0.109 |

| Worksheet 1D -- Multiple-Vehicle Nondrivable Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brmv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brmv (PDO)} (crashes/year) | (6) Predicted N _{brmv (TOTAL)} (crashes/year) |
| | from Table 12-4 | (9) _{FI} from Worksheet 1C | from Table 12-4 | (9) _{PDO} from Worksheet 1C | (9) _{TOTAL} from Worksheet 1C |
| Total | 1.000 | 0.030 | 1.000 | 0.109 | 0.138 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Rear-end collision | 0.845 | 0.025 | 0.842 | 0.092 | 0.117 |
| Head-on collision | 0.034 | 0.001 | 0.020 | 0.002 | 0.003 |
| Angle collision | 0.069 | 0.002 | 0.020 | 0.002 | 0.004 |
| Sideswipe, same direction | 0.001 | 0.000 | 0.078 | 0.008 | 0.009 |
| Sideswipe, opposite direction | 0.017 | 0.001 | 0.020 | 0.002 | 0.003 |
| Other multiple-vehicle collision | 0.034 | 0.001 | 0.020 | 0.002 | 0.003 |

| Worksheet 1E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|-------------------------|------|------------------------------------|----------------------------------|--|-----------------------------------|---|-------------------------------|------------------------------------|
| (1) Crash Severity Level | (2) SPF Coefficients | | (3) Overdispersion Parameter, k | (4) Initial N _{brsv} | (5) Proportion of Total Crashes | (6) Adjusted N _{brsv} | (7) Combined CMFs (6) from Worksheet 1B | (8) Calibration Factor, Cr | (9) Predicted N _{brsv} |
| | from Table 12-5 | | from Table 12-5 | from Equation 12-13 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | | | | | | | |
| Total | -5.74 | 0.54 | 1.37 | 0.029 | 1.000 | 0.029 | 1.62 | 1.00 | 0.048 |
| Fatal and Injury (FI) | -6.37 | 0.47 | 1.06 | 0.008 | (4) _{FI} /((4) _{FI} +(4) _{PDO}) 0.293 | 0.009 | 1.62 | 1.00 | 0.014 |
| Property Damage Only (PDO) | -6.29 | 0.56 | 1.93 | 0.020 | (5) _{TOTAL} -(5) _{FI} 0.707 | 0.021 | 1.62 | 1.00 | 0.034 |

| Worksheet 1F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brsv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brsv (PDO)} (crashes/year) | (6) Predicted N _{brsv (TOTAL)} (crashes/year) |
| | from Table 12-6 | (9) _{FI} from Worksheet 1E | from Table 12-6 | (9) _{PDO} from Worksheet 1E | (9) _{TOTAL} from Worksheet 1E |
| Total | 1.000 | 0.014 | 1.000 | 0.034 | 0.048 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with animal | 0.001 | 0.000 | 0.001 | 0.000 | 0.000 |
| Collision with fixed object | 0.688 | 0.010 | 0.963 | 0.033 | 0.042 |
| Collision with other object | 0.001 | 0.000 | 0.001 | 0.000 | 0.000 |
| Other single-vehicle collision | 0.310 | 0.004 | 0.035 | 0.001 | 0.006 |

| Worksheet 1G -- Multiple-Vehicle Driveway-Related Collisions by Driveway Type for Urban and Suburban Roadway Segments | | | | | |
|---|----------------------------|--------------------------------------|---|---|-------------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Driveway Type | Number of driveways, n_j | Crashes per driveway per year, N_j | Coefficient for traffic adjustment, t | Initial N_{brdwy} | Overdispersion parameter, k |
| | | from Table 12-7 | from Table 12-7 | Equation 12-16 $n_j * N_j * (AADT/15,000)^t$ | from Table 12-7 |
| Major commercial | 0 | 0.102 | 1.000 | 0.000 | -- |
| Minor commercial | 0 | 0.032 | 1.000 | 0.000 | |
| Major industrial/institutional | 0 | 0.110 | 1.000 | 0.000 | |
| Minor industrial/institutional | 0 | 0.015 | 1.000 | 0.000 | |
| Major residential | 0 | 0.053 | 1.000 | 0.000 | |
| Minor residential | 0 | 0.010 | 1.000 | 0.000 | |
| Other | 0 | 0.016 | 1.000 | 0.000 | |
| Total | -- | -- | -- | 0.000 | 1.10 |

| Worksheet 1H -- Multiple-Vehicle Driveway-Related Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | |
|--|--|---|----------------------------|-----------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Initial N_{brdwy} | Proportion of total crashes (f_{dwy}) | Adjusted N_{brdwy} | Combined CMFs | Calibration factor, C_r | Predicted N_{brdwy} |
| | (5) _{TOTAL} from Worksheet 1G | from Table 12-7 | (2) _{TOTAL} * (3) | (6) from Worksheet 1B | | (4)*(5)*(6) |
| Total | 0.000 | 1.000 | 0.000 | 1.62 | 1.00 | 0.000 |
| Fatal and injury (FI) | -- | 0.243 | 0.000 | 1.62 | 1.00 | 0.000 |
| Property damage only (PDO) | -- | 0.757 | 0.000 | 1.62 | 1.00 | 0.000 |

| Worksheet 1I -- Vehicle-Pedestrian Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|---|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{pedr} | Calibration factor, C_r | Predicted N_{pedr} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-8 | | (5)*(6)*(7) |
| Total | 0.138 | 0.048 | 0.000 | 0.186 | 0.041 | 1.00 | 0.008 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.008 |

| Worksheet 1J -- Vehicle-Bicycle Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|--|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{biker} | Calibration factor, C_r | Predicted N_{biker} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-9 | | (5)*(6)*(7) |
| Total | 0.138 | 0.048 | 0.000 | 0.186 | 0.027 | 1.00 | 0.005 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.005 |

| Worksheet 1K -- Crash Severity Distribution for Urban and Suburban Roadway Segments | | | |
|--|---|--|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J | (5) from Worksheet 1D and 1F; and (7) from Worksheet 1H | (6) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 1D) | 0.025 | 0.092 | 0.117 |
| Head-on collisions (from Worksheet 1D) | 0.001 | 0.002 | 0.003 |
| Angle collisions (from Worksheet 1D) | 0.002 | 0.002 | 0.004 |
| Sideswipe, same direction (from Worksheet 1D) | 0.000 | 0.008 | 0.009 |
| Sideswipe, opposite direction (from Worksheet 1D) | 0.001 | 0.002 | 0.003 |
| Driveway-related collisions (from Worksheet 1H) | 0.000 | 0.000 | 0.000 |
| Other multiple-vehicle collision (from Worksheet 1D) | 0.001 | 0.002 | 0.003 |
| Subtotal | 0.030 | 0.109 | 0.138 |
| SINGLE-VEHICLE | | | |
| Collision with animal (from Worksheet 1F) | 0.000 | 0.000 | 0.000 |
| Collision with fixed object (from Worksheet 1F) | 0.010 | 0.033 | 0.042 |
| Collision with other object (from Worksheet 1F) | 0.000 | 0.000 | 0.000 |
| Other single-vehicle collision (from Worksheet 1F) | 0.004 | 0.001 | 0.006 |
| Collision with pedestrian (from Worksheet 1I) | 0.008 | 0.000 | 0.008 |
| Collision with bicycle (from Worksheet 1J) | 0.005 | 0.000 | 0.005 |
| Subtotal | 0.027 | 0.034 | 0.060 |
| Total | 0.056 | 0.143 | 0.199 |

| Worksheet 1L -- Summary Results for Urban and Suburban Roadway Segments | | | |
|--|---|---------------------------------------|-------------------------------------|
| (1) | (2) | (3) | (4) |
| Crash Severity Level | Predicted average crash frequency, N_{predicted rs} (crashes/year) | Roadway segment length, L (mi) | Crash rate (crashes/mi/year) |
| | (Total) from Worksheet 1K | | (2) / (3) |
| Total | 0.199 | 0.08 | 2.6 |
| Fatal and injury (FI) | 0.1 | 0.08 | 0.7 |
| Property damage only (PDO) | 0.1 | 0.08 | 1.9 |

| Worksheet 1A -- General Information and Input Data for Urban and Suburban Roadway Segments | | | |
|--|--|----------------------|--|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | 5th Street |
| Agency or Company | Fehr & Peers | Roadway Section | Between Chester Street and Center Street |
| Date Performed | 01/02/19 | Jurisdiction | Oakland, CA |
| | | Analysis Year | 2019 |
| Input Data | | Base Conditions | Site Conditions |
| Roadway type (2U, 3T, 4U, 4D, ST) | | -- | 2U |
| Length of segment, L (mi) | | -- | 0.06 |
| AADT (veh/day) | AADT _{MAX} = 32,600 (veh/day) | -- | 2,565 |
| Type of on-street parking (none/parallel/angle) | | None | Parallel (Residential) |
| Proportion of curb length with on-street parking | | -- | 0.95 |
| Median width (ft) - for divided only | | 15 | Not Present |
| Lighting (present / not present) | | Not Present | Present |
| Auto speed enforcement (present / not present) | | Not Present | Not Present |
| Major commercial driveways (number) | | -- | 0 |
| Minor commercial driveways (number) | | -- | 0 |
| Major industrial / institutional driveways (number) | | -- | 1 |
| Minor industrial / institutional driveways (number) | | -- | 0 |
| Major residential driveways (number) | | -- | 0 |
| Minor residential driveways (number) | | -- | 4 |
| Other driveways (number) | | -- | 0 |
| Speed Category | | -- | Posted Speed 30 mph or Lower |
| Roadside fixed object density (fixed objects / mi) | | 0 | 27 |
| Offset to roadside fixed objects (ft) [If greater than 30 or Not Present, input 30] | | 30 | 15 |
| Calibration Factor, Cr | | 1.00 | 1.00 |

| Worksheet 1B -- Crash Modification Factors for Urban and Suburban Roadway Segments | | | | | |
|--|--------------------------------|----------------------|---------------------|-------------------------------------|---------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| CMF for On-Street Parking | CMF for Roadside Fixed Objects | CMF for Median Width | CMF for Lighting | CMF for Automated Speed Enforcement | Combined CMF |
| <i>CMF 1r</i> | <i>CMF 2r</i> | <i>CMF 3r</i> | <i>CMF 4r</i> | <i>CMF 5r</i> | <i>CMF comb</i> |
| from Equation 12-32 | from Equation 12-33 | from Table 12-22 | from Equation 12-34 | from Section 12.7.1 | (1)*(2)*(3)*(4)*(5) |
| 1.44 | 1.05 | 1.00 | 0.93 | 1.00 | 1.41 |

| Worksheet 1C -- Multiple-Vehicle Nondriveway Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|------------------|------|-----------------------------|---------------------------|--|----------------------------|---------------|------------------------|-----------------------------|
| (1) | (2) | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
| Crash Severity Level | SPF Coefficients | | Overdispersion Parameter, k | Initial N _{brmv} | Proportion of Total Crashes | Adjusted N _{brmv} | Combined CMFs | Calibration Factor, Cr | Predicted N _{brmv} |
| | a | b | | | | | | | |
| Total | -15.22 | 1.68 | 0.84 | 0.008 | 1.000 | 0.008 | 1.41 | 1.00 | 0.012 |
| Fatal and Injury (FI) | -16.22 | 1.66 | 0.65 | 0.003 | $\frac{(4)_{FI}}{(4)_{FI} + (4)_{PDO}}$ 0.302 | 0.002 | 1.41 | 1.00 | 0.003 |
| Property Damage Only (PDO) | -15.62 | 1.69 | 0.87 | 0.006 | $\frac{(5)_{TOTAL} - (5)_{FI}}{0.698}$ | 0.006 | 1.41 | 1.00 | 0.008 |

| Worksheet 1D -- Multiple-Vehicle Nondrivable Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brmv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brmv (PDO)} (crashes/year) | (6) Predicted N _{brmv (TOTAL)} (crashes/year) |
| | from Table 12-4 | (9) _{FI} from Worksheet 1C | from Table 12-4 | (9) _{PDO} from Worksheet 1C | (9) _{TOTAL} from Worksheet 1C |
| Total | 1.000 | 0.003 | 1.000 | 0.008 | 0.012 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Rear-end collision | 0.730 | 0.003 | 0.778 | 0.006 | 0.009 |
| Head-on collision | 0.068 | 0.000 | 0.004 | 0.000 | 0.000 |
| Angle collision | 0.085 | 0.000 | 0.079 | 0.001 | 0.001 |
| Sideswipe, same direction | 0.015 | 0.000 | 0.031 | 0.000 | 0.000 |
| Sideswipe, opposite direction | 0.073 | 0.000 | 0.055 | 0.000 | 0.001 |
| Other multiple-vehicle collision | 0.029 | 0.000 | 0.053 | 0.000 | 0.001 |

| Worksheet 1E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|-------------------------|------|------------------------------------|----------------------------------|--|-----------------------------------|---|-------------------------------|------------------------------------|
| (1) Crash Severity Level | (2) SPF Coefficients | | (3) Overdispersion Parameter, k | (4) Initial N _{brsv} | (5) Proportion of Total Crashes | (6) Adjusted N _{brsv} | (7) Combined CMFs (6) from Worksheet 1B | (8) Calibration Factor, Cr | (9) Predicted N _{brsv} |
| | from Table 12-5 | | from Table 12-5 | from Equation 12-13 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | | | | | | | |
| Total | -5.47 | 0.56 | 0.81 | 0.021 | 1.000 | 0.021 | 1.41 | 1.00 | 0.030 |
| Fatal and Injury (FI) | -3.96 | 0.23 | 0.50 | 0.007 | (4) _{FI} /((4) _{FI} +(4) _{PDO}) 0.339 | 0.007 | 1.41 | 1.00 | 0.010 |
| Property Damage Only (PDO) | -6.51 | 0.64 | 0.87 | 0.014 | (5) _{TOTAL} -(5) _{FI} 0.661 | 0.014 | 1.41 | 1.00 | 0.020 |

| Worksheet 1F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brsv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brsv (PDO)} (crashes/year) | (6) Predicted N _{brsv (TOTAL)} (crashes/year) |
| | from Table 12-6 | (9) _{FI} from Worksheet 1E | from Table 12-6 | (9) _{PDO} from Worksheet 1E | (9) _{TOTAL} from Worksheet 1E |
| Total | 1.000 | 0.010 | 1.000 | 0.020 | 0.030 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with animal | 0.026 | 0.000 | 0.066 | 0.001 | 0.002 |
| Collision with fixed object | 0.723 | 0.007 | 0.759 | 0.015 | 0.022 |
| Collision with other object | 0.010 | 0.000 | 0.013 | 0.000 | 0.000 |
| Other single-vehicle collision | 0.241 | 0.002 | 0.162 | 0.003 | 0.006 |

| Worksheet 1G -- Multiple-Vehicle Driveway-Related Collisions by Driveway Type for Urban and Suburban Roadway Segments | | | | | |
|---|----------------------------|--------------------------------------|---|---|-------------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Driveway Type | Number of driveways, n_j | Crashes per driveway per year, N_j | Coefficient for traffic adjustment, t | Initial N_{brdwy} | Overdispersion parameter, k |
| | | from Table 12-7 | from Table 12-7 | Equation 12-16 $n_j * N_j * (AADT/15,000)^t$ | from Table 12-7 |
| Major commercial | 0 | 0.158 | 1.000 | 0.000 | -- |
| Minor commercial | 0 | 0.050 | 1.000 | 0.000 | |
| Major industrial/institutional | 1 | 0.172 | 1.000 | 0.029 | |
| Minor industrial/institutional | 0 | 0.023 | 1.000 | 0.000 | |
| Major residential | 0 | 0.083 | 1.000 | 0.000 | |
| Minor residential | 4 | 0.016 | 1.000 | 0.011 | |
| Other | 0 | 0.025 | 1.000 | 0.000 | |
| Total | -- | -- | -- | 0.040 | 0.81 |

| Worksheet 1H -- Multiple-Vehicle Driveway-Related Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | |
|--|--|---|----------------------------|-----------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Initial N_{brdwy} | Proportion of total crashes (f_{dwy}) | Adjusted N_{brdwy} | Combined CMFs | Calibration factor, C_r | Predicted N_{brdwy} |
| | (5) _{TOTAL} from Worksheet 1G | from Table 12-7 | (2) _{TOTAL} * (3) | (6) from Worksheet 1B | | (4)*(5)*(6) |
| Total | 0.040 | 1.000 | 0.040 | 1.41 | 1.00 | 0.057 |
| Fatal and injury (FI) | -- | 0.323 | 0.013 | 1.41 | 1.00 | 0.018 |
| Property damage only (PDO) | -- | 0.677 | 0.027 | 1.41 | 1.00 | 0.039 |

| Worksheet 1I -- Vehicle-Pedestrian Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|---|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{pedr} | Calibration factor, C_r | Predicted N_{pedr} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-8 | | (5)*(6)*(7) |
| Total | 0.012 | 0.030 | 0.057 | 0.099 | 0.036 | 1.00 | 0.004 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.004 |

| Worksheet 1J -- Vehicle-Bicycle Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|--|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{biker} | Calibration factor, C_r | Predicted N_{biker} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-9 | | (5)*(6)*(7) |
| Total | 0.012 | 0.030 | 0.057 | 0.099 | 0.018 | 1.00 | 0.002 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.002 |

| Worksheet 1K -- Crash Severity Distribution for Urban and Suburban Roadway Segments | | | |
|--|---|--|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J | (5) from Worksheet 1D and 1F; and (7) from Worksheet 1H | (6) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 1D) | 0.003 | 0.006 | 0.009 |
| Head-on collisions (from Worksheet 1D) | 0.000 | 0.000 | 0.000 |
| Angle collisions (from Worksheet 1D) | 0.000 | 0.001 | 0.001 |
| Sideswipe, same direction (from Worksheet 1D) | 0.000 | 0.000 | 0.000 |
| Sideswipe, opposite direction (from Worksheet 1D) | 0.000 | 0.000 | 0.001 |
| Driveway-related collisions (from Worksheet 1H) | 0.018 | 0.039 | 0.057 |
| Other multiple-vehicle collision (from Worksheet 1D) | 0.000 | 0.000 | 0.001 |
| Subtotal | 0.022 | 0.047 | 0.068 |
| SINGLE-VEHICLE | | | |
| Collision with animal (from Worksheet 1F) | 0.000 | 0.001 | 0.002 |
| Collision with fixed object (from Worksheet 1F) | 0.007 | 0.015 | 0.022 |
| Collision with other object (from Worksheet 1F) | 0.000 | 0.000 | 0.000 |
| Other single-vehicle collision (from Worksheet 1F) | 0.002 | 0.003 | 0.006 |
| Collision with pedestrian (from Worksheet 1I) | 0.004 | 0.000 | 0.004 |
| Collision with bicycle (from Worksheet 1J) | 0.002 | 0.000 | 0.002 |
| Subtotal | 0.016 | 0.020 | 0.035 |
| Total | 0.037 | 0.066 | 0.104 |

| Worksheet 1L -- Summary Results for Urban and Suburban Roadway Segments | | | |
|--|---|---------------------------------------|-------------------------------------|
| (1) | (2) | (3) | (4) |
| Crash Severity Level | Predicted average crash frequency, N_{predicted rs} (crashes/year) | Roadway segment length, L (mi) | Crash rate (crashes/mi/year) |
| | (Total) from Worksheet 1K | | (2) / (3) |
| Total | 0.104 | 0.06 | 1.7 |
| Fatal and injury (FI) | 0.0 | 0.06 | 0.6 |
| Property damage only (PDO) | 0.1 | 0.06 | 1.1 |

| Worksheet 1A -- General Information and Input Data for Urban and Suburban Roadway Segments | | | |
|--|--|----------------------|---|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | 5th Street |
| Agency or Company | Fehr & Peers | Roadway Section | Between Center Street and Mandela Parkway |
| Date Performed | 01/02/19 | Jurisdiction | Oakland, CA |
| | | Analysis Year | 2019 |
| Input Data | | Base Conditions | Site Conditions |
| Roadway type (2U, 3T, 4U, 4D, ST) | | -- | 2U |
| Length of segment, L (mi) | | -- | 0.07 |
| AADT (veh/day) | AADT _{MAX} = 32,600 (veh/day) | -- | 3,715 |
| Type of on-street parking (none/parallel/angle) | | None | Angle (Comm/Ind) |
| Proportion of curb length with on-street parking | | -- | 0.84 |
| Median width (ft) - for divided only | | 15 | Not Present |
| Lighting (present / not present) | | Not Present | Present |
| Auto speed enforcement (present / not present) | | Not Present | Not Present |
| Major commercial driveways (number) | | -- | 0 |
| Minor commercial driveways (number) | | -- | 0 |
| Major industrial / institutional driveways (number) | | -- | 1 |
| Minor industrial / institutional driveways (number) | | -- | 4 |
| Major residential driveways (number) | | -- | 0 |
| Minor residential driveways (number) | | -- | 0 |
| Other driveways (number) | | -- | 0 |
| Speed Category | | -- | Posted Speed 30 mph or Lower |
| Roadside fixed object density (fixed objects / mi) | | 0 | 75 |
| Offset to roadside fixed objects (ft) [If greater than 30 or Not Present, input 30] | | 30 | 20 |
| Calibration Factor, Cr | | 1.00 | 1.00 |

| Worksheet 1B -- Crash Modification Factors for Urban and Suburban Roadway Segments | | | | | |
|--|--------------------------------|----------------------|---------------------|-------------------------------------|---------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| CMF for On-Street Parking | CMF for Roadside Fixed Objects | CMF for Median Width | CMF for Lighting | CMF for Automated Speed Enforcement | Combined CMF |
| <i>CMF 1r</i> | <i>CMF 2r</i> | <i>CMF 3r</i> | <i>CMF 4r</i> | <i>CMF 5r</i> | <i>CMF comb</i> |
| from Equation 12-32 | from Equation 12-33 | from Table 12-22 | from Equation 12-34 | from Section 12.7.1 | (1)*(2)*(3)*(4)*(5) |
| 4.23 | 1.19 | 1.00 | 0.93 | 1.00 | 4.70 |

| Worksheet 1C -- Multiple-Vehicle Nondriveway Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|------------------|------|-----------------------------|---------------------------|--|----------------------------|---------------|------------------------|-----------------------------|
| (1) | (2) | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
| Crash Severity Level | SPF Coefficients | | Overdispersion Parameter, k | Initial N _{brmv} | Proportion of Total Crashes | Adjusted N _{brmv} | Combined CMFs | Calibration Factor, Cr | Predicted N _{brmv} |
| | a | b | | | | | | | |
| Total | -15.22 | 1.68 | 0.84 | 0.017 | 1.000 | 0.017 | 4.70 | 1.00 | 0.082 |
| Fatal and Injury (FI) | -16.22 | 1.66 | 0.65 | 0.005 | $(4)_{FI} / ((4)_{FI} + (4)_{PDO})$ 0.300 | 0.005 | 4.70 | 1.00 | 0.024 |
| Property Damage Only (PDO) | -15.62 | 1.69 | 0.87 | 0.013 | $(5)_{TOTAL} - (5)_{FI}$ 0.700 | 0.012 | 4.70 | 1.00 | 0.057 |

| Worksheet 1D -- Multiple-Vehicle Nondrivable Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brmv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brmv (PDO)} (crashes/year) | (6) Predicted N _{brmv (TOTAL)} (crashes/year) |
| | from Table 12-4 | (9) _{FI} from Worksheet 1C | from Table 12-4 | (9) _{PDO} from Worksheet 1C | (9) _{TOTAL} from Worksheet 1C |
| Total | 1.000 | 0.024 | 1.000 | 0.057 | 0.082 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Rear-end collision | 0.730 | 0.018 | 0.778 | 0.044 | 0.062 |
| Head-on collision | 0.068 | 0.002 | 0.004 | 0.000 | 0.002 |
| Angle collision | 0.085 | 0.002 | 0.079 | 0.005 | 0.007 |
| Sideswipe, same direction | 0.015 | 0.000 | 0.031 | 0.002 | 0.002 |
| Sideswipe, opposite direction | 0.073 | 0.002 | 0.055 | 0.003 | 0.005 |
| Other multiple-vehicle collision | 0.029 | 0.001 | 0.053 | 0.003 | 0.004 |

| Worksheet 1E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|-------------------------|------|------------------------------------|----------------------------------|--|-----------------------------------|---|-------------------------------|------------------------------------|
| (1) Crash Severity Level | (2) SPF Coefficients | | (3) Overdispersion Parameter, k | (4) Initial N _{brsv} | (5) Proportion of Total Crashes | (6) Adjusted N _{brsv} | (7) Combined CMFs (6) from Worksheet 1B | (8) Calibration Factor, Cr | (9) Predicted N _{brsv} |
| | from Table 12-5 | | from Table 12-5 | from Equation 12-13 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | | | | | | | |
| Total | -5.47 | 0.56 | 0.81 | 0.030 | 1.000 | 0.030 | 4.70 | 1.00 | 0.140 |
| Fatal and Injury (FI) | -3.96 | 0.23 | 0.50 | 0.009 | (4) _{FI} /((4) _{FI} +(4) _{PDO}) 0.306 | 0.009 | 4.70 | 1.00 | 0.043 |
| Property Damage Only (PDO) | -6.51 | 0.64 | 0.87 | 0.020 | (5) _{TOTAL} -(5) _{FI} 0.694 | 0.021 | 4.70 | 1.00 | 0.097 |

| Worksheet 1F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brsv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brsv (PDO)} (crashes/year) | (6) Predicted N _{brsv (TOTAL)} (crashes/year) |
| | from Table 12-6 | (9) _{FI} from Worksheet 1E | from Table 12-6 | (9) _{PDO} from Worksheet 1E | (9) _{TOTAL} from Worksheet 1E |
| Total | 1.000 | 0.043 | 1.000 | 0.097 | 0.140 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with animal | 0.026 | 0.001 | 0.066 | 0.006 | 0.008 |
| Collision with fixed object | 0.723 | 0.031 | 0.759 | 0.074 | 0.105 |
| Collision with other object | 0.010 | 0.000 | 0.013 | 0.001 | 0.002 |
| Other single-vehicle collision | 0.241 | 0.010 | 0.162 | 0.016 | 0.026 |

| Worksheet 1G -- Multiple-Vehicle Driveway-Related Collisions by Driveway Type for Urban and Suburban Roadway Segments | | | | | |
|---|----------------------------|--------------------------------------|---|---|-------------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Driveway Type | Number of driveways, n_j | Crashes per driveway per year, N_j | Coefficient for traffic adjustment, t | Initial N_{brdwy} | Overdispersion parameter, k |
| | | from Table 12-7 | from Table 12-7 | Equation 12-16 $n_j * N_j * (AADT/15,000)^t$ | from Table 12-7 |
| Major commercial | 0 | 0.158 | 1.000 | 0.000 | -- |
| Minor commercial | 0 | 0.050 | 1.000 | 0.000 | |
| Major industrial/institutional | 1 | 0.172 | 1.000 | 0.043 | |
| Minor industrial/institutional | 4 | 0.023 | 1.000 | 0.023 | |
| Major residential | 0 | 0.083 | 1.000 | 0.000 | |
| Minor residential | 0 | 0.016 | 1.000 | 0.000 | |
| Other | 0 | 0.025 | 1.000 | 0.000 | |
| Total | -- | -- | -- | 0.065 | 0.81 |

| Worksheet 1H -- Multiple-Vehicle Driveway-Related Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | |
|--|--|---|----------------------------|-----------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Initial N_{brdwy} | Proportion of total crashes (f_{dwy}) | Adjusted N_{brdwy} | Combined CMFs | Calibration factor, C_r | Predicted N_{brdwy} |
| | (5) _{TOTAL} from Worksheet 1G | from Table 12-7 | (2) _{TOTAL} * (3) | (6) from Worksheet 1B | | (4)*(5)*(6) |
| Total | 0.065 | 1.000 | 0.065 | 4.70 | 1.00 | 0.307 |
| Fatal and injury (FI) | -- | 0.323 | 0.021 | 4.70 | 1.00 | 0.099 |
| Property damage only (PDO) | -- | 0.677 | 0.044 | 4.70 | 1.00 | 0.208 |

| Worksheet 1I -- Vehicle-Pedestrian Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|---|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{pedr} | Calibration factor, C_r | Predicted N_{pedr} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-8 | | (5)*(6)*(7) |
| Total | 0.082 | 0.140 | 0.307 | 0.529 | 0.036 | 1.00 | 0.019 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.019 |

| Worksheet 1J -- Vehicle-Bicycle Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|--|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{biker} | Calibration factor, C_r | Predicted N_{biker} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-9 | | (5)*(6)*(7) |
| Total | 0.082 | 0.140 | 0.307 | 0.529 | 0.018 | 1.00 | 0.010 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.010 |

| Worksheet 1K -- Crash Severity Distribution for Urban and Suburban Roadway Segments | | | |
|--|---|--|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J | (5) from Worksheet 1D and 1F; and (7) from Worksheet 1H | (6) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 1D) | 0.018 | 0.044 | 0.062 |
| Head-on collisions (from Worksheet 1D) | 0.002 | 0.000 | 0.002 |
| Angle collisions (from Worksheet 1D) | 0.002 | 0.005 | 0.007 |
| Sideswipe, same direction (from Worksheet 1D) | 0.000 | 0.002 | 0.002 |
| Sideswipe, opposite direction (from Worksheet 1D) | 0.002 | 0.003 | 0.005 |
| Driveway-related collisions (from Worksheet 1H) | 0.099 | 0.208 | 0.307 |
| Other multiple-vehicle collision (from Worksheet 1D) | 0.001 | 0.003 | 0.004 |
| Subtotal | 0.124 | 0.265 | 0.389 |
| SINGLE-VEHICLE | | | |
| Collision with animal (from Worksheet 1F) | 0.001 | 0.006 | 0.008 |
| Collision with fixed object (from Worksheet 1F) | 0.031 | 0.074 | 0.105 |
| Collision with other object (from Worksheet 1F) | 0.000 | 0.001 | 0.002 |
| Other single-vehicle collision (from Worksheet 1F) | 0.010 | 0.016 | 0.026 |
| Collision with pedestrian (from Worksheet 1I) | 0.019 | 0.000 | 0.019 |
| Collision with bicycle (from Worksheet 1J) | 0.010 | 0.000 | 0.010 |
| Subtotal | 0.071 | 0.097 | 0.169 |
| Total | 0.195 | 0.363 | 0.558 |

| Worksheet 1L -- Summary Results for Urban and Suburban Roadway Segments | | | |
|--|---|---------------------------------------|-------------------------------------|
| (1) | (2) | (3) | (4) |
| Crash Severity Level | Predicted average crash frequency, N_{predicted rs} (crashes/year) | Roadway segment length, L (mi) | Crash rate (crashes/mi/year) |
| | (Total) from Worksheet 1K | | (2) / (3) |
| Total | 0.558 | 0.07 | 7.9 |
| Fatal and injury (FI) | 0.2 | 0.07 | 2.7 |
| Property damage only (PDO) | 0.4 | 0.07 | 5.1 |

| Worksheet 1A -- General Information and Input Data for Urban and Suburban Roadway Segments | | | |
|--|--|----------------------|-----------------------------------|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | Chester Street |
| Agency or Company | Fehr & Peers | Roadway Section | Between 7th Street and 5th Street |
| Date Performed | 01/02/19 | Jurisdiction | Oakland, CA |
| | | Analysis Year | 2019 |
| Input Data | | Base Conditions | Site Conditions |
| Roadway type (2U, 3T, 4U, 4D, ST) | | -- | 2U |
| Length of segment, L (mi) | | -- | 0.09 |
| AADT (veh/day) | AADT _{MAX} = 32,600 (veh/day) | -- | 2,325 |
| Type of on-street parking (none/parallel/angle) | | None | Parallel (Residential) |
| Proportion of curb length with on-street parking | | -- | 0.76 |
| Median width (ft) - for divided only | | 15 | Not Present |
| Lighting (present / not present) | | Not Present | Present |
| Auto speed enforcement (present / not present) | | Not Present | Not Present |
| Major commercial driveways (number) | | -- | 0 |
| Minor commercial driveways (number) | | -- | 0 |
| Major industrial / institutional driveways (number) | | -- | 1 |
| Minor industrial / institutional driveways (number) | | -- | 1 |
| Major residential driveways (number) | | -- | 0 |
| Minor residential driveways (number) | | -- | 4 |
| Other driveways (number) | | -- | 0 |
| Speed Category | | -- | Posted Speed 30 mph or Lower |
| Roadside fixed object density (fixed objects / mi) | | 0 | 39 |
| Offset to roadside fixed objects (ft) [If greater than 30 or Not Present, input 30] | | 30 | 15 |
| Calibration Factor, Cr | | 1.00 | 1.00 |

| Worksheet 1B -- Crash Modification Factors for Urban and Suburban Roadway Segments | | | | | |
|--|--------------------------------|----------------------|---------------------|-------------------------------------|---------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| CMF for On-Street Parking | CMF for Roadside Fixed Objects | CMF for Median Width | CMF for Lighting | CMF for Automated Speed Enforcement | Combined CMF |
| <i>CMF 1r</i> | <i>CMF 2r</i> | <i>CMF 3r</i> | <i>CMF 4r</i> | <i>CMF 5r</i> | <i>CMF comb</i> |
| from Equation 12-32 | from Equation 12-33 | from Table 12-22 | from Equation 12-34 | from Section 12.7.1 | (1)*(2)*(3)*(4)*(5) |
| 1.35 | 1.10 | 1.00 | 0.93 | 1.00 | 1.38 |

| Worksheet 1C -- Multiple-Vehicle Nondriveway Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|------------------|------|-----------------------------|---------------------------|--|----------------------------|---------------|------------------------|-----------------------------|
| (1) | (2) | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
| Crash Severity Level | SPF Coefficients | | Overdispersion Parameter, k | Initial N _{brmv} | Proportion of Total Crashes | Adjusted N _{brmv} | Combined CMFs | Calibration Factor, Cr | Predicted N _{brmv} |
| | a | b | | | | | | | |
| Total | -15.22 | 1.68 | 0.84 | 0.010 | 1.000 | 0.010 | 1.38 | 1.00 | 0.013 |
| Fatal and Injury (FI) | -16.22 | 1.66 | 0.65 | 0.003 | $\frac{(4)_{FI}}{(4)_{FI}+(4)_{PDO}}$ 0.303 | 0.003 | 1.38 | 1.00 | 0.004 |
| Property Damage Only (PDO) | -15.62 | 1.69 | 0.87 | 0.007 | $\frac{(5)_{TOTAL}-(5)_{FI}}{0.697}$ | 0.007 | 1.38 | 1.00 | 0.009 |

| Worksheet 1D -- Multiple-Vehicle Nondrivable Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brmv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brmv (PDO)} (crashes/year) | (6) Predicted N _{brmv (TOTAL)} (crashes/year) |
| | from Table 12-4 | (9) _{FI} from Worksheet 1C | from Table 12-4 | (9) _{PDO} from Worksheet 1C | (9) _{TOTAL} from Worksheet 1C |
| Total | 1.000 | 0.004 | 1.000 | 0.009 | 0.013 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Rear-end collision | 0.730 | 0.003 | 0.778 | 0.007 | 0.010 |
| Head-on collision | 0.068 | 0.000 | 0.004 | 0.000 | 0.000 |
| Angle collision | 0.085 | 0.000 | 0.079 | 0.001 | 0.001 |
| Sideswipe, same direction | 0.015 | 0.000 | 0.031 | 0.000 | 0.000 |
| Sideswipe, opposite direction | 0.073 | 0.000 | 0.055 | 0.001 | 0.001 |
| Other multiple-vehicle collision | 0.029 | 0.000 | 0.053 | 0.000 | 0.001 |

| Worksheet 1E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|-------------------------|------|------------------------------------|----------------------------------|--|-----------------------------------|---|-------------------------------|------------------------------------|
| (1) Crash Severity Level | (2) SPF Coefficients | | (3) Overdispersion Parameter, k | (4) Initial N _{brsv} | (5) Proportion of Total Crashes | (6) Adjusted N _{brsv} | (7) Combined CMFs (6) from Worksheet 1B | (8) Calibration Factor, Cr | (9) Predicted N _{brsv} |
| | from Table 12-5 | | from Table 12-5 | from Equation 12-13 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | | | | | | | |
| Total | -5.47 | 0.56 | 0.81 | 0.028 | 1.000 | 0.028 | 1.38 | 1.00 | 0.039 |
| Fatal and Injury (FI) | -3.96 | 0.23 | 0.50 | 0.010 | (4) _{FI} /((4) _{FI} +(4) _{PDO}) 0.348 | 0.010 | 1.38 | 1.00 | 0.014 |
| Property Damage Only (PDO) | -6.51 | 0.64 | 0.87 | 0.019 | (5) _{TOTAL} -(5) _{FI} 0.652 | 0.018 | 1.38 | 1.00 | 0.025 |

| Worksheet 1F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brsv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brsv (PDO)} (crashes/year) | (6) Predicted N _{brsv (TOTAL)} (crashes/year) |
| | from Table 12-6 | (9) _{FI} from Worksheet 1E | from Table 12-6 | (9) _{PDO} from Worksheet 1E | (9) _{TOTAL} from Worksheet 1E |
| Total | 1.000 | 0.014 | 1.000 | 0.025 | 0.039 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with animal | 0.026 | 0.000 | 0.066 | 0.002 | 0.002 |
| Collision with fixed object | 0.723 | 0.010 | 0.759 | 0.019 | 0.029 |
| Collision with other object | 0.010 | 0.000 | 0.013 | 0.000 | 0.000 |
| Other single-vehicle collision | 0.241 | 0.003 | 0.162 | 0.004 | 0.007 |

| Worksheet 1G -- Multiple-Vehicle Driveway-Related Collisions by Driveway Type for Urban and Suburban Roadway Segments | | | | | |
|---|----------------------------|--------------------------------------|---|---|-------------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Driveway Type | Number of driveways, n_j | Crashes per driveway per year, N_j | Coefficient for traffic adjustment, t | Initial N_{brdwy} | Overdispersion parameter, k |
| | | from Table 12-7 | from Table 12-7 | Equation 12-16 $n_j * N_j * (AADT/15,000)^t$ | from Table 12-7 |
| Major commercial | 0 | 0.158 | 1.000 | 0.000 | -- |
| Minor commercial | 0 | 0.050 | 1.000 | 0.000 | |
| Major industrial/institutional | 1 | 0.172 | 1.000 | 0.027 | |
| Minor industrial/institutional | 1 | 0.023 | 1.000 | 0.004 | |
| Major residential | 0 | 0.083 | 1.000 | 0.000 | |
| Minor residential | 4 | 0.016 | 1.000 | 0.010 | |
| Other | 0 | 0.025 | 1.000 | 0.000 | |
| Total | -- | -- | -- | 0.040 | 0.81 |

| Worksheet 1H -- Multiple-Vehicle Driveway-Related Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | |
|--|--|---|----------------------------|-----------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Initial N_{brdwy} | Proportion of total crashes (f_{dwy}) | Adjusted N_{brdwy} | Combined CMFs | Calibration factor, C_r | Predicted N_{brdwy} |
| | (5) _{TOTAL} from Worksheet 1G | from Table 12-7 | (2) _{TOTAL} * (3) | (6) from Worksheet 1B | | (4)*(5)*(6) |
| Total | 0.040 | 1.000 | 0.040 | 1.38 | 1.00 | 0.055 |
| Fatal and injury (FI) | -- | 0.323 | 0.013 | 1.38 | 1.00 | 0.018 |
| Property damage only (PDO) | -- | 0.677 | 0.027 | 1.38 | 1.00 | 0.037 |

| Worksheet 1I -- Vehicle-Pedestrian Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|---|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{pedr} | Calibration factor, C_r | Predicted N_{pedr} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-8 | | (5)*(6)*(7) |
| Total | 0.013 | 0.039 | 0.055 | 0.108 | 0.036 | 1.00 | 0.004 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.004 |

| Worksheet 1J -- Vehicle-Bicycle Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|--|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{biker} | Calibration factor, C_r | Predicted N_{biker} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-9 | | (5)*(6)*(7) |
| Total | 0.013 | 0.039 | 0.055 | 0.108 | 0.018 | 1.00 | 0.002 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.002 |

| Worksheet 1K -- Crash Severity Distribution for Urban and Suburban Roadway Segments | | | |
|--|---|--|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J | (5) from Worksheet 1D and 1F; and (7) from Worksheet 1H | (6) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 1D) | 0.003 | 0.007 | 0.010 |
| Head-on collisions (from Worksheet 1D) | 0.000 | 0.000 | 0.000 |
| Angle collisions (from Worksheet 1D) | 0.000 | 0.001 | 0.001 |
| Sideswipe, same direction (from Worksheet 1D) | 0.000 | 0.000 | 0.000 |
| Sideswipe, opposite direction (from Worksheet 1D) | 0.000 | 0.001 | 0.001 |
| Driveway-related collisions (from Worksheet 1H) | 0.018 | 0.037 | 0.055 |
| Other multiple-vehicle collision (from Worksheet 1D) | 0.000 | 0.000 | 0.001 |
| Subtotal | 0.022 | 0.047 | 0.069 |
| SINGLE-VEHICLE | | | |
| Collision with animal (from Worksheet 1F) | 0.000 | 0.002 | 0.002 |
| Collision with fixed object (from Worksheet 1F) | 0.010 | 0.019 | 0.029 |
| Collision with other object (from Worksheet 1F) | 0.000 | 0.000 | 0.000 |
| Other single-vehicle collision (from Worksheet 1F) | 0.003 | 0.004 | 0.007 |
| Collision with pedestrian (from Worksheet 1I) | 0.004 | 0.000 | 0.004 |
| Collision with bicycle (from Worksheet 1J) | 0.002 | 0.000 | 0.002 |
| Subtotal | 0.019 | 0.025 | 0.045 |
| Total | 0.041 | 0.072 | 0.113 |

| Worksheet 1L -- Summary Results for Urban and Suburban Roadway Segments | | | |
|--|--|--------------------------------|------------------------------|
| (1) | (2) | (3) | (4) |
| Crash Severity Level | Predicted average crash frequency, $N_{\text{predicted rs}}$ (crashes/year) | Roadway segment length, L (mi) | Crash rate (crashes/mi/year) |
| | (Total) from Worksheet 1K | | (2) / (3) |
| Total | 0.113 | 0.09 | 1.3 |
| Fatal and injury (FI) | 0.0 | 0.09 | 0.5 |
| Property damage only (PDO) | 0.1 | 0.09 | 0.8 |

| Worksheet 1A -- General Information and Input Data for Urban and Suburban Roadway Segments | | | |
|--|--|----------------------|-----------------------------------|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | Mandela Parkway |
| Agency or Company | Fehr & Peers | Roadway Section | Between 7th Street and 5th Street |
| Date Performed | 01/02/19 | Jurisdiction | Oakland, CA |
| | | Analysis Year | 2019 |
| Input Data | | Base Conditions | Site Conditions |
| Roadway type (2U, 3T, 4U, 4D, ST) | | -- | 2U |
| Length of segment, L (mi) | | -- | 0.09 |
| AADT (veh/day) | AADT _{MAX} = 32,600 (veh/day) | -- | 6,175 |
| Type of on-street parking (none/parallel/angle) | | None | Parallel (Comm/Ind) |
| Proportion of curb length with on-street parking | | -- | 0.36 |
| Median width (ft) - for divided only | | 15 | Not Present |
| Lighting (present / not present) | | Not Present | Present |
| Auto speed enforcement (present / not present) | | Not Present | Not Present |
| Major commercial driveways (number) | | -- | 1 |
| Minor commercial driveways (number) | | -- | 2 |
| Major industrial / institutional driveways (number) | | -- | 1 |
| Minor industrial / institutional driveways (number) | | -- | 0 |
| Major residential driveways (number) | | -- | 0 |
| Minor residential driveways (number) | | -- | 0 |
| Other driveways (number) | | -- | 0 |
| Speed Category | | -- | Posted Speed 30 mph or Lower |
| Roadside fixed object density (fixed objects / mi) | | 0 | 79 |
| Offset to roadside fixed objects (ft) [If greater than 30 or Not Present, input 30] | | 30 | 25 |
| Calibration Factor, Cr | | 1.00 | 1.00 |

| Worksheet 1B -- Crash Modification Factors for Urban and Suburban Roadway Segments | | | | | |
|--|--------------------------------|----------------------|---------------------|-------------------------------------|---------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| CMF for On-Street Parking | CMF for Roadside Fixed Objects | CMF for Median Width | CMF for Lighting | CMF for Automated Speed Enforcement | Combined CMF |
| <i>CMF 1r</i> | <i>CMF 2r</i> | <i>CMF 3r</i> | <i>CMF 4r</i> | <i>CMF 5r</i> | <i>CMF comb</i> |
| from Equation 12-32 | from Equation 12-33 | from Table 12-22 | from Equation 12-34 | from Section 12.7.1 | (1)*(2)*(3)*(4)*(5) |
| 1.39 | 1.17 | 1.00 | 0.93 | 1.00 | 1.52 |

| Worksheet 1C -- Multiple-Vehicle Nondriveway Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|------------------|------|-----------------------------|---------------------------|---|----------------------------|---------------|------------------------|-----------------------------|
| (1) | (2) | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
| Crash Severity Level | SPF Coefficients | | Overdispersion Parameter, k | Initial N _{brmv} | Proportion of Total Crashes | Adjusted N _{brmv} | Combined CMFs | Calibration Factor, Cr | Predicted N _{brmv} |
| | a | b | | | | | | | |
| Total | -15.22 | 1.68 | 0.84 | 0.050 | 1.000 | 0.050 | 1.52 | 1.00 | 0.076 |
| Fatal and Injury (FI) | -16.22 | 1.66 | 0.65 | 0.015 | $\frac{(4)_{FI}}{((4)_{FI} + (4)_{PDO}}$ 0.297 | 0.015 | 1.52 | 1.00 | 0.022 |
| Property Damage Only (PDO) | -15.62 | 1.69 | 0.87 | 0.037 | $\frac{(5)_{TOTAL} - (5)_{FI}}{0.703}$ | 0.035 | 1.52 | 1.00 | 0.053 |

| Worksheet 1D -- Multiple-Vehicle Nondrivable Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brmv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brmv (PDO)} (crashes/year) | (6) Predicted N _{brmv (TOTAL)} (crashes/year) |
| | from Table 12-4 | (9) _{FI} from Worksheet 1C | from Table 12-4 | (9) _{PDO} from Worksheet 1C | (9) _{TOTAL} from Worksheet 1C |
| Total | 1.000 | 0.022 | 1.000 | 0.053 | 0.076 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Rear-end collision | 0.730 | 0.016 | 0.778 | 0.041 | 0.058 |
| Head-on collision | 0.068 | 0.002 | 0.004 | 0.000 | 0.002 |
| Angle collision | 0.085 | 0.002 | 0.079 | 0.004 | 0.006 |
| Sideswipe, same direction | 0.015 | 0.000 | 0.031 | 0.002 | 0.002 |
| Sideswipe, opposite direction | 0.073 | 0.002 | 0.055 | 0.003 | 0.005 |
| Other multiple-vehicle collision | 0.029 | 0.001 | 0.053 | 0.003 | 0.003 |

| Worksheet 1E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | | | | |
|---|-------------------------|------|------------------------------------|----------------------------------|--|-----------------------------------|---|-------------------------------|------------------------------------|
| (1) Crash Severity Level | (2) SPF Coefficients | | (3) Overdispersion Parameter, k | (4) Initial N _{brsv} | (5) Proportion of Total Crashes | (6) Adjusted N _{brsv} | (7) Combined CMFs (6) from Worksheet 1B | (8) Calibration Factor, Cr | (9) Predicted N _{brsv} |
| | from Table 12-5 | | from Table 12-5 | from Equation 12-13 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | | | | | | | |
| Total | -5.47 | 0.56 | 0.81 | 0.049 | 1.000 | 0.049 | 1.52 | 1.00 | 0.074 |
| Fatal and Injury (FI) | -3.96 | 0.23 | 0.50 | 0.012 | (4) _{FI} /((4) _{FI} +(4) _{PDO}) 0.263 | 0.013 | 1.52 | 1.00 | 0.019 |
| Property Damage Only (PDO) | -6.51 | 0.64 | 0.87 | 0.035 | (5) _{TOTAL} -(5) _{FI} 0.737 | 0.036 | 1.52 | 1.00 | 0.054 |

| Worksheet 1F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Roadway Segments | | | | | |
|---|---|--|--|---|---|
| (1) Collision Type | (2) Proportion of Collision Type _(FI) | (3) Predicted N _{brsv (FI)} (crashes/year) | (4) Proportion of Collision Type _(PDO) | (5) Predicted N _{brsv (PDO)} (crashes/year) | (6) Predicted N _{brsv (TOTAL)} (crashes/year) |
| | from Table 12-6 | (9) _{FI} from Worksheet 1E | from Table 12-6 | (9) _{PDO} from Worksheet 1E | (9) _{TOTAL} from Worksheet 1E |
| Total | 1.000 | 0.019 | 1.000 | 0.054 | 0.074 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with animal | 0.026 | 0.001 | 0.066 | 0.004 | 0.004 |
| Collision with fixed object | 0.723 | 0.014 | 0.759 | 0.041 | 0.055 |
| Collision with other object | 0.010 | 0.000 | 0.013 | 0.001 | 0.001 |
| Other single-vehicle collision | 0.241 | 0.005 | 0.162 | 0.009 | 0.013 |

| Worksheet 1G -- Multiple-Vehicle Driveway-Related Collisions by Driveway Type for Urban and Suburban Roadway Segments | | | | | |
|---|----------------------------|--------------------------------------|---|---|-------------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Driveway Type | Number of driveways, n_j | Crashes per driveway per year, N_j | Coefficient for traffic adjustment, t | Initial N_{brdwy} | Overdispersion parameter, k |
| | | from Table 12-7 | from Table 12-7 | Equation 12-16 $n_j * N_j * (AADT/15,000)^t$ | from Table 12-7 |
| Major commercial | 1 | 0.158 | 1.000 | 0.065 | -- |
| Minor commercial | 2 | 0.050 | 1.000 | 0.041 | |
| Major industrial/institutional | 1 | 0.172 | 1.000 | 0.071 | |
| Minor industrial/institutional | 0 | 0.023 | 1.000 | 0.000 | |
| Major residential | 0 | 0.083 | 1.000 | 0.000 | |
| Minor residential | 0 | 0.016 | 1.000 | 0.000 | |
| Other | 0 | 0.025 | 1.000 | 0.000 | |
| Total | -- | -- | -- | 0.177 | 0.81 |

| Worksheet 1H -- Multiple-Vehicle Driveway-Related Collisions by Severity Level for Urban and Suburban Roadway Segments | | | | | | |
|--|--|---|----------------------------|-----------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Initial N_{brdwy} | Proportion of total crashes (f_{dwy}) | Adjusted N_{brdwy} | Combined CMFs | Calibration factor, C_r | Predicted N_{brdwy} |
| | (5) _{TOTAL} from Worksheet 1G | from Table 12-7 | (2) _{TOTAL} * (3) | (6) from Worksheet 1B | | (4)*(5)*(6) |
| Total | 0.177 | 1.000 | 0.177 | 1.52 | 1.00 | 0.268 |
| Fatal and injury (FI) | -- | 0.323 | 0.057 | 1.52 | 1.00 | 0.087 |
| Property damage only (PDO) | -- | 0.677 | 0.120 | 1.52 | 1.00 | 0.182 |

| Worksheet 1I -- Vehicle-Pedestrian Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|---|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{pedr} | Calibration factor, C_r | Predicted N_{pedr} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-8 | | (5)*(6)*(7) |
| Total | 0.076 | 0.074 | 0.268 | 0.418 | 0.036 | 1.00 | 0.015 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.015 |

| Worksheet 1J -- Vehicle-Bicycle Collisions for Urban and Suburban Roadway Segments | | | | | | | |
|--|-----------------------|-----------------------|-----------------------|--------------------|-----------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) | (8) |
| Crash Severity Level | Predicted N_{brmv} | Predicted N_{brsv} | Predicted N_{brdwy} | Predicted N_{br} | f_{biker} | Calibration factor, C_r | Predicted N_{biker} |
| | (9) from Worksheet 1C | (9) from Worksheet 1E | (7) from Worksheet 1H | (2)+(3)+(4) | from Table 12-9 | | (5)*(6)*(7) |
| Total | 0.076 | 0.074 | 0.268 | 0.418 | 0.018 | 1.00 | 0.008 |
| Fatal and injury (FI) | -- | -- | -- | -- | -- | 1.00 | 0.008 |

| Worksheet 1K -- Crash Severity Distribution for Urban and Suburban Roadway Segments | | | |
|--|---|--|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J | (5) from Worksheet 1D and 1F; and (7) from Worksheet 1H | (6) from Worksheet 1D and 1F; (7) from Worksheet 1H; and (8) from Worksheet 1I and 1J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 1D) | 0.016 | 0.041 | 0.058 |
| Head-on collisions (from Worksheet 1D) | 0.002 | 0.000 | 0.002 |
| Angle collisions (from Worksheet 1D) | 0.002 | 0.004 | 0.006 |
| Sideswipe, same direction (from Worksheet 1D) | 0.000 | 0.002 | 0.002 |
| Sideswipe, opposite direction (from Worksheet 1D) | 0.002 | 0.003 | 0.005 |
| Driveway-related collisions (from Worksheet 1H) | 0.087 | 0.182 | 0.268 |
| Other multiple-vehicle collision (from Worksheet 1D) | 0.001 | 0.003 | 0.003 |
| Subtotal | 0.109 | 0.235 | 0.344 |
| SINGLE-VEHICLE | | | |
| Collision with animal (from Worksheet 1F) | 0.001 | 0.004 | 0.004 |
| Collision with fixed object (from Worksheet 1F) | 0.014 | 0.041 | 0.055 |
| Collision with other object (from Worksheet 1F) | 0.000 | 0.001 | 0.001 |
| Other single-vehicle collision (from Worksheet 1F) | 0.005 | 0.009 | 0.013 |
| Collision with pedestrian (from Worksheet 1I) | 0.015 | 0.000 | 0.015 |
| Collision with bicycle (from Worksheet 1J) | 0.008 | 0.000 | 0.008 |
| Subtotal | 0.042 | 0.054 | 0.096 |
| Total | 0.151 | 0.289 | 0.441 |

| Worksheet 1L -- Summary Results for Urban and Suburban Roadway Segments | | | |
|--|---|---------------------------------------|-------------------------------------|
| (1) | (2) | (3) | (4) |
| Crash Severity Level | Predicted average crash frequency, N_{predicted rs} (crashes/year) | Roadway segment length, L (mi) | Crash rate (crashes/mi/year) |
| | (Total) from Worksheet 1K | | (2) / (3) |
| Total | 0.441 | 0.09 | 5.1 |
| Fatal and injury (FI) | 0.2 | 0.09 | 1.7 |
| Property damage only (PDO) | 0.3 | 0.09 | 3.3 |

| Worksheet 2A -- General Information and Input Data for Urban and Suburban Arterial Intersections | | | |
|--|--------------------------------------|----------------------|-------------------------------|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | 7th Street and Chester Street |
| Agency or Company | Fehr & Peers | Intersection | Oakland, CA |
| Date Performed | 01/02/19 | Jurisdiction | 2019 |
| | | Analysis Year | |
| Input Data | | Base Conditions | Site Conditions |
| Intersection type (3ST, 3SG, 4ST, 4SG) | | -- | 4ST |
| AA _{major} (veh/day) | AA _{MAX} = 46,800 (veh/day) | -- | 6,960 |
| AA _{minor} (veh/day) | AA _{MAX} = 5,900 (veh/day) | -- | 2,160 |
| Intersection lighting (present/not present) | | Not Present | Present |
| Calibration factor, C _i | | 1.00 | 1.00 |
| Data for unsignalized intersections only: | | -- | -- |
| Number of major-road approaches with left-turn lanes (0,1,2) | | 0 | 2 |
| Number of major-road approaches with right-turn lanes (0,1,2) | | 0 | 0 |
| Data for signalized intersections only: | | -- | -- |
| Number of approaches with left-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | |
| Number of approaches with right-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | |
| Number of approaches with left-turn signal phasing [for 3SG, use maximum value of 3] | | -- | |
| Type of left-turn signal phasing for Leg #1 | | Permissive | |
| Type of left-turn signal phasing for Leg #2 | | -- | |
| Type of left-turn signal phasing for Leg #3 | | -- | |
| Type of left-turn signal phasing for Leg #4 (if applicable) | | -- | |
| Number of approaches with right-turn-on-red prohibited [for 3SG, use maximum value of 3] | | 0 | |
| Intersection red light cameras (present/not present) | | Not Present | |
| Sum of all pedestrian crossing volumes (PedVol) -- Signalized intersections only | | | |
| Maximum number of lanes crossed by a pedestrian (n _{lanesx}) | | -- | |
| Number of bus stops within 300 m (1,000 ft) of the intersection | | 0 | |
| Schools within 300 m (1,000 ft) of the intersection (present/not present) | | Not Present | |
| Number of alcohol sales establishments within 300 m (1,000 ft) of the intersection | | 0 | |

| Worksheet 2B -- Crash Modification Factors for Urban and Suburban Arterial Intersections | | | | | | |
|--|----------------------------------|--------------------------|---------------------------|---------------------|---------------------------|-------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| CMF for Left-Turn Lanes | CMF for Left-Turn Signal Phasing | CMF for Right-Turn Lanes | CMF for Right Turn on Red | CMF for Lighting | CMF for Red Light Cameras | Combined CMF |
| CMF _{1i} | CMF _{2i} | CMF _{3i} | CMF _{4i} | CMF _{5i} | CMF _{6i} | CMF _{COMB} |
| from Table 12-24 | from Table 12-25 | from Table 12-26 | from Equation 12-35 | from Equation 12-36 | from Equation 12-37 | (1)*(2)*(3)*(4)*(5)*(6) |
| 0.53 | 1.00 | 1.00 | 1.00 | 0.91 | 0.97 | 0.47 |

Worksheet 2C -- Multiple-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---------------------|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bimv} | Proportion of Total Crashes | Adjusted N_{bimv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bimv} |
| | from Table 12-10 | | | from Table 12-10 | from Equation 12-21 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -8.90 | 0.82 | 0.25 | 0.40 | 1.316 | 1.000 | 1.316 | 0.47 | 1.00 | 0.620 |
| Fatal and Injury (FI) | -11.13 | 0.93 | 0.28 | 0.48 | 0.472 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.357 | 0.469 | 0.47 | 1.00 | 0.221 |
| Property Damage Only (PDO) | -8.74 | 0.77 | 0.23 | 0.40 | 0.851 | $(5)_{TOTAL}-(5)_{FI}$ 0.643 | 0.847 | 0.47 | 1.00 | 0.399 |

Worksheet 2D -- Multiple-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections

| (1) | (2) | (3) | (4) | (5) | (6) |
|----------------------------------|--|---|---------------------------------------|--|---|
| Collision Type | Proportion of Collision Type _(FI) | Predicted N_{bimv} (FI) (crashes/year) | Proportion of Collision Type (PDO) | Predicted N_{bimv} (PDO) (crashes/year) | Predicted N_{bimv} (TOTAL) (crashes/year) |
| | from Table 12-11 | (9) _{FI} from Worksheet 2C | from Table 12-11 | (9) _{PDO} from Worksheet 2C | (9) _{PDO} from Worksheet 2C |
| Total | 1.000 | 0.221 | 1.000 | 0.399 | 0.620 |
| | | $(2)*(3)_{FI}$ | | $(4)*(5)_{PDO}$ | $(3)+(5)$ |
| Rear-end collision | 0.338 | 0.075 | 0.374 | 0.149 | 0.224 |
| Head-on collision | 0.041 | 0.009 | 0.030 | 0.012 | 0.021 |
| Angle collision | 0.440 | 0.097 | 0.335 | 0.134 | 0.231 |
| Sideswipe | 0.121 | 0.027 | 0.044 | 0.018 | 0.044 |
| Other multiple-vehicle collision | 0.060 | 0.013 | 0.217 | 0.087 | 0.100 |

Worksheet 2E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bisv} | Proportion of Total Crashes | Adjusted N_{bisv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bisv} |
| | from Table 12-12 | | | from Table 12-12 | from Eqn. 12-24; (FI) from Eqn. 12-24 or 12-27 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -5.33 | 0.33 | 0.12 | 0.65 | 0.226 | 1.000 | 0.226 | 0.47 | 1.00 | 0.106 |
| Fatal and Injury (FI) | -- | -- | -- | -- | 0.063 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.304 | 0.069 | 0.47 | 1.00 | 0.032 |
| Property Damage Only (PDO) | -7.04 | 0.36 | 0.25 | 0.54 | 0.144 | $(5)_{TOTAL}-(5)_{FI}$ 0.696 | 0.157 | 0.47 | 1.00 | 0.074 |

| Worksheet 2F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections | | | | | |
|---|--|---|------------------------------------|--|--|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Collision Type | Proportion of Collision Type _(FI) | Predicted N _{bisv (FI)} (crashes/year) | Proportion of Collision Type (PDO) | Predicted N _{bisv (PDO)} (crashes/year) | Predicted N _{bisv (TOTAL)} (crashes/year) |
| | from Table 12-13 | (9) _{FI} from Worksheet 2E | from Table 12-13 | (9) _{PDO} from Worksheet 2E | (9) _{PDO} from Worksheet 2E |
| Total | 1.000 | 0.032 | 1.000 | 0.074 | 0.106 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with parked vehicle | 0.001 | 0.000 | 0.001 | 0.000 | 0.000 |
| Collision with animal | 0.001 | 0.000 | 0.026 | 0.002 | 0.002 |
| Collision with fixed object | 0.679 | 0.022 | 0.847 | 0.063 | 0.085 |
| Collision with other object | 0.089 | 0.003 | 0.070 | 0.005 | 0.008 |
| Other single-vehicle collision | 0.051 | 0.002 | 0.007 | 0.001 | 0.002 |
| Single-vehicle noncollision | 0.179 | 0.006 | 0.049 | 0.004 | 0.009 |

| Worksheet 2G -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Stop-Controlled Intersections | | | | | | |
|---|-----------------------------|-----------------------------|---------------------------|-------------------|------------------------------------|-----------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N _{bimv} | Predicted N _{bisv} | Predicted N _{bi} | f _{pedi} | Calibration factor, C _i | Predicted N _{pedi} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-16 | | (4)*(5)*(6) |
| Total | 0.620 | 0.106 | 0.726 | 0.022 | 1.00 | 0.016 |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | 0.016 |

| Worksheet 2H -- Crash Modification Factors for Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | |
|---|-------------------|--------------------------------------|--------------|
| (1) | (2) | (3) | (4) |
| CMF for Bus Stops | CMF for Schools | CMF for Alcohol Sales Establishments | Combined CMF |
| CMF _{1p} | CMF _{2p} | CMF _{3p} | |
| from Table 12-28 | from Table 12-29 | from Table 12-30 | (1)*(2)*(3) |
| -- | -- | -- | -- |

| Worksheet 2I -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | | | | | | | | |
|--|------------------|----|----|----|----|-----------------------------|----------------------|-----------------------|------------------------------------|-----------------------------|
| (1) | (2) | | | | | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | SPF Coefficients | | | | | Overdispersion Parameter, k | N _{pedbase} | Combined CMF | Calibration factor, C _i | Predicted N _{pedi} |
| | from Table 12-14 | | | | | | from Equation 12-29 | (4) from Worksheet 2H | | (4)*(5)*(6) |
| | a | b | c | d | e | | | | | |
| Total | -- | -- | -- | -- | -- | -- | -- | -- | 1.00 | -- |
| Fatal and Injury (FI) | -- | -- | -- | -- | -- | -- | -- | -- | 1.00 | -- |

| Worksheet 2J -- Vehicle-Bicycle Collisions for Urban and Suburban Arterial Intersections | | | | | | |
|--|-----------------------|-----------------------|--------------------|------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N_{bimv} | Predicted N_{bisv} | Predicted N_{bi} | f_{bikei} | Calibration factor, C_i | Predicted N_{bikei} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-17 | | (4)*(5)*(6) |
| Total | 0.620 | 0.106 | 0.726 | 0.018 | 1.00 | 0.013 |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | 0.013 |

| Worksheet 2K -- Crash Severity Distribution for Urban and Suburban Arterial Intersections | | | |
|---|---|------------------------------|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J | (5) from Worksheet 2D and 2F | (6) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 2D) | 0.075 | 0.149 | 0.224 |
| Head-on collisions (from Worksheet 2D) | 0.009 | 0.012 | 0.021 |
| Angle collisions (from Worksheet 2D) | 0.097 | 0.134 | 0.231 |
| Sideswipe (from Worksheet 2D) | 0.027 | 0.018 | 0.044 |
| Other multiple-vehicle collision (from Worksheet 2D) | 0.013 | 0.087 | 0.100 |
| Subtotal | 0.221 | 0.399 | 0.620 |
| SINGLE-VEHICLE | | | |
| Collision with parked vehicle (from Worksheet 2F) | 0.000 | 0.000 | 0.000 |
| Collision with animal (from Worksheet 2F) | 0.000 | 0.002 | 0.002 |
| Collision with fixed object (from Worksheet 2F) | 0.022 | 0.063 | 0.085 |
| Collision with other object (from Worksheet 2F) | 0.003 | 0.005 | 0.008 |
| Other single-vehicle collision (from Worksheet 2F) | 0.002 | 0.001 | 0.002 |
| Single-vehicle noncollision (from Worksheet 2F) | 0.006 | 0.004 | 0.009 |
| Collision with pedestrian (from Worksheet 2G or 2I) | 0.016 | 0.000 | 0.016 |
| Collision with bicycle (from Worksheet 2J) | 0.013 | 0.000 | 0.013 |
| Subtotal | 0.061 | 0.074 | 0.135 |
| Total | 0.282 | 0.473 | 0.755 |

| Worksheet 2L -- Summary Results for Urban and Suburban Arterial Intersections | |
|---|--|
| (1) | (2) |
| Crash severity level | Predicted average crash frequency, $N_{predicted int}$ (crashes/year) |
| | (Total) from Worksheet 2K |
| Total | 0.8 |
| Fatal and injury (FI) | 0.3 |
| Property damage only (PDO) | 0.5 |

Worksheet 2A -- General Information and Input Data for Urban and Suburban Arterial Intersections

| General Information | | Location Information | |
|--|--|----------------------|------------------------------|
| Analyst | Jordan Brooks | Roadway | 7th Street and Center Street |
| Agency or Company | Fehr & Peers | Intersection | Oakland, CA |
| Date Performed | 01/02/19 | Jurisdiction | 2019 |
| | | Analysis Year | |
| Input Data | | Base Conditions | Site Conditions |
| Intersection type (3ST, 3SG, 4ST, 4SG) | | -- | 3SG |
| AADT _{major} (veh/day) | AADT _{MAX} = 58,100 (veh/day) | -- | 7,330 |
| AADT _{minor} (veh/day) | AADT _{MAX} = 16,400 (veh/day) | -- | 500 |
| Intersection lighting (present/not present) | | Not Present | Present |
| Calibration factor, C _i | | 1.00 | 1.00 |
| Data for unsignalized intersections only: | | -- | -- |
| Number of major-road approaches with left-turn lanes (0,1,2) | | 0 | |
| Number of major-road approaches with right-turn lanes (0,1,2) | | 0 | |
| Data for signalized intersections only: | | -- | -- |
| Number of approaches with left-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | 1 |
| Number of approaches with right-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | 0 |
| Number of approaches with left-turn signal phasing [for 3SG, use maximum value of 3] | | -- | 0 |
| Type of left-turn signal phasing for Leg #1 | | Permissive | Permissive |
| Type of left-turn signal phasing for Leg #2 | | -- | Permissive |
| Type of left-turn signal phasing for Leg #3 | | -- | Not Applicable |
| Type of left-turn signal phasing for Leg #4 (if applicable) | | -- | |
| Number of approaches with right-turn-on-red prohibited [for 3SG, use maximum value of 3] | | 0 | 0 |
| Intersection red light cameras (present/not present) | | Not Present | Not Present |
| Sum of all pedestrian crossing volumes (PedVol) -- Signalized intersections only | | | 3,010 |
| Maximum number of lanes crossed by a pedestrian (n _{lanesx}) | | -- | 3 |
| Number of bus stops within 300 m (1,000 ft) of the intersection | | 0 | 2 |
| Schools within 300 m (1,000 ft) of the intersection (present/not present) | | Not Present | Not Present |
| Number of alcohol sales establishments within 300 m (1,000 ft) of the intersection | | 0 | 2 |

Worksheet 2B -- Crash Modification Factors for Urban and Suburban Arterial Intersections

| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
|-------------------------|----------------------------------|--------------------------|---------------------------|-------------------------|---------------------------|---------------------------|
| CMF for Left-Turn Lanes | CMF for Left-Turn Signal Phasing | CMF for Right-Turn Lanes | CMF for Right Turn on Red | CMF for Lighting | CMF for Red Light Cameras | Combined CMF |
| <i>CMF_{1i}</i> | <i>CMF_{2i}</i> | <i>CMF_{3i}</i> | <i>CMF_{4i}</i> | <i>CMF_{5i}</i> | <i>CMF_{6i}</i> | <i>CMF_{COMB}</i> |
| from Table 12-24 | from Table 12-25 | from Table 12-26 | from Equation 12-35 | from Equation 12-36 | from Equation 12-37 | (1)*(2)*(3)*(4)*(5)*(6) |
| 0.93 | 1.00 | 1.00 | 1.00 | 0.91 | 1.00 | 0.85 |

Worksheet 2C -- Multiple-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---------------------|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bimv} | Proportion of Total Crashes | Adjusted N_{bimv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bimv} |
| | from Table 12-10 | | | from Table 12-10 | from Equation 12-21 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -12.13 | 1.11 | 0.26 | 0.33 | 0.530 | 1.000 | 0.530 | 0.85 | 1.00 | 0.449 |
| Fatal and Injury (FI) | -11.58 | 1.02 | 0.17 | 0.30 | 0.236 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.446 | 0.236 | 0.85 | 1.00 | 0.200 |
| Property Damage Only (PDO) | -13.24 | 1.14 | 0.30 | 0.36 | 0.292 | $(5)_{TOTAL}-(5)_{FI}$ 0.554 | 0.293 | 0.85 | 1.00 | 0.248 |

Worksheet 2D -- Multiple-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections

| (1) | (2) | (3) | (4) | (5) | (6) |
|----------------------------------|--|---|---------------------------------------|--|---|
| Collision Type | Proportion of Collision Type _(FI) | Predicted N_{bimv} (FI) (crashes/year) | Proportion of Collision Type (PDO) | Predicted N_{bimv} (PDO) (crashes/year) | Predicted N_{bimv} (TOTAL) (crashes/year) |
| | from Table 12-11 | (9) _{FI} from Worksheet 2C | from Table 12-11 | (9) _{PDO} from Worksheet 2C | (9) _{PDO} from Worksheet 2C |
| Total | 1.000 | 0.200 | 1.000 | 0.248 | 0.449 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Rear-end collision | 0.549 | 0.110 | 0.546 | 0.136 | 0.246 |
| Head-on collision | 0.038 | 0.008 | 0.020 | 0.005 | 0.013 |
| Angle collision | 0.280 | 0.056 | 0.204 | 0.051 | 0.107 |
| Sideswipe | 0.076 | 0.015 | 0.032 | 0.008 | 0.023 |
| Other multiple-vehicle collision | 0.057 | 0.011 | 0.198 | 0.049 | 0.061 |

Worksheet 2E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bisv} | Proportion of Total Crashes | Adjusted N_{bisv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bisv} |
| | from Table 12-12 | | | from Table 12-12 | from Eqn. 12-24; (FI) from Eqn. 12-24 or 12-27 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -9.02 | 0.42 | 0.40 | 0.36 | 0.061 | 1.000 | 0.061 | 0.85 | 1.00 | 0.052 |
| Fatal and Injury (FI) | -9.75 | 0.27 | 0.51 | 0.24 | 0.015 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.240 | 0.015 | 0.85 | 1.00 | 0.012 |
| Property Damage Only (PDO) | -9.08 | 0.45 | 0.33 | 0.53 | 0.049 | $(5)_{TOTAL}-(5)_{FI}$ 0.760 | 0.046 | 0.85 | 1.00 | 0.039 |

| Worksheet 2F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections | | | | | |
|---|--|---|------------------------------------|--|--|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Collision Type | Proportion of Collision Type _(FI) | Predicted N _{bisv (FI)} (crashes/year) | Proportion of Collision Type (PDO) | Predicted N _{bisv (PDO)} (crashes/year) | Predicted N _{bisv (TOTAL)} (crashes/year) |
| | from Table 12-13 | (9) _{FI} from Worksheet 2E | from Table 12-13 | (9) _{PDO} from Worksheet 2E | (9) _{PDO} from Worksheet 2E |
| Total | 1.000 | 0.012 | 1.000 | 0.039 | 0.052 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with parked vehicle | 0.001 | 0.000 | 0.001 | 0.000 | 0.000 |
| Collision with animal | 0.001 | 0.000 | 0.003 | 0.000 | 0.000 |
| Collision with fixed object | 0.653 | 0.008 | 0.895 | 0.035 | 0.043 |
| Collision with other object | 0.091 | 0.001 | 0.069 | 0.003 | 0.004 |
| Other single-vehicle collision | 0.045 | 0.001 | 0.018 | 0.001 | 0.001 |
| Single-vehicle noncollision | 0.209 | 0.003 | 0.014 | 0.001 | 0.003 |

| Worksheet 2G -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Stop-Controlled Intersections | | | | | | |
|---|-----------------------------|-----------------------------|---------------------------|-------------------|------------------------------------|-----------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N _{bimv} | Predicted N _{bisv} | Predicted N _{bi} | f _{pedi} | Calibration factor, C _i | Predicted N _{pedi} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-16 | | (4)*(5)*(6) |
| Total | -- | -- | -- | -- | 1.00 | -- |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | -- |

| Worksheet 2H -- Crash Modification Factors for Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | |
|---|-------------------|--------------------------------------|--------------|
| (1) | (2) | (3) | (4) |
| CMF for Bus Stops | CMF for Schools | CMF for Alcohol Sales Establishments | Combined CMF |
| CMF _{1p} | CMF _{2p} | CMF _{3p} | |
| from Table 12-28 | from Table 12-29 | from Table 12-30 | (1)*(2)*(3) |
| 2.78 | 1.00 | 1.12 | 3.11 |

| Worksheet 2I -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | | | | | | | | |
|--|------------------|------|------|------|------|-----------------------------|----------------------|-----------------------|------------------------------------|-----------------------------|
| (1) | (2) | | | | | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | SPF Coefficients | | | | | Overdispersion Parameter, k | N _{pedbase} | Combined CMF | Calibration factor, C _i | Predicted N _{pedi} |
| | from Table 12-14 | | | | | | from Equation 12-29 | (4) from Worksheet 2H | | (4)*(5)*(6) |
| | a | b | c | d | e | | | | | |
| Total | -6.60 | 0.05 | 0.24 | 0.41 | 0.09 | 0.52 | 0.039 | 3.11 | 1.00 | 0.122 |
| Fatal and Injury (FI) | -- | -- | -- | -- | -- | -- | -- | -- | 1.00 | 0.122 |

| Worksheet 2J -- Vehicle-Bicycle Collisions for Urban and Suburban Arterial Intersections | | | | | | |
|--|-----------------------|-----------------------|--------------------|------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N_{bimv} | Predicted N_{bisv} | Predicted N_{bi} | f_{bikei} | Calibration factor, C_i | Predicted N_{bikei} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-17 | | (4)*(5)*(6) |
| Total | 0.449 | 0.052 | 0.500 | 0.011 | 1.00 | 0.006 |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | 0.006 |

| Worksheet 2K -- Crash Severity Distribution for Urban and Suburban Arterial Intersections | | | |
|---|---|------------------------------|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J | (5) from Worksheet 2D and 2F | (6) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 2D) | 0.110 | 0.136 | 0.246 |
| Head-on collisions (from Worksheet 2D) | 0.008 | 0.005 | 0.013 |
| Angle collisions (from Worksheet 2D) | 0.056 | 0.051 | 0.107 |
| Sideswipe (from Worksheet 2D) | 0.015 | 0.008 | 0.023 |
| Other multiple-vehicle collision (from Worksheet 2D) | 0.011 | 0.049 | 0.061 |
| Subtotal | 0.200 | 0.248 | 0.449 |
| SINGLE-VEHICLE | | | |
| Collision with parked vehicle (from Worksheet 2F) | 0.000 | 0.000 | 0.000 |
| Collision with animal (from Worksheet 2F) | 0.000 | 0.000 | 0.000 |
| Collision with fixed object (from Worksheet 2F) | 0.008 | 0.035 | 0.043 |
| Collision with other object (from Worksheet 2F) | 0.001 | 0.003 | 0.004 |
| Other single-vehicle collision (from Worksheet 2F) | 0.001 | 0.001 | 0.001 |
| Single-vehicle noncollision (from Worksheet 2F) | 0.003 | 0.001 | 0.003 |
| Collision with pedestrian (from Worksheet 2G or 2I) | 0.122 | 0.000 | 0.122 |
| Collision with bicycle (from Worksheet 2J) | 0.006 | 0.000 | 0.006 |
| Subtotal | 0.140 | 0.039 | 0.179 |
| Total | 0.340 | 0.288 | 0.627 |

| Worksheet 2L -- Summary Results for Urban and Suburban Arterial Intersections | |
|---|--|
| (1) | (2) |
| Crash severity level | Predicted average crash frequency, $N_{predicted int}$ (crashes/year) |
| | (Total) from Worksheet 2K |
| Total | 0.6 |
| Fatal and injury (FI) | 0.3 |
| Property damage only (PDO) | 0.3 |

| Worksheet 2A -- General Information and Input Data for Urban and Suburban Arterial Intersections | | | |
|--|--|----------------------|--------------------------------|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | 7th Street and Mandela Parkway |
| Agency or Company | Fehr & Peers | Intersection | Oakland, CA |
| Date Performed | 01/02/19 | Jurisdiction | 2019 |
| | | Analysis Year | |
| Input Data | | Base Conditions | Site Conditions |
| Intersection type (3ST, 3SG, 4ST, 4SG) | | -- | 4SG |
| AADT _{major} (veh/day) | AADT _{MAX} = 67,700 (veh/day) | -- | 8,780 |
| AADT _{minor} (veh/day) | AADT _{MAX} = 33,400 (veh/day) | -- | 7,530 |
| Intersection lighting (present/not present) | | Not Present | Present |
| Calibration factor, C _i | | 1.00 | 1.00 |
| Data for unsignalized intersections only: | | -- | -- |
| Number of major-road approaches with left-turn lanes (0,1,2) | | 0 | |
| Number of major-road approaches with right-turn lanes (0,1,2) | | 0 | |
| Data for signalized intersections only: | | -- | -- |
| Number of approaches with left-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | 3 |
| Number of approaches with right-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | 0 |
| Number of approaches with left-turn signal phasing [for 3SG, use maximum value of 3] | | -- | 2 |
| Type of left-turn signal phasing for Leg #1 | | Permissive | Protected |
| Type of left-turn signal phasing for Leg #2 | | -- | Protected |
| Type of left-turn signal phasing for Leg #3 | | -- | Permissive |
| Type of left-turn signal phasing for Leg #4 (if applicable) | | -- | Permissive |
| Number of approaches with right-turn-on-red prohibited [for 3SG, use maximum value of 3] | | 0 | 0 |
| Intersection red light cameras (present/not present) | | Not Present | Not Present |
| Sum of all pedestrian crossing volumes (PedVol) -- Signalized intersections only | | | 1,660 |
| Maximum number of lanes crossed by a pedestrian (n _{lanesx}) | | -- | 5 |
| Number of bus stops within 300 m (1,000 ft) of the intersection | | 0 | 3 |
| Schools within 300 m (1,000 ft) of the intersection (present/not present) | | Not Present | Not Present |
| Number of alcohol sales establishments within 300 m (1,000 ft) of the intersection | | 0 | 2 |

| Worksheet 2B -- Crash Modification Factors for Urban and Suburban Arterial Intersections | | | | | | |
|--|----------------------------------|--------------------------|---------------------------|-------------------------|---------------------------|---------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| CMF for Left-Turn Lanes | CMF for Left-Turn Signal Phasing | CMF for Right-Turn Lanes | CMF for Right Turn on Red | CMF for Lighting | CMF for Red Light Cameras | Combined CMF |
| <i>CMF_{1i}</i> | <i>CMF_{2i}</i> | <i>CMF_{3i}</i> | <i>CMF_{4i}</i> | <i>CMF_{5i}</i> | <i>CMF_{6i}</i> | <i>CMF_{COMB}</i> |
| from Table 12-24 | from Table 12-25 | from Table 12-26 | from Equation 12-35 | from Equation 12-36 | from Equation 12-37 | (1)*(2)*(3)*(4)*(5)*(6) |
| 0.73 | 0.88 | 1.00 | 1.00 | 0.91 | 1.00 | 0.59 |

Worksheet 2C -- Multiple-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---------------------|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bimv} | Proportion of Total Crashes | Adjusted N_{bimv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bimv} |
| | from Table 12-10 | | | from Table 12-10 | from Equation 12-21 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -10.99 | 1.07 | 0.23 | 0.39 | 2.179 | 1.000 | 2.179 | 0.59 | 1.00 | 1.280 |
| Fatal and Injury (FI) | -13.14 | 1.18 | 0.22 | 0.33 | 0.630 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.300 | 0.655 | 0.59 | 1.00 | 0.384 |
| Property Damage Only (PDO) | -11.02 | 1.02 | 0.24 | 0.44 | 1.468 | $(5)_{TOTAL}-(5)_{FI}$ 0.700 | 1.525 | 0.59 | 1.00 | 0.896 |

Worksheet 2D -- Multiple-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections

| (1) | (2) | (3) | (4) | (5) | (6) |
|----------------------------------|--|--|------------------------------------|---|---|
| Collision Type | Proportion of Collision Type _(FI) | Predicted $N_{bimv (FI)}$ (crashes/year) | Proportion of Collision Type (PDO) | Predicted $N_{bimv (PDO)}$ (crashes/year) | Predicted $N_{bimv (TOTAL)}$ (crashes/year) |
| | from Table 12-11 | (9) _{FI} from Worksheet 2C | from Table 12-11 | (9) _{PDO} from Worksheet 2C | (9) _{PDO} from Worksheet 2C |
| Total | 1.000 | 0.384 | 1.000 | 0.896 | 1.280 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Rear-end collision | 0.450 | 0.173 | 0.483 | 0.433 | 0.606 |
| Head-on collision | 0.049 | 0.019 | 0.030 | 0.027 | 0.046 |
| Angle collision | 0.347 | 0.133 | 0.244 | 0.219 | 0.352 |
| Sideswipe | 0.099 | 0.038 | 0.032 | 0.029 | 0.067 |
| Other multiple-vehicle collision | 0.055 | 0.021 | 0.211 | 0.189 | 0.210 |

Worksheet 2E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|--|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bisv} | Proportion of Total Crashes | Adjusted N_{bisv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bisv} |
| | from Table 12-12 | | | from Table 12-12 | from Eqn. 12-24; (FI) from Eqn. 12-24 or 12-27 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -10.21 | 0.68 | 0.27 | 0.36 | 0.197 | 1.000 | 0.197 | 0.59 | 1.00 | 0.116 |
| Fatal and Injury (FI) | -9.25 | 0.43 | 0.29 | 0.09 | 0.063 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.325 | 0.064 | 0.59 | 1.00 | 0.038 |
| Property Damage Only (PDO) | -11.34 | 0.78 | 0.25 | 0.44 | 0.132 | $(5)_{TOTAL}-(5)_{FI}$ 0.675 | 0.133 | 0.59 | 1.00 | 0.078 |

| Worksheet 2F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections | | | | | |
|---|--|---|------------------------------------|--|--|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Collision Type | Proportion of Collision Type _(FI) | Predicted N _{bisv (FI)} (crashes/year) | Proportion of Collision Type (PDO) | Predicted N _{bisv (PDO)} (crashes/year) | Predicted N _{bisv (TOTAL)} (crashes/year) |
| | from Table 12-13 | (9) _{FI} from Worksheet 2E | from Table 12-13 | (9) _{PDO} from Worksheet 2E | (9) _{PDO} from Worksheet 2E |
| Total | 1.000 | 0.038 | 1.000 | 0.078 | 0.116 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with parked vehicle | 0.001 | 0.000 | 0.001 | 0.000 | 0.000 |
| Collision with animal | 0.002 | 0.000 | 0.002 | 0.000 | 0.000 |
| Collision with fixed object | 0.744 | 0.028 | 0.870 | 0.068 | 0.096 |
| Collision with other object | 0.072 | 0.003 | 0.070 | 0.005 | 0.008 |
| Other single-vehicle collision | 0.040 | 0.002 | 0.023 | 0.002 | 0.003 |
| Single-vehicle noncollision | 0.141 | 0.005 | 0.034 | 0.003 | 0.008 |

| Worksheet 2G -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Stop-Controlled Intersections | | | | | | |
|---|-----------------------------|-----------------------------|---------------------------|-------------------|------------------------------------|-----------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N _{bimv} | Predicted N _{bisv} | Predicted N _{bi} | f _{pedi} | Calibration factor, C _i | Predicted N _{pedi} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-16 | | (4)*(5)*(6) |
| Total | -- | -- | -- | -- | 1.00 | -- |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | -- |

| Worksheet 2H -- Crash Modification Factors for Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | |
|---|-------------------|--------------------------------------|--------------|
| (1) | (2) | (3) | (4) |
| CMF for Bus Stops | CMF for Schools | CMF for Alcohol Sales Establishments | Combined CMF |
| CMF _{1p} | CMF _{2p} | CMF _{3p} | |
| from Table 12-28 | from Table 12-29 | from Table 12-30 | (1)*(2)*(3) |
| 4.15 | 1.00 | 1.12 | 4.65 |

| Worksheet 2I -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | | | | | | | | |
|--|------------------|------|------|------|------|-----------------------------|----------------------|-----------------------|------------------------------------|-----------------------------|
| (1) | (2) | | | | | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | SPF Coefficients | | | | | Overdispersion Parameter, k | N _{pedbase} | Combined CMF | Calibration factor, C _i | Predicted N _{pedi} |
| | from Table 12-14 | | | | | | from Equation 12-29 | (4) from Worksheet 2H | | (4)*(5)*(6) |
| | a | b | c | d | e | | | | | |
| Total | -9.53 | 0.40 | 0.26 | 0.45 | 0.04 | 0.24 | 0.116 | 4.65 | 1.00 | 0.539 |
| Fatal and Injury (FI) | -- | -- | -- | -- | -- | -- | -- | -- | 1.00 | 0.539 |

| Worksheet 2J -- Vehicle-Bicycle Collisions for Urban and Suburban Arterial Intersections | | | | | | |
|--|-----------------------|-----------------------|--------------------|------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N_{bimv} | Predicted N_{bisv} | Predicted N_{bi} | f_{bikei} | Calibration factor, C_i | Predicted N_{bikei} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-17 | | (4)*(5)*(6) |
| Total | 1.280 | 0.116 | 1.396 | 0.015 | 1.00 | 0.021 |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | 0.021 |

| Worksheet 2K -- Crash Severity Distribution for Urban and Suburban Arterial Intersections | | | |
|---|---|------------------------------|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J | (5) from Worksheet 2D and 2F | (6) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 2D) | 0.173 | 0.433 | 0.606 |
| Head-on collisions (from Worksheet 2D) | 0.019 | 0.027 | 0.046 |
| Angle collisions (from Worksheet 2D) | 0.133 | 0.219 | 0.352 |
| Sideswipe (from Worksheet 2D) | 0.038 | 0.029 | 0.067 |
| Other multiple-vehicle collision (from Worksheet 2D) | 0.021 | 0.189 | 0.210 |
| Subtotal | 0.384 | 0.896 | 1.280 |
| SINGLE-VEHICLE | | | |
| Collision with parked vehicle (from Worksheet 2F) | 0.000 | 0.000 | 0.000 |
| Collision with animal (from Worksheet 2F) | 0.000 | 0.000 | 0.000 |
| Collision with fixed object (from Worksheet 2F) | 0.028 | 0.068 | 0.096 |
| Collision with other object (from Worksheet 2F) | 0.003 | 0.005 | 0.008 |
| Other single-vehicle collision (from Worksheet 2F) | 0.002 | 0.002 | 0.003 |
| Single-vehicle noncollision (from Worksheet 2F) | 0.005 | 0.003 | 0.008 |
| Collision with pedestrian (from Worksheet 2G or 2I) | 0.539 | 0.000 | 0.539 |
| Collision with bicycle (from Worksheet 2J) | 0.021 | 0.000 | 0.021 |
| Subtotal | 0.598 | 0.078 | 0.676 |
| Total | 0.982 | 0.974 | 1.956 |

| Worksheet 2L -- Summary Results for Urban and Suburban Arterial Intersections | |
|---|--|
| (1) | (2) |
| Crash severity level | Predicted average crash frequency, $N_{predicted int}$ (crashes/year) |
| | (Total) from Worksheet 2K |
| Total | 2.0 |
| Fatal and injury (FI) | 1.0 |
| Property damage only (PDO) | 1.0 |

Worksheet 2A -- General Information and Input Data for Urban and Suburban Arterial Intersections

| General Information | | Location Information | |
|--|--|----------------------|-------------------------------|
| Analyst | Jordan Brooks | Roadway | 5th Street and Chester Street |
| Agency or Company | Fehr & Peers | Intersection | Oakland, CA |
| Date Performed | 01/02/19 | Jurisdiction | 2019 |
| | | Analysis Year | |
| Input Data | | Base Conditions | Site Conditions |
| Intersection type (3ST, 3SG, 4ST, 4SG) | | -- | 4ST |
| AADT _{major} (veh/day) | AADT _{MAX} = 46,800 (veh/day) | -- | 1,740 |
| AADT _{minor} (veh/day) | AADT _{MAX} = 5,900 (veh/day) | -- | 700 |
| Intersection lighting (present/not present) | | Not Present | Present |
| Calibration factor, C _i | | 1.00 | 1.00 |
| Data for unsignalized intersections only: | | -- | -- |
| Number of major-road approaches with left-turn lanes (0,1,2) | | 0 | 0 |
| Number of major-road approaches with right-turn lanes (0,1,2) | | 0 | 0 |
| Data for signalized intersections only: | | -- | -- |
| Number of approaches with left-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | |
| Number of approaches with right-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | |
| Number of approaches with left-turn signal phasing [for 3SG, use maximum value of 3] | | -- | |
| Type of left-turn signal phasing for Leg #1 | | Permissive | |
| Type of left-turn signal phasing for Leg #2 | | -- | |
| Type of left-turn signal phasing for Leg #3 | | -- | |
| Type of left-turn signal phasing for Leg #4 (if applicable) | | -- | |
| Number of approaches with right-turn-on-red prohibited [for 3SG, use maximum value of 3] | | 0 | |
| Intersection red light cameras (present/not present) | | Not Present | |
| Sum of all pedestrian crossing volumes (PedVol) -- Signalized intersections only | | | |
| Maximum number of lanes crossed by a pedestrian (n _{lanesx}) | | -- | |
| Number of bus stops within 300 m (1,000 ft) of the intersection | | 0 | |
| Schools within 300 m (1,000 ft) of the intersection (present/not present) | | Not Present | |
| Number of alcohol sales establishments within 300 m (1,000 ft) of the intersection | | 0 | |

Worksheet 2B -- Crash Modification Factors for Urban and Suburban Arterial Intersections

| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
|-------------------------|----------------------------------|--------------------------|---------------------------|-------------------------|---------------------------|---------------------------|
| CMF for Left-Turn Lanes | CMF for Left-Turn Signal Phasing | CMF for Right-Turn Lanes | CMF for Right Turn on Red | CMF for Lighting | CMF for Red Light Cameras | Combined CMF |
| <i>CMF_{1i}</i> | <i>CMF_{2i}</i> | <i>CMF_{3i}</i> | <i>CMF_{4i}</i> | <i>CMF_{5i}</i> | <i>CMF_{6i}</i> | <i>CMF_{COMB}</i> |
| from Table 12-24 | from Table 12-25 | from Table 12-26 | from Equation 12-35 | from Equation 12-36 | from Equation 12-37 | (1)*(2)*(3)*(4)*(5)*(6) |
| 1.00 | 1.00 | 1.00 | 1.00 | 0.91 | 0.98 | 0.89 |

Worksheet 2C -- Multiple-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---------------------|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bimv} | Proportion of Total Crashes | Adjusted N_{bimv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bimv} |
| | from Table 12-10 | | | from Table 12-10 | from Equation 12-21 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -8.90 | 0.82 | 0.25 | 0.40 | 0.319 | 1.000 | 0.319 | 0.89 | 1.00 | 0.285 |
| Fatal and Injury (FI) | -11.13 | 0.93 | 0.28 | 0.48 | 0.095 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.296 | 0.094 | 0.89 | 1.00 | 0.084 |
| Property Damage Only (PDO) | -8.74 | 0.77 | 0.23 | 0.40 | 0.226 | $(5)_{TOTAL}-(5)_{FI}$ 0.704 | 0.224 | 0.89 | 1.00 | 0.201 |

Worksheet 2D -- Multiple-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections

| (1) | (2) | (3) | (4) | (5) | (6) |
|----------------------------------|--|--|------------------------------------|---|---|
| Collision Type | Proportion of Collision Type _(FI) | Predicted $N_{bimv (FI)}$ (crashes/year) | Proportion of Collision Type (PDO) | Predicted $N_{bimv (PDO)}$ (crashes/year) | Predicted $N_{bimv (TOTAL)}$ (crashes/year) |
| | from Table 12-11 | (9) _{FI} from Worksheet 2C | from Table 12-11 | (9) _{PDO} from Worksheet 2C | (9) _{PDO} from Worksheet 2C |
| Total | 1.000 | 0.084 | 1.000 | 0.201 | 0.285 |
| | | $(2)*(3)_{FI}$ | | $(4)*(5)_{PDO}$ | $(3)+(5)$ |
| Rear-end collision | 0.338 | 0.028 | 0.374 | 0.075 | 0.103 |
| Head-on collision | 0.041 | 0.003 | 0.030 | 0.006 | 0.009 |
| Angle collision | 0.440 | 0.037 | 0.335 | 0.067 | 0.104 |
| Sideswipe | 0.121 | 0.010 | 0.044 | 0.009 | 0.019 |
| Other multiple-vehicle collision | 0.060 | 0.005 | 0.217 | 0.044 | 0.049 |

Worksheet 2E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|--|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bisv} | Proportion of Total Crashes | Adjusted N_{bisv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bisv} |
| | from Table 12-12 | | | from Table 12-12 | from Eqn. 12-24; (FI) from Eqn. 12-24 or 12-27 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -5.33 | 0.33 | 0.12 | 0.65 | 0.125 | 1.000 | 0.125 | 0.89 | 1.00 | 0.111 |
| Fatal and Injury (FI) | -- | -- | -- | -- | 0.035 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.346 | 0.043 | 0.89 | 1.00 | 0.039 |
| Property Damage Only (PDO) | -7.04 | 0.36 | 0.25 | 0.54 | 0.066 | $(5)_{TOTAL}-(5)_{FI}$ 0.654 | 0.082 | 0.89 | 1.00 | 0.073 |

| Worksheet 2F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections | | | | | |
|---|--|---|------------------------------------|--|--|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Collision Type | Proportion of Collision Type _(FI) | Predicted N _{bisv (FI)} (crashes/year) | Proportion of Collision Type (PDO) | Predicted N _{bisv (PDO)} (crashes/year) | Predicted N _{bisv (TOTAL)} (crashes/year) |
| | from Table 12-13 | (9) _{FI} from Worksheet 2E | from Table 12-13 | (9) _{PDO} from Worksheet 2E | (9) _{PDO} from Worksheet 2E |
| Total | 1.000 | 0.039 | 1.000 | 0.073 | 0.111 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with parked vehicle | 0.001 | 0.000 | 0.001 | 0.000 | 0.000 |
| Collision with animal | 0.001 | 0.000 | 0.026 | 0.002 | 0.002 |
| Collision with fixed object | 0.679 | 0.026 | 0.847 | 0.062 | 0.088 |
| Collision with other object | 0.089 | 0.003 | 0.070 | 0.005 | 0.009 |
| Other single-vehicle collision | 0.051 | 0.002 | 0.007 | 0.001 | 0.002 |
| Single-vehicle noncollision | 0.179 | 0.007 | 0.049 | 0.004 | 0.010 |

| Worksheet 2G -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Stop-Controlled Intersections | | | | | | |
|---|-----------------------------|-----------------------------|---------------------------|-------------------|------------------------------------|-----------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N _{bimv} | Predicted N _{bisv} | Predicted N _{bi} | f _{pedi} | Calibration factor, C _i | Predicted N _{pedi} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-16 | | (4)*(5)*(6) |
| Total | 0.285 | 0.111 | 0.396 | 0.022 | 1.00 | 0.009 |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | 0.009 |

| Worksheet 2H -- Crash Modification Factors for Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | |
|---|-------------------|--------------------------------------|--------------|
| (1) | (2) | (3) | (4) |
| CMF for Bus Stops | CMF for Schools | CMF for Alcohol Sales Establishments | Combined CMF |
| CMF _{1p} | CMF _{2p} | CMF _{3p} | |
| from Table 12-28 | from Table 12-29 | from Table 12-30 | (1)*(2)*(3) |
| -- | -- | -- | -- |

| Worksheet 2I -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | | | | | | | | |
|--|------------------|----|----|----|----|-----------------------------|----------------------|-----------------------|------------------------------------|-----------------------------|
| (1) | (2) | | | | | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | SPF Coefficients | | | | | Overdispersion Parameter, k | N _{pedbase} | Combined CMF | Calibration factor, C _i | Predicted N _{pedi} |
| | from Table 12-14 | | | | | | from Equation 12-29 | (4) from Worksheet 2H | | (4)*(5)*(6) |
| | a | b | c | d | e | | | | | |
| Total | -- | -- | -- | -- | -- | -- | -- | -- | 1.00 | -- |
| Fatal and Injury (FI) | -- | -- | -- | -- | -- | -- | -- | -- | 1.00 | -- |

| Worksheet 2J -- Vehicle-Bicycle Collisions for Urban and Suburban Arterial Intersections | | | | | | |
|--|-----------------------|-----------------------|--------------------|------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N_{bimv} | Predicted N_{bisv} | Predicted N_{bi} | f_{bikei} | Calibration factor, C_i | Predicted N_{bikei} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-17 | | (4)*(5)*(6) |
| Total | 0.285 | 0.111 | 0.396 | 0.018 | 1.00 | 0.007 |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | 0.007 |

| Worksheet 2K -- Crash Severity Distribution for Urban and Suburban Arterial Intersections | | | |
|---|---|------------------------------|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J | (5) from Worksheet 2D and 2F | (6) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 2D) | 0.028 | 0.075 | 0.103 |
| Head-on collisions (from Worksheet 2D) | 0.003 | 0.006 | 0.009 |
| Angle collisions (from Worksheet 2D) | 0.037 | 0.067 | 0.104 |
| Sideswipe (from Worksheet 2D) | 0.010 | 0.009 | 0.019 |
| Other multiple-vehicle collision (from Worksheet 2D) | 0.005 | 0.044 | 0.049 |
| Subtotal | 0.084 | 0.201 | 0.285 |
| SINGLE-VEHICLE | | | |
| Collision with parked vehicle (from Worksheet 2F) | 0.000 | 0.000 | 0.000 |
| Collision with animal (from Worksheet 2F) | 0.000 | 0.002 | 0.002 |
| Collision with fixed object (from Worksheet 2F) | 0.026 | 0.062 | 0.088 |
| Collision with other object (from Worksheet 2F) | 0.003 | 0.005 | 0.009 |
| Other single-vehicle collision (from Worksheet 2F) | 0.002 | 0.001 | 0.002 |
| Single-vehicle noncollision (from Worksheet 2F) | 0.007 | 0.004 | 0.010 |
| Collision with pedestrian (from Worksheet 2G or 2I) | 0.009 | 0.000 | 0.009 |
| Collision with bicycle (from Worksheet 2J) | 0.007 | 0.000 | 0.007 |
| Subtotal | 0.054 | 0.073 | 0.127 |
| Total | 0.139 | 0.273 | 0.412 |

| Worksheet 2L -- Summary Results for Urban and Suburban Arterial Intersections | |
|---|--|
| (1) | (2) |
| Crash severity level | Predicted average crash frequency, $N_{predicted int}$ (crashes/year) |
| | (Total) from Worksheet 2K |
| Total | 0.4 |
| Fatal and injury (FI) | 0.1 |
| Property damage only (PDO) | 0.3 |

| Worksheet 2A -- General Information and Input Data for Urban and Suburban Arterial Intersections | | | |
|--|--|----------------------|------------------------------|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | 5th Street and Center Street |
| Agency or Company | Fehr & Peers | Intersection | Oakland, CA |
| Date Performed | 01/02/19 | Jurisdiction | 2019 |
| | | Analysis Year | |
| Input Data | | Base Conditions | Site Conditions |
| Intersection type (3ST, 3SG, 4ST, 4SG) | | -- | 3ST |
| AADT _{major} (veh/day) | AADT _{MAX} = 45,700 (veh/day) | -- | 3,150 |
| AADT _{minor} (veh/day) | AADT _{MAX} = 9,300 (veh/day) | -- | 200 |
| Intersection lighting (present/not present) | | Not Present | Present |
| Calibration factor, C _i | | 1.00 | 1.00 |
| Data for unsignalized intersections only: | | -- | -- |
| Number of major-road approaches with left-turn lanes (0,1,2) | | 0 | 0 |
| Number of major-road approaches with right-turn lanes (0,1,2) | | 0 | 0 |
| Data for signalized intersections only: | | -- | -- |
| Number of approaches with left-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | |
| Number of approaches with right-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | |
| Number of approaches with left-turn signal phasing [for 3SG, use maximum value of 3] | | -- | |
| Type of left-turn signal phasing for Leg #1 | | Permissive | |
| Type of left-turn signal phasing for Leg #2 | | -- | |
| Type of left-turn signal phasing for Leg #3 | | -- | |
| Type of left-turn signal phasing for Leg #4 (if applicable) | | -- | |
| Number of approaches with right-turn-on-red prohibited [for 3SG, use maximum value of 3] | | 0 | |
| Intersection red light cameras (present/not present) | | Not Present | |
| Sum of all pedestrian crossing volumes (PedVol) -- Signalized intersections only | | | |
| Maximum number of lanes crossed by a pedestrian (n _{lanesx}) | | -- | |
| Number of bus stops within 300 m (1,000 ft) of the intersection | | 0 | |
| Schools within 300 m (1,000 ft) of the intersection (present/not present) | | Not Present | |
| Number of alcohol sales establishments within 300 m (1,000 ft) of the intersection | | 0 | |

| Worksheet 2B -- Crash Modification Factors for Urban and Suburban Arterial Intersections | | | | | | |
|--|----------------------------------|--------------------------|---------------------------|-------------------------|---------------------------|---------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| CMF for Left-Turn Lanes | CMF for Left-Turn Signal Phasing | CMF for Right-Turn Lanes | CMF for Right Turn on Red | CMF for Lighting | CMF for Red Light Cameras | Combined CMF |
| <i>CMF_{1i}</i> | <i>CMF_{2i}</i> | <i>CMF_{3i}</i> | <i>CMF_{4i}</i> | <i>CMF_{5i}</i> | <i>CMF_{6i}</i> | <i>CMF_{COMB}</i> |
| from Table 12-24 | from Table 12-25 | from Table 12-26 | from Equation 12-35 | from Equation 12-36 | from Equation 12-37 | (1)*(2)*(3)*(4)*(5)*(6) |
| 1.00 | 1.00 | 1.00 | 1.00 | 0.91 | 1.00 | 0.91 |

Worksheet 2C -- Multiple-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---------------------|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bimv} | Proportion of Total Crashes | Adjusted N_{bimv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bimv} |
| | from Table 12-10 | | | from Table 12-10 | from Equation 12-21 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -13.36 | 1.11 | 0.41 | 0.80 | 0.106 | 1.000 | 0.106 | 0.91 | 1.00 | 0.096 |
| Fatal and Injury (FI) | -14.01 | 1.16 | 0.30 | 0.69 | 0.046 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.484 | 0.051 | 0.91 | 1.00 | 0.047 |
| Property Damage Only (PDO) | -15.38 | 1.20 | 0.51 | 0.77 | 0.049 | $(5)_{TOTAL}-(5)_{FI}$ 0.516 | 0.055 | 0.91 | 1.00 | 0.050 |

Worksheet 2D -- Multiple-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections

| (1) | (2) | (3) | (4) | (5) | (6) |
|----------------------------------|--|---|---------------------------------------|--|---|
| Collision Type | Proportion of Collision Type _(FI) | Predicted N_{bimv} (FI) (crashes/year) | Proportion of Collision Type (PDO) | Predicted N_{bimv} (PDO) (crashes/year) | Predicted N_{bimv} (TOTAL) (crashes/year) |
| | from Table 12-11 | (9) _{FI} from Worksheet 2C | from Table 12-11 | (9) _{PDO} from Worksheet 2C | (9) _{PDO} from Worksheet 2C |
| Total | 1.000 | 0.047 | 1.000 | 0.050 | 0.096 |
| | | $(2)*(3)_{FI}$ | | $(4)*(5)_{PDO}$ | $(3)+(5)$ |
| Rear-end collision | 0.421 | 0.020 | 0.440 | 0.022 | 0.041 |
| Head-on collision | 0.045 | 0.002 | 0.023 | 0.001 | 0.003 |
| Angle collision | 0.343 | 0.016 | 0.262 | 0.013 | 0.029 |
| Sideswipe | 0.126 | 0.006 | 0.040 | 0.002 | 0.008 |
| Other multiple-vehicle collision | 0.065 | 0.003 | 0.235 | 0.012 | 0.015 |

Worksheet 2E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bisv} | Proportion of Total Crashes | Adjusted N_{bisv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bisv} |
| | from Table 12-12 | | | from Table 12-12 | from Eqn. 12-24; (FI) from Eqn. 12-24 or 12-27 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -6.81 | 0.16 | 0.51 | 1.14 | 0.060 | 1.000 | 0.060 | 0.91 | 1.00 | 0.054 |
| Fatal and Injury (FI) | -- | -- | -- | -- | 0.018 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.364 | 0.022 | 0.91 | 1.00 | 0.020 |
| Property Damage Only (PDO) | -8.36 | 0.25 | 0.55 | 1.29 | 0.032 | $(5)_{TOTAL}-(5)_{FI}$ 0.636 | 0.038 | 0.91 | 1.00 | 0.034 |

| Worksheet 2F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections | | | | | |
|---|--|---|------------------------------------|--|--|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Collision Type | Proportion of Collision Type _(FI) | Predicted N _{bisv (FI)} (crashes/year) | Proportion of Collision Type (PDO) | Predicted N _{bisv (PDO)} (crashes/year) | Predicted N _{bisv (TOTAL)} (crashes/year) |
| | from Table 12-13 | (9) _{FI} from Worksheet 2E | from Table 12-13 | (9) _{PDO} from Worksheet 2E | (9) _{PDO} from Worksheet 2E |
| Total | 1.000 | 0.020 | 1.000 | 0.034 | 0.054 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with parked vehicle | 0.001 | 0.000 | 0.003 | 0.000 | 0.000 |
| Collision with animal | 0.003 | 0.000 | 0.018 | 0.001 | 0.001 |
| Collision with fixed object | 0.762 | 0.015 | 0.834 | 0.029 | 0.044 |
| Collision with other object | 0.090 | 0.002 | 0.092 | 0.003 | 0.005 |
| Other single-vehicle collision | 0.039 | 0.001 | 0.023 | 0.001 | 0.002 |
| Single-vehicle noncollision | 0.105 | 0.002 | 0.030 | 0.001 | 0.003 |

| Worksheet 2G -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Stop-Controlled Intersections | | | | | | |
|---|-----------------------------|-----------------------------|---------------------------|-------------------|------------------------------------|-----------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N _{bimv} | Predicted N _{bisv} | Predicted N _{bi} | f _{pedi} | Calibration factor, C _i | Predicted N _{pedi} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-16 | | (4)*(5)*(6) |
| Total | 0.096 | 0.054 | 0.150 | 0.021 | 1.00 | 0.003 |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | 0.003 |

| Worksheet 2H -- Crash Modification Factors for Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | |
|---|-------------------|--------------------------------------|--------------|
| (1) | (2) | (3) | (4) |
| CMF for Bus Stops | CMF for Schools | CMF for Alcohol Sales Establishments | Combined CMF |
| CMF _{1p} | CMF _{2p} | CMF _{3p} | |
| from Table 12-28 | from Table 12-29 | from Table 12-30 | (1)*(2)*(3) |
| -- | -- | -- | -- |

| Worksheet 2I -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | | | | | | | | |
|--|------------------|----|----|----|----|-----------------------------|----------------------|-----------------------|------------------------------------|-----------------------------|
| (1) | (2) | | | | | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | SPF Coefficients | | | | | Overdispersion Parameter, k | N _{pedbase} | Combined CMF | Calibration factor, C _i | Predicted N _{pedi} |
| | from Table 12-14 | | | | | | from Equation 12-29 | (4) from Worksheet 2H | | (4)*(5)*(6) |
| | a | b | c | d | e | | | | | |
| Total | -- | -- | -- | -- | -- | -- | -- | -- | 1.00 | -- |
| Fatal and Injury (FI) | -- | -- | -- | -- | -- | -- | -- | -- | 1.00 | -- |

| Worksheet 2J -- Vehicle-Bicycle Collisions for Urban and Suburban Arterial Intersections | | | | | | |
|--|-----------------------|-----------------------|--------------------|------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N_{bimv} | Predicted N_{bisv} | Predicted N_{bi} | f_{bikei} | Calibration factor, C_i | Predicted N_{bikei} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-17 | | (4)*(5)*(6) |
| Total | 0.096 | 0.054 | 0.150 | 0.016 | 1.00 | 0.002 |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | 0.002 |

| Worksheet 2K -- Crash Severity Distribution for Urban and Suburban Arterial Intersections | | | |
|---|---|------------------------------|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J | (5) from Worksheet 2D and 2F | (6) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 2D) | 0.020 | 0.022 | 0.041 |
| Head-on collisions (from Worksheet 2D) | 0.002 | 0.001 | 0.003 |
| Angle collisions (from Worksheet 2D) | 0.016 | 0.013 | 0.029 |
| Sideswipe (from Worksheet 2D) | 0.006 | 0.002 | 0.008 |
| Other multiple-vehicle collision (from Worksheet 2D) | 0.003 | 0.012 | 0.015 |
| Subtotal | 0.047 | 0.050 | 0.096 |
| SINGLE-VEHICLE | | | |
| Collision with parked vehicle (from Worksheet 2F) | 0.000 | 0.000 | 0.000 |
| Collision with animal (from Worksheet 2F) | 0.000 | 0.001 | 0.001 |
| Collision with fixed object (from Worksheet 2F) | 0.015 | 0.029 | 0.044 |
| Collision with other object (from Worksheet 2F) | 0.002 | 0.003 | 0.005 |
| Other single-vehicle collision (from Worksheet 2F) | 0.001 | 0.001 | 0.002 |
| Single-vehicle noncollision (from Worksheet 2F) | 0.002 | 0.001 | 0.003 |
| Collision with pedestrian (from Worksheet 2G or 2I) | 0.003 | 0.000 | 0.003 |
| Collision with bicycle (from Worksheet 2J) | 0.002 | 0.000 | 0.002 |
| Subtotal | 0.025 | 0.035 | 0.060 |
| Total | 0.072 | 0.084 | 0.156 |

| Worksheet 2L -- Summary Results for Urban and Suburban Arterial Intersections | |
|---|--|
| (1) | (2) |
| Crash severity level | Predicted average crash frequency, $N_{predicted int}$ (crashes/year) |
| | (Total) from Worksheet 2K |
| Total | 0.2 |
| Fatal and injury (FI) | 0.1 |
| Property damage only (PDO) | 0.1 |

| Worksheet 2A -- General Information and Input Data for Urban and Suburban Arterial Intersections | | | |
|--|--|----------------------|--------------------------------|
| General Information | | Location Information | |
| Analyst | Jordan Brooks | Roadway | 5th Street and Mandela Parkway |
| Agency or Company | Fehr & Peers | Intersection | Oakland, CA |
| Date Performed | 01/02/19 | Jurisdiction | 2019 |
| | | Analysis Year | |
| Input Data | | Base Conditions | Site Conditions |
| Intersection type (3ST, 3SG, 4ST, 4SG) | | -- | 4SG |
| AADT _{major} (veh/day) | AADT _{MAX} = 67,700 (veh/day) | -- | 4,740 |
| AADT _{minor} (veh/day) | AADT _{MAX} = 33,400 (veh/day) | -- | 3,820 |
| Intersection lighting (present/not present) | | Not Present | Present |
| Calibration factor, C _i | | 1.00 | 1.00 |
| Data for unsignalized intersections only: | | -- | -- |
| Number of major-road approaches with left-turn lanes (0,1,2) | | 0 | |
| Number of major-road approaches with right-turn lanes (0,1,2) | | 0 | |
| Data for signalized intersections only: | | -- | -- |
| Number of approaches with left-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | 0 |
| Number of approaches with right-turn lanes (0,1,2,3,4) [for 3SG, use maximum value of 3] | | 0 | 0 |
| Number of approaches with left-turn signal phasing [for 3SG, use maximum value of 3] | | -- | 0 |
| Type of left-turn signal phasing for Leg #1 | | Permissive | Permissive |
| Type of left-turn signal phasing for Leg #2 | | -- | Permissive |
| Type of left-turn signal phasing for Leg #3 | | -- | Permissive |
| Type of left-turn signal phasing for Leg #4 (if applicable) | | -- | Permissive |
| Number of approaches with right-turn-on-red prohibited [for 3SG, use maximum value of 3] | | 0 | 0 |
| Intersection red light cameras (present/not present) | | Not Present | Not Present |
| Sum of all pedestrian crossing volumes (PedVol) -- Signalized intersections only | | | 2,850 |
| Maximum number of lanes crossed by a pedestrian (n _{lanesx}) | | -- | 2 |
| Number of bus stops within 300 m (1,000 ft) of the intersection | | 0 | 2 |
| Schools within 300 m (1,000 ft) of the intersection (present/not present) | | Not Present | Not Present |
| Number of alcohol sales establishments within 300 m (1,000 ft) of the intersection | | 0 | 2 |

| Worksheet 2B -- Crash Modification Factors for Urban and Suburban Arterial Intersections | | | | | | |
|--|----------------------------------|--------------------------|---------------------------|---------------------|---------------------------|-------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| CMF for Left-Turn Lanes | CMF for Left-Turn Signal Phasing | CMF for Right-Turn Lanes | CMF for Right Turn on Red | CMF for Lighting | CMF for Red Light Cameras | Combined CMF |
| CMF _{1i} | CMF _{2i} | CMF _{3i} | CMF _{4i} | CMF _{5i} | CMF _{6i} | CMF _{COMB} |
| from Table 12-24 | from Table 12-25 | from Table 12-26 | from Equation 12-35 | from Equation 12-36 | from Equation 12-37 | (1)*(2)*(3)*(4)*(5)*(6) |
| 1.00 | 1.00 | 1.00 | 1.00 | 0.91 | 1.00 | 0.91 |

Worksheet 2C -- Multiple-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---------------------|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bimv} | Proportion of Total Crashes | Adjusted N_{bimv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bimv} |
| | from Table 12-10 | | | from Table 12-10 | from Equation 12-21 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -10.99 | 1.07 | 0.23 | 0.39 | 0.964 | 1.000 | 0.964 | 0.91 | 1.00 | 0.878 |
| Fatal and Injury (FI) | -13.14 | 1.18 | 0.22 | 0.33 | 0.262 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.283 | 0.273 | 0.91 | 1.00 | 0.248 |
| Property Damage Only (PDO) | -11.02 | 1.02 | 0.24 | 0.44 | 0.665 | $(5)_{TOTAL}-(5)_{FI}$ 0.717 | 0.691 | 0.91 | 1.00 | 0.630 |

Worksheet 2D -- Multiple-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections

| (1) | (2) | (3) | (4) | (5) | (6) |
|----------------------------------|--|---|---------------------------------------|--|---|
| Collision Type | Proportion of Collision Type _(FI) | Predicted N_{bimv} (FI) (crashes/year) | Proportion of Collision Type (PDO) | Predicted N_{bimv} (PDO) (crashes/year) | Predicted N_{bimv} (TOTAL) (crashes/year) |
| | from Table 12-11 | (9) _{FI} from Worksheet 2C | from Table 12-11 | (9) _{PDO} from Worksheet 2C | (9) _{PDO} from Worksheet 2C |
| Total | 1.000 | 0.248 | 1.000 | 0.630 | 0.878 |
| | | $(2)*(3)_{FI}$ | | $(4)*(5)_{PDO}$ | $(3)+(5)$ |
| Rear-end collision | 0.450 | 0.112 | 0.483 | 0.304 | 0.416 |
| Head-on collision | 0.049 | 0.012 | 0.030 | 0.019 | 0.031 |
| Angle collision | 0.347 | 0.086 | 0.244 | 0.154 | 0.240 |
| Sideswipe | 0.099 | 0.025 | 0.032 | 0.020 | 0.045 |
| Other multiple-vehicle collision | 0.055 | 0.014 | 0.211 | 0.133 | 0.147 |

Worksheet 2E -- Single-Vehicle Collisions by Severity Level for Urban and Suburban Arterial Intersections

| (1) | (2) | | | (3) | (4) | (5) | (6) | (7) | (8) | (9) |
|----------------------------|------------------|------|------|-----------------------------|---|--|---------------------------|--|---------------------------|----------------------|
| Crash Severity Level | SPF Coefficients | | | Overdispersion Parameter, k | Initial N_{bisv} | Proportion of Total Crashes | Adjusted N_{bisv} | Combined CMFs (7) from Worksheet 2B | Calibration Factor, C_i | Predicted N_{bisv} |
| | from Table 12-12 | | | from Table 12-12 | from Eqn. 12-24; (FI) from Eqn. 12-24 or 12-27 | | (4) _{TOTAL} *(5) | | | (6)*(7)*(8) |
| | a | b | c | | | | | | | |
| Total | -10.21 | 0.68 | 0.27 | 0.36 | 0.108 | 1.000 | 0.108 | 0.91 | 1.00 | 0.098 |
| Fatal and Injury (FI) | -9.25 | 0.43 | 0.29 | 0.09 | 0.040 | $(4)_{FI}/((4)_{FI}+(4)_{PDO})$ 0.368 | 0.040 | 0.91 | 1.00 | 0.036 |
| Property Damage Only (PDO) | -11.34 | 0.78 | 0.25 | 0.44 | 0.069 | $(5)_{TOTAL}-(5)_{FI}$ 0.632 | 0.068 | 0.91 | 1.00 | 0.062 |

| Worksheet 2F -- Single-Vehicle Collisions by Collision Type for Urban and Suburban Arterial Intersections | | | | | |
|---|--|---|------------------------------------|--|--|
| (1) | (2) | (3) | (4) | (5) | (6) |
| Collision Type | Proportion of Collision Type _(FI) | Predicted N _{bisv (FI)} (crashes/year) | Proportion of Collision Type (PDO) | Predicted N _{bisv (PDO)} (crashes/year) | Predicted N _{bisv (TOTAL)} (crashes/year) |
| | from Table 12-13 | (9) _{FI} from Worksheet 2E | from Table 12-13 | (9) _{PDO} from Worksheet 2E | (9) _{PDO} from Worksheet 2E |
| Total | 1.000 | 0.036 | 1.000 | 0.062 | 0.098 |
| | | (2)*(3) _{FI} | | (4)*(5) _{PDO} | (3)+(5) |
| Collision with parked vehicle | 0.001 | 0.000 | 0.001 | 0.000 | 0.000 |
| Collision with animal | 0.002 | 0.000 | 0.002 | 0.000 | 0.000 |
| Collision with fixed object | 0.744 | 0.027 | 0.870 | 0.054 | 0.081 |
| Collision with other object | 0.072 | 0.003 | 0.070 | 0.004 | 0.007 |
| Other single-vehicle collision | 0.040 | 0.001 | 0.023 | 0.001 | 0.003 |
| Single-vehicle noncollision | 0.141 | 0.005 | 0.034 | 0.002 | 0.007 |

| Worksheet 2G -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Stop-Controlled Intersections | | | | | | |
|---|-----------------------------|-----------------------------|---------------------------|-------------------|------------------------------------|-----------------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N _{bimv} | Predicted N _{bisv} | Predicted N _{bi} | f _{pedi} | Calibration factor, C _i | Predicted N _{pedi} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-16 | | (4)*(5)*(6) |
| Total | -- | -- | -- | -- | 1.00 | -- |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | -- |

| Worksheet 2H -- Crash Modification Factors for Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | |
|---|-------------------|--------------------------------------|--------------|
| (1) | (2) | (3) | (4) |
| CMF for Bus Stops | CMF for Schools | CMF for Alcohol Sales Establishments | Combined CMF |
| CMF _{1p} | CMF _{2p} | CMF _{3p} | |
| from Table 12-28 | from Table 12-29 | from Table 12-30 | (1)*(2)*(3) |
| 2.78 | 1.00 | 1.12 | 3.11 |

| Worksheet 2I -- Vehicle-Pedestrian Collisions for Urban and Suburban Arterial Signalized Intersections | | | | | | | | | | |
|--|------------------|------|------|------|------|-----------------------------|----------------------|-----------------------|------------------------------------|-----------------------------|
| (1) | (2) | | | | | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | SPF Coefficients | | | | | Overdispersion Parameter, k | N _{pedbase} | Combined CMF | Calibration factor, C _i | Predicted N _{pedi} |
| | from Table 12-14 | | | | | | from Equation 12-29 | (4) from Worksheet 2H | | (4)*(5)*(6) |
| | a | b | c | d | e | | | | | |
| Total | -9.53 | 0.40 | 0.26 | 0.45 | 0.04 | 0.24 | 0.100 | 3.11 | 1.00 | 0.311 |
| Fatal and Injury (FI) | -- | -- | -- | -- | -- | -- | -- | -- | 1.00 | 0.311 |

| Worksheet 2J -- Vehicle-Bicycle Collisions for Urban and Suburban Arterial Intersections | | | | | | |
|--|-----------------------|-----------------------|--------------------|------------------|---------------------------|-----------------------|
| (1) | (2) | (3) | (4) | (5) | (6) | (7) |
| Crash Severity Level | Predicted N_{bimv} | Predicted N_{bisv} | Predicted N_{bi} | f_{bikei} | Calibration factor, C_i | Predicted N_{bikei} |
| | (9) from Worksheet 2C | (9) from Worksheet 2E | (2) + (3) | from Table 12-17 | | (4)*(5)*(6) |
| Total | 0.878 | 0.098 | 0.976 | 0.015 | 1.00 | 0.015 |
| Fatal and injury (FI) | -- | -- | -- | -- | 1.00 | 0.015 |

| Worksheet 2K -- Crash Severity Distribution for Urban and Suburban Arterial Intersections | | | |
|---|---|------------------------------|---|
| (1) | (2) | (3) | (4) |
| Collision type | Fatal and injury (FI) | Property damage only (PDO) | Total |
| | (3) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J | (5) from Worksheet 2D and 2F | (6) from Worksheet 2D and 2F; (7) from 2G or 2I and 2J |
| MULTIPLE-VEHICLE | | | |
| Rear-end collisions (from Worksheet 2D) | 0.112 | 0.304 | 0.416 |
| Head-on collisions (from Worksheet 2D) | 0.012 | 0.019 | 0.031 |
| Angle collisions (from Worksheet 2D) | 0.086 | 0.154 | 0.240 |
| Sideswipe (from Worksheet 2D) | 0.025 | 0.020 | 0.045 |
| Other multiple-vehicle collision (from Worksheet 2D) | 0.014 | 0.133 | 0.147 |
| Subtotal | 0.248 | 0.630 | 0.878 |
| SINGLE-VEHICLE | | | |
| Collision with parked vehicle (from Worksheet 2F) | 0.000 | 0.000 | 0.000 |
| Collision with animal (from Worksheet 2F) | 0.000 | 0.000 | 0.000 |
| Collision with fixed object (from Worksheet 2F) | 0.027 | 0.054 | 0.081 |
| Collision with other object (from Worksheet 2F) | 0.003 | 0.004 | 0.007 |
| Other single-vehicle collision (from Worksheet 2F) | 0.001 | 0.001 | 0.003 |
| Single-vehicle noncollision (from Worksheet 2F) | 0.005 | 0.002 | 0.007 |
| Collision with pedestrian (from Worksheet 2G or 2I) | 0.311 | 0.000 | 0.311 |
| Collision with bicycle (from Worksheet 2J) | 0.015 | 0.000 | 0.015 |
| Subtotal | 0.362 | 0.062 | 0.424 |
| Total | 0.610 | 0.692 | 1.301 |

| Worksheet 2L -- Summary Results for Urban and Suburban Arterial Intersections | |
|---|--|
| (1) | (2) |
| Crash severity level | Predicted average crash frequency, $N_{predicted int}$ (crashes/year) |
| | (Total) from Worksheet 2K |
| Total | 1.3 |
| Fatal and injury (FI) | 0.6 |
| Property damage only (PDO) | 0.7 |



MEMORANDUM

Date: January 29, 2019
To: Rebecca Auld, Lamphier-Gregory
From: Sam Tabibnia and Jordan Brooks, Fehr & Peers
Subject: **West Oakland BART TOD – Transportation and Parking Demand Management Plan**

OK18-0294

The proposed West Oakland BART TOD project is required to prepare a Transportation and Parking Demand Management (TDM) Plan per the *City of Oakland's Transportation Impact Review Guidelines* and the City's Standard Conditions of Approval because the project would generate more than 50 net new peak hour trips. Since the project would generate more than 100 net new peak hour trips, the goal of the TDM Plan is to achieve a 20 percent vehicle trip reduction (VTR). This memorandum describes the project and its setting, lists the mandatory TDM strategies that the project shall implement to achieve the 20 percent VTR, provides the additional strategies that should be considered if the 20 percent VTR is not achieved, and describes the monitoring, evaluation, and enforcement of the TDM Plan.

PROJECT DESCRIPTION

The proposed project would be located adjacent to the West Oakland BART station, bounded by 7th Street to the north, Mandela Parkway to the east, 5th Street to the south, and Chester Street to the west. The project would consist of four buildings that would include:

- 762 multi-family dwelling units
- approximately 382,000 square feet of office space
- approximately 75,000 square feet of ground-level commercial space

The project would also include 400 automobile parking spaces in a garage accessible via a driveway on Chester Street.



The project site is currently occupied by surface parking lots that provide 413 parking spaces for the West Oakland BART station, which the project would eliminate.

The following infrastructure improvements in the project vicinity are assumed to be part of the project because they are shown on the project site plan:

- Raised one-way Class 4 separated bikeways on both sides of 7th Street between Chester Street and Mandela Parkway.
- One-way Class 4 separated bikeways on both sides of Mandela Parkway between 7th and 5th Streets.
- A bike station on the east side of the existing BART station under the BART tracks and adjacent to a mid-block crossing on Mandela Parkway. The bike station is estimated to accommodate at least 500 bicycles, and would provide a repair station.
- The project proposes a 19-foot sidewalk along the project frontage on 5th Street, between Chester Street and Mandela Parkway. The sidewalk would have a minimum eight-foot pedestrian through zone, and the sidewalk width would accommodate the needs of pedestrians, bus passengers, and curbside passenger loading.
- The project proposes a sidewalk along the project frontage on 7th Street with a minimum eight-foot pedestrian through zone between Chester Street and Mandela Parkway. The sidewalk would provide adequate width to accommodate the high level of pedestrians with pedestrian amenities such as seating, real-time bus arrival information, trash receptacles, and pedestrian-lighting.
- The project proposes an 11 to 15-foot sidewalk along the project frontage on Chester Street and a 15-foot sidewalk along Mandela Parkway between 5th and 7th Street. All sidewalks would have a minimum eight-foot pedestrian through zone.
- As part of implementing a Class 4 cycletrack along westbound 7th Street, the project would eliminate the second receiving lane west of Mandela Parkway and shorten the pedestrian crossing distance for the west crosswalk at the 7th Street/Mandela Parkway intersection.
- The sidewalks along the project frontage and the internal pedestrian plazas would provide pedestrian-scale lighting and street trees/plantings.
- At the intersections of 5th Street with Chester Street, Center Street and Mandela Parkway, the project would provide high-visibility crosswalks, and directional ramps along all approaches.
- At the 5th Street/Center Street intersection, project would provide curb extensions (bulb-outs) at all four intersection corners.



- High-visibility, mid-block pedestrian crossing would be provided on Mandela Parkway between 5th and 7th Streets to align with the east-west pedestrian path within the project site. The midblock crossing would also allow access between the bike station and the northbound Class 4 cycletrack on Mandela Parkway.
- The project would provide a bus stop/layover zone along the project frontage on 5th Street just west of Mandela Parkway. The bus zone would be at least 170 feet long and a concrete bus pad would also be installed in the roadway. The bus stop and layover for AC Transit Lines 36 and 62 could be relocated to this location.
- The existing bus stop on eastbound 7th Street west of Mandel Parkway would be retained and extended for an approximate length of 270 feet. This stop could serve AC Transit Lines 29, 36, and 62 and could serve as both a stop and layover space for AC Transit Line 14. The bus stop would be located on a 10-foot bus island that separates the Class 4 cycletrack along this segment of 7th Street.
- A new bus stop would be installed on westbound 7th Street just west of Center Street that could serve AC Transit Line 29. The bus stop would be about 130 feet long. The bus stop would be located on a 10-foot bus island that separates the Class 4 cycletrack along this segment of 7th Street.
- The sidewalks along project frontage on 5th and 7th Street would have adequate width and would accommodate a high level of passenger amenities, including shelters with seating, maps and other information, and real-time bus arrival information; trash receptacles; and lighting. In addition, the roadway pavement would be upgraded to provide concrete pads for the bus stops.
- To facilitate buses turning from northbound Chester Street to eastbound 7th Street, Chester Street is redesigned so that buses are positioned closer to the center line of Chester Street, which would improve current conditions for buses. Due to the tight turning radius of the corner, buses cannot make the turn from Chester Street to 7th Street when positioned close to the curb on northbound Chester Street.
- The following would be designated for passenger loading and unloading:
 - Approximately 100 feet of linear curb along the north side of 5th street east of Center Street and about 200 feet west of Center Street
 - Approximately 250 feet of linear curb along the south side of 7th Street between Chester and Center Streets, with about 50 feet of curb on eastbound 7th Street just west of Center Street designated as a blue accessible loading zone.
- Parking would be prohibited at the following locations:
 - On the west side of Mandela Parkway between 5th and 7th Street



- On the east side of Chester Street between 5th and 7th Streets and on the west side of Chester Street between the mid-block crossing and 7th Street.

PROJECT LOCATION

The project is located in a moderately dense area with streets generally laid out in a grid and sidewalks on most streets. It is located near some existing neighborhood-serving retail and industrial uses, and there are several proposed projects in the area that would increase residential density and provide neighborhood-serving retail uses. Additionally, the project is located within two miles of Downtown Oakland, a dense employment center.

The project is adjacent to the West Oakland BART Station, which is served by four BART lines and four AC Transit local bus lines. AC Transit Lines 14 and 62 have 15-minute peak headways, while Line 29 has 20-minute peak headways, and Line 36 has 30-minute peak headways. The Line 800 overnight bus also operates adjacent to the project site. No major changes to the bus routes operating near the project site are planned, though the project would involve relocating the bus stops within the site to the adjacent streets.

The project's proximity to regional transit and dense employment centers is likely to result in relatively high rates of walking, bicycling and transit use by residents and visitors. This is evidenced in part by the travel patterns of the area's existing residents. Based on US Census data, **Table 1** summarizes the transportation mode split for employed residents' journey to work for the census tracts in the project vicinity. About 46 percent of employed residents report driving alone to work. A high proportion of residents, approximately 29 percent, used public transportation to travel to work. The proportion of residents who walk or bike to work was also relatively high, with 12 percent reporting walking or biking to work. **Table 2** summarizes vehicle ownership for renter households for the census tracts in the project vicinity. About 38 percent of renter households near the project do not own vehicles, and the average automobile ownership is about 0.8 vehicles per renter household.

The number of automobile trips generated by the project is estimated to be slightly more than half the trips generated by a typical suburban residential development, as shown in **Table 3**. The project would also be expected to generate a vehicle-miles traveled (VMT) per resident that is about 83 percent of the regional VMT per worker, as the residential VMT per capita in the project TAZ is 12.5, compared to the regional average of 15.0, as documented in the Project CEQA Analysis document.



**TABLE 1
 JOURNEY TO WORK FOR EMPLOYED RESIDENTS**

| Transportation Mode | Percent of Households with Employed Residents |
|----------------------------|--|
| Drove Alone | 46% |
| Carpooled | 5% |
| Public transportation | 29% |
| Motorcycle | 2% |
| Bicycle | 7% |
| Walked | 5% |
| Other | 6% |
| Total | 100% |

Source: U.S. Census Bureau, 2012-2016 American Community Survey 5-Year Estimates, Census Tracts 4018, 4022, 4024, 4025, and 4105, Table B08006.

**TABLE 2
 VEHICLE OWNERSHIP FOR EMPLOYED RESIDENTS**

| Vehicles Available | Percent of Renter Households with Employed Residents |
|---------------------------|---|
| No vehicle available | 38% |
| 1 vehicle available | 46% |
| 2 vehicles available | 14% |
| 3+ vehicles available | 2% |
| Total | 100% |

Source: U.S. Census Bureau, 2012-2016 American Community Survey 5-Year Estimates, Census Tracts 4018, 4022, 4024, 4025, and 4105, Table B08203.



TABLE 3
WEST OAKLAND BART TOD PROJECT TRIP GENERATION BY TRAVEL MODE¹

| Mode | Mode Share Adjustment Factors ² | Daily | AM Peak Hour | PM Peak Hour |
|--------------------|--|---------------|--------------|--------------|
| Automobile | 53.1% | 6,650 | 472 | 628 |
| Transit | 29.7% | 3,720 | 264 | 351 |
| Bike | 5.1% | 640 | 45 | 60 |
| Walk | 10.5% | 1,310 | 93 | 124 |
| Total Trips | | 12,320 | 874 | 1,163 |

Notes:

1. See West Oakland BART TOD – Transportation Assessment (non-CEQA) Memorandum for detailed assumptions and calculations.
2. Based on *City of Oakland Transportation Impact Study Guidelines* assuming project site is in an urban environment less than 0.5 miles from a BART station.

Source: Fehr & Peers, 2019.

MANDATORY TDM STRATEGIES

This section describes the mandatory strategies that shall be implemented as part of the project. These strategies shall be directly implemented by the project applicant and building management. **Table 4** describes all mandatory TDM strategies that apply to the project, as well as the effectiveness of each strategy based on research compiled in *Quantifying Greenhouse Gas Mitigation Measures* (California Air Pollution Control Officers Association (CAPCOA), August 2010). The CAPCOA report is a resource for local agencies to quantify the benefit, in terms of reduced travel demand, of implementing various TDM strategies.

The City of Oakland Standard Conditions of Approval lists infrastructure and operational strategies that must be incorporated into a TDM plan based on project location and other characteristics. **Appendix A** presents these strategies and indicates if and how they apply to the proposed project.



**TABLE 4
 MANDATORY TDM PROGRAM COMPONENTS**

| TDM Strategy | Description | Estimated Vehicle Trip Reduction ¹ | |
|---|--|---|-----------------|
| | | Residents | Workers |
| Infrastructure Improvements | Various improvements | -- ³ | -- ³ |
| Limited Residential Parking Supply | Project would provide a maximum of 0.5 parking spaces per unit, compared to average vehicle ownership of 0.8 in the surrounding neighborhood | 8 – 15% ² | N/A |
| Unbundled Parking | Parking spaces leased separately from unit rent | | |
| No or Minimal Parking for Office/Commercial Uses | No or minimal parking is provided for the office or commercial uses | N/A | 10 – 15% |
| Commercial Parking Management | No monthly permits and market-rate parking rates | | |
| Carshare Parking Spaces | Dedicated on-site carshare parking spaces | <1% | <1% |
| Guaranteed Ride Home | Promotion of and enrollment of employees in Alameda County's Guaranteed Ride Home program | N/A | -- ³ |
| Bicycle Parking Supply and Monitoring | Provide bicycle parking above the minimum requirement and monitor usage of the bicycle parking facilities | <1% | <1% |
| Transit Operations | Contribute to AC Transit service enhancement | N/A | N/A |
| Transit Fare Subsidy | Provide transit subsidy to residents and employees ⁴ | 5 – 10% | 10 – 15% |
| Pre-Tax Commuter Benefit | Enroll in a service to assist with employees deducting transit passes using pre-tax income | N/A | -- ³ |
| TDM Marketing and Education | Active marketing of carpooling, BART, AC Transit, bikesharing, and other non-auto modes | -- ³ | 1% |
| On-Site TDM Coordinator | Coordinator responsible for implementing and managing the TDM Plan | | |
| Component Estimated Vehicle Trip Reduction | | 13 – 25% | 21 – 31% |
| Percent of Total Trip Generation | | 44% | 56% |



Total Estimated Vehicle Trip Generation

17 – 28%

Notes:

1. The focus of the CAPCOA document is reductions to VMT but the research used to generate the reductions also indicates vehicle trip reductions are applicable as well. For the purposes of this analysis the VTR is assumed to equal the VMT reduction. See the cited CAPCOA research for more information and related information on page 8 of the BAAQMD *Transportation Demand Management Tool User's Guide* (June 2012).
2. CAPCOA document suggest that limited parking supply combined with unbundled parking can result in up to 20% VTR. However, the CAPCOA results assume minimal other parking facilities in the area. Thus, the CAPCOA-based results are adjusted because some free unrestricted on-street parking is available in the project area.
3. The effectiveness of this strategy cannot be quantified at this time. This does not necessarily imply that the strategy is ineffective. It only demonstrates that at the time of the CAPCOA report development, existing literature did not provide a robust methodology for calculating its effectiveness. In addition, many strategies are complementary to each other and isolating their specific effectiveness may not be feasible.
4. Assuming a subsidy of about \$1.50 per unit and per employee per day available to all residents and employees.

Source: Fehr & Peers, 2019.

The mandatory operational strategies in Table 4 are generally targeted at project residents and employees. While some of the mandatory operational strategies would also affect the travel behavior of retail customers and residential and office visitors, these groups are not directly targeted with TDM programs. The majority of the retail customers would likely be local residents and workers who would walk or bike to the site, and most residential and office visitors would visit the project too infrequently to be aware of the TDM benefits or to make them cost effective. The TDM program also includes infrastructure improvements that would benefit all site residents, employees, and visitors, as well residents, employees, and visitors in the surrounding areas, and BART riders at the West Oakland BART Station.

The VTR estimates in Table 4 represent conservative assumptions about potential trip reduction at the low end of the range. Due to the project's location in an area with very good transit, bicycle, and pedestrian access, it is expected that the high end of the VTR range would be achieved with this TDM program.

The TDM strategies include both one-time physical improvements and on-going operational strategies. Physical improvements will be constructed as part of the project and are therefore anticipated to have a one-time capital cost. Some level of ongoing maintenance cost may also be required for certain improvements. Operational strategies provide on-going incentives and support for the use of non-auto transportation modes. These TDM measures have monthly or annual costs and will require on-going management. A more detailed description of the TDM measures that comprise the mandatory TDM program is provided below:



- *Infrastructure Improvements* – the following infrastructure improvements in the project vicinity were identified as part of the Site Plan Review for the project, and improve the bicycling, walking, and transit systems in the area and further encourage the use of these mode:
 - Review the final site plans for the project to ensure that the garage driveway on Chester Street and the loading docks for each project building would provide adequate sight distance between vehicles exiting the garage and pedestrians on the adjacent sidewalk.
 - Implement the following at the 7th Street/Mandela Parkway intersection:
 - Convert the existing through/right-turn lane on the westbound 7th Street approach to a right-turn/bus only lane, and remove the merge lane on westbound 7th Street west of the intersection
 - Modify the signal timings at the intersection to provide a bus only phase for the westbound approach, and reduce the signal cycle length to 90 seconds
 - After the completion of the first phase of the project, conduct a signal warrant analysis at the 7th Street/Chester Street intersection to determine if and when the intersection should be signalized. If signalization is warranted, the project shall signalize the intersection with protected left-turn phasing for the east/west 7th Street approaches. In addition and as determined by the City of Oakland staff, the signal may be interconnected with existing adjacent signals along 7th Street. If signalization is not warranted, the project shall conduct an analysis to determine if other control devices, such as all-way stop controls, or rectangular rapid flash beacon (RRFB) should be installed at the intersection. The project shall implement the recommended improvement at the intersection as approved by the City of Oakland.
 - Ensure that the Ford GoBike station currently located in-street on 7th Street just east of Center Street is relocated on the BART Station Plaza to provide close and convenient access to the West Oakland BART station and the bicycle facilities adjacent to the project site.
 - Explore the feasibility of (and implement, if feasible) installing curb extensions (bulb-outs) and directional curb ramps with truncated domes at the following locations:
 - Southwest corner of the 7th Street/Chester Street intersection.
 - All four corners of the 5th Street/Mandela Parkway intersection and curb extensions (bulb-outs) across the 5th Street approaches of the southwest and northeast corners.
 - Provide all-way stop control at the 5th Street/Center Street and 5th Street/Chester Street intersection.



- If reviewed and approved by BART and Oakland Fire Department, provide rolled curb instead of curb cuts for emergency vehicle access points on Chester Street and Mandela Parkway.
- Install a pedestrian scramble at the 7th Street/Center Street intersection.
- Install improvement measures at the proposed mid-block crossing on Mandela Parkway, such as raised crosswalk, RRFB, or other measures as approved by the City of Oakland.
- Coordinate with the City of Oakland and the appropriate property owners to determine the feasibility of and if deemed feasible, complete the sidewalk gap on the south side of 5th Street just east of Center Street.
- Consider designating a bus stop for intercity coaches (e.g., Megabus and Bolt) and other shuttles on 7th Street between Henry and Chester Streets.
- *Limited Residential Parking Supply* – The project would provide up to 400 off-street automobile parking spaces for the residential component of the project, which corresponds to a maximum of 0.5 spaces per unit. This is less than the current average auto ownership of 0.8 vehicles per household in the project area, as shown in Table 1, and would attract households with no vehicles.
- *Unbundled Parking* – Unbundle parking costs from housing costs (as required by Oakland Municipal Code, Section 17.116.310). This would result in residents paying one price for the residential unit and a separate price for parking, should they opt for a space. The price of a parking space can be adjusted so that resident parking demand matches the building's parking supply.
- *No or Minimal Parking for Office/Commercial Uses* – The project would provide none or minimal automobile parking for the office/commercial component.
- *Commercial Parking Management* – If the project provides parking for the commercial and retail components of the project, or parking for the general public, the following shall also be implemented:
 - *No monthly permits and establish minimum price floor for any public parking* — required by the City of Oakland if proposed parking ratio exceeds 1:1,000 square feet (commercial) but should be implemented regardless.
 - *Price parking to achieve desired usage goals* - parking should be priced at the market rate at a minimum and ideally set at a level that makes driving more expensive than non-automobile modes of transportation



- *Carshare Parking Spaces* – Offer to dedicate for free at least six on-site parking spaces available for carsharing. Monitor the usage of the carsharing spaces and adjust if necessary.
- *Guaranteed Ride Home* – Encourage project commercial tenants to register their employees and promote the Alameda County Transportation Commission Guaranteed Ride Home (GRH) program. GRH programs encourage the use of alternative modes of transportation by offering free rides home if an illness or crisis occurs, if the employee is required to work unscheduled overtime, if a carpool or vanpool is unexpectedly unavailable, or if a bicycle problem arises. The Alameda County Transportation Commission offers their GRH service for all registered permanent employees who are employed within Alameda County, live within 100 miles of their worksite, and do not drive alone to work. The GRH program is offered at no cost to the employer, and employers are not required to register in order for their employees to enroll and use the program.
- *Bicycle Parking Supply and Monitoring* – The project would include long-term on-site parking for project residents and employees, a bike station at the BART station, and short-term parking in the form of bike racks along the project frontages, exceeding the City's minimum requirements for bicycle parking. Building management shall monitor the usage of these facilities and provide additional bicycle parking, if necessary.
- *Transit Operations* – The project applicant shall, if feasible, contribute its fair share to AC Transit service enhancements to meet access goals outlined in the City of Oakland West Oakland Specific Plan and AC Transit's ACgo expanded service plan and improve connections to local goods and services. Alternatively, the project applicant may explore and propose other TDM measure(s), including those already set forth in the TDM plan, in lieu of this fair share contribution. The City may approve the substitute TDM measure(s) if the City, in its discretion, deems the measure(s) more feasible, reasonably related and roughly proportional to the transportation impacts of the development.
- *Transit Fare Subsidy (Residents)* – Provide a monthly transit benefit to each dwelling unit. Options include providing discounted Adult 31-Day AC Transit Pass (valued at \$84.60 as of January 2019), AC Transit EasyPass, or monthly Clipper Card contributions.
- *Transit Fare Subsidy (Workers)* – Building management shall either offer to provide or require project tenants to provide free or reduced cost transit in order to increase transit mode share. This analysis assumes that a subsidy of \$1.50 per weekday per worker (value to worker) would be available to all site workers. Options include:
 - Building management or employers can offer a monthly commuter check (or alternatively Clipper Card, which is accepted by BART, AC Transit, and other major transit providers in the Bay Area) to employees to use public transit. Note that as of 2018, IRS allows up to \$260 per employee per month.



- Building management or employers can participate in AC Transit's EasyPass program, which enables employers to purchase annual bus passes for their employees in bulk at a deep discount. The passes allow unlimited rides on all AC Transit buses for all employees. For more information, see www.actransit.org/rider-info/easypass.
- *Pre-tax Commuter Benefits* – Building management shall encourage project tenants to enroll in a service (such as WageWorks) to help with pre-tax commuter savings. This strategy allows employees to deduct monthly transit passes or other amount using pre-tax dollars. This can help to lower payroll taxes and allows employees to save on transit.
- *TDM Marketing and Resident Education* – Site management shall provide residents and employees information about transportation options. This information would also be posted at central location(s) and be updated as necessary. This information shall include:
 - *Transit Routes* – Promote the use of transit by providing user-focused maps. These maps provide residents with wayfinding to nearby transit stops and transit-accessible destinations and are particularly useful for those without access to portable mapping applications. The project should consider installing real-time transit information, such as TransitScreen, in a visible location to provide residents with up-to-date transit arrival and departure times.
 - *Transit Fare Discounts* – Provide information about local discounted fare options offered by BART and AC Transit, including discounts for youth, elderly, persons with disabilities, and Medicare cardholders.
 - *Car Sharing* – Promote accessible car sharing programs, such as Zipcar, and Getaround by informing residents and employees of on-site and nearby car sharing locations and applicable membership information.
 - *Ridesharing* – Provide residents and employees with phone numbers and contact information for ride sharing options including Uber, Lyft, and Oakland taxi cab services.
 - *Carpooling* – Provide residents and employees with phone numbers and contact information for carpool matching services such as the Metropolitan Transportation Commission's 511 RideMatching.
 - *Walking and Biking Events* – Provide information about local biking and walking events, such as Oaklavia, as events are planned.
 - *Bikeshare* – Educate residents and employees about nearby bike sharing station locations and membership information.
- *On-Site TDM Coordinator* – The project shall provide an on-site TDM coordinator responsible for implementing and managing the TDM Plan. The TDM coordinator would also be responsible



for ensuring that all residents, employees, and visitors are aware of their transportation options and would serve as a point of contact for hotel guests and employees regarding TDM programs.

ADDITIONAL OPERATIONAL STRATEGIES

If the mandatory measures do not meet the required goal of 20 percent VTR, and additional vehicle trip reduction is needed, the project shall consider the implementation of some or all of the following additional strategies to limit automobile use and encourage non-automotive travel.

- *Residential Parking Management* – Restrict parking to one parking space per unit or less, thereby discouraging multiple car ownership and/or use. Exceptions will only be made for residents with management approved Reasonable Accommodation Requests. A Reasonable Accommodation Request shall need to demonstrate a hardship wherein a household requires more than one vehicle per unit. Examples could include households with multiple disabled residents requiring vehicles or households with multiple residents with places of work inaccessible via transit. Additionally, if a residential parking permit (RPP) program is implemented in the project vicinity, project residents shall not be eligible for parking permits.
- *Bikeshare/Scooter Membership* – Provide tenants and residents a subsidy to offset the cost of bikeshare and/or scooter membership and encourage the use of non-automobile modes.
- *Carshare Memberships* – Provide residents with free or discounted carshare membership to offset the cost of car sharing programs and reduce the demand for private vehicle ownership.
- *Increased Transit Fare Subsidy* – Increase the transit fare subsidy for project residents and employees.
- *Personalized Trip Planning* – In the form of in-person assistance or as a web tool, provides residents and employees with a customized menu of options for commuting. Trip planning reduces the barriers the residents and employees see to making a walk, bike, or transit trip to the site. Transit trip making tools, such as those available from Google or 511.org, could be promoted to inform residents and employees of transit options to/from work. Providing a preferred walking map routes to residents and employees living within one mile of the site and a bicycling route map to all residents and employees living within five miles of the site would be a proactive strategy to encourage those employees to use alternatives to driving.

TDM MONITORING, EVALUATION AND ENFORCEMENT

Consistent with the requirements of the City's Standard Conditions of Approval, this TDM program requires regular periodic evaluation to determine if the program goal of reducing automobile trips has been satisfied and to assess the effectiveness of the implemented strategies. Beginning the first



year after the development and occupancy of the project, building management must prepare an annual TDM monitoring report consisting of the following:

- Summary of implemented TDM measures and their effectiveness (e.g. bicycle parking occupancy, number of transit passes issued, etc.)
- Results of project resident and employee transportation surveys to monitor the vehicle trip generation and mode share for project residents and employees
- Weekday AM and PM peak period and daily traffic volume counts at the garage driveway on Chester Street

As previously discussed, the goal of the TDM program is to reduce the number of vehicle trips generated by the project by 20 percent. This level would correspond to a total project vehicle trip generation of no more than 378 trips during the AM peak hour and 467 in the PM peak hour.

Based on the results of the surveys, TDM programs shall be increased if these goals are not met. This program ensures the implementation of the mandatory TDM measures and related requirements through compliance with the Mitigation Monitoring and Reporting Program, as implemented through the Conditions of Approval adopted for the project.

The first monitoring report must be prepared one year after full occupancy of the first phase of the project, and subsequent monitoring reports must be prepared annually. If following the annual monitoring the TDM goals are not satisfied, additional measures shall be implemented, with consultation with City staff, until the goal is met.

If in two successive years the project's TDM goals are not satisfied, site management shall prepare and submit for City approval a Corrective Action Plan. The Corrective Action Plan shall detail the additional TDM measures to be implemented on site and their expected modal split reduction.

If, one year after the Corrective Action Plan is implemented, the required automobile mode share reduction target is still not being achieved, or if site management fails to submit a report as described above, or if the reports do not meet City requirements outlined above, the City may, in addition to its other remedies, (a) assess the project a financial penalty based on the observed reduction in the automobile mode share compared to the target; or (b) refer the matter to the City Planning Commission for scheduling of a compliance hearing to determine whether the project's approvals should be revoked, altered or additional conditions of approval imposed.



The penalty as described in (a) above shall be determined by assigning a cost to the number of additional automobile trips to be reduced in order to meet the required goal. Assuming the cost per new alternative commuter is \$26/day and that there are 261 workdays per year, the annual cost per new alternative commuter is \$6,790. The project shall therefore pay a penalty of \$6,790 per year for each trip that should have been using an alternative mode if the 20 percent reduction after completion of the Project had been achieved.

In determining if a financial penalty or other remedy is appropriate, the City shall not impose a penalty if the project has made a good faith effort to comply with the TDM program. The City would only have the ability to impose a monetary penalty after a reasonable cure period and in accordance with the enforcement process outlined in the City's Planning Code Chapter 17.152. If a financial penalty is imposed, such penalty sums shall be used by the City solely toward the implementation of the TDM plan.

If in five successive years the project is found to meet the stated TDM goal, additional surveys and monitoring shall be suspended until such a time as the City deems they are needed.

Please contact Sam Tabibnia (s.tabibnia@fehrandpeers.com or 510-835-1943) with questions or comments.



**APPENDIX A
 TDM PROGRAM CONSISTENCY WITH CITY REQUIREMENTS**

| TDM Strategy | Required When | Required for Proposed Project? |
|--|--|---|
| Bus boarding bulbs or islands | <ul style="list-style-type: none"> • A bus boarding bulb or island does not already exist, and a bus stop is located along the project frontage; and/or • A bus stop along the project frontage serves a route with 15 minutes or better peak hour service and has a shared bus-bike lane curb | Yes , the project would relocate several bus stops from within the BART station to adjacent streets, including bus boarding islands on both directions of 7th Street. |
| Bus shelter | <ul style="list-style-type: none"> • A stop with no shelter is located within the project frontage, or • The project is located within 0.10 miles of a flag stop with 25 or more boardings per day | Yes , bus shelters would be provided at all bus stops along the project frontage. |
| Concrete bus pad | <ul style="list-style-type: none"> • A bus stop is located along the project frontage and a concrete bus pad does not already exist | Yes , concrete bus pads would be provided at all the bus stops relocated to the project frontage. |
| Curb extensions or bulb-outs | <ul style="list-style-type: none"> • Identified as an improvement within site analysis | Yes , the project would provide curb extensions at intersections along the project frontage |
| Implementation of a corridor-level bikeway improvement | <ul style="list-style-type: none"> • A buffered Class 2 or Class 4 bikeway facility is in a local or county adopted plan within 0.10 miles of the project location; and • The project would generate 500 or more daily bicycle trips | Yes , the project would provide Class 4 bikeways on both directions of 7th Street and Mandela Parkway along the project frontage. |
| Implementation of a corridor-level transit capital improvement | <ul style="list-style-type: none"> • A high-quality transit facility is in a local or county adopted plan within 0.25 miles of the project location; and • The project would generate 400 or more peak period transit trips | Yes , while the project is estimated to generate fewer than 400 peak hour transit trips, the project would implement a bus queue jump Lane on westbound 7th Street at Mandela Parkway. |
| Installation of amenities such as lighting; pedestrian-oriented green infrastructure, trees, or other greening landscape; and trash receptacles per the Pedestrian Master Plan and any applicable streetscape plan | <ul style="list-style-type: none"> • Always required | Yes , the project would upgrade the pedestrian amenities within the site and on the adjacent sidewalks. |



**APPENDIX A
 TDM PROGRAM CONSISTENCY WITH CITY REQUIREMENTS**

| TDM Strategy | Required When | Required for Proposed Project? |
|---|---|---|
| <p>Installation of safety improvements identified in the Pedestrian Master Plan (such as crosswalk striping, curb ramps, count down signals, bulb outs, etc.)</p> | <ul style="list-style-type: none"> When improvements are identified in the Pedestrian Master Plan (PMP) along project frontage or at an adjacent intersection | <p>Yes, although the PMP does not identify any specific improvements near the project, the project would provide high-visibility crosswalk striping and directional curb ramps at intersection adjacent to the project.</p> |
| <p>In-street bicycle corral</p> | <ul style="list-style-type: none"> A project includes more than 10,000 square feet of ground floor retail, is located along a Tier 1 bikeway, and on-street vehicle parking is provided along the project frontages. | <p>No, the project would not provide on-street vehicle parking along the project frontage. Short-term bicycle parking will be accommodated within the project site.</p> |
| <p>Intersection improvements, including but not limited to visibility improvements, shortening corner radii, pedestrian safety islands, accounting for pedestrian desire lines.</p> | <ul style="list-style-type: none"> Identified as an improvement within site analysis | <p>Yes, the project would provide curb extensions at intersections along the project frontage.</p> |
| <p>New sidewalk, curb ramps, curb and gutter meeting current City and ADA standards</p> | <ul style="list-style-type: none"> Always required | <p>Yes, the project would upgrade the sidewalks along the project frontage.</p> |
| <p>No monthly permits and establish minimum price floor for public parking</p> | <ul style="list-style-type: none"> If proposed parking ratio exceeds 1:1,000 sf (commercial) | <p>Yes, if commercial parking is provided, no monthly permit would be provided and a minimum price floor for public parking would be established. Although, off-street commercial parking would be at less than 1:1,000 sf, if provided.</p> |
| <p>Parking garage is designed with retrofit capability</p> | <ul style="list-style-type: none"> Optional if proposed parking ratio exceeds 1:1.25 (residential) or 1:1,000 sf (commercial) | <p>Not applicable, the residential parking ratio would be less than 1.25; if off-street commercial parking is provided, it would be at less than 1:1,000 sf.</p> |



**APPENDIX A
 TDM PROGRAM CONSISTENCY WITH CITY REQUIREMENTS**

| TDM Strategy | Required When | Required for Proposed Project? |
|--|--|---|
| Parking space reserved for car share | <ul style="list-style-type: none"> A project is located within downtown (CBD and D-LM zones). One car share space preserved for buildings between 50 – 200 units, then one car share space per 200 units. | <p>Yes, although the project is not located in a downtown zone, the project would offer to dedicate up to six spaces in the garage for car share.</p> |
| Paving, lane striping or restriping (vehicle and bicycle), and signs to midpoint of street section | <ul style="list-style-type: none"> Typically required | <p>Yes, provided.</p> |
| Pedestrian crossing improvements, pedestrian-supportive signal changes, including but not limited to reducing signal cycle lengths to less than 90 seconds to avoid pedestrian crossings against the signal, providing a leading pedestrian interval, provide a “scramble” signal phase where appropriate. | <ul style="list-style-type: none"> Identified as an improvement within site analysis Identified as an improvement within operations analysis | <p>Yes, cycle lengths adjacent to the project would be reduced to 90 seconds and a pedestrian scramble would be provided at the 7th Street/ Center Street intersection.</p> |
| Real-time transit information system | <ul style="list-style-type: none"> A project frontage block includes a bus stop or BART station and is along a Tier 1 transit route with 2 or more routes or peak period frequency of 15 minutes or better | <p>Yes, project would provide real-time transit information.</p> |
| Relocating bus stops to far side | <ul style="list-style-type: none"> A project is located within 0.10 mile of any active bus stop that is currently near-side | <p>Yes, project would relocate bus stops from within the BART Station to adjacent streets, including the far sides of westbound 7th Street at Center Street and eastbound 5th Street at Mandela Parkway.</p> |
| Signal upgrades, including typical traffic lights, pedestrian signals, bike actuated signals, transit only signals | <ul style="list-style-type: none"> Project size exceeds 100 residential units, 80,000 sf of retail, or 100,000 sf of commercial; and Project frontage abuts an intersection with signal infrastructure older than 15 years | <p>Yes, a new traffic signal may be installed at the 7th Street/ Chester Street intersection.</p> |
| Transit queue jumps | <ul style="list-style-type: none"> Identified as a needed improvement within operations analysis of a project with frontage along a Tier 1 transit route with 2 or more routes or peak period frequency of 15 minutes or better | <p>Yes, the project would provide a bus queue jump Lane on westbound 7th Street at Mandela Parkway.</p> |



**APPENDIX A
 TDM PROGRAM CONSISTENCY WITH CITY REQUIREMENTS**

| TDM Strategy | Required When | Required for Proposed Project? |
|--|--|---|
| Trenching and placement of conduit for providing traffic signal interconnect | <ul style="list-style-type: none"> • Project size exceeds 100 units, 80,000 sf of retail, or 100,000 sf of commercial; and • Project frontage block is identified for signal interconnect improvements as part of a planned ITS improvement; and • A major transit improvement is identified within operations analysis requiring traffic signal interconnect | <p>Yes, a new traffic signal may be installed at the 7th Street/ Chester Street intersection and be interconnected with existing signals along 7th Street.</p> |
| Unbundled parking | <ul style="list-style-type: none"> • New multifamily dwelling residential facilities of ten (10) or more units, with the exception of affordable housing | <p>Yes, the residential component of the project would provide unbundled parking.</p> |

Sources: City of Oakland Transportation Impact Review Guidelines, 2017 and City of Oakland Municipal Code, 2018



PREPARED FOR: Dara O'Byrne
City of Oakland, Bureau of Planning

PREPARED BY: Rebecca Auld
Lamphier-Gregory, Inc.
1944 Embarcadero, Oakland, CA 94606

SUBJECT: **West Oakland BART TOD Project – Assessment of Project Changes**

DATE: October 22, 2020

Background and Purpose

The West Oakland Bay Area Rapid Transit (WOB) station Transportation Oriented Development (TOD) Preliminary Development Permit (Project) was approved at a Planning Commission hearing on February 6, 2019. Addendum #1 to the West Oakland Specific Plan Environmental Impact Report (EIR) (SCH#2012102047) (2019 EIR Addendum) was accepted at the same time for compliance with the California Environmental Quality Act (CEQA). The Project analyzed in the 2019 EIR Addendum is referred to in this document as the “2019 Project.”

Since the February 2019 approval, the applicant has proposed some changes to the project, as described under the *Revisions to the Project* header below. The revised project assessed in this document is referred to as the “2020 Project.”

The purpose of this memo is to assess whether the changes to the project would require subsequent analysis. CEQA Guidelines Section 15162 provides the following guidance:

- (a) When an EIR has been certified or a Negative Declaration adopted for a project, no subsequent EIR shall be prepared for that project unless the lead agency determines, on the basis of substantial evidence in the light of the whole record, one or more of the following:
 - (1) Substantial changes are proposed in the project which will require major revisions of the previous EIR or negative declaration due to the involvement of new significant environmental effects or a substantial increase in the severity of previously identified significant effects;
 - (2) Substantial changes occur with respect to the circumstances under which the project is undertaken which will require major revisions of the previous EIR or Negative Declaration due to the involvement of new significant environmental effects or a substantial increase in the severity of previously identified significant effects; or
 - (3) New information of substantial importance, which was not known and could not have been known with the exercise of reasonable diligence at the time the previous EIR was certified as complete or the Negative Declaration was adopted, shows any of the following:
 - (A) The project will have one or more significant effects not discussed in the previous EIR or negative declaration;

- (B) Significant effects previously examined will be substantially more severe than shown in the previous EIR;
 - (C) Mitigation measures or alternatives previously found not to be feasible would in fact be feasible, and would substantially reduce one or more significant effects of the project, but the project proponents decline to adopt the mitigation measure or alternative; or
 - (D) Mitigation measures or alternatives which are considerably different from those analyzed in the previous EIR would substantially reduce one or more significant effects on the environment, but the project proponents decline to adopt the mitigation measure or alternative.
- (b) If changes to a project or its circumstances occur or new information becomes available after adoption of a negative declaration, the lead agency shall prepare a subsequent EIR if required under subdivision (a). Otherwise the lead agency shall determine whether to prepare a subsequent negative declaration, an addendum, or no further documentation.

Revisions to the Project

As under the 2019 Project, the 2020 Project is split into the same four development areas referred to as T-1 through T-4. Building locations, overall heights, and general massing would not change (**Figure 1**).




Figure 1: Development Areas

Compared to the 2019 Project, the proposed changes would result in an overall reduction of 82,460 square feet (sf) of office space, 17,377 sf of retail space, 15 parking stalls, 35,395 sf of residential open space, and 10,425 sf of ground floor public open space. While the overall number of residential units would be unchanged, 22 units would be moved from T-1 to T-3. The proposed changes broken down by development area are shown in **Table 1**.

Table 1. 2020 Project Development Summary (change from 2019 Project in parentheses)

| Uses | T1 | T2 | T3 | T4 | Total |
|---|-----------------------------------|----------------------------------|----------------------------------|-----------------------------------|--|
| Office | 0 sf (-82,460 sf) | | | 300,000 sf | 300,000 sf (-82,460 sf) |
| Retail | 14,350 sf (-2,835 sf) | 0 sf ¹ (-7,670 sf) | 15,944 sf (+ 794 sf) | 23,184 sf (-7,616 sf) | 53,478 sf (-17,377 sf) ² |
| Residential | 522 units (+ 22 units) | | 240 units (-22 units) | | 762 units |
| Public Open Space | | | | | 75,368 sf (-10,425 sf) |
| Residential Open Space ³ | 17,648 sf (-1,454sf) | | 24,815 sf (-33,941 sf) | | 42,463 sf (-35,395 sf) |
| Parking ⁴ | 125 stalls (previously shared) | | 50 stalls (previously shared) | 210 stalls (previously shared) | 385 stalls (-15 stalls) |
| <p>Notes:</p> <p>¹ The 2019 EIR Addendum analyzed a total of “up to 75,000 square feet of retail,” this table used 70,855 sf for calculations, which was the exact amount approved.</p> <p>² The 2020 Project flexible programming space would include no permanent structures, so is reflected here as having 0 sf of retail.</p> <p>³ Referenced residential open space is based upon amounts approved with the 2019 Project and is calculated per the city’s Municipal Code Chapter 17.126.</p> <p>⁴ To clarify: the project analyzed in the 2019 EIR Addendum had one shared parking garage with a total of 400 stalls whereas the current project has a total of 385 stalls in three separate parking garages.</p> | | | | | |

With the replacement of some office/retail space to less-tall residential units in the T-1 development, the total number of stories would increase by one story to 31 stories within the same height as proposed under the 2019 Project.

Parking was provided in one shared garage under the 2019 Project but would instead be provided in separate garages for the development areas under the 2020 Project.

This document includes a summary of the changes between the 2019 and 2020 Projects that could be relevant to the environmental analysis. Comparative figures are included as **Figures 2** through **7**. Further details are available as part of the project file at the City.




Figure 2: Floor Plan, Ground Floor - 2020 Project (currently proposed)




Figure 3: Floor Plan, Ground Floor - 2019 Project (for comparison)



Figure 4. Illustrative View, Looking South - 2020 Project (currently proposed)



Figure 5. Illustrative View, Looking South - 2019 Project (for comparison)



Figure 6. Illustrative View, Looking North - 2020 Project (currently proposed)



Figure 7. Illustrative View, Looking North – 2019 Project (for comparison)

CEQA Assessment

The potential of the project changes to result in changes in the analysis and conclusions in the 2019 EIR Addendum are addressed below.

Aesthetics

As noted in the 2019 EIR Addendum (page 32), under CEQA, the aesthetics of an infill project in a transit priority area (such as the proposed Project) are not considered significant environmental impacts. While there have been some changes to the look of the buildings proposed, their aesthetics need not be analyzed from an environmental perspective.

Therefore, the changes in the 2020 Project would not result in a new significant impact or a substantial increase in the severity of previously identified impacts related to aesthetics beyond those disclosed in the 2019 EIR Addendum and there is no need for further environmental review of this topic.

Air Quality and Greenhouse Gas Emissions

The 2020 Project proposes the same amount of residential units and reduced office and retail space and would still be required to implement a Greenhouse Gas Reduction Plan as a standard condition of approval. Regulations and standard conditions would continue to apply to the 2020 Project to ensure that no significant impacts would occur including standard conditions to implement dust and emissions controls during construction activities and to minimize emissions from stationary equipment including emergency generators. Therefore, anticipated emissions would be the same or reduced as compared to the 2019 Project.

Therefore, the changes in the 2020 Project would not result in a new significant impact or a substantial increase in the severity of previously identified impacts related to air quality and greenhouse gas emissions beyond those disclosed in the 2019 EIR Addendum, and there is no need for further environmental review of this topic.

Land Use

The 2020 Project proposes the same types of uses on the same site with the same general locations, massing, and heights, and would not change the conclusion in the 2019 EIR Addendum that the project would be substantially consistent with the development density established by existing zoning, community plan, or General Plan policies and the State Affordable Housing Density Bonus Law, which requires that the City grant a density bonus if the project meets affordable housing requirements. The 2020 Project would revise the requested concession for reduced parking and open space provisions, but as noted previously, requested variations from base zoning, community plan, or General Plan requirements are allowable under the applicable local and State regulations and would therefore not represent significant environmental conflicts with applicable plans.

Therefore, the changes in the 2020 Project would not result in a new significant impact or a substantial increase in the severity of previously identified impacts related to land use beyond those disclosed in the 2019 EIR Addendum, and there is no need for further environmental review of this topic.

Transportation

The 2020 Project proposes the same or reduced amount of residential units and office and retail space and would still be required to implement a TDM Plan as a standard condition of approval. Therefore,

anticipated trips would be the same or reduced as compared to the 2019 Project. The project location remains unchanged, and continues to meet the City's "Near Transit Stations" criterion to demonstrate a less than significant impact with regard to the project's Vehicle Miles Traveled (VMT).

With the revision from one shared parking garage to three garages, the 2020 Project would add two driveways on Mandela Parkway that were not previously proposed. The driveways will be required to meet relevant safety standards.

The 2020 Project would not result in substantial changes in pedestrian and bicycle facilities compared to those proposed under the 2019 Project and will be required to meet relevant standards and requirements.

The 2020 Project remains consistent with both the City's 2017 Pedestrian Master Plan and the 2007 Bicycle Master Plan as it would not make major modifications to existing pedestrian or bicycle facilities in the surrounding areas and would not adversely affect installation of future facilities. The same infrastructure improvements are proposed including new bicycle lanes and improved/enhanced bus facilities and pedestrian amenities.

Therefore, the changes in the 2020 Project would not result in a new significant impact or a substantial increase in the severity of previously identified impacts related to transportation beyond those disclosed in the 2019 EIR Addendum, and there is no need for further environmental review of this topic.

Other Construction-Related Topics

The 2019 EIR Addendum assessed the potential of the project to cause impacts due to demolition and ground disturbance. Both the 2019 and 2020 Project will disturb basically the entire site. Regulations and standard conditions would continue to apply to the 2020 Project to ensure that no significant impacts would occur including standard conditions to implement a Construction Management Plan, ensure compliance with tree removal and replacement regulations, avoid breeding season or survey for and address nesting birds, assess and address potential cultural resource discovery, compliance with the geotechnical report to address seismic and soil considerations, assessment and appropriate handling of chemical products used in construction and any encountered hazardous building materials or soil contamination, and implementation of erosion and sedimentation control measures. There would be no changes in the analysis or conclusions of demolition and ground disturbance related topics, such as construction-period biological, cultural, hazardous materials, geology, or hydrology.

The 2019 EIR Addendum assessed the potential of the project to cause impacts due to construction activities. Regulations and standard conditions would continue to apply to the 2020 Project to ensure that no significant impacts would occur including standard conditions to implement noise controls during construction activities, and to implement a construction traffic control plan and repair any damage to public streets.

Therefore, the changes in the 2020 Project would not result in a new significant impact or a substantial increase in the severity of previously identified impacts for construction-related topics beyond those disclosed in the 2019 EIR Addendum, and there is no need for further environmental review of these topics.

Other Operational-Related Topics

The 2019 EIR Addendum assessed the potential of the project to cause impacts during operations. Regulations and standard conditions would continue to apply to the 2020 Project to ensure that no significant impacts would occur including standard conditions to minimize noise from on-site equipment including HVAC systems, and to implement measures to reduce stormwater runoff.

Therefore, the changes in the 2020 Project would not result in a new significant impact or a substantial increase in the severity of previously identified impacts for other operational-related topics beyond those disclosed in the 2019 EIR Addendum, and there is no need for further environmental review of these topics.

Other Environmental Topics

Due to the lack of such features on the site or related to the Project, the 2019 EIR Addendum concluded that the Project would not have the potential to cause significant impacts related to creeks or other sensitive habitats, flood hazards, or displacement of housing or people. As further noted in the 2019 EIR Addendum, the project is located on a site already provided with utilities and public services and consistent with growth assumptions and supply planning and no additional facility improvements are anticipated to be required to accommodate future demand other than those proposed with the project or already planned as part of a fee program to which this project would contribute. The 2020 Project would not change conclusions related to population growth, public services, parks, and recreation, and utilities and service systems.

With no changes to the conclusions in any topic areas as demonstrated in this document, the 2020 Project would also not result in any changes to mandatory findings related to environmental quality, cumulative impacts, and adverse effects on human beings.

Therefore, the changes in the 2020 Project would not result in a new significant impact or a substantial increase in the severity of previously identified impacts related to agriculture and forestry resources, flooding, land use and planning, mineral resources, population and housing, public services, recreation, and utilities beyond those disclosed in the 2019 EIR Addendum, and there is no need for further environmental review of these topics.

Conclusions

Therefore, given the substantial evidence above, the 2020 Project would not require subsequent analysis per CEQA Guidelines Section 15162, as confirmed by the following statements:

- (1) The 2020 Project would not result in new significant environmental effects or a substantial increase in the severity of previously identified significant effects;
- (2) There are no changes in circumstances that would result in new significant environmental effects or a substantial increase in the severity of previously identified significant effects; or
- (3) There is no new information resulting in a new significant effect not discussed that would result in new significant environmental effects, a substantial increase in the severity of previously identified significant effects, or a change in the feasibility (or acceptance) of mitigation measures.

While changes to the project have occurred after acceptance of the 2019 EIR Addendum, this assessment has determined that no further documentation is required per CEQA Guidelines Section 15162. The 2019 EIR Addendum continues to serve as the applicable environmental review document pursuant to the requirements of CEQA for approval of the 2020 Project and the associated adopted Standard Conditions of Approval and Mitigation Monitoring and Reporting Program would remain fully applicable.


ATTACHMENT B:

**Previously Approved West Oakland BART TOD
Preliminary Development Plan and Design Guidelines,
February 6, 2019**

WEST OAKLAND STATION

PRELIMINARY DEVELOPMENT PLAN

JANUARY 28, 2019



WEST OAKLAND BART

DRAWING INDEX

GENERAL

G100 TITLE SHEET, DRAWING INDEX

CONTEXT INFO

A00.01 RENDERING 1
 A00.02 RENDERING 2
 A00.03 RENDERING 3
 A00.04 RENDERING 4
 A00.05 RENDERING 5
 A00.06 RENDERING 6
 A00.07 RENDERING 7
 A00.08 ZONING INFO
 A00.09 ZONING SUMMARY
 A00.10 CONSTRUCTION SCHEDULE
 A00.11 PHASING PLAN
 A00.12 LEED CHECK LIST
 A00.13 LEED CHECK LIST
 A00.14 LEED CHECK LIST
 A00.15.1 SPECIFIC PLAN GUIDELINE CHECKLIST
 A00.15.2 SPECIFIC PLAN GUIDELINE CHECKLIST
 A00.15.3 SPECIFIC PLAN GUIDELINE CHECKLIST
 A00.15.4 DESIGN GUIDELINE CHECKLIST
 A00.15.5 DESIGN GUIDELINE CHECKLIST
 A00.15.6 DESIGN GUIDELINE CHECKLIST
 A00.15.7 DESIGN GUIDELINE CHECKLIST
 A00.15.8 DESIGN GUIDELINE CHECKLIST
 A00.17 CONTEXT MAP
 A00.18 CONTEXT PHOTOS
 A00.19 OPEN SPACE ANALYSIS

CIVIL PLANS

C1.00 EXISTING CONDITIONS PLAN
 C1.01 LOT MERGER PLAN
 C2.00 PROPOSED GRADING PLAN
 C3.00 STORMWATER MANAGEMENT PLAN
 C4.00 EROSION CONTROL PLAN
 C4.01 EROSION CONTROL PLAN DETAILS

LANDSCAPE PLANS

L00.01 TREE REMOVAL PLAN
 L00.02 LANDSCAPE PLAN ON-GRADE
 L00.03 LANDSCAPE PLAN ON-STRUCTURE
 L00.04 PROPOSED PLANTS
 L00.05 PROPOSED PLANTS

L00.06 PROPOSED PAVING
 L00.07 PROPOSED LIGHTING
 L00.08 PRELIMINARY LIGHTING PLAN

TYPICAL ARCHITECTURAL PLANS AND ELEVATION

A10.00.00 PUBLIC SPACE IMPROVEMENT
 A10.00.01 PUBLIC SPACE IMPROVEMENT
 A10.00.02 PUBLIC SPACE IMPROVEMENT
 A10.00.03 PUBLIC SPACE IMPROVEMENT
 A10.00.04 PUBLIC SPACE IMPROVEMENT
 A10.00.05 PUBLIC SPACE IMPROVEMENT
 A10.00.06 PUBLIC SPACE IMPROVEMENT
 A10.00.07 PUBLIC SPACE IMPROVEMENT
 A10.00.08 PUBLIC SPACE IMPROVEMENT
 A10.00.09 PUBLIC SPACE IMPROVEMENT
 A10.01 SITE PLAN
 A10.02 SIGN PLAN
 A10.03 MATERIAL BOARD
 A10.04 MATERIAL BOARD
 A10.05 FOOTPRINT AREA
 A10.06 EMERGENCY VEHICLE ACCESS
 A10.07 MASSING DIAGRAM

 A 11.01 GROUND FLOOR PLAN
 A 11.02 2ND FLOOR PLAN
 A 11.03 3-4TH FLOOR PLAN (OFFICE PODIUM)
 A 11.04 5TH FLOOR PLAN (COMMON LEVEL)
 A 11.05 6TH FLOOR PLAN
 A 11.06 7TH FLOOR PLAN (CO-HOUSING)
 A 11.07 8-18TH FLOOR PLAN (TYPICAL LOWER TOWER)
 A 11.08 19-30TH FLOOR PLAN (TYPICAL HIGHER TOWER)
 A 11.09 ROOF PLAN
 A 11.10 BASEMENT FLOOR PLAN


 A 20.01 7TH STREET ELEVATION
 A 20.02 MANDELA PKWY ELEVATION
 A 20.03 5TH STREET ELEVATION
 A 20.04 CHESTER STREET ELEVATION
 A 20.05 T1 SOUTH ELEVATION
 A 20.06 T1 & T4 WEST ELEVATION
 A 20.07 T3 NORTH & EAST ELEVATION
 A 20.08 T3 SOUTH & WEST ELEVATION
 A 20.09 T4 NORTH & EAST ELEVATION
 A 20.10 T4 SOUTH & WEST ELEVATION
 A 20.11 RETAIL UNDER BART ELEVATION

 A 30.01 SECTION A-A
 A 30.02 SECTION B-B
 A 30.03 SECTION C-C



WEST OAKLAND BART

1451 7th St, Oakland, CA 94607



JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com



PROJ. # 168-153 WO BART
 DATE: January 18, 2019

DRAWING INDEX


SHEET:

G-100



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

RENDERING 7TH STREET LOOKING EAST

SHEET:


A-00.01





WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

7TH & CHESTER CORNER VIEW


SHEET: A-00.02






WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019


AERIAL VIEW
LOOKING SOUTH

SHEET: A-00.03



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

5TH & MANDELA CORNER VIEW


SHEET: A-00.04





WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

AERIAL VIEW LOOKING NORTH

SHEET: A-00.05



5TH & MANDELA



5TH & CHESTER




7TH STREET PLAZA



**WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

**STREET
VIEWS**

SHEET: **A-00.06**




ART ALLEY



MAKERS PLAZA



**WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



JRDV URBAN INTERNATIONAL
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019

STREET
VIEWS


SHEET: A-00.07

Scheme A

| USES | T1 | T2 | T3 | T4 | Program Total |
|-------------|-----------|----------|------------------------|------------|------------------------------------|
| OFFICE | 82,460 sf | | | 300,000 sf | 382,460 sf |
| RETAIL | 17,185 sf | 7,670 sf | 15,200 sf | 30,800 sf | 70,855 sf |
| RESIDENTIAL | 500 units | | 240 units 22 duplex | | 762 units (20% min. affordable) |
| PARKING | | | 272 spaces | 128 spaces | 400 spaces |



**WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



Scheme A - Zoning Analysis

| Total Site Area | | | |
|----------------------------------|----------------------------|-------------------|---------------------------|
| T2/T3 | S-15W 60' | 111,230 SF | |
| T1/T4 | S-15W 100' | 131,900 SF | |
| | Total | 243,130 SF | |
| Residential Density | | Site Area | Net Required Site Area |
| Units (zone 60') | 262 | | |
| SF/Unit | 375 | 98,250 | |
| Affordable Housing Density Bonus | 1.35 | | |
| PUD Density Bonus | 1.25 | | |
| | Required Site Area | 58,250 | 58,250 SF |
| Units (zone 100') | 500 | | |
| SF/Unit | 225 | 112,500 | |
| Affordable Housing Density Bonus | 1.35 | | |
| PUD Density Bonus | 1.25 | | |
| | Required Site Area | 66,600 | 66,600 SF |
| | Total Req Site Area | | 124,850 SF |
| Commercial Office Density | | | |
| Program Area | 382,460 SF | | |
| | FAR | Site Area | Allowable FAR Area |
| T1/T4 | 5.0 | 65,300 | 326,500 SF |
| T2/T3 | 3.0 | 52,980 | 158,940 SF |
| | Total Allowable | | 485,440 SF |
| Required PUD Density Bonus | 0% | | 382,460 SF |
| GP Density Max. | 5.0 | 118,280 | 591,400 SF |

Scheme A - Open Space Analysis

| Residential Open Space Req | | | |
|----------------------------|-----------------------|------------------|--|
| 262 Units | 150 | 39,300 SF | |
| 500 Units | 75 | 37,500 SF | |
| | | 76,800 SF | |
| Open Space Provided | | | |
| Courtyard | | 6,055 SF | |
| RoofDecks | | 33,575 SF | |
| | | 39,630 SF | |
| Private Decks (x2) | | 38,228 SF | |
| | Total Provided | 77,858 SF | |

Scheme A - Parking Analysis

| Resi-Required Paking | 262 | 0.5 | 131 |
|----------------------|--------------|-----|----------------------------|
| | 500 | 0.5 | 250 |
| Commercial Pkg | 70,855 | 600 | 118 |
| | Total | | 499 Spaces |
| PKG Reductions | | | |
| Transit | 0.3 | | 150 Spaces |
| Car Share | 0.2 | | 100 Spaces |
| | | | Residential PKG Req |
| | | | 250 Spaces |
| Parking Provided | | | |
| T3 Parking | | | 272 Spaces |
| T4 Parking | | | 128 Spaces |
| | Total | | 400 Spaces |

JRDV ARCHITECTS, INC.
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com

BKF100+
YEARS
ENGINEERS, SURVEYORS, PLANNERS

stök
LANDSCAPE ARCHITECTS

PGAdesign
LANDSCAPE ARCHITECTS

PROJ. # 168-153 WO BART
DATE: January 18, 2019

**ZONING
INFO**


SHEET:
A-00.08

| GENERAL ZONING INFORMATION | REFERENCE | NOTES |
|---|----------------|---|
| ASSESSORS BLOCK | Survey | See Survey; Tract 8046, Blocks 494 and 493 |
| ZONING USE DISTRICT | Oak GIS | S-15W |
| PERMITTED AND/OR CONDITIONAL USES | 17.97.010-.020 | Residential, Community Assembly, General Retail, Full +Limited Service Retail, Parking, Commercial Office permitted |
| HEIGHT & BULK DISTRICT | 17.97 | S-15W 60' and S-15W 100'; master plan consistent with zoning requirements |
| GENERAL PLAN / POLICY PLAN | OAK-GIS | General Commercial; West Oakland Specific Plan |
| HISTORIC OR LANDMARK STATUS | OAK-GIS | None |
| LIQUEFACTION HAZARD ZONE | OAK-GIS | Severity 4 |
| CONDO CONVERSION IMPACT AREA | OAK-GIS | None |
| HEIGHT AND BULK CONTROLS | | |
| SITE AREA | Survey | 243,132 SF |
| FLOOR AREA RATIO (FAR) | 17.97.130 | S-15W 60' - 3.0; S-15W 100' - 5.0; Master Plan within zoning density requirements |
| HEIGHT LIMIT | 17.97 | 60' and 100' (Height limit modified to allow 80' and 320' tall building pursuant to State Affordable Housing Exemption) |
| REQUIRED SETBACKS | 17.97.060 | No Front Yard Setbacks Required; Interior Lot subject to PUD |
| REAR YARDS / COURTS | | None Required |
| ADJACENCIES | | None Significant |
| UNIT SEPARATION / EXPOSURE REQUIREMENTS | 17.108.080 | 8' minimum at living room window +2' for each floor above = maximum 10% of It width |
| DETAILED CONTROLS & REQUIREMENTS | | |
| RESIDENTIAL DENSITY LIMITS | 17.97.130 | S-15W 60' - 375sf/unit; S-15W100' - 225sf/unit; Density increase per State Affordable Housing and PUD density bonus |
| OPEN SPACE REQUIREMENTS | 17.97.130 | S-15W 60' - 150sf/unit; and S-15W 100' - 75sf/unit; Overall master plan within zoning limites |
| SCREENING & SETBACK OF PARKING & LOADING | 17.116.290 | All parking garages are screened per zoning requirements |
| OFF-STREET PARKING - RESIDENTIAL | 17.116.060 | 0.5 parking space per dwelling unit required; Parking meets zoning requirements with approved reductions |
| OFF-STREET PARKING - RETAIL | 17.116.080 | 1 space/600 Sf of ground floor; Parking meets zoning requirements with approved reductions |
| OFF-STREET PARKING - COMMERCIAL | 17.116.080 | None required |
| OFF-STREET PARKING DIMENSIONS | 17.116.200 | 50-50 compact / standard; or 75% intermediate + 12.5% compact |
| OFF-STREET DRIVE AISLE DIMENSIONS | 17.116.210 | 21'-24' two way aisle widths |
| OFF-STREET LOADING - RESIDENTIAL | 17.116.120 | Loading per zoning requirements |
| OFF-STREET LOADING - RETAIL | 17.116.150 | Loading per zoning requirements |
| LOADING BERTH DIMENSIONS | 17.116.220 | 12'x33', 14' high |
| BICYCLE REQUIREMENTS - RESIDENTIAL | 17.117.090 | LT: total 229 spaces; ST: total 57 spaces LT: 1 per 10,000 sf of commercial; ST: 1 per 20,000 sf of commercial LT: 0.25 spaces per dwelling unit; ST: 0.05 per dwelling unit; bicycle parking provide per zoning code |
| BICYCLE REQUIREMENTS - RETAIL | 17.117.110 | LT: total 5 spaces; ST: total 30 spaces LT: 1 per 12k; ST: 1 per 2k; bicycle parking provided per zoning code |




WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019

ZONING SUMMARY


SHEET:

A-00.09



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

PHASING PLAN

SHEET: A-00.11


LEED CS v4 SCORECARD

West Oakland Station T4



WEST OAKLAND BART

1451 7th St, Oakland, CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



| IP | Confirmed | | | | Phase | Credit Number | Credit Name | Points Available | |
|---------------------------|---------------|-------|----|-----------|-------|---------------|---|------------------|-----------|
| | Likely | Maybe | No | Confirmed | | | | | |
| 1 | 1 | | | | D | Credit | Integrative Process - In design phases, achieve synergies between building, energy AND water related systems | 1 | |
| Totals | | | | | | | | 1 | |
| LOCATION & TRANSPORTATION | 20 | | | | D | Credit | LEED for Neighborhood Development Location - Locate within LEED ND certified development site boundary | 20 | |
| | 2 | | | | D | Credit | Sensitive Land Protection - Develop on previously developed land or follow criteria for non-sensitive | 2 | |
| | 2 | | 1 | | D | Credit | High Priority Site - Locate project on infill location in historic district, priority designation or brownfield | 3 | |
| | 2 | 2 | | 2 | D | Credit | Surrounding Density & Diverse Uses - Site within 1/4 mile of surrounding density criteria and/or a 1/2 mile of diverse uses | 6 | |
| | 6 | | | | D | Credit | Access to Quality Transit - Locate functional entries within 1/4 mile of existing transit or 1/2 mile of planned transit services | 6 | |
| | 1 | | | | D | Credit | Bicycle Facilities - Provide a bike network and storage areas | 1 | |
| | 1 | | | | D | Credit | Reduced Parking Footprint - Don't exceed minimum local code requirements for parking capacity | 1 | |
| | 1 | | | | D | Credit | Green Vehicles - 5% of spaces or 20% discount for parking and electric car charging OR liquid, gas or battery facilities | 1 | |
| | Totals | | | | | | | | 20 |

| SUSTAINABLE SITES | Confirmed | | | | Phase | Credit Number | Credit Name | Points Available |
|-------------------|-----------|-------|----|-----------|-------|---------------|--|------------------|
| | Likely | Maybe | No | Confirmed | | | | |
| Yes | | | | | C | Prereq | Construction Activity Pollution Prevention - Implement an erosion control plan, per the EPA CGP v2012 | NA |
| | | | 1 | | D | Credit | Site Assessment - Complete site survey including: topography, hydrology, climate, vegetation, soils, human use, human health | 1 |
| | | | 2 | | D | Credit | Site Development - Protect or Restore Habitat - Preserve 40% of greenfield AND on-site restoration OR financial support | 2 |
| 1 | | | | | D | Credit | Open Space - Provide outdoor space greater than or equal to 30% of total site area, 25% of which is vegetated | 1 |
| | | | 3 | | D | Credit | Rainwater Management - Manage runoff for at least the 85th percentile of local rainfall events | 3 |
| | 1 | | | | D | Credit | Heat Island Reduction - Meet nonroof and roof criteria OR place a minimum of 75% parking spaces under cover | 2 |
| 1 | | | | | D | Credit | Light Pollution Reduction - Backlight-uplight-glare method or calculation method, exterior luminaires and signage requirements | 1 |
| 1 | | | | | D | Credit | Tenant Design and Construction Guidelines - Provide Manual or automative glare control devices | 1 |
| Totals | | | | | | | | 11 |

| WATER | Confirmed | | | | Phase | Credit Number | Credit Name | Points Available |
|---------------|-----------|-------|----|-----------|-------|---------------|---|------------------|
| | Likely | Maybe | No | Confirmed | | | | |
| Yes | | | | | D | Prereq 1 | Outdoor Water Use Reduction - Permanent non-irrigated landscape OR reduce landscape water use 30% for peak watering month | NA |
| Yes | | | | | D | Prereq 2 | Indoor Water Use Reduction - Reduce aggregate water use by 20% for fixtures and fittings | NA |
| Yes | | | | | D | Prereq 3 | Building-Level Water Metering - Install permanent water meters that measure potable water use, share data with USGBC | NA |
| 1 | | | 1 | | D | Credit | Outdoor Water Use Reduction - Reduce water use no irrigation or reduced irrigation 50% - 100% | 2 |
| 3 | | | 3 | | D | Credit | Indoor Water Use Reduction - Reduce fixture and fitting water use by 25% - 50% | 6 |
| | | | 2 | | D | Credit | Cooling Tower Water Use - Conduct a one-time potable water analysis, measure control parameters in Table 1 | 2 |
| | | | 1 | | D | Credit | Water Metering - Meters for 2 or more water subsystems: irrigation, indoor plumbing, hot water, boiler, reclaimed water, or other | 1 |
| Totals | | | | | | | | 11 |

| ENERGY & ATMOSPHERE | Confirmed | | | | Phase | Credit Number | Credit Name | Points Available |
|---------------------|-----------|-------|----|-----------|-------|---------------|--|------------------|
| | Likely | Maybe | No | Confirmed | | | | |
| Yes | | | | | C | Prereq 1 | Fundamental Commissioning and Verification - Commissioning for ASHRAE 0-2005 and 1.1-2007 | NA |
| Yes | | | | | D | Prereq 2 | Minimum Energy Performance - Whole building energy simulation OR ASHRAE 50% Design Guide OR ABCPG | NA |
| Yes | | | | | D | Prereq 3 | Building-Level Energy Metering - Use building-level energy meters or submeters that can aggregate building-level data | NA |
| Yes | | | | | D | Prereq 4 | Fundamental Refrigerant Management - Do not use CFC-based refrigerants in HVAC&R systems, or have a phase out plan | NA |
| 3 | 1 | | 2 | | C | Credit | Enhanced Commissioning - Implement systems commissioning or monitor-based commissioning | 6 |
| 5 | 2 | | 11 | | D | Credit | Optimize Energy Performance - Whole building energy simulation or follow ASHRAE Advanced Energy Design Guide | 18 |
| | | | 1 | | D | Credit | Advanced Energy Metering - Install advanced energy metering for whole building and individual energy sources | 1 |
| | | | 2 | | C | Credit | Demand Response - Participate in existing demand response program or provide infrastructure for demand response programs | 2 |
| | | | 3 | | D | Credit | Renewable Energy Production - Use renewable energy system to meet 1-10% of usage | 3 |
| | | | 1 | | D | Credit | Enhanced Refrigerant Management - Refrigerants with ODP of 0 and GWP of less than 50 OR calculate refrigerant impact | 1 |
| | | | 2 | | C | Credit | Green Power and Carbon Offsets - Use 50-100% green power or carbon offsets | 2 |
| Totals | | | | | | | | 33 |

| MATERIALS & RESOURCES | Confirmed | | | | Phase | Credit Number | Credit Name | Points Available |
|-----------------------|-----------|-------|----|-----------|-------|---------------|---|------------------|
| | Likely | Maybe | No | Confirmed | | | | |
| Yes | | | | | D | Prereq | Storage and Collection of Recyclables - Dedicated areas for waste collection, collection and storage | NA |
| Yes | | | | | D | Prereq | Construction and Demolition Waste Management Planning - Establish C&D waste diversion goals | NA |
| | 3 | | 3 | | C | Credit | Building Life-Cycle Impact Reduction - Historic building reuse, renovate blighted buildings OR whole building LCA | 6 |
| | 1 | | 1 | | C | Credit | Building Product Disclosure and Optimization - Environmental Product Declarations | 2 |
| | 1 | | 1 | | C | Credit | Building Product Disclosure and Optimization - Sourcing of Raw Materials | 2 |
| | 1 | | 1 | | C | Credit | Building Product Disclosure and Optimization - Material Ingredients | 2 |
| | 1 | | 1 | | C | Credit | C&D Waste Management - Divert 50% (3 streams), 75% (4 streams) OR 2.5 lbs. waste per square foot | 2 |
| Totals | | | | | | | | 14 |

| INDOOR ENVIRONMENTAL | Confirmed | | | | Phase | Credit Number | Credit Name | Points Available |
|----------------------|-----------|-------|----|-----------|-------|---------------|--|------------------|
| | Likely | Maybe | No | Confirmed | | | | |
| Yes | | | | | D | Prereq | Minimum Indoor Air Quality Performance - Meet ASHRAE 62.1-2010 | NA |
| Yes | | | | | D | Prereq | Environmental Tobacco Smoke Control - Prohibit smoking indoors, restrict outdoor smoking within 25 feet | NA |
| 1 | 1 | | | | D | Credit | Enhanced Indoor Air Quality Strategies - Comply with enhanced IAQ strategies | 2 |
| 1 | 1 | | 1 | | C | Credit | Low-Emitting Materials - Achieve level of compliance for product categories or use budget calculation method | 3 |
| | | | 1 | | C | Credit | Construction IAQM Plan - Implement IAQMP & protect materials and equipment during construction | 1 |
| | | | 3 | | D | Credit | Daylight - Install glare control devices, spatial daylight autonomy, illuminance calculations OR daylight floor area measurement | 3 |
| | 1 | | | | D | Credit | Quality Views - Vision glazing for 75% of regularly occupied floor area, with at least two kinds of view types | 1 |
| Totals | | | | | | | | 10 |

| INNOVATION* | Confirmed | | | | Phase | Credit Number | Credit Name | Points Available |
|---------------|-----------|-------|----|-----------|-------|---------------|-------------------------------------|------------------|
| | Likely | Maybe | No | Confirmed | | | | |
| | | | 1 | | D | Credit | Innovation: Low Mercury Lighting | 1 |
| | | | 1 | | D | Credit | Innovation: Greenbuilding Education | 1 |
| | | | 1 | | D | Credit | TBD | 1 |
| | | | 1 | | D | Credit | TBD | 1 |
| | | | 1 | | D | Credit | TBD | 1 |
| 1 | | | | | C | Credit | LEED Accredited Professional | 1 |
| Totals | | | | | | | | 6 |

*Innovation in Design includes Exemplary Performance credits

| REGIONAL** | Confirmed | | | | Phase | Credit Number | Credit Name | Points Available |
|---------------|-----------|-------|----|-----------|-------|---------------|---|------------------|
| | Likely | Maybe | No | Confirmed | | | | |
| | | | 1 | | D | Credit | Optimize Energy Performance (10 Points) | 1 |
| 1 | | | | | D | Credit | Access to Quality Transit (5 Points) | 1 |
| | | | 1 | | D | Credit | BPDO - Raw Materials (1 point) | 1 |
| | | | 1 | | D | Credit | Rainwater Management (3 Points) | 1 |
| | | | 1 | | D | Credit | Outdoor Water Use Reduction (2 points) | 1 |
| | | | 1 | | D | Credit | Indoor Water Use Reduction (1 point) | 1 |
| Totals | | | | | | | | 4 |

**only 4 Regional Credits are Applicable

| | |
|---|-------------------|
| Confirmed Certification Level: | Not SILVER |
| Confirmed + Likely Certification Level: | Silver |
| Confirmed + Likely + Maybe Certification Level: | |
| Total Confirmed Points | 32 |
| Total Confirmed + Likely Points | 58 |
| Total Confirmed + Likely + Maybe Points | 58 |

PROJ. # 168-153 WO BART

DATE: January 18, 2019

SHEET:

LEED CHECK LIST

A-00.12

WEST OAKLAND STATION T3



NEW HOME RATING SYSTEM, VERSION 7.0

Blueprint Scoresheet




| | | Points Targeted | Community | Energy | IAQ/Health | Resources | Water | Responsible Party | Blueprint Page No. | |
|---|---|-----------------|-----------|-------------|------------|-----------|------------|-------------------|--------------------|--|
| | | Possible Points | | | | | | | | |
| CALGreen | | | | | | | | | | |
| Yes | CALGreen Res (REQUIRED) | 4 | | 1 | 1 | 1 | 1 | | | |
| C. LANDSCAPE | | | | | | | | | | |
| Yes | C1. Plants Grouped by Water Needs (Hydrozoning) | 1 | | | | | 1 | | | |
| C3. Resource Efficient Landscapes | | | | | | | | | | |
| Yes | C3.1 No Invasive Species Listed by Cal-IPC | 1 | | | | 1 | | | | |
| Yes | C3.3 Drought Tolerant, California Native, Mediterranean Species, or Other Appropriate Species | 1 | | | | | 3 | | | |
| E. EXTERIOR | | | | | | | | | | |
| Yes | E4. Durable and Non-Combustible Cladding Materials | 1 | | | | 1 | | | | |
| E5. Durable Roofing Materials | | | | | | | | | | |
| Yes | E5.2 Roofing Warranty for Shingle Roofing | Y | R | R | R | R | R | | | |
| F. INSULATION | | | | | | | | | | |
| F1. Insulation with 30% Post-Consumer or 60% Post-Industrial Recycled Content | | | | | | | | | | |
| Yes | F1.1 Walls and Floors | 1 | | | | 1 | | | | |
| F2. Insulation that Meets the CDPH Standard Method—Residential for Low Emissions | | | | | | | | | | |
| Yes | F2.1 Walls and Floors | 1 | | | 1 | | | | | |
| Yes | F2.2 Ceilings | 1 | | | 1 | | | | | |
| G. PLUMBING | | | | | | | | | | |
| G2. Install Water-Efficient Fixtures | | | | | | | | | | |
| Yes | G2.1 WaterSense Showerheads 1.8 gpm with Matching Compensation Valve | 2 | | | | | 2 | | | |
| Yes | G2.2 WaterSense Bathroom Faucets with 1.0gpm or less | 1 | | | | | 1 | | | |
| 1.28 gpf | G2.3 WaterSense Toilets with a Maximum Performance (MaP) Threshold of No Less Than 500 Grams 1.28gpf OR 1.1 gpf | 1 | | | | | 2 | | | |
| H. HEATING, VENTILATION, AND AIR CONDITIONING | | | | | | | | | | |
| H6. Whole House Mechanical Ventilation Practices to Improve Indoor Air Quality | | | | | | | | | | |
| Yes | H6.1 Meet ASHRAE Standard 62.2-2010 Ventilation Residential Standards | Y | R | R | R | R | R | | | |
| J. BUILDING PERFORMANCE AND TESTING | | | | | | | | | | |
| J5. Building Performance Exceeds Title 24 Part 6 | | | | | | | | | | |
| Option 1: Compliance Over Title 24 | J5.1 Home Outperforms Title 24 | 25 | | 25+ | | | | | | |
| N. COMMUNITY | | | | | | | | | | |
| N1. Smart Development | | | | | | | | | | |
| Yes | N1.1 Infill Site | 2 | 1 | | | 1 | | | | |
| N2. Home(s)/Development Located Near Transit | | | | | | | | | | |
| Yes | N2.2. Within 1/2 mile of a Major Transit Stop | 2 | 2 | | | | | | | |
| N3. Pedestrian and Bicycle Access | | | | | | | | | | |
| | N3.1 Pedestrian Access to Services Within 1/2 Mile of Community Services | 2 | 2 | | | | | | | |
| 10 | Enter the number of Tier 1 services | | | | | | | | | |
| 10 | Enter the number of Tier 2 services | | | | | | | | | |
| Yes | N9.2 Community Location | 2 | 1 | | 1 | | | | | |
| O. OTHER | | | | | | | | | | |
| Yes | O1. GreenPoint Rated Checklist in Blueprints | Y | R | R | R | R | R | | | |
| Yes | O2. Pre-Construction Kickoff Meeting with Rater and Subcontractors | 2 | | 0.5 | | 1 | 0.5 | | | |
| Yes | O7. Green Appraisal Addendum | Y | R | R | R | R | R | | | |
| P. DESIGN CONSIDERATIONS | | | | | | | | | | |
| P3. Commissioning | | | | | | | | | | |
| Yes | P3.1 Design Phase | 2 | | 1 | 1 | | | | | |
| Yes | P3.2 Construction Phase | 3 | | 2 | 1 | | | | | |
| Yes | P3.3 Post-Construction Phase | 3 | | 2 | 1 | | | | | |
| Summary | | | Community | Energy | IAQ/Health | Resources | Water | | | |
| Total Available Points in Specific Categories | | 375.5 | 46 | 110.5 | 70 | 95 | 54 | | | |
| Minimum Points Required in Specific Categories | | 50 | 2 | 25 | 6 | 6 | 6 | | | |
| Total Points Targeted | | 58 | 6 | 31.5 | 7 | 6 | 7.5 | | | |



WEST OAKLAND BART

1451 7th St, Oakland, CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART

DATE: January 18, 2019

LEED CHECK LIST

SHEET:

A-00.14

RELEVANT WEST OAKLAND SPECIFIC PLAN POLICY

1. Enhancements could include mitigating the sound and visual effects of the elevated BART tracks

2. Create an enhanced local transit system involving streetcar, light rail, buses, and/or shuttles to serve employment, business, and community centers.

3. Ensure adequate parking to attract and support development while encouraging alternative travel modes;

4. Improve lighting and street appearance so as to deter dumping and blight.

5. Ensure that new development employs sustainable “green” building practices, facilitates access to pedestrian and transit networks, and enhances streetscapes and open spaces.

6. Promote energy efficiency throughout all aspects of new development and redevelopment.

7. Encourage sustainable development that incorporates innovative approaches to storm water management and air pollution mitigation, and continues to enhance the well-being of residents of West Oakland.

8. Recognize and market the artisan and arts community for their contribution to social, cultural, youth education and the economic development in West Oakland.

9. Establish new grocery stores in West Oakland that can serve the un-met food needs of current and future West Oakland consumers. A grocery anchor can also create a customer flow that can be leveraged to successfully attract other retail shops that can then draw patrons from the anchor tenant’s shoppers. A safe and pleasant pedestrian environment will be necessary, especially near the transit station.

10. Neighborhood amenities such as benches, kiosks, lighting, and outdoor cafes are needed to enrich and enhance the urban setting.

NOTES ON COMPLIANCE WITH GUIDELINES

1. Residential and commercial buildings will be constructed with sound insulating window and wall construction to meet Title 24 requirements.

2. Access plan is designed to accommodate maximum flexibility of current and future transit modes. This includes planned curb space for AC Transit buses and curb drop-off for transit riders. The site has been designed to maximize the pedestrian access from all surrounding blocks. Bike access is enhanced with dedicated bike tracks on the 7th Street and Mandela Street sides of the project.

3. Site design complies. The on-site parking exceeds minimum requirements for proposed uses and will, provide adequate parking for the residential, commercial and retail uses on site. The site plan is also designed to maximize the use of transit and non-vehicular use of and access to the site. The Site design is planned to encourage pedestrian and bike access to the BART station and the public uses on site.

4. The Lighting plan will be designed to create well lighted plazas and pedestrian pathways throughout the site. The visual security of all pedestrian spaces within the site is facilitated by locating retail and other public activities along all edges of the development.

5. All new buildings and the site design meet or exceed requirements for energy efficiency and sustainable development. By developing an infill site with a high density residential and commercial uses, this development is “green” in terms of land use. The site plan has been designed to maximize transit access, pedestrian and bike access to the site and to the BART station.

6. All new buildings and the site are designed to incorporate energy efficient systems and design standards. The buildings will be designed to meet or exceed local Green Building standards. Measures employed during the design and construction of the project will contribute additional environmental benefits. These measures will promote occupant comfort while conserving water, energy, water and natural resources.

7. Site is designed to provide innovative strategies policy for achieving storm water management on site. The overall site design will meet or exceed city standard for stormwater management and air pollution mitigation. The master plan concept is designed to encourage the overall comfort and wellbeing of residents and visitors to the site. The overall plan concept will promote occupant comfort while conserving water, energy, water and natural resources.

8. The project will incorporate significant and innovative arts, education and cultural programming on site. The open spaces will be programmed with year round cultural, community and arts events that encourages use of the site, and supports the involvement of local arts and artists within the West Oakland community. This cultural, education and arts programming is incorporated into the overall design, leasing and operations to encourage and incubate the arts in West Oakland.


9. It is anticipated food, grocery or other neighborhood serving retail will be incorporated into the tenant leasing of the ground floor retail. Planning incorporates large retail spaces with loading and transit access that are conducive to these neighborhood serving uses. The pedestrian environment is designed to encourage local shopping by planning safe, active pedestrian spaces and access to promote local community use and a quality shopping pedestrian experience.

10. The site design is designed to facilitate flexible community uses including: recreation, community events, farmers markets, makers markets, arts events, festivals and other events that promote this as a destination for the local and regional community. Neighborhood amenities, such as seating, lighting, retail kiosks, cafes, maker spaces and other activated uses will be incorporated into the pedestrian edges of all public edges of the development. This will ensure that the overall development becomes a year round and activated urban community destination.



**WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

**SPECIFIC PLAN
GUIDELINE
CHECKLIST**

SHEET:
A-00.15.1

11. Potential conflicts between vehicles and pedestrians in and around the station will need to be eliminated.

12. **Mandela/7th 1: Site Planning.** Close to the West Oakland BART station, a large civic plaza should be created near the intersection of Mandela Parkway and 7th Street that is surrounded by ground floors that include publicly accessible uses such as restaurants, retail, building lobbies, galleries, and studios.

13. **Mandela/7th -2: Massing, Height.** Taller buildings are encouraged along Mandela Parkway and in particular to mark intersection of 7th St and Mandela Parkway.

14. **Mandela/7th- 3: Height.** It is encouraged that taller buildings mark the intersection of 7th Street and Mandela Parkway.

15. **Mandela /7th -4: Fenestration.** Ground floors should have large openings and a high degree of transparency in the blocks adjacent to the West Oakland BART Station.

16. **Mandela/7th - 5: Landscape.** Landscaping should be coordinated with that of the existing public landscaped areas along Mandela Parkway and should include a similarly high quality of planting and paving.

17. **7th Street TOD Env-1: New residences within the West Oakland BART Station TOD area will be subject to Title 24 of the California Code of Regulations, which requires an interior noise standard of 45 dBA DNL in any habitable room, and requires an acoustical analysis demonstrating how dwelling units have been designed to meet this interior standard. To meet the interior noise standard, a noise level reduction of up to nearly 35 dBA will likely be necessary from the exterior façades of the buildings facing towards the I-880 freeway and BART tracks and station.**

18. **7th Street TOD Env.-4: New development of all sensitive receptor uses at the West Oakland BART Station TOD sites must mitigate the anticipated health risks and air quality hazards at this location through implementation of Best Management Practices (BMPs) for air quality.**

11. The Site Circulation and Access plan is designed to coordinate the vehicle and pedestrian access and use of the site. The design intentionally mitigates potential vehicular and pedestrian by minimizing vehicular traffic Parking is restricted to non-pedestaling areas. Building loading areas are located so as to minimize pedestrian conflicts, and to minimize conflicts with transit and other access modes to the site.

12. Site design complies. A larger civic plaza and pedestrian passages have been designed into the site design to celebrate the central location of the site at the gateway to the BART station and to enhance the Mandela corridor. . This plaza is located central to the overall site in order to increase its public importance, public access, and public use for community, arts and cultural events. The central plaza is visible and accessible from Mandela and 7th Street.

13. Site design complies. Larger buildings are located on 7th street and Mandela. A signature tower will be located at the intersection of Mandela and 7th Street to create a visual icon for the West Oakland community. This massing will reinforce the importance of Mandela and 7th Street corridors.

14. Site design complies. Larger buildings are located on 7th street and Mandela. This massing will reinforce the importance of Mandela and 7th Street corridors. The urban design of the overall site locates smaller buildings along 5th and Chester Streets to transition the scale lower to the south and west portions of the site.

15. Site design complies. Ground floors have high floor to floor heights and retail with high proportion of glass store front for good retail transparency. The ground floor retail spaces are planned at all building ground floors to provide activated street edges, and to activate the interior plazas and pedestrian passages. Quality materials and varied design will be incorporated into the ground floor retail design to create visual interest for shoppers and pedestrians using the site.

16. Site design complies. Landscape plan is designed to enhance 7th street corridor and to create a high quality pedestrian experience and civic prominence. The existing trees will be replaced because of conflicts with the access plan. The new tree planting will complement the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience. Planting and paving materials will be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events. The landscape plan is designed to create a visually significant destination and center for the West Oakland community and users of the transit hub.


17. Residential and commercial buildings will be constructed with code complying sound insulating window and wall construction to meet Title 24 requirements. This includes required sound insulation from the I-880 freeway to ensure development meets necessary noise reduction criteria. The station location has reduced BART noise due to low speed of trains at this station.

18. Site design complies. The building design will use practical and cost effective Best Management Practices (BPM) practices in the design of all structures and open space to mitigate the anticipated health risks and air quality hazards. It is also the intent of the overall plan to facilitate dramatic increases in transit use which will have a major impact on the decrease in air quality hazards in the community.



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

SPECIFIC PLAN GUIDELINE CHECKLIST

SHEET:
A-00.15.2

19. Provide a more effective and substantial transition in building heights nearest to the South Prescott neighborhood, with buildings nearest to this neighborhood as low as 2-stories.

20. Ensure that new development projects along 7th Street are of compatible height and mass as the existing, newer developments within Mandela Gateway.

21. Target 15% of the new units to be built in the Plan Area between now and 2035 for low and moderate income households

22. Neighborhood Commercial 3: Height. Except when located at important intersections such as Mandela Parkway and 7th Street, buildings over 5 stories in height should generally include a significant step-back along commercial arterial roadways to harmonize the scale of new buildings with the existing neighborhood.

23. Neighborhood Commercial 8: Landscape. Publicly accessible outdoor space areas should be comprehensively designed with high quality pavement, landscaping, and seating, and are encouraged at the following locations: Mandela and 7th Street.

24. Intent: The intersection of Mandela Parkway and 7th Street needs to establish an important civic focus adjacent to the West Oakland BART station. The following Design Guidelines apply to properties immediately fronting onto the intersection of Mandela Parkway and 7th Street (see Figure A-12 and A-13).

19. Site Design complies. The project places the maximum height along Mandela and 7th Street, and transitions down to 5th Street and Chester Street. The Chester Street frontage has been designed with 3 level residential buildings that reflect more of the scale and detail of the structures of the South Prescott neighborhood, to further mitigate the height of the larger structures and to create a urban scale transition to the smaller structures in the neighborhood. It is the intent to use a more modern design vocabulary along Chester Street that uses scale and fenestration elements that relate to the neighboring structures.

20. Site design complies. The base of the larger buildings has been articulated with a cornice height, materials and a variety of window fenestrations that intentionally scales the buildings to relate to the lower existing structures along 7th Street and 5th Street neighborhood context. These larger buildings are designed with a clear separation of lower tower and upper towers to differentiate the higher structures, and to emphasize the importance of the lower buildings that create the activated street elevations.

21. Site complies. The development plan will meet or exceed the requirement for affordable units on-site. .

22. Site design complies. The lower 5 floors of the high-rise buildings have been articulated with a cornice and clear differentiation between the lower and upper portions of the building. The building massing is designed to provide a varied base and street elevation that relates to the smaller scale of the surrounding buildings along the 7th Street corridor. Residential buildings along 5th Street exceed the 5-floor step-back in order to have a well- proportioned street façade. The building base massing to provide a variety of scales to provide a visually active street scape, and to relate to the varied neighborhood context.


23. Site design complies. The landscape materials are designed with high quality stone, brick, finished concrete and other materials to create a high quality public pedestrian experience and to maximize the types of uses that can occur on site. The landscape will be designed to relate to a larger vision for the 7th Street corridor. The new tree planting will complement the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience. Planting and paving materials will be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events. The landscape plan is designed to create a visually significant destination and center for the West Oakland community and users of the transit hub.

24. Site design complies. The site is designed with a series of important civic open spaces, including: major civic plaza at 7th Street fronting BART Station entrance; Pedestrian Plaza replacing the vacated Center Street, Pedestrian Paseo along and under the trackway, expanded sidewalks and building arcades along 7th Street, expanded pedestrian sidewalks at 5th Street. These pedestrian spaces are designed with the highest level of decorative planting, paving, flexible seating and night lighting to create a community hub and activated social center for the community, and to maximize access to BART and associated transit modes.



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

SPECIFIC PLAN GUIDELINE CHECKLIST

SHEET: A-00.15.3

2. Access plan is designed to accommodate maximum flexibility of current and future transit modes. This includes planned curb space for AC Transit buses and curb drop-off for transit riders. The site has been designed to maximize the pedestrian access from all surrounding blocks. Bike access is enhanced with dedicated bike tracks on the 7th Street and Mandela Street sides of the project.

3. Site design complies. The on-site parking exceeds minimum requirements for proposed uses and will, provide adequate parking for the residential, commercial and retail uses on site. The site plan is also designed to maximize the use of transit and non-vehicular use of and access to the site. The Site design is planned to encourage pedestrian and bike access to the BART station and the public uses on site.


4. The Lighting plan will be designed to create well lighted plazas and pedestrian pathways throughout the site. The visual security of all pedestrian spaces within the site is facilitated by locating retail and other public activities along all edges of the development.

8. The project will incorporate significant and innovative arts, education and cultural programming on site. The open spaces will be programmed with year round cultural, community and arts events that encourages use of the site, and supports the involvement of local arts and artists within the West Oakland community. This cultural, education and arts programming is incorporated into the overall design, leasing and operations to encourage and incubate the arts in West Oakland.

9. It is anticipated food, grocery or other neighborhood serving retail will be incorporated into the tenant leasing of the ground floor retail. Planning incorporates large retail spaces with loading and transit access that are conducive to these neighborhood serving uses. The pedestrian environment is designed to encourage local shopping by planning safe, active pedestrian spaces and access to promote local community use and a quality shopping pedestrian experience.


10. The site design is designed to facilitate flexible community uses including: recreation, community events, farmers markets, makers markets, arts events, festivals and other events that promote this as a destination for the local and regional community. Neighborhood amenities, such as seating, lighting, retail kiosks, cafes, maker spaces and other activated uses will be incorporated into the pedestrian edges of all public edges of the development. This will ensure that the overall development becomes a year round and activated urban community destination.

11. The Site Circulation and Access plan is designed to coordinate the vehicle and pedestrian access and use of the site. The design intentionally mitigates potential vehicular and pedestrian by minimizing vehicular traffic. Parking is restricted to non-pedestaling areas. Building loading areas are located so as to minimize pedestrian conflicts, and to minimize conflicts with transit and other access modes to the site.



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

DESIGN GUIDELINE CHECKLIST


SHEET:
A-00.15.4

12. Site design complies. A larger civic plaza and pedestrian passages have been designed into the site design to celebrate the central location of the site at the gateway to the BART station and to enhance the Mandela corridor. This plaza is located central to the overall site in order to increase its public importance, public access, and public use for community, arts and cultural events. The central plaza is visible and accessible from Mandela and 7th Street.

16. Site design complies. Landscape plan is designed to enhance 7th street corridor and to create a high quality pedestrian experience and civic prominence. The existing trees will be replaced because of conflicts with the access plan. The new tree planting will complement the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience. Planting and paving materials will be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events. The landscape plan is designed to create a visually significant destination and center for the West Oakland community and users of the transit hub.


23. Site design complies. The landscape materials are designed with high quality stone, brick, finished concrete and other materials to create a high quality public pedestrian experience and to maximize the types of uses that can occur on site. The landscape will be designed to relate to a larger vision for the 7th Street corridor. The new tree planting will complement the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience. Planting and paving materials will be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events. The landscape plan is designed to create a visually significant destination and center for the West Oakland community and users of the transit hub.

24. Site design complies. The site is designed with a series of important civic open spaces, including: major civic plaza at 7th Street fronting BART Station entrance; Pedestrian Plaza replacing the vacated Center Street, Pedestrian Paseo along and under the trackway, expanded sidewalks and building arcades along 7th Street, expanded pedestrian sidewalks at 5th Street. These pedestrian spaces are designed with the highest level of decorative planting, paving, flexible seating and night lighting to create a community hub and activated social center for the community, and to maximize access to BART and associated transit modes.



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

DESIGN GUIDELINE CHECKLIST

SHEET:
A-00.15.5

13. Site design complies. Larger buildings are located on 7th street and Mandela. A signature tower will be located at the intersection of Mandela and 7th Street to create a visual icon for the West Oakland community. This massing will reinforce the importance of Mandela and 7th Street corridors.

14. Site design complies. Larger buildings are located on 7th street and Mandela. This massing will reinforce the importance of Mandela and 7th Street corridors. The urban design of the overall site locates smaller buildings along 5th and Chester Streets to transition the scale lower to the south and west portions of the site.


19. Site Design complies. The project places the maximum height along Mandela and 7th Street, and transitions down to 5th Street and Chester Street. The Chester Street frontage has been designed with 3 level residential buildings that reflect more of the scale and detail of the structures of the South Prescott neighborhood, to further mitigate the height of the larger structures and to create a urban scale transition to the smaller structures in the neighborhood. It is the intent to use a more modern design vocabulary along Chester Street that uses scale and fenestration elements that relate to the neighboring structures.

17. Residential and commercial buildings will be constructed with code complying sound insulating window and wall construction to meet Title 24 requirements. This includes required sound insulation from the I-880 freeway to ensure development meets necessary noise reduction criteria. The station location has reduced BART noise due to low speed of trains at this station.

22. Site design complies. The lower 5 floors of the high-rise buildings have been articulated with a cornice and clear differentiation between the lower and upper portions of the building. The building massing is designed to provide a varied base and street elevation that relates to the smaller scale of the surrounding buildings along the 7th Street corridor. Residential buildings along 5th Street exceed the 5-floor step-back in order to have a well-proportioned street façade. The building base massing to provide a variety of scales to provide a visually active street scape, and to relate to the varied neighborhood context.

20. Site design complies. The base of the larger buildings has been articulated with a cornice height, materials and a variety of window fenestrations that intentionally scales the buildings to relate to the lower existing structures along 7th Street and 5th Street neighborhood context. These larger buildings are designed with a clear separation of lower tower and upper towers to differentiate the higher structures, and to emphasize the importance of the lower buildings that create the activated street elevations.

15. Site design complies. Ground floors have high floor to floor heights and retail with high proportion of glass store front for good retail transparency. The ground floor retail spaces are planned at all building ground floors to provide activated street edges, and to activate the interior plazas and pedestrian passages. Quality materials and varied design will be incorporated into the ground floor retail design to create visual interest for shoppers and pedestrians using the site.



MANDELA

CHESTER

7TH STREET ELEVATION



CHESTER


MANDELA

5TH STREET ELEVATION



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

DESIGN GUIDELINE CHECKLIST

SHEET:
A-00.15.6

14. Site design complies. Larger buildings are located on 7th street and Mandela. This massing will reinforce the importance of Mandela and 7th Street corridors. The urban design of the overall site locates smaller buildings along 5th and Chester Streets to transition the scale lower to the south and west portions of the site.

18. Site design complies. The building design will use practical and cost effective Best Management Practices (BPM) practices in the design of all structures and open space to mitigate the anticipated health risks and air quality hazards. It is also the intent of the overall plan to facilitate dramatic increases in transit use which will have a major impact on the decrease in air quality hazards in the community.

19. Site Design complies. The project places the maximum height along Mandela and 7th Street, and transitions down to 5th Street and Chester Street. The Chester Street frontage has been designed with 3 level residential buildings that reflect more of the scale and detail of the structures of the South Prescott neighborhood, to further mitigate the height of the larger structures and to create a urban scale transition to the smaller structures in the neighborhood. It is the intent to use a more modern design vocabulary along Chester Street that uses scale and fenestration elements that relate to the neighboring structures.

20. Site design complies. The base of the larger buildings has been articulated with a cornice height, materials and a variety of window fenestrations that intentionally scales the buildings to relate to the lower existing structures along 7th Street and 5th Street neighborhood context. These larger buildings are designed with a clear separation of lower tower and upper towers to differentiate the higher structures, and to emphasize the importance of the lower buildings that create the activated street elevations.

22. Site design complies. The lower 5 floors of the high-rise buildings have been articulated with a cornice and clear differentiation between the lower and upper portions of the building. The building massing is designed to provide a varied base and street elevation that relates to the smaller scale of the surrounding buildings along the 7th Street corridor. Residential buildings along 5th Street exceed the 5-floor step-back in order to have a well-proportioned street façade. The building base massing to provide a variety of scales to provide a visually active street scape, and to relate to the varied neighborhood context.

15. Site design complies. Ground floors have high floor to floor heights and retail with high proportion of glass store front for good retail transparency. The ground floor retail spaces are planned at all building ground floors to provide activated street edges, and to activate the interior plazas and pedestrian passages. Quality materials and varied design will be incorporated into the ground floor retail design to create visual interest for shoppers and pedestrians using the site.

17. Residential and commercial buildings will be constructed with code complying sound insulating window and wall construction to meet Title 24 requirements. This includes required sound insulation from the I-880 freeway to ensure development meets necessary noise reduction criteria. The station location has reduced BART noise due to low speed of trains at this station.



MANDELA PKWY ELEVATION




CHESTER STREET ELEVATION



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

DESIGN GUIDELINE CHECKLIST

SHEET:
A-00.15.7

22. Site design complies. The lower 5 floors of the high-rise buildings have been articulated with a cornice and clear differentiation between the lower and upper portions of the building. The building massing is designed to provide a varied base and street elevation that relates to the smaller scale of the surrounding buildings along the 7th Street corridor. Residential buildings along 5th Street exceed the 5-floor step-back in order to have a well-proportioned street façade. The building base massing to provide a variety of scales to provide a visually active street scape, and to relate to the varied neighborhood context.




19. Site Design complies. The project places the maximum height along Mandela and 7th Street, and transitions down to 5th Street and Chester Street. The Chester Street frontage has been designed with 3 level residential buildings that reflect more of the scale and detail of the structures of the South Prescott neighborhood, to further mitigate the height of the larger structures and to create a urban scale transition to the smaller structures in the neighborhood. It is the intent to use a more modern design vocabulary along Chester Street that uses scale and fenestration elements that relate to the neighboring structures.



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019


DESIGN GUIDELINE CHECKLIST

SHEET:
A-00.15.8



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



SITE LOCATION



LOCATION OF PROJECT SITE WITHIN WEST OAKLAND NEIGHBORHOOD






5 ACRE PROJECT SITE




PROJ. # 168-153 WO BART
DATE: January 18, 2019

CONTEXT MAP

SHEET: A-00.17



SITE



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607

JRDV URBAN INTERNATIONAL
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019

CONTEXT PHOTOS


SHEET: A-00.18

Landscaped Courtyard
6,055 Square Feet Common Open Space
3,750 Private Space




BUILDING T3 - LEVEL 3 - AMENITY

Landscaped Terrace
1,673 Square Feet Common Open Space




BUILDING T3 - LEVEL 7 - AMENITY

Landscaped Terrace
7,830 Square Feet Common Open Space




BUILDING T1 - LEVEL 5 - AMENITY

Landscaped Terrace
5,712 Square Feet Common Open Space



BUILDING T1 - LEVEL 18 - AMENITY



GROUND LEVEL - OPEN SPACE 85,793 SF

Ground Level

Level 1 - Public Open Space 85,793 Square Feet

Building T3

Level 3 - Common Use Courtyard 6,055 Square Feet

Level 7 - Common Use Terrace 1,673 Square Feet

Roof Deck - Common Use Terrace 15,000 Square Feet

Levels 2-7 Private Decks & Terraces - 18,014 (x2) Square Feet

Building T1

Level 5 - Common Use Terrace 7,830 Square Feet

Level 5 - Private Decks 1,100 (x2) Square Feet


Level 28 - Common Use Terrace 5,712 Square Feet

Common Use Decks - 3,360 Square Feet



WEST OAKLAND
BART

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

OPEN
SPACE
ANALYSIS

SHEET:
A-00.19



NOTE:

EXISTING BOUNDARY FROM RECORD INFORMATION FOR PLANNING PURPOSES ONLY



0 40 80



SCALE: 1" = 80'



STAMP



WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607

PROJ. # 168-153 WO BART

DATE: January 28, 19

EXISTING
CONDITIONS
PLAN

SHEET:

C1.00

| Revisions | |
|-----------|-------------|
| No. | Description |
| | |
| | |
| | |
| | |

| | |
|-----------|------------|
| Date: | 12/06/2018 |
| Scale: | AS SHOWN |
| Design: | N/A |
| Drawn: | ADD |
| Approved: | KS |
| Job No.: | 180384 |

SYMBOLS & LEGEND

EXISTING



- FOUND CITY OF OAKLAND MONUMENT
- VALVE
- FIRE HYDRANT
- BACKFLOW PREVENTION DEVICE
- RISER
- SIGN
- STREET LIGHT (UNLESS NOTED OTHERWISE)
- LIGHT POLE (UNLESS NOTED OTHERWISE)
- GUY ANCHOR
- UTILITY POLE
- TELEPHONE MANHOLE
- MANHOLE

SUBJECT PROPERTY

- ADJOINING LOT
- CENTERLINE
- SURVEY TIE
- STORM DRAIN
- SANITARY SEWER
- OVERHEAD UTILITY LINE
- CONCRETE
- DETECTABLE WARNING

ABBREVIATIONS

- AC ASPHALT CONCRETE
- CA CABLE
- CB CATCH BASIN
- CO CLEAN OUT
- COMM COMMUNICATION
- CONC CONCRETE
- DI DROP INLET
- DWY DRIVEWAY
- E ELECTRIC
- EP EDGE OF PAVEMENT
- FL SURFACE FLOWLINE
- G GAS
- GYP GUY POLE
- INV BOTTOM INSIDE OF PIPE
- LG LIP OF GUTTER
- M METER
- MH MANHOLE
- OH OVERHEAD UTILITY LINE
- SD STORM DRAIN
- SL STREETLIGHT
- SS SANITARY SEWER
- TC TOP FACE OF CURB
- TEL TELECOMMUNICATION LINE
- TG TOP OF GRATE
- TS TRAFFIC SIGNAL
- TV TELEVISION
- UB UTILITY BOX
- V VALVE
- VLT VAULT
- W WATER
- WM WATER METER




DRAWING NAME: K:\2018\180384_180384.dwg; Author: J.M.T.; Date: 12/06/2018; Plot Date: 12/06/2018; Plot Scale: 1/2000; Plot Units: Feet; Plot Orientation: Landscape; Plot Color: Black; Plot Lineweight: 0.20; Plot Style: Standard; Plot Weight: 0.20; Plot Color: Black; Plot Lineweight: 0.20; Plot Style: Standard; Plot Weight: 0.20

SYMBOLS & LEGEND

- EXISTING**
- FOUND CITY OF OAKLAND MONUMENT
 - VALVE
 - FIRE HYDRANT
 - BACKFLOW PREVENTION DEVICE
 - RISER
 - SIGN
 - STREET LIGHT (UNLESS NOTED OTHERWISE)
 - LIGHT POLE (UNLESS NOTED OTHERWISE)
 - GUY ANCHOR
 - UTILITY POLE
 - TELEPHONE MANHOLE
 - MANHOLE
- CONCRETE**
- SUBJECT PROPERTY
 - ADJOINING LOT
 - CENTERLINE
 - SURVEY TIE
 - STORM DRAIN
 - SANITARY SEWER
 - OVERHEAD UTILITY LINE
 - CONCRETE
 - DETECTABLE WARNING

ABBREVIATIONS

- AC ASPHALT CONCRETE
- CA CABLE
- CB CATCH BASIN
- CO CLEAN OUT
- COMM COMMUNICATION
- CONC CONCRETE
- DI DROP INLET
- DWY DRIVEWAY
- E ELECTRIC
- EP EDGE OF PAVEMENT
- FL SURFACE FLOWLINE
- G GAS
- GYP GUY POLE
- INV BOTTOM INSIDE OF PIPE
- LG LIP OF GUTTER
- M METER
- MH MANHOLE
- OH OVERHEAD UTILITY LINE
- SD STORM DRAIN
- SL STREETLIGHT
- SS SANITARY SEWER
- TC TOP FACE OF CURB
- TEL TELECOMMUNICATION LINE
- TG TOP OF GRATE
- TS TRAFFIC SIGNAL
- TV TELEVISION
- UB UTILITY BOX
- V VALVE
- VLT VAULT
- W WATER
- WM WATER METER



1646 N. CALIFORNIA BLVD.,
 SUITE 400
 WALNUT CREEK, CA 94596
 (925) 940-2200
 www.bkf.com

BKF 100 YEARS
 ENGINEERS · SURVEYORS · PLANNERS

TOPOGRAPHIC AND BOUNDARY SURVEY
 WEST OAKLAND BART

CALIFORNIA
 COUNTY OF ALAMEDA

| | | | |
|-----------------|------------|------------|--|
| Date: | 12/06/2018 | No.: | |
| Scale: | AS SHOWN | Revisions: | |
| Design: | N/A | | |
| Drawn: | ADD | | |
| Approved: | KS | | |
| Job No.: | 180384 | | |
| Drawing Number: | 180384 | | |
| | 4 OF 5 | | |

DRAWING NAME: K:\DATA\180384\180384_001\180384_001.dwg
 USER: JAMES
 DATE: 12/06/2018 10:00:00 AM
 PLOT DATE: 12/06/2018 10:00:00 AM

TENTATIVE PARCEL MAP NO. 10940

FOR A VOLUNTARY MERGE OF 41 PARCELS INTO 1 LOT




TENTATIVE PARCEL MAP NO. 10940

CALIFORNIA

CITY OF OAKLAND

| | | | |
|-----------------|------------|-----|---|
| Date | 01/22/2019 | No. | |
| Scale | AS SHOWN | | |
| Design | CC | | |
| Drawn | CC | | |
| Approved | ES | | |
| Job No. | 010180384 | | |
| Drawing Number: | 1 | OF | 1 |



SYMBOLS & LEGEND

EXISTING

- FOUND CITY OF OAKLAND MONUMENT
- VALVE
- FIRE HYDRANT
- BACKFLOW PREVENTION DEVICE
- RISER
- SIGN
- STREET LIGHT (UNLESS NOTED OTHERWISE)
- LIGHT POLE (UNLESS NOTED OTHERWISE)
- GUY ANCHOR
- UTILITY POLE
- TELEPHONE MANHOLE
- MANHOLE
- SUBJECT PROPERTY
- ADJOINING LOT
- CENTERLINE
- SURVEY TIE
- STORM DRAIN
- SANITARY SEWER
- OVERHEAD UTILITY LINE
- CONCRETE
- DETECTABLE WARNING
- PROPOSED LOT LINE

ABBREVIATIONS

- AC ASPHALT CONCRETE
- CA CABLE
- CB CATCH BASIN
- CO CLEAN OUT
- COMM COMMUNICATION
- CONC CONCRETE
- DI DROP INLET
- DWY DROVEWAY
- E ELECTRIC
- EP EDGE OF PAVEMENT
- EVAE EMERGENCY VEHICLE ACCESS EASEMENT
- FL SURFACE FLOWLINE
- G GAS
- GYP GUY POLE
- INV BOTTOM INSIDE OF PIPE
- LG LIP OF GUTTER
- M METER
- MH MANHOLE
- OH OVERHEAD UTILITY LINE
- SD STORM DRAIN
- SL STREET LIGHT
- SS SANITARY SEWER
- TC TOP FACE OF CURB
- TEL TELECOMMUNICATION LINE
- TG TOP OF GRATE
- TS TRAFFIC SIGNAL
- TV TELEVISION
- UB UTILITY BOX
- V VALVE
- VLT VAULT
- W WATER
- WM WATER METER

PROPERTY ADDRESS:

1451 7TH STREET
OAKLAND, CA 94607
510-465-2278

OWNER AND SUBDIVIDER:

SAN FRANCISCO BAY AREA RAPID TRANSIT DISTRICT
300 LAKESIDE DRIVE, 22ND FLOOR
OAKLAND, CA 94012
510-597-6300

BASIS OF BEARINGS

THE BEARING OF NORTH 72°53'28" WEST BETWEEN FOUND MONUMENTS ON 5TH AVENUE BETWEEN HENRY STREET AND KIRKHAM STREET AS SHOWN ON THAT RECORD OF SURVEY, R/S 1687, FILED AUGUST 7, 2000 IN BOOK 25 OF RECORDS OF SURVEY AT PAGES 58-69, INCLUSIVE, ALAMEDA COUNTY RECORDS, WAS TAKEN AS THE BASIS OF BEARINGS FOR THIS SURVEY.

BENCHMARK

THE ELEVATIONS SHOWN HEREON ARE BASED ON A FOUND CITY OF OAKLAND BENCHMARK, DESIGNATION 25/H, BEING A BRONZE DISK STAMPED, "SEC 25 STA H," ELEVATION 10.784 FEET (DATUM = MEAN SEA LEVEL).

NOTES

- THE CONTROL SURVEY WAS CONDUCTED IN NOVEMBER OF 2018.
- ALL UNITS ARE IN US SURVEY FEET AND DECIMALS THEREOF.
- THE PROPERTY BOUNDARY SHOWN HEREON IS BASED ON AN ONGOING BOUNDARY RESOLUTION SURVEY. THIS RESOLVED BOUNDARY SURVEY WILL BE COMPLETED IN CONFORMANCE WITH THE REQUIREMENTS OF THE PROFESSIONAL LAND SURVEYORS' ACT PRIOR TO PARCEL MAP SUBMITTAL.
- THE TOPOGRAPHIC MAPPING SHOWN HEREON IS A WORKING DOCUMENT. THE TOPOGRAPHIC SURVEY AND MAPPING IS IN PROGRESS AND HAS NOT BEEN COMPLETED OR FINALIZED.
- ALL BUILDINGS TO THE NORTH OF THE BART STATION SHALL BE SET BACK A MINIMUM OF 30' FROM THE BART PLATFORM, AND ALL BUILDINGS TO THE SOUTH OF THE BART STATION SHALL BE SET BACK A MINIMUM OF 33' FROM THE BART PLATFORM.
- ALL EMERGENCY VEHICLE ACCESS EASEMENTS SHALL BE A MINIMUM OF 26' WIDE.

SURVEYOR'S STATEMENT:


THIS MAP CORRECTLY REPRESENTS A SURVEY MADE BY ME OR UNDER MY DIRECTION IN CONFORMANCE WITH THE REQUIREMENTS OF THE PROFESSIONAL LAND SURVEYOR'S ACT.

BARRY WILLIAMS, P.L.S. NO. 6711



DATE: _____




| Tree number | DBH (in) | Species Name |
|-------------|----------|-------------------------|
| 16 | 36 | Pinus Pinea |
| 17 | 32 | Pinus Pinea |
| 20 | 13 | Liriodendron Tulipifera |
| 27 | 12 | Maytenus Boaria |
| 29 | 16 | Maytenus Boaria |
| 31 | 13 | Liriodendron Tulipifera |
| 33 | 13 | Liriodendron Tulipifera |
| 36 | 12 | Liriodendron Tulipifera |
| 48 | 18 | Platanus X Acerifolia |
| 51 | 17 | Platanus X Acerifolia |
| 52 | 12 | Liriodendron Tulipifera |



DRAWING NAME: K:\2018\180384_West_Oakland_BART_TOD_Survey\ENG\TENTATIVE_PARCEL_MAP\WOBART_TMAP.dwg
PLOT DATE: 01-28-19 PLOTTED BY: chuc



STAMP




WEST OAKLAND
 BART
 1451 7th St, Oakland,
 CA 94607

PROJ. # 168-153 WO BART
 DATE: December 06, 18

LOT
 MERGER
 PLAN

SHEET:
 C1.01



ABBREVIATIONS:

| | |
|----|------------------|
| FF | FINISHED FLOOR |
| FG | FINISHED GROUND |
| FS | FINISHED SURFACE |
| FL | FLOW LINE |
| MA | MATCH |
| TC | TOP OF CURB |
| TS | TOP OF STEP |
| TW | TOP OF WALL |

GRADING NOTES:

1. TC ELEVATIONS ARE 6" ABOVE ADJACENT PAVEMENT FL ELEVATIONS, UNLESS OTHERWISE NOTED ON PLAN.

LEGEND:


- DIRECTION OF PROPOSED DRAINAGE
- GRADE BREAK
- CONTOUR

EARTHWORK SUMMARY:

TOTAL EXCAVATION: 51,303 CUBIC YARDS
 TOTAL FILL: 0 CUBIC YARDS
 TOTAL OFFHAUL: 51,303 CUBIC YARDS



STAMP




WEST OAKLAND
 BART
 1451 7th St, Oakland,
 CA 94607





PROJ. # 168-153 WO BART
 DATE: December 06, 18

PROPOSED
 GRADING
 PLAN

SHEET:
 C2.00




LEGEND:


-  DRAINAGE MANAGEMENT AREA (DMA)
-  PERMEABLE PAVERS
-  FILTER VAULT
SEE SHEET C3.01
-  TREATMENT AREA LABEL

STORMWATER MANAGEMENT NOTES:

1. THE TREATMENT VAULTS WERE SELECTED BASED ON 243,131 SF OF IMPERVIOUS SURFACE AND A TREATMENT INTENSITY OF 0.2 IN/HR. SEE OLD CASTLE WASHINGTON GULD PF-V-8-WA-0001 PERK FILTER DETAIL ON SHEET C3.01. ALL FILTER VAULTS SHOWN ARE COMPRISED OF (31) - 18" CARTRIDGES.



0 40 80



SCALE: 1" = 80'

| DMA | Impervious Area (SF) | Pervious Area (SF) | Treatment Type | Designated Treatment Area |
|-----|----------------------|--------------------|------------------|---------------------------|
| 1 | 74,600 | 28,445 | Filter Vault | T1 |
| 2 | 58,278 | 0 | Filter Vault | T2 |
| 3 | 69,667 | 0 | Filter Vault | T3 |
| 4 | 0 | 12,140 | Permeable Pavers | T4 |

| TOTAL SITE AREA (SF) | TOTAL LAND AREA DISTURBED (SF) | TOTAL EXISTING/PRE-PROJECT IMPERVIOUS SURFACE (SF) | REPLACED IMPERVIOUS SURFACE (SF) | NEW IMPERVIOUS SURFACE (SF) | TOTAL POST-PROJECT IMPERVIOUS SURFACE (SF) |
|----------------------|--------------------------------|--|----------------------------------|-----------------------------|--|
| 243,130 | 243,130 | 212,865 | 177,410 | 25,135 | 202,545 |



STAMP




WEST OAKLAND
BART
1451 7th St, Oakland,
CA 94607




PROJ. # 168-153 WO BART
DATE: December 06, 18

STORMWATER
MANAGEMENT
PLAN

SHEET:
C3.00





EROSION CONTROL LEGEND:

-  STABILIZED CONSTRUCTION ENTRANCE (TC-1)**
WITH ENTRANCE/OUTLET TIRE WASH (TC-3)**
-  STORM DRAIN INLET PROTECTION (SC-10)**
-  FIBER ROLL (SC-05)**

**REFER TO SHEET C4.01 FOR DETAILS

EROSION CONTROL NOTES:

1. SITE ACCESS SHOWN ON THIS PLAN IS PROVIDED FOR INFORMATION PURPOSES ONLY. CONTRACTOR SHALL LOCATE CONSTRUCTION ACCESS DRIVEWAYS AS NECESSARY.
2. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN EFFECT AND MAINTAINED BY THE CONTRACTOR ON A YEAR-ROUND BASIS UNTIL ALL DISTURBED AREAS ARE STABILIZED UNLESS OTHERWISE PERMITTED BY THE COUNTY INSPECTOR.
3. ALL INLETS RECEIVING STORM WATER RUNOFF FROM THE PROJECT AREA MUST BE EQUIPPED WITH REQUIRED INLET PROTECTION.
4. ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIALS AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT LADEN RUNOFF ENTERING THE STORM DRAIN SYSTEM.
5. STOCKPILED EARTHEN MATERIAL SHALL BE EITHER COVERED WITH A TARP OR WATERED SUFFICIENTLY TO ELIMINATE DUST.
6. REFERENCE: "CALIFORNIA STORM WATER BEST MANAGEMENT PRACTICE (BMP) HANDBOOK", JANUARY 2015.



STAMP





WEST OAKLAND
BART
1451 7th St, Oakland,
CA 94607

PROJ. # 168-153 WO BART
DATE: December 06, 18

EROSION
CONTROL
PLAN

SHEET:
C4.00




SECTION A-A


NOTES:

1. PLACE CURB TYPE SEDIMENT BARRIERS ON GENTLY SLOPING STREET SEGMENTS, WHERE WATER CAN POND AND ALLOW SEDIMENT TO SEPARATE FROM RUNOFF.
2. SANDBAGS OF EITHER BURLAP OR WOVEN 'GEOTEXTILE' FABRIC, ARE FILLED WITH GRAVEL LAYERED AND PACKED TIGHTLY.
3. LEAVE A ONE SANDBAG GAP IN THE TOP ROW TO PROVIDE A SPILLWAY FOR OVERFLOW.
4. INSPECT BARRIERS AND REMOVE SEDIMENT AFTER EACH STORM EVENT. SEDIMENT AND GRAVEL MUST BE REMOVED FROM THE TRAVELED WAY IMMEDIATELY.

① CURB INLET SEDIMENT BARRIER
NOT TO SCALE



ENTRENCHMENT DETAIL
IN FLAT AREA




ENTRENCHMENT DETAIL
IN SLOPED AREA

NOTES

1. FIBER ROLLS ARE TUBES MADE FROM POROUS BIODEGRADABLE FIBER STUFFED IN A PHOTO-DEGRADABLE OPEN WEAVE NETTING. THEY ARE APPROXIMATELY 8" DIAMETER.
2. FIBER ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE ROLL IN A TRENCH, 2"-4" DEEP, DUG ON CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND ROLL. ROLLS SHOULD BE ABUTTED SECURELY TO PROVIDE A TIGHT JOINT, NOT OVERLAPPED.

② FIBER ROLL
NOT TO SCALE



Notes:

1. The entrance shall be maintained to prevent sediment tracking or flowing onto public right-of-ways. This may require top dressing, repair and/or cleanout or other measures that trap sediment.
2. When necessary, wheels shall be cleaned prior to entering public right-of-way.
3. When washing is required, it shall be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin.

③ Site Entrance



STAMP




WEST OAKLAND
BART
1451 7th St, Oakland,
CA 94607

PROJ. # 168-153 WO BART
DATE: December 06, 18

EROSION
CONTROL
PLAN DETAILS

SHEET:
C4.01



Trees Proposed for Removal

| Key | Species | DBH (in) |
|-----|--------------------|----------|
| 1 | Pistacia chinensis | 4 |
| 2 | Pistacia chinensis | 4 |
| 3 | Pistacia chinensis | 4 |
| 4 | Pistacia chinensis | 3 |
| 5 | Pistacia chinensis | 5 |
| 6 | Pistacia chinensis | 4 |
| 7 | Pistacia chinensis | 4 |
| 8 | Pistacia chinensis | 4 |
| 9 | Pistacia chinensis | 4 |
| 10 | Pistacia chinensis | 4 |
| 11 | Pistacia chinensis | 4 |
| 12 | Pistacia chinensis | 4 |
| 13 | Pistacia chinensis | 4 |

| Key | Species | DBH (in) |
|-----|-------------------------|----------|
| 14 | Pistacia chinensis | 4 |
| 15 | Pistacia chinensis | 4 |
| 16 | Pinus pinea | 36 |
| 17 | Pinus pinea | 32 |
| 18 | Liriodendron tulipifera | 9 |
| 19 | Liriodendron tulipifera | 11 |
| 20 | Liriodendron tulipifera | 13 |
| 21 | Pistacia chinensis | 4 |
| 22 | Pistacia chinensis | 4 |
| 23 | Pistacia chinensis | 4 |
| 24 | Pistacia chinensis | 4 |
| 25 | Pistacia chinensis | 5 |
| 26 | Maytenus boaria | 7 |

| Key | Species | DBH (in) |
|-----|-------------------------|----------|
| 27 | Maytenus boaria | 12 |
| 28 | Maytenus boaria | 5 |
| 29 | Maytenus boaria | 16 |
| 30 | Maytenus boaria | 2 |
| 31 | Liriodendron tulipifera | 13 |
| 32 | Liriodendron tulipifera | 11 |
| 33 | Liriodendron tulipifera | 13 |
| 34 | Liriodendron tulipifera | 11 |
| 35 | Liriodendron tulipifera | 9 |
| 36 | Liriodendron tulipifera | 12 |
| 37 | Liriodendron tulipifera | 11 |
| 38 | Liriodendron tulipifera | 10 |
| 39 | Liriodendron tulipifera | 11 |

| Key | Species | DBH (in) |
|-----|-------------------------|----------|
| 40 | Liriodendron tulipifera | 9 |
| 41 | Liriodendron tulipifera | 10 |
| 42 | Liriodendron tulipifera | 10 |
| 43 | Liriodendron tulipifera | 9 |
| 44 | Liriodendron tulipifera | 7 |
| 45 | Liriodendron tulipifera | 8 |
| 46 | Liriodendron tulipifera | 8 |
| 47 | Liriodendron tulipifera | 9 |
| 48 | Platanus X acerifolia | 18 |
| 49 | Platanus X acerifolia | 10 |
| 50 | Platanus X acerifolia | 10 |
| 51 | Platanus X acerifolia | 17 |
| 52 | Liriodendron tulipifera | 12 |

| Key | Species | DBH (in) |
|-----|-------------------------|----------|
| 53 | Liriodendron tulipifera | 8 |
| 54 | Liriodendron tulipifera | 8 |
| 55 | Liriodendron tulipifera | 9 |
| 56 | Liriodendron tulipifera | 10 |
| 57 | Liriodendron tulipifera | 5 |
| 58 | Liriodendron tulipifera | 8 |
| 59 | Liriodendron tulipifera | 7 |
| 60 | Liriodendron tulipifera | 9 |
| 61 | Maytenus boaria | 5 |
| 62 | Maytenus boaria | 5 |
| 63 | Maytenus boaria | 7 |

Bolded trees are protected trees.



LANDSCAPE ARCHITECTS



STAMP

WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607


PROJ. # 168-153 WO BART

DATE: JANUARY 11, 2019

**TREE REMOVAL
PLAN**

SHEET:


L-00.01



- ① CYCLE TRACK a separated, protected bike lane located adjacent to 7th street, distinct from both the sidewalk and 7th street.
- ② PERVIOUS PAVING see Stormwater Management Plan
- ③ ALLEY OF LIGHTS
- ④ OPEN PLAZA the space between 7th Street and the fair gates to the station will be kept open

- ⑤ EMEGENCY VEHICLE ACCESS
- ⑥ GREENWALLS, TYP. Vertical panels of wire mesh with living plants, 15' high.
- ⑦ PEDESTRIAN HARDSCAPE paving bands of concrete pavers, poured in place colored concrete, and stone highlights.

- ⑧ MOVEABLE FURNITURE custom planters, benches, seats, and tables, that can be manually positioned to create a variety of seating arrangements and support a variety of programed activities.
- ⑨ STREETSCAPE sidewalks designed with a substructure to support healthy street trees.



LANDSCAPE ARCHITECTS



STAMP

WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607

PROJ. # 168-153 WO BART

DATE: JANUARY 11, 2019

LANDSCAPE PLAN ON-GRADE

SHEET:

L-00.02

Planting Design Intent & Notes

- 1 The project planting and irrigation design will be designed with low water use plants and efficient irrigation system which will meet the state's model water efficient landscape ordinance. Completed calculations and worksheets will be provided during building permit phase.
- 2 Plants selected will be primarily low water use and irrigation will consist of subsurface drip with a smart irrigation controller.
- 3 All shrubs, groundcovers, trees and vines selected for planting are low water use. All shrubs and groundcover areas (non-turf areas) to be irrigated with drip irrigation. All turf areas irrigated with high-efficiency spray.
- 4 Non-turf areas: at least 75% of the plant selection is native or climate appropriate low water use species and require minimal water once established. Up to 25% of the plants may be non-drought tolerant variety as long as they are appropriately grouped together and irrigated separately and efficiently as hydrozones.
- 5 No planted species can be listed by CAL-IPC (California Invasive Plant Council) as invasive in the San Francisco bay area, and plant right, keep invasive plants in check by California Horticultural Invasive's Prevention (CAL-HIP).

Irrigation Design Intent & WELO

- 1 Irrigation system will be designed to provide the minimum amount of water necessary to sustain good plant health. All selected components to be commercial grade, selected for durability, vandal resistance and minimum maintenance requirement.
- 2 The system will be a combination of overhead sprinkler and subsurface irrigation as appropriate to plant type, exposure and slope conditions.
- 3 Control of the system will be via a weather-enabled controller capable of daily self-adjustment based on real-time weather conditions as measured by an on-site weather sensor.
- 4 The system will include a master control valve and flow sensing capability which will shut down all or part of the system if leaks are detected.
- 5 The landscape is over 2,500 square feet of new landscaping and will therefore meet the requirements of the water efficiency landscape ordinance (WELO): <https://water.ca.gov/legacyfiles/wateruseefficiency/docs/mwelo09-10-09.pdf>

Irrigation Notes will Comply with Following:

- Landscape design to comply with City of Oakland Bay-Friendly's ordinance, in addition the nine required practices are summarized below:
- 1 Mulch all shrub areas with 3-inch-thick layer of mulch. All soil on site is protected with a minimum of 3 inches of mulch after construction. All mulch is arbor waste material.
 - 2 Amend soil with compost before planting. Compost is specified as the soil amendment, at the rates indicated by a soil analysis to bring the soil organic matter content to a minimum of 3.5% by dry weight or 1 inch of compost. Option 1: require import topsoil to meet organic matter content of a minimum 3.5% by dry weight. Option 2: submit soils report that identifies existing topsoil meets organic matter content of 3.5% by dry weight or greater.
 - 3 Reduce and recycle landscape construction waste. Divert 50% of landscape construction and demolition waste by volume or weight.
 - 4 Choose and locate plants that grow to natural size and avoid shearing. No plant species will require shearing. Select species and spacing to allow plants to grow to natural size and shape without shearing at any point in the lifespan of the plant, excluding structural and regular maintenance.

- 5 Do not plant invasive species. None of the plant species listed by CAS-IPC as invasive in the San Francisco Bay area are included in the planting design.
- 6 Grow drought tolerant, California native, Mediterranean, or climate adapted plants. A minimum of 75% of the total number of plants in the non-turf areas must be species that require no or little summer watering once established. Species should be adapted to the climate in which they will be planted, as referenced by a third-party source. Plant shall be rated for moderate or occasional water use for this region and climate.
- 7 Minimize turf. A maximum of 25% of total irrigated area is specified as turf, with sports or multi-use fields exempted.
- 8 Specify automatic weather-based controller with soil moisture and/or rain sensor. Weather-based irrigation controllers, soil moisture-based controllers, or other self-adjusting irrigation controllers, shall be required for entire irrigation system.
- 9 Sprinkler and spray heads are not specified in areas less than 8 feet wide. Sprinkler and spray heads are not specified in areas less than or equal to 8 feet wide to prevent overspray and runoff. Acceptable alternatives include bubbler or drip with subsurface rigid lateral pipes. Bubblers shall not exceed 1.5 gallons per minute per bubbler.

- 1 OPEN GREEN
- 2 ROOFTOP DINNING ROOM SERVES AS OUTDOOR DINING ARE FOR RESIDENTS AND GUESTS
- 3 OUTDOOR KITCHEN AND GRILL
- 4 MOVEABLE TABLES AND CHAIRS
- 5 COMMUNAL SEATING UNDER CANOPY
- 6 WOOD LOUNGE PLATFORMS
- 7 EDIBLE GARDEN




T-3 COURTYARD PLAN

- 1 ROOFTOP DINNING ROOM SERVES AS OUTDOOR DINING ARE FOR RESIDENTS AND GUESTS
- 2 OUTDOOR KITCHEN AND GRILL
- 3 MOVEABLE TABLES AND CHAIRS
- 4 TREE SHADED WOOD LOUNGE PLATFORMS
- 5 EDIBLE GARDEN
- 6 BUFFER PLANTING
- 7 PRIVATE DECK OVERLOOKS gathering areas for small groups
- 8 DOG RUN fully enclosed artificial turf with expandable overhead canopy
- 9 BOCCIE COURT
- 10 CHILDREN PLAY SPACE
- 11 GAS FIRE PIT
- 12 WOOD DECK



T-3 ROOF DECK PLAN



STAMP

WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607

PROJ. # 168-153 WO BART

DATE: JANUARY 11, 2019

LANDSCAPE PLAN
ON-STRUCTURE

SHEET:

L-00.03



Gleditsia triacanthos 'Street Keeper'



Azara microphylla 15'x15'



Mahonia 'Soft Caress' 4'x4'



Agave attenuata 'Raea's Gold' 3'x3'



Cordyline 'Design-a Line' 3'x3'



Pittosporum tobira 'Mojo' 3'x3'



Digiplexis Illumination 'Apricot' 2'Hx18"W



Phormium 'Tony Tiger' 2.5'x2.5'



Echeveria 'Black Prince' 1'x1'



Mahonia repens 18"Hx3'W



LANDSCAPE ARCHITECTS



STAMP

WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607

PROJ. # 168-153 WO BART

DATE: JANUARY 11, 2019

PROPOSED PLANTS- IMAGES

SHEET:

L-00.04



Prunus seratta



Helleborus argutifolius 3'x3'



Abutilon megapotamicum 'Lemon' 3'x3'



Arctostaphylos 'Emeral Carpet'



Maytenus boaria



Acer palmatum 'Sango kaku' 12'Hx8"W



Berberis 'Orange Rocket' 4'Hx2'W



Phormium 'Yellow Wave'



Cotinus coggygria



Arbutus 'Marina' Multi trunk 15'x15'



Nandina domestica Alba 'Lemon-Lime' 4'Hx3'W



Woodwardia fimbriata



Carex divulsa



LANDSCAPE ARCHITECTS



STAMP

WEST OAKLAND

BART

1451 7th St, Oakland, CA 94607

PROJ. # 168-153 WO BART

DATE: JANUARY 11, 2019

PROPOSED PLANTS- IMAGES

SHEET:

L-00.05



PERVIOUS PAVING



CONCRETE PAVERS



COLORED CONCRETE



STAMP

WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607

PROJ. # 168-153 WO BART

DATE: JANUARY 11, 2019

PROPOSED PAVING- IMAGES

SHEET:

L-00.06

ASPENTI COLLECTION

Aspenti provides a modern industrial look with flexible illumination options. The integrated LED light with a textured diffuser illuminates up and down.



ASPENTI 20
CHARCOAL


ASPENTI 14
BRONZE

ASPENTI 5
CHARCOAL

ASPENTI 20

MODEL: **OD1061**
FINISH: **BZ** bronze
CH charcoal
LAMP: **LED930** integrated LED; 120v; 10.4w; 996 delivered lumens; 3000K; 90 CRI
LED 930277 integrated LED; 277v; 10.4w; 996 delivered lumens; 3000K; 90 CRI

LOCATION: **W** wet




sample item number: **OD1061BZLED930W**
Aspenti 20, bronze, integrated LED, wet

ASPENTI 14

MODEL: **OD1062**
FINISH: **BZ** bronze
CH charcoal
LAMP: **LED930** integrated LED; 120v; 10.4w; 996 delivered lumens; 3000K; 90 CRI
LED 930277 integrated LED; 277v; 10.4w; 996 delivered lumens; 3000K; 90 CRI

LOCATION: **W** wet




sample item number: **OD1062CHLED930W**
Aspenti 14, charcoal, integrated LED, wet

ASPENTI 5

MODEL: **OD1060**
FINISH: **BZ** bronze
CH charcoal
LAMP: **LED930** integrated LED; 120v; 10.4w; 996 delivered lumens; 3000K; 90 CRI
LED 930277 integrated LED; 277v; 10.4w; 996 delivered lumens; 3000K; 90 CRI

LOCATION: **W** wet




sample item number: **OD1060CHLED930W**
Aspenti 5, charcoal, integrated LED, wet



WALL LIGHTING

Domus Luminaire



Manufacturer(s): Lumec

Catalog #:
DMS50-HPS-SC3M-SMB-SCITX (Large Domus)
DOSHPS-SG3--SMB-SCITX-LMS (Small Domus)

Photometric File:
s0105312.ies (Domus DMS50, 200-250W)
s0206071.ies (Domus DOS, 35-150W)

Application:
Domus DMS50 - Arterial and/or collector street lighting
Domus DOS - Residential street lighting and/or sidewalk side pedestrian lighting

Lamp Type: 35W, 100W, 150W, 250W HPS

Optical System: Type III

Ballast Voltage: Multi-tap 120/240V

Color: Teal Green only

Special Requirements:

Luminaire Cost: \$\$\$

As shown: Domus DOS luminaire w/ 3' arm on 16' octagonal pole.
Color: Teal Green
Location: Coliseum Gardens



Page 19 of 71

STREET LIGHTING



Ritorno® Square Asymmetrical selux



| Series | Mounting | Height | Lamping | Lamp Color | Finish | Voltage | Options | | | | |
|---|-----------------------------|---------------------|---------------------|------------------------|--|---------------------------------|--|-------------|------------------|--|--|
| RSA Ritorno® Square Asymmetrical | 1 Single W Wall Mount | RP10 10 ft. | Metal Halide | | WH White BK Black BZ Bronze SV Silver SP Specify Premium Color | 120 208 240 277 347 | REC GFCI Receptacle (pole mount only) FS ¹ Single Fusing Consult factory for other options. | | | | |
| | | RP12 12 ft. | NOL | No Lamp Supplied | | | | 830 3000° K | | | |
| | | RP14 14 ft. | H050 | 50w | | | | 830 3000° K | | | |
| | | RP16 16 ft. | H070 | 70w | | | | 940 4200° K | | | |
| | | | H100 | 100w | | | | | | | |
| | | | H150 | 150w | | | | | | | |
| | | | | T8 Metal Halide | | | | NOL | No Lamp Supplied | | |
| | | | | H070T6 ² | | | | 70w | 830 3000° K | | |
| | | | | H150T6 | | | | 150w | 942 4200° K | | |
| | | | | HPS | | | | NOL | No Lamp Supplied | | |
| | | | | S050 ² | | | | 50w | 221 2100° K | | |
| | | | | S070 | | | | 70w | | | |
| | | S100 | 100w | | | | | | | | |
| | | S150 | 150w | | | | | | | | |
| | | QL Induction | | 830 3000° K | | | | | | | |
| | | QL85 ¹ | 85w | 840 4000° K | | | | | | | |
| | | QL165 ¹ | 165w | 850 5000° K | | | | | | | |

¹ Not available with 347V ² Not available with 240V/208V

Selux Corp. © 2015
TEL (845) 834-1400
FAX (845) 834-1401
www.selux.us
RSA-0715-01 (SS-v3.5)

NRTL Listed (i.e. UL, CSA)

Union Made Affiliated
with IBEW Local 363



In a continuing effort to offer the best product possible, we reserve the right to change, without notice, specifications or materials that in our opinion will not alter the function of the product. Specification sheets found at www.selux.us are the most recent versions and supersede all other printed or electronic versions.

PEDESTRIAN LIGHTING ON PLAZA



LANDSCAPE ARCHITECTS



STAMP

WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607

PROJ. # 168-153 WO BART
DATE: JANUARY 11, 2019

PROPOSED
LIGHTING-
IMAGES

SHEET:

L-00.07



LANDSCAPE ARCHITECTS



STAMP

WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607

PROJ. # 168-153 WO BART

DATE: JANUARY 11, 2019

PRELIMINARY LIGHTING PLAN


SHEET:

L-00.08



LEGEND

-  WALL LIGHTING
-  STREET LIGHTING
-  PEDESTRIAN LIGHTING



Plazas & Pedestrian Walkways

Public Space Improvements:

The public spaces for the West Oakland Station site will be designed to reinforce the vibrant mixed-use development that furthers Oakland's efforts to promote urban living at key transit sites, and provides an active and delightful center for the West Oakland community.

The site is designed with a series of important civic open spaces, including:


- **Mandela Plaza**, major community civic plaza at 7th Street fronting BART Station entrance;
- **Maker Square**, a pedestrian plaza replacing the vacated Center Street, and
- **Art Alley**, a pedestrian paseo along the BART trackway.

The perimeter of the site is designed to promote public access and to provide an enhanced pedestrian experience, with expanded sidewalks and retail frontages along 7th and 5th Streets.

Hardscape and Green-scape Design:

Landscape plan should be designed to enhance the pedestrian public spaces to create a high quality of pedestrian experience and civic prominence. The existing trees will be replaced because of conflicts with the access plan.

The new tree planting will complement the overall landscape strategy of the 7th and 5th Street corridors to ensure a continuous, interesting and varied visual experience. Planting and paving materials shall be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events.



Landscape Materials: The landscape materials are designed with high quality stone, brick, finished concrete and other materials to create a high quality public pedestrian experience and to maximize the types of uses that can occur on site. The landscape will be designed to relate to a larger vision for the 7th Street corridor. The new tree planting will complement the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience.


Planting and paving materials will be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events.

Site Lighting: The Lighting plan will be designed to create well lighted plazas and pedestrian pathways through the site. The visual security of all pedestrian spaces within the site is facilitated by locating retail and other public activities along all edges of the development. The landscape plan will provide adequate lighting to provide a safe environment while conforming to current best practices to mitigate light pollution.



WEST OAKLAND BART

1451 7th St, Oakland, CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

PUBLIC SPACE IMPROVEMENT: PLAZA & PUBLIC WALKWAYS

SHEET: A-10.00.0

Mandela Plaza

Mandela Plaza - Community Civic Space:

A larger civic plaza will be provided along 7th Street at the BART station to provide increased visibility and access to the BART station, and also to celebrate the civic importance of this site in the community. This plaza is located to be central to the overall site in order to increase its public importance, public access, and public use for community, arts and cultural events. The central plaza should be designed to enhance the 7th Street corridor activation and public experience.

The Landscape plan is designed to enhance 7th street corridor and to create a high quality pedestrian experience and civic prominence.

The new tree planting will complement the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience.

Paving materials will be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events. The landscape plan is designed to create a visually significant destination and center for the West Oakland community and users of the transit hub.



VIEW FROM 7TH STREET




VIEW FROM 7TH STREET



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019

PUBLIC SPACE IMPROVEMENT: MANDELA PLAZA

SHEET:
A-10.00.1

Mandela Plaza



VIEW OF BART ENTRANCE AT 7TH STREET




VIEW FROM CHESTER STREET



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

PUBLIC SPACE
IMPROVEMENT:
ART ALLEY

SHEET: A-10.00.2

Art Alley

Art Alley: The mid-block passage south of the BART trackway will be designed as an active pedestrian paseo. Buildings will set back to provide both adequate emergency vehicle access and to create a delightful and activated pedestrian passage through the site to the BART station. The space will be lined with public uses that activate the space, including: retail kiosks, maker spaces, a bike station, and other cultural uses that provide day and night activation and safety for pedestrians using the space. Art and other cultural/historical installations should be introduced into this space to provide a meaningful and innovative public experience.

Landscape Materials: The landscape materials are designed with high quality stone, brick, finished concrete and other materials to create a high quality public pedestrian experience and to maximize the types of uses that can occur on site.

Site Lighting: The Lighting plan will be designed to create well lit plazas and pedestrian pathways through the site. The visual security of all pedestrian spaces within the site is facilitated by locating retail and other public activities along all edges of the development. The landscape plan will provide adequate lighting to provide a safe environment while conforming to current best practices to mitigate light pollution.



VIEW FROM CHESTER STREET



VIEW AT MAKER SQUARE




VIEW FROM MANDELA PARKWAY



WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

PUBLIC SPACE
IMPROVEMENT:
ART ALLEY

SHEET: A-10.00.2

Maker Square

Maker Square: The vacated Center Street will be transformed into an active urban destination for the neighborhood. This space is both an important pedestrian connection to the BART station and a significant public plaza for the surrounding community. It will be lined with public uses, including: retail, food, cultural and maker spaces. The space will be an inviting place for the neighborhood to shop, dine, and relish a quality community experience.

The landscape materials are designed with high quality stone, brick, finished concrete and other materials to create a high quality public pedestrian experience and to maximize the types of uses that can occur on site.

Site Lighting: The Lighting plan will be designed to create well lit plazas and pedestrian pathways through the site. The visual security of all pedestrian spaces within the site is facilitated by locating retail and other public activities along all edges of the development. The landscape plan will provide adequate lighting to provide a safe environment while conforming to current best practices to mitigate light pollution.



VIEW FROM 5TH STREET



VIEW TOWARD BART STATION




VIEW OF ART ALLEY FROM MAKER SQUARE



WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

PUBLIC SPACE
IMPROVEMENT:
MAKER SQUARE

SHEET:
A-10.00.3

Sidewalks

7th Street (between Mandela Parkway and Chester Street):


The sidewalk width will be min 8' pedestrian clear zone. in order to accommodate the needs of pedestrians, bus passengers, and curbside passenger loading. The sidewalk will be buffered from adjacent parking and street traffic by a street furnishings zone including pedestrian-scale lighting and street trees and/or other plantings.

5th Street (between Mandela Parkway and Center Street):

The sidewalk width will be min 8' pedestrian clear zone in order to accommodate the needs of pedestrians, bus passengers, and curbside passenger loading.

5th Street (between Center and Chester Street):

Between 5th and 7th Streets, sidewalks adjacent to the project site will be min 8' pedestrian clear zone. The sidewalk will be buffered from adjacent parking and street traffic by a street furnishings zone including pedestrian-scale lighting and street trees and/or other plantings.



Parking and Truck Loading Entrances: For the project will be designed to provide clear sight lines, should include ADA features such as tactile warning strips, and should provide audible warnings for when vehicles cross the pedestrian path of travel.

Wayfinding Signage: Lighting, and installation of other pedestrian amenities (e.g., seating, trash receptacles, trees and other landscaping) will be provided along all public roadways bordering the project site.




WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607

Mandela
Parkway Section

Chester Street
Section

5th Street
Section



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019


PUBLIC SPACE IMPROVEMENT: SIDEWALKS

SHEET:
A-10.00.4


Sidewalk Sections




SECTION AT 7TH STREET




SECTION AT 5TH STREET



SECTION AT CHESTER STREET




SECTION AT MANDELA PARKWAY



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

PUBLIC SPACE IMPROVEMENT: SIDEWALKS

SHEET:

A-10.00.5

Bikeways

Mandela Cycle Tracks:

To facilitate bicycle access from the bicycle lanes on Mandela Parkway south of 7th Street and north of 5th Street, two one-way cycle tracks are recommended along the west and east sides of Mandela Parkway between 7th and 5th Streets.

The recommended width for a one-way cycle track travel surface is 6 feet, and a three-foot buffer from the face of curb to the edge of the cycle track is also recommended. In addition to the cycle track and buffer, sidewalks with a minimum width of eight feet should also be provided.

7th St Cycle Tracks Eastbound:


To facilitate bicycle access in conjunction with passenger loading from vehicles and buses along eastbound 7th Street between Chester Street and Mandela Parkway, a one-way cycle track will be located with a minimum width of 6 feet.

The recommended width for a one-way cycle track travel surface is 6 feet, and an 8-foot buffer and sidewalk from the face of curb to the edge of the cycle track is also recommended.

7th St Cycle Tracks Westbound:

On westbound 7th Street between Mandela Parkway and Chester Street, a one-way cycle track will be located with a minimum width of 6 feet.

The recommended width for a one-way cycle track travel surface is 6 feet, and an 8-foot buffer and sidewalk from the face of curb to the edge of the cycle track is also recommended.




Bike Station:

The project will include an enhanced bicycle station located on the east side of the station structure that provides both valet and 24-hour secure bicycle parking to accommodate a minimum of 500 bicycles. The bike station will also include a retail and repair facility (both self-service and a bike shop).

Additional bicycle parking for BART and commercial patrons will be provided throughout the site in the form of bicycle racks. Bicycle parking for the TOD's commercial and residential tenants will also be provided in accordance with City of Oakland requirements.



WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607



JRDV URBAN INTERNATIONAL
 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com

E. MCFARLAN
 LICENSED ARCHITECT
 EDWARD MCFARLAN
 014723
 EXP. 05-31-19
 STATE OF CALIFORNIA



PROJ. # 168-153 WO BART
 DATE: January 18, 2019

**PUBLIC SPACE
 IMPROVEMENT:
 BIKEWAYS**

SHEET:
A-10.00.6

Crosswalks & Intersections


5th Street/Center Street and 5th Street/Chester Street Intersection: High-visibility crosswalks will be installed along with directional, ADA compliant curb ramps, and pedestrian refuges on 5th Street.

Mandela Parkway/7th Street Intersection: Further design and engineering analyses will be required for this intersection.

Mid-Block Crossing on Mandela: A high-visibility, mid-block pedestrian crossing is recommended on Mandela Parkway between 7th and 5th Streets. The crossing design will need to be coordinated with the design of the two-way cycle track to facilitate safe pedestrian crossing of both the roadway and the cycle track.

Currently, there are a relatively large number of pedestrians crossing Mandela Parkway at this location because it is the most direct path of travel from parking locations east of the station to the station entrance. It is expected that this will continue to be a preferred pedestrian path of travel once the surface parking lots to the east of the station are redeveloped.


Mandela Parkway/5th Street Intersection: Crosswalks at this intersection will be straightened to minimize pedestrian crossing distances and ADA-compliant, directional curb ramps should be installed.



WEST OAKLAND

BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

PUBLIC SPACE
IMPROVEMENT:
CROSSWALKS &
INTERSECTIONS

SHEET:
A-10.00.7

Passenger Loading

7th Street Passenger Loading:

Will be located on the south side of 7th Street west of Center Street. A portion (at least 50 linear feet) of this loading area closest to the intersection with Center Street should be designated as a loading space for passengers with disabilities. This area provides the most direct access to the station entrance.

5th Street Passenger Loading:

Approximately 130 feet of linear curb is proposed along westbound 5th street on the nearside of the intersection with Center Street, and another 255 feet of linear curb is proposed on eastbound 7th Street on the near side of the intersection with Center Street for passenger loading and unloading.


Differentiated TNC Loading:

Loading zones will be further differentiated between kiss-and-ride and TNC passenger loading with on-the-ground and in-app wayfinding for TNC passengers.

Wayfinding:

Signage directing vehicles to loading zones will be provided at key decision points like the Mandela Parkway and 7th Street intersection and the 5th Street and Kirkham or Union Street intersections. Loading zone locations should also be incorporated into smartphone mapping and TNC apps to facilitate safe and efficient circulation and access.

Install curbside passenger loading for BART pick-up/ drop-off (~255' of curb length)




Install curbside passenger loading for BART pick-up/ drop-off (~130' of curb length)



WEST OAKLAND

BART

1451 7th St, Oakland, CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

PUBLIC SPACE IMPROVEMENT: PASSENGER LOADING

SHEET: A-10.00.8

Bus Stops

7th Street Eastbound:

The existing bus stop on eastbound 7th Street will be retained and extended to the intersection with Center Street for an approximate total length of 270 linear feet. This stop would serve AC Transit Lines 29, 36, and 62 and would serve as both a stop and layover space for AC Transit Line 14. If Emery-Go-Round service is extended to the West Oakland Station, this stop could serve Emery-Go-Round vehicles as well.

7th Street Westbound:

A new bus stop will be installed on westbound 7th Street to serve AC Transit Line 29 and Emery-Go-Round, if the service is extended to the West Oakland Station. A minimum of 126 feet of linear curb is needed at this location to accommodate transit vehicles, as well as a concrete bus pad in the roadway. If a bus stop is installed at this location, AC Transit has requested that a barrier be placed in the median of 7th Street to prevent illegal mid-block pedestrian crossings between the bus stop and the BART station.


5th Street Westbound:

The bus stop and layover for lines 36 and 62 will be relocated to westbound 5th Street on the far side of the intersection with Mandela Parkway. At least 170 feet of curb length will be provided to accommodate the bus stops and layovers, and a concrete bus pad would need to be installed in the roadway.

Install bus stop for intercity coaches (Bolt, Megabus)

Start sidewalk taper immediately after crosswalk to better accommodate bus access

Install bus stop for line 29 and Emery-Go-Round (at least 126' of curb length needed)



Bus stop for lines 29, 36, 62 & Emery-Go-Round Bus stop and layover for line 14

Potential layover space for lines 36 & 62, requires further evaluation

Redesign Chester St cross-section to facilitate buses turning right

Install median barrier to prevent jaywalking to/from bus stop

Bus stop and layover for lines 62 & 36 (~170' of curb length)

Intercity & Private Bus Stops: A bus stop for intercity coaches (e.g., Megabus and Bolt) could be installed on 7th Street between Henry and Chester Streets. Private employer shuttle could also utilize this stop. The existing BART surface parking immediately adjacent to this curb could be utilized for bus and shuttle transit passenger pick-up and drop-off (if not utilized as a layover space for AC Transit buses).

Passenger Amenities:


All bus stops should provide a high level of passenger amenities, including shelters with seating, maps and other information, and real-time bus arrival information; trash receptacles; and lighting.



WEST OAKLAND

BART

1451 7th St, Oakland, CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019

PUBLIC SPACE IMPROVEMENT: BUS STOPS


SHEET: A-10.00.9



**WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019



SITE PLAN

SHEET: **A-10.01**



WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607



 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com






PROJ. # 168-153 WO BART
 DATE: January 18, 2019

SITE PLAN

SHEET: A-10.01



PYLON WITH BART SIGNAGE



CORPORATE SIGN




COMERCIAL BLADE SIGN



WEST OAKLAND BART

1451 7th St, Oakland, CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019


SIGN PLAN

SHEET: A-10.02

T1 RESIDENTIAL TOWER




PODIUM
CONC. PRE-CAST W/ INTEGRATED COLOR & TEXTURE




CURTAIN WALL
HIGH SOLAR PERFORMANCE WINDOW SYSTEM



CHANNEL GLASS SCREEN
HIGH PERFORMANCE CHANNEL GLASS



PANEL SYSTEM
PRE-CAST FIBER CEMENT PANEL



PANEL SYSTEM
HIGH SOLAR PERFORMANCE GLASS - OPERABLE


T3 RESIDENTIAL MID-RISE



CONC. PRE-CAST W/ INTEGRATED COLOR & TEXTURE



CONC. PRE-CAST W/ INTEGRATED COLOR & TEXTURE




GLAZING
HIGH SOLAR PERFORMANCE WINDOW SYSTEM



PANEL SYSTEM
CORRUGATED METAL


T4 OFFICE BUILDING



PODIUM
CONC. PRE-CAST W/ INTEGRATED COLOR & TEXTURE



PODIUM
CONC. PRE-CAST W/ INTEGRATED COLOR & TEXTURE




CURTAIN WALL
HIGH SOLAR PERFORMANCE WINDOW SYSTEM



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

MATERIAL BOARD

SHEET:

A-10.03




CURTAIN WALL
HIGH SOLAR PERFORMANCE WINDOW SYSTEM



PANEL SYSTEM
PRE-CAST FIBER CEMENT PANEL



**WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



JRDV URBAN INTERNATIONAL
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019



**MATERIAL
BOARD**

SHEET: A-10.04



**WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607



| | | |
|----------------------|-----------------------------|-------------------------------------|
| SITE AREA 273,756 SF | BART GROUND LEVEL 11,556 SF | TOTAL BUILDING FOOTPRINT 146,955 SF |
| PROPERTY 243,132 SF | BART FOOTPRINT 42,865 SF | OPEN SPACE 85,793 SF |




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019


**FOOTPRINT
AREA**

SHEET: **A-10.05**



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019


MASSING DIAGRAM

SHEET: A-10.07





***** The recycling space on T1 site is 1,207 cubic feet, on T3 site is 548 cubic feet, and on T4 site is 654 cubic feet. The total recycling space on site is 2,409 cubic feet.



JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com

EDWARD MCFARLAN
 LICENSED ARCHITECT
 STATE OF CALIFORNIA
 EXP. 05-31-19

ENGINEERS, SURVEYORS, PLANNERS

PGAdesign
 LANDSCAPE ARCHITECTS

PROJ. # 168-153 WO BART
 DATE: January 18, 2019


GROUND FLOOR PLAN

SHEET: A-11.01




**WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

**2ND FLOOR
PLAN**

SHEET: A-11.02




1 2ND FLOOR PLAN
1/32" = 1' - 0"



**WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019

**3-4TH FLOOR
PLAN**


SHEET: **A-11.03**




1 3-4TH FLOOR PLAN
1/32" = 1' - 0"



WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com










PROJ. # 168-153 WO BART
 DATE: January 18, 2019

5TH FLOOR
PLAN


SHEET:
A-11.04


1 5TH FLOOR PLAN
 1/32" = 1' - 0"



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019


7TH FLOOR PLAN

SHEET:

A-11.06




1 7TH FLOOR PLAN
1/32" = 1' - 0"



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019


19-30TH FLOOR PLAN

SHEET:

A-11.08




1 19-30TH FLOOR PLAN
1/32" = 1' - 0"



WEST OAKLAND
BART

1451 7th St, Oakland,
 CA 94607





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com










PROJ. # 168-153 WO BART
 DATE: January 18, 2019

ROOF
PLAN


SHEET: **A-11.09**


1 ROOF PLAN
 1/32" = 1' - 0"



**WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

**BASEMENT
FLOOR
PLAN**

SHEET: **A-11.10**




1 BASEMENT PLAN
1/32" = 1' - 0"



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

7TH STREET ELEVATION

SHEET: A-20.01




7TH STREET ELEVATION 1



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

MANDELA PKWY ELEVATION

SHEET: A-20.02




MANDELA PKWY ELEVATION 1



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

5TH STREET ELEVATION

SHEET: A-20.03




5TH STREET ELEVATION 1



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

CHESTER STREET ELEVATION

SHEET: A-20.04




CHESTER STREET ELEVATION 1



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

T1 SOUTH ELEVATION

SHEET: A-20.05




T1 SOUTH ELEVATION 1



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019


T1 & T4 WEST ELEVATION

SHEET: A-20.06




T1&T4 WEST ELEVATION

1



CONC. PRE-CAST W/
INTEGRATED COLOR &
TEXTURE



T3 NORTH ELEVATION

1



CONC. PRE-CAST W/
INTEGRATED COLOR &
TEXTURE

CURTAIN WALL
HIGH SOLAR
PERFORMANCE
WINDOW SYSTEM




T3 EAST ELEVATION

2



WEST OAKLAND
BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

T3 NORTH & EAST
ELEVATION

SHEET:

A-20.07

1 2 3 4 5 6 7 8 9 10

+ 80'-0"
ROOF DECK

+ 38'-0"
ROOF DECK
+ 28'-0"
LV3 DUPLEX UNITS
+ 18'-0"
LV2 DUPLEX UNITS

+ 0'-0"
GROUND



T3 SOUTH ELEVATION

1

N M L J I G E C A

+ 80'-0"
ROOF
+ 70'-0"
LV7 ROOF DECK
+ 60'-0"
LV6
+ 50'-0"
LV5
+ 40'-0"
LV4
+ 30'-0"
LV3
+ 20'-0"
LV2
+ 10'-0"
PARKING
+ 0'-0"
GROUND




T3 WEST ELEVATION

2



WEST OAKLAND
BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

T3 SOUTH & WEST
ELEVATION



SHEET:

A-20.08



T4 NORTH ELEVATION

1




T4 EAST ELEVATION

2



WEST OAKLAND
BART

1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

T4 NORTH & EAST
ELEVATION

SHEET: A-20.09



T4 SOUTH ELEVATION

1




T4 WEST ELEVATION

2



WEST OAKLAND
BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

T4 SOUTH & WEST
ELEVATION


SHEET:

A-20.10



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019

SHEET:

RETAIL UNDER BART ELEVATIONS


A-20.11




RETAIL UNDER BART NORTH ELEVATION 1




RETAIL UNDER BART SOUTH ELEVATION 2



RETAIL UNDER BART WEST ELEVATION 3




RETAIL UNDER BART EAST ELEVATION 4



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: January 18, 2019

SECTION A-A

SECTION A-A


1

SHEET: A-30.01




WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

SECTION B-B

SHEET:



A-30.02

1



WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



SECTION C-C

1



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: January 18, 2019

SECTION C-C

SHEET:

A-30.03

WEST OAKLAND STATION

DESIGN GUIDELINES

JANUARY 25, 2019



WEST OAKLAND STATION

DESIGN GUIDELINES

TABLE OF CONTENTS

| | |
|---------------------------|----|
| Vision | 3 |
| Guiding Principles | 4 |
| Site Planning | 5 |
| Architectural Design | 7 |
| <i>7th St</i> | 8 |
| <i>5th St</i> | 14 |
| <i>Mandela Parkway</i> | 21 |
| <i>Chester St</i> | 25 |
| Public Space Improvements | 30 |
| <i>Mandela Plaza</i> | 31 |
| <i>Maker Plaza</i> | 32 |
| <i>Art Alley</i> | 33 |
| <i>Art & Culture</i> | 34 |
| <i>Access</i> | 35 |
| <i>Landscape</i> | 36 |
| Sustainable Design | 39 |

VISION FOR WEST OAKLAND BART STATION



SITE AERIAL VIEW

The West Oakland Station master plan development will create a vibrant mixed-use neighborhood at this key transit site and central location for the West Oakland Neighborhood – creating a revitalized gateway to West Oakland and to the greater East Bay. This development will serve to revitalize the surrounding West Oakland neighborhoods by activating streets and public spaces with quality urban architecture, delightful public spaces, and activated retail and cultural programming. The development will improve the safety of the neighborhood by providing “eyes on the street” from the residential and commercial uses. Finally, this dense mixed-use development at a transit station will provide much-needed jobs and housing while reducing automobile trips to ease pollution and traffic congestion.

GUIDING PRINCIPLES

1. **Urban Design:** Revitalize the neighborhood by creating well designed urban architecture that supports activated public uses of this key neighborhood site. The massing and design of buildings should contribute to the overall form and structure of the community, to the spatial definition of public spaces and streets, and to the visual diversity and interest of the public realm of this important neighborhood site. The overall master plan will develop a composition of well-designed building masses that enhance the streetscapes and public spaces of adjacent neighborhoods. It will create buildings that engage the public realm, are well-articulated, and provide physical and visual access to the project site.
2. **Transit:** Support principles of transit oriented development by creating a dense and thriving community adjacent to BART station and AC transit stops. Include site design and public amenities that encourage bicycle use, carpooling, and car sharing to minimize automobile trips.
3. **Identity:** Introduce a new higher density urban architecture that is compatible with the character of neighborhood, with well-composed buildings that are built of quality materials, appropriately scaled details, and balanced proportions that improve the urban context. Use frontage along 7th and 5th Streets to improve the BART station identity and to create a design “statement” that conveys the unique character of the neighborhood to region at large.
4. **Community:** Provide a mixture jobs and housing that can act as a catalyst for the economic development of West Oakland. Bring a mix of market rate and affordable housing units that

supports a diverse mix of residents and users on site. The master plan will integrate commercial and residential uses with streetscape design to allow for “eyes on the street” to promote an active and safe day and nighttime environment.

5. **Sustainability:** Incorporate design and building strategies that protect the environment and contribute to the well-being of the residents and community alike.

These design guidelines provide the specific strategies to implement the guiding concepts outlines in the previous section. The plan sheet annotations in these guidelines correspond to the Project Plan Set prepared by JRDV Urban International.

There are four primary parts to the design guidelines:

1. **Site Planning**
2. **Architectural Design**
3. **Public Space Improvements**
4. **Sustainable Design**

SITE PLANNING

Street Frontages: Set buildings along edge of sidewalks with appropriate setbacks to ensure adequate public use and circulation. Buildings should be located along street frontages to establish a clear urban street edge, and to ensure ease of pedestrian connections to retail and other public uses. Street frontages should be designed to encourage active retail uses and maintain a clear “street wall” defining the edge of the public realm.

Open Space: Provide enhanced and activated open space areas within the project to ensure good public access to the BART station and to create a public destination of the site for the larger West Oakland community.

BART Station and BART Trackway: Maintain good visual and physical access to the BART Station. Create an improved and safer transit rider experience. Improve the pedestrian experience and safety of the under-track areas and pedestrian walk-ways adjacent to the BART trackway, and incorporate these areas into active, safe and delightful urban places.

Parking: Locate parking structures away from street frontages to all retail and other public uses at public open spaces. Insure that parking is clearly marked and that vehicular access does not conflict with the pedestrian access and use of the site.

Pedestrian access / lobbies / retail: Locate building lobbies and retail uses at prominent locations along pedestrian routes including street corners and cross intersections to ensure that public spaces are activated and promote public use of the site. Site Design should ensure enhanced pedestrian access from the surrounding community, and ensure safe and accessible access to the BART station.

Bicycle Route Connections: Site design shall encourage bike access to the site and the BART station by establishing new east-west cycle tracks along 7th Street and north-south access along Mandela Parkway. Create a new Bike Station and storage that is located in a manner to allow easy connection to proposed bicycle routes, and is sized to accommodate the long-term demand for bike use on site.


Activated Public Frontages: Provide entries for commercial, residential and retail uses along interior and exterior public frontages to ensure that there is a strong visual connection between the street and the building(s) and an active street presence.

ARCHITECTURAL DESIGN

The architectural urban design is intended to respond to the specific scale and character along each public frontage; therefore, the guidelines of this section are arranged according to the four primary frontages: 7th Street, 5th Street, Mandela Parkway, Chester Street and Interior public circulation spaces.



AERIAL VIEW FROM 5TH ST




AERIAL VIEW FROM 7TH ST

ARCHITECTURAL DESIGN: 7TH STREET

The 7th Street frontage is one of the most important civic and commercial neighborhood streets in West Oakland. Larger buildings are located on 7th street at Mandela Parkway to emphasize the importance of this intersection in West Oakland.

A signature tower will be located at the intersection of Mandela and 7th Street to create a visual icon for the West Oakland community and to mark the importance of this key transit site as a gateway West Oakland and the greater City of Oakland. The signature tower will be designed to complement the public plaza in front of the BART station and Chester Street intersection.

The buildings and street-scape are designed to enhance 7th street corridor and to create a high quality of pedestrian experience and civic prominence. The architecture will be designed to create a visually significant destination for the West Oakland community. Development heights will step down as buildings get closer to adjacent neighborhoods.



7TH STREET ELEVATION

ARCHITECTURAL DESIGN: 7TH STREET

Height, Bulk, and Scale: Proposed buildings along 7th Street should allow high-rise development that reflect the importance of this transit site. The site massing will locate the tallest massing at the intersection of 7th Street and Mandela, emphasizing this important intersection. Building heights will step down toward Chester Streets. A varied building silhouette along 7th Street is encouraged through significant changes in massing at rooflines, stepping down from Mandela to Chester Street.

Buildings that Provide Strong Spatial Definition: Buildings along 7th Street should shape and define the public street scape and other public spaces, and define a high quality of public experience of the 7th Street corridor and BART station in the community.

Building Massing Articulation: Building facades along 7th Street will be designed to become lively and delightful edges to streets and open spaces through the variation of building materials and facade typologies. Within these overall massing envelopes, additional variation and articulation should be provided in both the horizontal plane and the vertical profile of buildings to break down their perceived mass and bulk, and to promote a finer increment of urban architecture.

7th Street and Mandela Corner: The 7th and Mandela Corner should receive special visual emphasis and treatment to establish the importance of this key urban intersection

Building Base Articulation: The lower portion 4-5 floors of tall buildings should be clearly articulated with massing, changes of material and facade fenestration to establish an urban street base that is more in scale with the current and future surrounding blocks. Building massing should provide additional variation and architectural interest that promotes a cohesive community scale and an attractive pedestrian environment.

Sidewalk Setbacks: Buildings along 7th Street will be generally built to the property lines of streets to provide a clear “street wall” definition, but will be massed and articulated to avoid the creation of an undifferentiated and monolithic environment. Ground floor setbacks may be used to ensure adequate public circulation and access for transit riders.

BART Station Access and Identity: Building placement and design should promote BART transit rider access and the enhanced civic importance of this transit site. The architecture should create and enhance a new community civic plaza along 7th Street at the BART station to provide increased visibility and access to the BART station, and also to celebrate the civic importance of this site in the community. The plaza should be designed to enhance the 7th Street corridor activation and overall public experience.


ARCHITECTURAL DESIGN: 7TH STREET

Activated 7th Street Corridor


These building frontages should adhere to the following guidelines:

1. The ground floor-to-floor dimension should promote viable retail uses that are welcoming and transparent in nature, with a minimum floor-to-floor height of 20'.
2. The minimum depth of retail space from storefront to rear should be at least 40 feet to promote viable uses.
3. The retail frontage should be built with adequate set-back to the property line to provide public transit use of the sidewalk and possible café tables and other retail uses at the sidewalk edge.
4. The interior finished floor elevation should be generally flush with the street or promenade frontage.
5. Building entries should be oriented to the street or promenade with intervals that promote activate street experience, except for major anchor tenants such as grocery or drug stores, which could be a greater interval.

6. Shop fronts should be designed with a high level of transparency – at least 75% glass storefront along the 7th Street edge.
7. The use of canvas awnings, metal canopies and building overhangs are encouraged to provide shelter and shade to the pedestrian, and color and life to the building facade (see diagram views)



ARCHITECTURAL DESIGN: 7TH STREET



7TH STREET ELEVATION DETAIL

Special visual emphasis on 7th & Mandela corner

75% glass transparency at street facade at 7th street



7TH & MANDELA CORNER

ARCHITECTURAL DESIGN: 7TH STREET

Shop fronts should be designed with a high level of transparency – at least 75% glass storefront



7TH STREET STOREFRONT

Building entries should be oriented to the street or promenade with intervals that promote activate street experience



7TH STREET STREETScape

Ground floor setbacks may be used to ensure adequate public circulation and access for transit riders.

ARCHITECTURAL DESIGN: 7TH STREET at CIVIC PLAZA

Building placement and design should promote BART transit rider access and the enhanced civic importance of this transit site.



MANDELA PLAZA WEST

The architecture should create and enhance a new community civic plaza along 7th Street at the BART station to provide increased visibility and access to the BART station



MANDELA PLAZA EAST


ARCHITECTURAL DESIGN: 5TH STREET

The 5th Street frontage will create an important community frontage that connects the BART station to the surrounding neighborhoods to the south. The 5th Street frontage should be designed to appropriately transition the larger building heights along 7th Street to the lower scale of current and future buildings in the neighborhood. Although it is recognized that current building heights in the surrounding community are low; it is anticipated that higher and larger building will be built as this transit hub location develops. The design of the station site is intended to become a bridge between the current historic South Prescott neighborhood and the future higher density neighborhood to come.

5th Street is also an important commercial street for the community. It should provide both enhanced access to the BART station, as well as neighborhood retail shopping for the surrounding community. This street frontage should be activated with local retail and cultural uses that reinforce the 7 day-a-week activation to ensure the safety and desirability of the station location. The architecture of 5th Street should be designed to create a high quality of pedestrian experience and civic prominence, and reinforce the visual significance of the overall site for the West Oakland community.

Buildings should transition down in height from Mandela to Chester St

Building massing should provide additional variation and architectural interest that promotes a cohesive community scale and an attractive pedestrian environment.



5TH STREET ELEVATION

ARCHITECTURAL DESIGN: 5TH STREET

Height, Bulk, and Scale: Proposed buildings along 5th Street should build to the 100' high-rise height allowed east of Chester Street to increase the visibility and importance of the Station site. Buildings should transition down in height west of Center Street to 80'. Building heights should transition to a lower 3 levels at Chester Street to reflect the lower urban scale of the historic buildings to the west of Center Street.

A varied building silhouette along 5th Street is encouraged through changes in massing or materials at rooflines, stepping down from Mandela to Chester Street.

Buildings that Provide Strong Spatial Definition: Buildings along 5th Street should be designed to create a visually active urban "street wall" that shapes and defines the important public experience of 5th Street corridor.

Building Massing Articulation: Building facades along 5th Street will be designed to become lively and delightful edges to streets and open spaces through the variation of building materials and facade typologies. Within these overall massing envelopes, additional variation and articulation should be provided in both the horizontal plane and the vertical profile of buildings to break down their perceived mass and bulk, and to promote a finer increment of development.

Building Massing and Articulation – East of Center Street: The lower portion 4-5 floors of high-rise buildings east of Center Street should be clearly articulated with massing, changes of material and facade fenestration to establish a street base that is more in scale with the current and future surrounding blocks. Building massing should provide additional variation and architectural interest that promotes a cohesive community scale and an attractive

pedestrian environment.

Building Massing and Articulation – West of Center Street: Residential buildings west of Center Street shall have a clearly defined base-middle-top articulation. The building massing shall be designed to provide a variety of facade typologies to provide a visually active street scape, and to relate better to the varied architecture in the neighborhood context. Building massing and fenestration should provide variation and architectural interest that promotes a cohesive community scale and an attractive pedestrian environment.

Step Down to Chester Street: The street massing should step down to 3 levels at Chester Street to provide a better scale transition to the lower buildings in the South Prescott neighborhood.

Sidewalk Setbacks: Buildings along 5th Street will be generally built to the property lines of streets to provide a well-defined "street wall", but will be massed and articulated to avoid the creation of an undifferentiated and monolithic environment. Ground floor setbacks may be used to ensure adequate public circulation and access for transit riders.

Maker Square - Center Street Plaza: Buildings should be designed with an elevated (20' min.) ground floor, an architecturally defined base, and activated retail or cultural program to create an activated and important public space for this key pedestrian plaza and gateway to the BART station. Buildings along Marker Square should be lined with retail, art and other cultural uses in order to create an active and safe 7 day-a-week public experience at this central public space.


ARCHITECTURAL DESIGN: 5TH STREET

Activated 5th Street Corridor

Along the 5th Street frontage, building frontages should adhere to the following guidelines:

1. The ground floor-to-floor dimension should promote viable retail uses that are welcoming and transparent in nature, with a minimum floor-to-floor height of 20'.
2. The minimum depth of retail space from storefront to rear should be at least 25-30 feet to promote viable uses.
3. The retail frontage should be built with adequate set-backs to the property line to provide adequate public transit-rider use of the sidewalk and possible café tables and other retail uses at the sidewalk edge.
4. The interior finished floor elevation should be generally flush with the street or promenade frontage.
5. Building entries should be oriented to the street or promenade with intervals that promote activate street experience, except for major anchor tenants such as grocery or drug stores, which could be a greater interval.
6. Shop fronts should be designed with a high level of transparency – at least 60% glass storefront along the 5th Street edge.

7. Use architectural details on residential structures such as balconies, railings, lighting, canopies, and other elements that enliven the facade and reinforce the human scale of the development
8. Provide recessed windows on residential structures to ensure depth, shade, and shadow on the building facade.
9. The use of canvas awnings, metal canopies and building overhangs are encouraged to provide shelter and shade to the pedestrian, and color and life to the building facade (see diagram views)



ARCHITECTURAL DESIGN: 5TH STREET - East of Center Street

Distinguish Upper Floors with glass and varied fenestration

Base of high-rise buildings east of Center Street should be articulated with massing, changes of material and facade fenestration to establish an active base

20' min ground floor height



5TH STREET ELEVATION EAST OF CENTER

Base of high-rise buildings east of Center Street should be articulated with massing, changes of material and facade fenestration to establish an active base



5TH & MANDELA CORNER

ARCHITECTURAL DESIGN: 5TH STREET - West of Center Street

A varied building silhouette along 5th Street is encouraged through changes in massing or materials at rooflines, stepping down from Mandela to Chester Street



Building massing shall be designed to provide a variety of facade typologies to provide a visually active street scape

Visually transparent ground floor with pilasters to connect to upper floors



5TH STREET ELEVATION WEST OF CENTER

Visually identify the Center St/Maker Plaza entry corner



5TH STREET AT MAKER SQUARE

ARCHITECTURAL DESIGN: 5TH STREET - West of Center Street

Building entries should be oriented to the street or promenade with intervals that promote activate street experience, except for major anchor tenants such as grocery or drug stores, which could be a greater interval.



5TH STREET STREETScape

Shop fronts should be designed with a high level of transparency – at least 60% glass storefront



5TH STREET STOREFRONT

Retail frontage should be built with adequate set-backs to the property line to provide adequate public transit-rider use of the sidewalk and possible café tables and other retail uses at the sidewalk edge

ARCHITECTURAL DESIGN: 5TH STREET - Maker Square

Buildings along Marker Square should be lined with retail, art and other cultural uses in order to create an active and safe 7 day-a-week public experience at this central public space.



VIEW OF BART FROM MAKER SQUARE

Buildings should be designed with an elevated (20' min.) ground floor, an architecturally defined base with min. 75% transparency.



MAKER SQUARE ENTRY FROM 5TH ST


ARCHITECTURAL DESIGN: MANDELA PARKWAY

The Mandela Parkway frontage provides an important visual and physical north-south link to the site. This frontage should be designed to transition the larger building heights along 7th Street to the lower scale of 5th Street. However, it is also recognized that the future buildings along Mandela Parkway will be taller urban buildings that form a new higher-density context for the Station site development. The design of Mandela Parkway frontage is intended to set a high quality design standard for the future urban neighborhood to come.

Mandela Parkway should provide enhanced bike access to the BART station, with a north-south cycle-track that connects to a mid-block bike station. It is a less important retail shopping street, but should maintain a quality pedestrian walking experience with retail edges and a high level of architectural expression. Service and loading areas should be designed to minimize pedestrian disruption and to ensure pedestrian safety.

Development heights will step down across the site from taller buildings along 7th Street to lower buildings along the 5th Street corridor.


Building facades along Mandela Parkway will be designed to become lively and delightful edges to streets and open spaces through the variation of building materials and facade typologies.



ARCHITECTURAL DESIGN: MANDELA PARKWAY

Building Massing and Articulation: Building facades along Mandela Parkway will be designed to become lively and delightful edges to streets and open spaces through the variation of building materials and facade typologies. The architecture along Mandela Parkway will be designed to be consistent with the high quality a design, materials and fenestration of the 7th and 5th Street facades. Development heights will step down across the site from taller buildings along 7th Street to lower buildings along the 5th Street corridor.

Sidewalk Setbacks: Buildings along Mandela Parkway will be generally built to the property lines of streets to provide a clear “street wall” definition, but will be massed and articulated to avoid the creation of an undifferentiated and monolithic environment. Ground floor setbacks may be used to ensure adequate public circulation and access for transit riders.



Activated Mandela Parkway Corridor:

Along the Mandela Parkway frontage, building frontages should adhere to the following guidelines:

1. The ground floor-to-floor dimension should promote viable retail uses that are welcoming and transparent in nature, with a minimum floor-to-floor height of 20’.
2. Service and Loading areas should be well designed and visually protected from pedestrian view. Service and loading areas should be designed to minimize pedestrian disruption and to ensure pedestrian safety.
3. The building frontage should be built with adequate set-back to the property line to provide pedestrian use of the sidewalk.
4. The interior finished floor elevation should be generally flush with the street or promenade frontage.
5. Retail and other public uses should be provided where possible. Shop fronts should be designed with a high level of transparency and visual interest.
6. Service and loading areas should be designed to minimize pedestrian disruption and to ensure pedestrian safety.

ARCHITECTURAL DESIGN: MANDELA PARKWAY


Building facades will be designed with a variation of building materials and facade typologies.

Ground floor-to-floor dimension should be welcoming with a minimum floor-to-floor height of 20'.



MANDELA ELEVATION DETAIL

Building Setbacks from the BART tracks.



T1, T4 & BART TRACK SECTION

ARCHITECTURAL DESIGN: MANDELA PARKWAY

Street barriers should be active and lively to ensure an interesting pedestrian experience



MANDELA STREETSCAPE

Street facade should be active and lively to ensure an interesting pedestrian experience



ART ALLEY EAST

ARCHITECTURAL DESIGN: CHESTER STREET

The Chester Street frontage should be designed as a transition from the larger building heights along 5th Street to the lower scale historic structures of the South Prescott neighborhood. Chester Street should be designed to become a modern bridge between the current historic community and the future higher density development at the Station site.

Building facades along Chester Street will be designed to a smaller residential scaled street, except as necessary to screen the BART trackway



CHESTER STREET RESIDENTIAL SREETScape

ARCHITECTURAL DESIGN: CHESTER STREET

Building Massing and Articulation: Building facades along Chester Street will be designed to a smaller residential scaled street, except as necessary to screen the BART trackway. Chester Street should be designed with a lower 3 level height and a more individually articulated building massing. Although it may use a more modern architectural vocabulary, the buildings along Chester Street should be articulated with bay windows and a range of smaller window sizes and fenestration. Individual building entrances and “stoops” at the street will reinforce this more traditional community streetscape.

Street Activation: Although Chester Street is not a major retail location, this street frontage may be activated with local maker spaces that reinforce the 7 day-a-week activation to ensure the safety and desirability of the overall station location.

Sidewalk Setbacks: Buildings along Chester Street will be generally built to the property lines of streets to provide a clear “street wall” definition. Ground floor setbacks may be used to ensure adequate public circulation and access for good pedestrian circulation.


Mid-Block Pedestrian Access: An important mid-block pedestrian access will be established at the BART trackway. Buildings will set back to provide both adequate emergency vehicle access and to create a delightful and activated pedestrian passage through the site to the BART station. The architecture of the buildings should be designed to provide visual interest and identity at this key mid-block public passage.

ARCHITECTURAL DESIGN: CHESTER STREET

Activated Chester Street Corridor

Along the Chester Street frontage, building frontages should adhere to the following guidelines:

1. The ground floor-to-floor dimension should promote potential retail uses with a minimum floor-to-floor height of 16'.
2. Residential uses should have individual entries that activate the street and provide a more traditional neighborhood scale.
3. The interior finished floor elevation should be generally flush with the street or promenade frontage.
4. Building should promote activate street experience with ground floors that support public retail or maker spaces.
5. Use architectural details on residential structures such as balconies, railings, canopies, and other elements that enliven the facade and reinforce the human scale of the development
6. Provide recessed windows along building base elevations to ensure depth, shade, and shadow on the building facade.
7. Service and loading areas should be designed to minimize pedestrian disruption and to ensure pedestrian safety.



ARCHITECTURAL DESIGN: CHESTER STREET

Building facades along Chester Street will be designed to a smaller residential scaled street, except as necessary to screen the BART trackway



CHESTER STREET ELEVATION DETAIL

Residential uses should have individual entries that activate the street and provide a more traditional neighborhood scale.



CHESTER STREET RESIDENTIAL SREETScape


ARCHITECTURAL DESIGN: CHESTER STREET

An important mid-block pedestrian access will be established at the BART trackway. Buildings will set back to provide both adequate emergency vehicle access and to create a delightful and activated pedestrian passage through the site to the BART station.



ART ALLEY VIEW

Building Setback from BART trackway



T3 & BART TRACK SECTION

PUBLIC SPACE IMPROVEMENTS

The public spaces for the West Oakland Station site should be designed to reinforce the vibrant mixed-use development that furthers Oakland’s efforts to promote urban living at key transit sites, and provides an active and delightful center for the West Oakland community. The site is designed with a series of important civic open spaces, including:

- **Mandela Plaza**, major community civic plaza at 7th Street fronting BART Station entrance;
- **Maker Square**, a pedestrian plaza replacing the vacated Center Street, and
- **Art Alley**, a pedestrian paseo along the BART trackway.

The perimeter of the site is designed to promote public access and to provide an enhanced pedestrian experience, with expanded sidewalks and retail frontages along 7th and 5th Streets. These pedestrian spaces are designed with the highest level of materials, planting, paving, seating and lighting to create a vital and dynamic center for the community, and to maximize access to BART and associated transit modes.

Public Space Goals: The following urban design principles are intended to support public space strategy:

1. Establish a continuous, diverse and active network of public open spaces, including plazas, activated streetscapes and pedestrian paseos that connect site and BART station to the surrounding community.
2. Configure and design the open space system to serve as center for the West Oakland community and a destination for Oakland and the East Bay.
3. Create walkable and lively public streets, open spaces and pedestrian ways that provide an delightful, safe and activated 7 day-a-week destination for the neighborhood, transit riders and East Bay.
4. Provide a range of cultural, recreational and commercial activities that reinforce the public destination appeal and civic role of the Station site as a whole.

PUBLIC SPACE IMPROVEMENTS: MANDELA PLAZA

Mandela Plaza - Community Civic Plaza: A larger civic plaza should be provided along 7th Street at the BART station to provide increased visibility and access to the BART station, and also to celebrate the civic importance of this site in the community. This plaza is located to be central to the overall site in order to increase its public importance, public access, and public use for community, arts and cultural events. The central plaza should be designed to enhance the 7th Street corridor activation and public experience.



PLAZA VIEW FROM CHESTER ST

PUBLIC SPACE IMPROVEMENTS: MAKER SQUARE

Maker Square: The vacated Center Street should be transformed into an active urban destination for the neighborhood. This space is both an important pedestrian connection to the BART station and a significant public plaza for the surrounding community. It should be lined with public uses, including: retail, food, cultural and maker spaces. The space should be an inviting place for the neighborhood to shop, dine, and relish a quality community experience.



MAKER SQUARE VIEW

PUBLIC SPACE IMPROVEMENTS: ART ALLEY

Art Alley: The mid-block passage south of the BART trackway should be designed as an active pedestrian paseo. Buildings will set back to provide both adequate emergency vehicle access and to create a delightful and activated pedestrian passage through the site to the BART station. The space should be lined with public uses that activate the space, including: retail kiosks, maker spaces, a bike station, and other cultural uses that provide day and night activation and safety for pedestrians using the space. Art and other cultural/historical installations should be introduced into this space to provide a meaningful and innovative public experience.



ART ALLEY VIEW

PUBLIC SPACE IMPROVEMENTS: ART & CULTURE


Integrated Art and Public Spaces: The public spaces should be designed to facilitate flexible community uses including: recreation, community events, farmers markets, makers markets, arts events, festivals and other events that promote this as a central destination for the local and regional community. Neighborhood amenities, such as seating, lighting, retail kiosks, cafes, maker spaces and other activated uses will be appropriately incorporated into the public edges of the development. This will ensure that the overall development becomes a year round activated urban community destination.

Arts and Cultural Programming: The site program will incorporate significant and innovative arts, education and cultural programming integrated into the public spaces and buildings on site. The open spaces will be programmed with year round cultural, community and arts events that encourages use of the site, and encourages local arts and artists within the West Oakland community. This cultural, education and arts programming is incorporated into the overall design, leasing and operations to encourage and incubate the arts in West Oakland.

7th Street Walk of Fame

The public open space improvements should enhance development of the “The Music They Played on 7th Street Oakland Walk of Fame” plaques which were partially installed in 2012. Plaques immortalizing the blues, R&B and Jazz musicians including “Terrible Tom” Bowden, Sugar Pie DeSanto, B.B.King, Aretha Franklin among many others will be integrated into the site design and highly visible on the facades and within the open spaces of the development.

WALK OF FAME- THE MUSIC THEY PLAYED ON 7TH ST



PUBLIC SPACE IMPROVEMENTS: ACCESS

Site Uses to Encourage Neighborhood Retail Shopping: It is anticipated food, grocery or other neighborhood serving retail will be incorporated into the tenant leasing of the ground floor retail. Planning incorporates large retail spaces with loading and transit access that are conducive to these neighborhood serving uses. The pedestrian environment is designed to encourage local shopping by planning safe, active pedestrian spaces and access and to promote community use and a quality shopping pedestrian experience

Vehicular and Service Access: The Site Circulation and Access plan is designed to coordinate the vehicle and pedestrian access and use of the site. The design minimizes these conflicts to ensure safety and enjoyment for all users. Vehicular traffic is minimized on site to ensure maximum pedestrian safety, access and use. Parking is restricted to non-pedestaling areas. Building loading areas are located on Mandela and 5th Street to minimize pedestrian conflicts, and to minimize conflicts with transit and other access modes to the site

Transit Access: The overall site Access Plan is designed to accommodate maximum flexibility of current and future transit modes. This includes planned curb space for AC buses and curb drop-off for transit riders. The site has been designed to maximize the pedestrian access from all surrounding blocks. Bike access is enhanced with dedicated cycle tracks on the 7th Street and Mandela Streets.

PUBLIC SPACE IMPROVEMENTS: LANDSCAPE

Hardscape and Green-scape Design: Landscape plan should be designed to enhance the pedestrian public spaces to create a high quality of pedestrian experience and civic prominence. The existing trees will be replaced because of conflicts with the access plan. The new tree planting will complement the overall landscape strategy of the 7th and 5th Street corridors to ensure a continuous, interesting and varied visual experience. Planting and paving materials shall be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events. The landscape plan shall be designed to create a visually significant destination and center for the West Oakland community and users of the transit hub.

The landscape materials are designed with high quality stone, brick, finished concrete and other materials to create a high quality public pedestrian experience and to maximize the types of uses that can occur on site. The landscape will be designed to relate to a larger vision for the 7th Street corridor. The new tree planting will complement the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience. Planting and paving materials will be of high quality and will be aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events.

Site Lighting: The Lighting plan will be designed to create well lighted plazas and pedestrian pathways through the site. The visual security of all pedestrian spaces within the site is facilitated by locating retail and other public activities along all edges of the development. The landscape plan will provide adequate lighting


to provide a safe environment while conforming to current best practices to mitigate light pollution.

Storm Water Management: Site should be designed to provide innovative strategies policy for achieving storm water management on site. The public spaces are designed to encourage the overall comfort and wellbeing of residents and visitors to the site while conserving water, energy, water and natural resources.


PUBLIC SPACE IMPROVEMENTS: LANDSCAPE



PERVIOUS PAVING



CONCRETE PAVERS



COLORED CONCRETE

HARDSCAPE

PUBLIC SPACE IMPROVEMENTS: LANDSCAPE



Helleborus argutifolius 3'x3'



Abutilon megapotamicum 'Lemon' 3'x3'



Acer rubrum 'Armstrong'



Acer saccharum nigrum



Azara microphylla 15'x15'



Cordyline 'Design-a-Line' 3'x3'



Berberis 'Orange Rocket' 4'Hx2'W



Robinia x ambigua 'Purple Robe'



Fraxinus americana 'Empire'



Quercus coccinea



Mahonia 'Soft Caress' 4'x4'



Pittosporum tobira 'Mojo' 3'x3'



Nandina domestica Alba 'Lemon-Lime' 4'Hx3'W



Agave attenuata 'Raea's Gold' 3'x3'



Digiplexis Illumination 'Apricot' 2'Hx18"W

GREENSCAPE

SUSTAINABLE DESIGN

By developing a transit urban infill site with a high density of residential and commercial use near a transit stop, this development is already inherently “green” in terms of land use. Further measures employed during the design and construction of the project can contribute additional environmental benefits. These measures, when taken as a whole, will promote occupant comfort and well-being while conserving energy, water, and natural resources. A few general measures are as follows:

Site Design Measures: The development shall employ architectural strategies that are respond to the local climate including solar orientation, prevailing winds, and precipitation.

- Orient units and / or provide architectural shading treatments to maximize winter solar exposure and minimize summer exposure.
- Provide on-site storm water treatment as appropriate to the scale of the buildings and available open space.
- Provide on-site secure bicycle parking
- Reduce parking capacity to reasonable minimum.
- Consider designated parking for carpool vans or car share vehicles.
- Use native and drought-tolerant landscaping to minimize irrigation required.

Building Design Measures:

- Use reflective roofing to minimize heat island effect.
- Use water-conserving fixtures and irrigation systems.
- Design building envelope, HVAC systems, lighting, and other systems to maximize energy efficiency. Consider fundamental commissioning of development systems.
- Consider on-site electrical generation or purchase of off-site

renewable energy.

- Provide adequate facilities to allow for recycling by residents.
- Where possible, use recycled, salvaged, sustainably harvested, or locally produced materials.
- Use low or no-VOC materials in interior spaces.
- Recommend that the development be designed and constructed in accordance with the recommendations of a recognized “green” rating system such as: GreenPoints Enterprise Green Communities, USGBC LEED rating.

ATTACHMENT C:

**Proposed Revision to West Oakland BART TOD
Preliminary Development Plan, dated September 16, 2020**

MANDELA STATION

@ West Oakland BART

PRELIMINARY DEVELOPMENT PLAN

July 24, 2020
Amended September 16, 2020



HENSEL PHELPS



GENERAL

G100 TITLE SHEET, DRAWING INDEX

CONTEXT INFO

A-00.01 - RENDERINGS
A-00.21

A-01.00 SUMMARY OF PROPOSED ENTITLEMENT REVISIONS

A-01.01 ZONING INFO
A-01.02 ZONING SUMMARY
A-01.03 OPEN SPACE ANALYSIS
A-01.04 PHASING PLAN
A-01.06 LEED CHECK LIST
A-01.07 GREENPOINTRATED
A-01.08 GREENPOINTRATED
A-01.09 CONTEXT MAP
A-01.10 CONTEXT PHOTOS

CIVIL PLANS

C1.00 EXISTING CONDITIONS PLAN
180384 1-5 TOPOGRAPHIC AND BOUNDARY SURVEY

C-1.01A - TENTATIVE PARCEL MAP
C-1.01C

C1.02 LOT MERGER PLAN

C2.00 PROPOSED GRADING PLAN

C3.00 STORMWATER MANAGEMENT PLAN
C3.01 STORMWATER MANAGEMENT DETAILS
C3.02 STORMWATER MANAGEMENT DETAILS

C4.00 EROSION CONTROL PLAN
C4.01 EROSION CONTROL PLAN DETAILS

C5.00 PROPOSED SITE IMPROVEMENT PLAN
C5.01 CYCLE TRACK CASE STUDY
C5.02 CONSTRUCTION DETAILS
C5.03 CONSTRUCTION DETAILS
C5.04 CONSTRUCTION DETAILS
C5.05 CONSTRUCTION DETAILS
C5.06 CONSTRUCTION DETAILS
C6.00 PROPOSED UTILITY PLAN

LANDSCAPE PLANS

L1.00 TREE REMOVAL PLAN
L1.01 LAYOUT & MATERIALS PLAN
L1.01.02 PUBLIC ACCESS PLAN
L1.02 LANDSCAPE WALL HEIGHT PLAN
L1.03 LANDSCAPE SECTIONS
L1.04 LANDSCAPE SECTIONS
L1.05 STREET SECTIONS
L1.06 PRELIMINARY LIGHTING PLAN
L1.07 PLANTING ZONES
L1.08 LANDSCAPE PLANTS
L1.09 LANDSCAPE MATERIALS
L1.10 LIGHTING IMAGES
L1.11 LIGHT LEVEL GOALS
L01.12 LANDSCAPE VIEWS


ARCHITECTURAL PLANS, ELEVATIONS, AND DETAILS

A-9.00 SITE PLAN
A-9.01 PUBLIC SPACE IMPROVEMENT: PUBLIC SPACE DESIGN
A-9.02 PUBLIC SPACE IMPROVEMENT: MANDELA PLAZA
A-9.03 PUBLIC SPACE IMPROVEMENT: MANDELA PLAZA
A-9.04 EVENT SPACE PROGRAM
A-9.05 - PUBLIC SPACE IMPROVEMENT: UNDER TRACK SPACE
A-9.07
A-9.08 - MANDELA PLAZA
A9.11
A9.12 PUBLIC SPACE IMPROVEMENT: ART ALLEY
A-9.14
A-9.15 - PUBLIC SPACE IMPROVEMENT: CENTER SQUARE
A-9.19
A-10.04 - PUBLIC SPACE IMPROVEMENT: CROSSWALKS & INTERSECTIONS
A-10.04.07
A-10.05 PUBLIC SPACE IMPROVEMENT: SIDEWALKS
A-10.06 PUBLIC SPACE IMPROVEMENT: BIKES
A-10.07 PUBLIC SPACE IMPROVEMENT: PASSENGER LOADING
A-10.08 PUBLIC SPACE IMPROVEMENT: BUS STOPS
A-10.09 EMERGENCY VEHICLE ACCESS
A-10.10 SIGN PLAN
A-10.11 T1 MATERIAL BOARD
A-10.11 T3 MATERIAL BOARD
A-10.11 T4 MATERIAL BOARD
A-10.12 MASSING DIAGRAM

A-10.13 SITE PLAN
A-11.01 GROUND FLOOR PLAN
A-11.02 2ND FLOOR PLAN
A-11.03 3RD FLOOR PLAN
A-11.04 4TH FLOOR PLAN
A-11.05 5TH FLOOR PLAN
A-11.06 6 - 7TH FLOOR PLAN
A-11.07 8 - 18TH FLOOR PLAN
A-11.08 19TH FLOOR PLAN
A-11.09 20 - 31TH FLOOR PLAN
A-11.10 ROOF PLAN
A-11.11 B1 FLOOR PLAN
A-11.12 B2 FLOOR PLAN

A-20.01 7TH STREET ELEVATION
A-20.02 MANDELA PKWY ELEVATION
A-20.03 5TH STREET ELEVATION
A-20.04 CHESTER STREET ELEVATION
A 20.05 T1 & T4 WEST ELEVATION
A-20.06 T1 SOUTH ELEVATION

A-30.01 SECTION A-A
A-30.02 SECTION B-B
A-30.03 SECTION C-C

**MANDELA STATION
@WEST OAKLAND
BART**1451 7th St, Oakland,
CA 94607

JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART


DATE: July 24, 2020


**DRAWING
INDEX**


SHEET:


G-100




































































SUMMARY OF PROPOSED ENTITLEMENT CHANGES


Development Program

- 
 T1 – eliminated the 82,460sf of office, and added 22 market rate units that have been transferred from T3; reduced retail from 17,185sf to 14,350sf; increased to 31 stories
- 
 T2 – eliminated the under-track retail kiosks
- 
 T3 – moved the 22 market rate units to T1
- 
 T4 – reduced the retail from 30,800sf to 23,184sf
- 
 Parking – changed the shared 400 car parking garage to 3 separate garages: T1-125 spaces; T3-50 spaces; T4- 210spaces
- 
 Requested State Affordable Housing Bonus waivers for parking and open space.

Revision Cloud Key



MANDELA STATION
@WEST OAKLAND
BART
1451 7th St, Oakland,
CA 94607



JRDV URBAN INTERNATIONAL
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

SUMMARY OF PROPOSED ENTITLEMENT REVISIONS


SHEET: A-01.00

Proposed Program

| USES | T1 | T2 | T3 | T4 | Program Total |
|-----------------------|-----------|------------------------|------------|------------|------------------------------------|
| OFFICE | | | | 300,000 sf | 300,000 sf |
| RETAIL | 14,350 sf | Flexible Kiosk Program | 15,944 sf | 23,184 sf | 53,478 sf |
| OTHER NON-RESIDENTIAL | | | 2,057 sf | 8,540 sf | 10,597 sf |
| RESIDENTIAL | 522 units | | 240 units* | | 762 units (20% min. affordable) |
| PARKING | 125 | | 50 | 210 | 385 spaces |

*79 units at 30% AMI, 11 units at 50% AMI, 148 units at 60% AMI, 2 units at 120% AMI

Note: Program is based on the previously approved Conditions of Approval, As approved by the Planning Commission February 6, 2019.



Open Space Calculation


| | |
|---|-------------------|
| Residential Open Space Req | |
| 240 Units | 200 48,000 SF |
| 522 Units | 200 104,400 SF |
| Required Open Space | 152,400 SF |
| Open Space Provided | |
| T1 Open Space | 17,648 SF |
| T3 Open Space | 24,815 SF |
| | 42,463* SF |
| Approximate Public Open Space Provided | |
| Mandela Plaza | 30,032 SF |
| Under Track Plaza | 8,464 SF |
| Art Alley | 20,923 SF |
| Center Square | 15,949 SF |
| | 75,368 SF |



Note:
 The Applicant is requesting a waiver/reduction of the group usable open space requirements for T-1 and for T-3 pursuant to Government Code section 65915 (e); and
 The Applicant is requesting a reduction in the amount of parking required for T-1 and T-3 pursuant to Government Code section 65915 (p)
 The Hall of Fame Plaques will be removed from the right of way to be relocated back into the 7th Street right of way at an appropriate realigned location by the completion of T1.
 The dancing lights will be removed from the right of way and there is no plan for their relocation as part of the FDP at this time.



**MANDELA STATION
 @WEST OAKLAND
 BART**
 1451 7th St, Oakland,
 CA 94607



JRDV URBAN INTERNATIONAL
 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com



PROJ. # 168-153 WO BART
 DATE: July 24, 2020

**ZONING
 INFO**

SHEET: A-01.01

| GENERAL ZONING INFORMATION | REFERENCE | NOTES |
|---|----------------|---|
| ASSESORS BLOCK | Survey | See Survey; Tract 8046, Blocks 494 and 493 |
| ZONING USE DISTRICT | Oak GIS | S-15W |
| PERMITTED AND/OR CONDITIONAL USES | 17.97.010-.020 | Residential, Community Assembly, General Retail, Full +Limited Service Retail, Parking, Commercial Office permitted |
| HEIGHT & BULK DISTRICT | 17.97 | S-15W 60' and S-15W 100'; master plan consistent with zoning requirements |
| GENERAL PLAN / POLICY PLAN | OAK-GIS | General Commercial; West Oakland Specific Plan |
| HISTORIC OR LANDMARK STATUS | OAK-GIS | None |
| LIQUEFACTION HAZARD ZONE | OAK-GIS | Severity 4 |
| CONDO CONVERSION IMPACT AREA | OAK-GIS | None |
| HEIGHT AND BULK CONTROLS | | |
| SITE AREA | Survey | 241,282 SF |
| FLOOR AREA RATIO (FAR) | 17.97.130 | S-15W 60' - 3.0; S-15W 100' - 5.0; Master Plan within zoning density requirements |
| HEIGHT LIMIT | 17.97 | 60' and 100' (Height limit modified to allow 80' and 320' tall building pursuant to State Affordable Housing Exemption) |
| REQUIRED SETBACKS | 17.97.060 | No Front Yard Setbacks Required; Interior Lot subject to PUD |
| REAR YARDS / COURTS | | None Required |
| ADJACENCIES | | None Significant |
| UNIT SEPARATION / EXPOSURE REQUIREMENTS | 17.108.080 | 8' minimum at living room window +2' for each floor above = maximum 10% of It width |
| DETAILED CONTROLS & REQUIREMENTS | | |
| RESIDENTIAL DENSITY LIMITS | 17.97.130 | S-15W 60' - 375sf/unit; S-15W100' - 225sf/unit; Density increase per State Affordable Housing and PUD density bonus |
| OPEN SPACE REQUIREMENTS | 17.97.130 | S-15W 60' - 150sf/unit; and S-15W 100' - 75sf/unit; Overall master plan within zoning limites |
| SCREENING & SETBACK OF PARKING & LOADING | 17.116.290 | All parking garages are screened per zoning requirements |
| OFF-STREET PARKING - RESIDENTIAL | 17.116.060 | 0.5 parking space per dwelling unit required; Parking meets zoning requirements with approved reductions |
| OFF-STREET PARKING - RETAIL | 17.116.080 | 1 space/600 Sf of ground floor; Parking meets zoning requirements with approved reductions |
| OFF-STREET PARKING - COMMERCIAL | 17.116.080 | None required |
| OFF-STREET PARKING DIMENSIONS | 17.116.200 | 50-50 compact / standard; or 75% intermediate + 12.5% compact |
| OFF-STREET DRIVE AISLE DIMENSIONS | 17.116.210 | 21'-24' two way aisle widths |
| OFF-STREET LOADING - RESIDENTIAL | 17.116.120 | Loading per zoning requirements |
| OFF-STREET LOADING - RETAIL | 17.116.150 | Loading per zoning requirements |
| LOADING BERTH DIMENSIONS | 17.116.220 | 10'x23', 12' high for residential activities, 10'x25', 8' high for undertaking service commercial activities |
| BICYCLE REQUIREMENTS - RESIDENTIAL+COMMERCIAL | 17.117.090 | LT: total 221 spaces; ST: total 54 spaces LT: 1 per 10,000 sf of commercial; ST: 1 per 20,000 sf of commercial LT: 0.25 spaces per dwelling unit; ST: 0.05 per dwelling unit; bicycle parking provide per zoning code |
| BICYCLE REQUIREMENTS - RETAIL | 17.117.110 | LT: total 6 spaces; ST: total 28 spaces LT: 1 per 12k; ST: 1 per 2k; bicycle parking provided per zoning code |


*The Hall of Fame Plaques will be removed from the right of way to be relocated back into the 7th Street right of way at an appropriate realigned location by the completion of T1.

*The dancing lights will be removed from the right of way and there is no plan for their relocation as part of the FDP at this time.



**MANDELA STATION
@WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART

DATE: July 24, 2020


**ZONING
SUMMARY**

SHEET:

A-01.02


BUILDING T1

Landscaped Terrace
Common Open Space



BUILDING T1 - LEVEL 4 - AMENITY

Common Use Terrace
Level 5-31 - Common Use Decks




BUILDING T1 - LEVEL 19 - AMENITY


| | |
|------------------|-------------------|
| Common Use Decks | 2,334 SF |
| Roof Terraces | 15,314 SF |
| TOTAL | 17,648* SF |

*Open space waiver of 86,752 sf requested for T1 per Density Bonus Letter.


BUILDING T3



LEVEL 2



LEVELS 3-6




LEVEL 7

| LEVEL | COMMON | PRIVATE |
|----------------------------|--------------------|-----------------------|
| LV2 | 10,187 SF | 2,528 SF |
| LV3 | | 1,161 SF |
| LV4 | | 1,161 SF |
| LV5 | | 1,161 SF |
| LV6 | | 1,161 SF |
| LV7 | | 142 SF |
| SUBTOTAL | 10,187 SF | 14,628 SF (X2) |
| TOTAL T3 OPEN SPACE | 24,815 SF * | |

*Open space waiver of 23,185 sf requested for T3 per Density Bonus Letter



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



JRDV URBAN INTERNATIONAL
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: July 24, 2020

SHEET: OPEN SPACE ANALYSIS
A-01.03


Note: The Applicant is requesting a waiver/reduction of the group usable open space requirements for T-1 and for T-3 pursuant to Government Code section 65915 (e);

PUBLIC OPEN SPACE

GROUND LEVEL - PUBLIC OPEN SPACE 75,368± SF




**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



**JRDV URBAN
INTERNATIONAL**
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com

**BKF100
YEARS**
ENGINEERS · SURVEYORS · PLANNERS

stök
PGAdesign
LANDSCAPE ARCHITECTS



PROJECT SCHEDULE

| | | | | | | | |
|---|---|---|--|---|---|---|--|
| 1. Horizontal | | | | 3. Phase II – T1 Development & T2 Development (plus PZ/PX for that phase) | | | |
| i. | Submit application for Final Development Plan | 1 year following PDP approval | | i. | Submit application for Final Development Plan | 3 years following PDP approval | |
| ii. | Anticipated FDP approval date by Agency | 1 year following submittal of Horizontal FDP application | | ii. | Anticipated FDP approval date by Agency | 1 year following submittal of Phase II FDP application | |
| iii. | Commence construction – Initial PX and/or PZ job (additional PX and PZ jobs will be tied to each later phase) | 2 years following FDP approval | | iii. | Commence construction | The latter of 2 years following FDP approval or 2 years following Phase I commencement of construction | |
| 2. Phase I – T3 Development (plus PZ/PX for that phase) | | | | 4. Phase III – T4 Development (plus PZ/PX for that phase) | | | |
| i. | Submit application for Final Development Plan | 1 year following PDP approval | | i. | Submit application for Final Development Plan | 5 years following PDP approval | |
| ii. | Anticipated FDP approval date by Agency | 1 year following submittal of Phase I FDP application | | ii. | Anticipated FDP approval date by Agency | 1 year following submittal of Phase III FDP application | |
| iii. | Commence construction | 2 years following FDP approval (allowing time to secure affordable financing) | | iii. | Commence construction | The latter of 2 years following FDP approval or 2 years following Phase II commencement of construction | |

PROJ. # 168-153 WO BART
DATE: July 24, 2020

**PHASING
PLAN**

SHEET: A-01.04

LEED CS v4 SCORECARD


West Oakland Station T4

| | Confirmed | Likely | Maybe | No | Phase | Credit Number | Credit Name | Points Available |
|---------------------------|-------------------|--------|-------|----|--------|--|--|--|
| | | | | | | | | |
| | 1 | | | | D | Credit | Integrative Process - In design phases, achieve synergies between building, energy AND water related systems | 1 |
| | 1 | | | | | | | 1 |
| LOCATION & TRANSPORTATION | 20 | | | | D | Credit | LEED for Neighborhood Development Location - Locate within LEED ND certified development site boundary | 20 |
| | 2 | | | | D | Credit | Sensitive Land Protection - Develop on previously developed land or follow criteria for non-sensitive | 2 |
| | 2 | | 1 | | D | Credit | High Priority Site - Locate project on infill location in historic district, priority designation or brownfield | 3 |
| | 2 | 2 | | 2 | D | Credit | Surrounding Density & Diverse Uses - Site within 1/4 mile of surrounding density criteria and/or a 1/2 mile of diverse uses | 6 |
| | 6 | | | | D | Credit | Access to Quality Transit - Locate functional entries within 1/4 mile of existing transit or 1/2 mile of planned transit services | 6 |
| | 1 | | | | D | Credit | Bicycle Facilities - Provide a bike network and storage areas | 1 |
| | 1 | | | | D | Credit | Reduced Parking Footprint - Don't exceed minimum local code requirements for parking capacity | 1 |
| | 1 | | | | D | Credit | Green Vehicles - 5% of spaces or 20% discount for parking and electric car charging OR liquid, gas or battery facilities | 1 |
| | 12 | 5 | | 20 | | | Totals | 20 |
| | SUSTAINABLE SITES | Yes | | | | C | Prereq | Construction Activity Pollution Prevention - Implement an erosion control plan, per the EPA CGP v2012 |
| | | | 1 | | D | Credit | Site Assessment - Complete site survey including: topography, hydrology, climate, vegetation, soils, human use, human health | 1 |
| | | | 2 | | D | Credit | Site Development - Protect or Restore Habitat - Preserve 40% of greenfield AND on-site restoration OR financial support | 2 |
| 1 | | | | | D | Credit | Open Space - Provide outdoor space greater than or equal to 30% of total site area, 25% of which is vegetated | 1 |
| | | | 3 | | D | Credit | Rainwater Management - Manage runoff for at least the 85th percentile of local rainfall events | 3 |
| | | 1 | | 1 | D | Credit | Heat Island Reduction - Meet nonroof and roof criteria OR place a minimum of 75% parking spaces under cover | 2 |
| 1 | | | | | D | Credit | Light Pollution Reduction - Backlight-uplight-glare method or calculation method, exterior luminaires and signage requirements | 1 |
| 1 | | | | D | Credit | Tenant Design and Construction Guidelines - Provide Manual or automative glare control devices | 1 | |
| 3 | 1 | | 7 | | | Totals | 11 | |
| WATER | Yes | | | | D | Prereq 1 | Outdoor Water Use Reduction - Permanent non-irrigated landscape OR reduce landscape water use 30% for peak watering month | NA |
| | Yes | | | | D | Prereq 2 | Indoor Water Use Reduction - Reduce aggregate water use by 20% for fixtures and fittings | NA |
| | Yes | | | | D | Prereq 3 | Building-Level Water Metering - Install permanent water meters that measure potable water use, share data with USGBC | NA |
| | 1 | | | 1 | D | Credit | Outdoor Water Use Reduction - Reduce water use no irrigation or reduced irrigation 50% - 100% | 2 |
| | 3 | | | 3 | D | Credit | Indoor Water Use Reduction - Reduce fixture and fitting water use by 25% - 50% | 6 |
| | | | 2 | D | Credit | Cooling Tower Water Use - Conduct a one-time potable water analysis, measure control parameters in Table 1 | 2 | |
| | | | 1 | D | Credit | Water Metering - Meters for 2 or more water subsystems: irrigation, indoor plumbing, hot water, boiler, reclaimed water, or other | 1 | |
| 4 | | | 7 | | | Totals | 11 | |
| ENERGY & ATMOSPHERE | Yes | | | | C | Prereq 1 | Fundamental Commissioning and Verification - Commissioning for ASHRAE 0-2005 and 1.1-2007 | NA |
| | Yes | | | | D | Prereq 2 | Minimum Energy Performance - Whole building energy simulation OR ASHRAE 50% Design Guide OR ABCPG | NA |
| | Yes | | | | D | Prereq 3 | Building-Level Energy Metering - Use building-level energy meters or submeters that can aggregate building-level data | NA |
| | Yes | | | | D | Prereq 4 | Fundamental Refrigerant Management - Do not use CFC-based refrigerants in HVAC&R systems, or have a phase out plan | NA |
| | 3 | 1 | | 2 | C | Credit | Enhanced Commissioning - Implement systems commissioning or monitor-based commissioning | 6 |
| | 5 | 2 | | 11 | D | Credit | Optimize Energy Performance - Whole building energy simulation or follow ASHRAE Advanced Energy Design Guide | 18 |
| | | | | 1 | D | Credit | Advanced Energy Metering - Install advanced energy metering for whole building and individual energy sources | 1 |
| | | | | 2 | C | Credit | Demand Response - Participate in existing demand response program or provide infrastructure for demand response programs | 2 |
| | | | | 3 | D | Credit | Renewable Energy Production - Use renewable energy system to meet 1-10% of usage | 3 |
| | | | | 1 | D | Credit | Enhanced Refrigerant Management - Refrigerants with ODP of 0 and GWP of less than 50 OR calculate refrigerant impact | 1 |
| | | | 2 | C | Credit | Green Power and Carbon Offsets - Use 50-100% green power or carbon offsets | 2 | |
| 8 | 6 | | 19 | | | Totals | 33 | |

| | Confirmed | Likely | Maybe | No | Phase | Credit Number | Credit Name | Points Available |
|---|-----------|--------|-------|----|-------|---------------|---|-------------------|
| | | | | | | | | |
| MATERIALS & RESOURCES | Yes | | | | D | Prereq | Storage and Collection of Recyclables - Dedicated areas for waste collection, collection and storage | NA |
| | Yes | | | | D | Prereq | Construction and Demolition Waste Management Planning - Establish C&D waste diversion goals | NA |
| | | 3 | | 3 | C | Credit | Building Life-Cycle Impact Reduction - Historic building reuse, renovate blighted buildings OR whole building LCA | 6 |
| | | 1 | | 1 | C | Credit | Building Product Disclosure and Optimization - Environmental Product Declarations | 2 |
| | | 1 | | 1 | C | Credit | Building Product Disclosure and Optimization - Sourcing of Raw Materials | 2 |
| | | 1 | | 1 | C | Credit | Building Product Disclosure and Optimization - Material Ingredients | 2 |
| | 1 | 6 | | 7 | | | Totals | 14 |
| INDOOR ENVIRONMENTAL | Yes | | | | D | Prereq | Minimum Indoor Air Quality Performance - Meet ASHRAE 62.1-2010 | NA |
| | Yes | | | | D | Prereq | Environmental Tobacco Smoke Control - Prohibit smoking indoors, restrict outdoor smoking within 25 feet | NA |
| | 1 | 1 | | | D | Credit | Enhanced Indoor Air Quality Strategies - Comply with enhanced IAQ strategies | 2 |
| | 1 | 1 | | 1 | C | Credit | Low-Emitting Materials - Achieve level of compliance for product categories or use budget calculation method | 3 |
| | | | | 1 | C | Credit | Construction IAQM Plan - Implement IAQMP & protect materials and equipment during construction | 1 |
| | | | | 3 | D | Credit | Daylight - Install glare control devices, spatial daylight autonomy, illuminance calculations OR daylight floor area measurement | 3 |
| | 1 | | | | D | Credit | Quality Views - Vision glazing for 75% of regularly occupied floor area, with at least two kinds of view types | 1 |
| 2 | 3 | | 5 | | | Totals | 10 | |
| INNOVATION* | | 1 | | | D | Credit | Innovation: Low Mercury Lighting | 1 |
| | | 1 | | | D | Credit | Innovation: Greenbuilding Education | 1 |
| | | | | 1 | D | Credit | TBD | 1 |
| | | | | 1 | D | Credit | TBD | 1 |
| | | | | 1 | D | Credit | TBD | 1 |
| | 1 | 2 | | 3 | | | Totals | 6 |
| <i>*Innovation in Design includes Exemplary Performance credits</i> | | | | | | | | |
| REGIONAL** | | | | 1 | D | Credit | Optimize Energy Performance (10 Points) | 1 |
| | 1 | | | | D | Credit | Access to Quality Transit (5 Points) | 1 |
| | | 1 | | | D | Credit | BPDO - Raw Materials (1 point) | 1 |
| | | | | 1 | D | Credit | Rainwater Management (3 Points) | 1 |
| | | | | 1 | D | Credit | Outdoor Water Use Reduction (2 points) | 1 |
| 1 | 2 | | 3 | | | Totals | 4 | |
| <i>**only 4 Regional Credits are Applicable</i> | | | | | | | | |
| Confirmed Certification Level: | | | | | | | | Not SILVER |
| Confirmed + Likely Certification Level: | | | | | | | | Silver |
| Confirmed + Likely + Maybe Certification Level: | | | | | | | | |
| Total Confirmed Points | | | | | | | | 32 |
| Total Confirmed + Likely Points | | | | | | | | 58 |
| Total Confirmed + Likely + Maybe Points | | | | | | | | 58 |



MANDELA STATION
@WEST OAKLAND
BART
1451 7th St, Oakland,
CA 94607



JRDV ARCHITECTS, INC.
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: June 6, 2020

LEED CHECK LIST

SHEET: A-01.06




NEW HOME RATING SYSTEM, VERSION 7.0

Blueprint Scoresheet

| Mandela Station T1 | | Points Targeted | Community | Energy | IAQ/Health | Resources | Water |
|---|---|-----------------|-----------|-------------|------------|-----------|-------------|
| | | Possible Points | | | | | |
| CALGreen | | | | | | | |
| Yes | CALGreen Res (REQUIRED) | 4 | | 1 | 1 | 1 | 1 |
| A. SITE | | | | | | | |
| Yes | A6. Stormwater Control: Prescriptive Path | | | | | | |
| | A6.3 Non-Leaching Roofing Materials | 1 | | | | | 1 |
| C. LANDSCAPE | | | | | | | |
| C3. Resource Efficient Landscapes | | | | | | | |
| Yes | C3.3 Drought Tolerant, California Native, Mediterranean Species, or Other Appropriate Species | 3 | | | | | 3 |
| E. EXTERIOR | | | | | | | |
| Yes | E4. Durable and Non-Combustible Cladding Materials | 1 | | | | 1 | |
| Yes | E5. Durable Roofing Materials | | | | | | |
| | E5.2 Roofing Warranty for Shingle Roofing | Y | R | R | R | R | R |
| F. INSULATION | | | | | | | |
| F1. Insulation with 30% Post-Consumer or 60% Post-Industrial Recycled Content | | | | | | | |
| Yes | F1.1 Walls and Floors | 1 | | | | 1 | |
| Yes | F1.2 Ceilings | 1 | | | | 1 | |
| F2. Insulation that Meets the CDPH Standard Method—Residential for Low Emissions | | | | | | | |
| Yes | F2.1 Walls and Floors | 1 | | | 1 | | |
| Yes | F2.2 Ceilings | 1 | | | 1 | | |
| G. PLUMBING | | | | | | | |
| G2. Install Water-Efficient Fixtures | | | | | | | |
| Yes | G2.1 WaterSense Showerheads 1.8 gpm with Matching Compensation Valve | 2 | | | | | 2 |
| Yes | G6. Submeter Water for Tenants | 2 | | | | | 2 |
| H. HEATING, VENTILATION, AND AIR CONDITIONING | | | | | | | |
| H6. Whole House Mechanical Ventilation Practices to Improve Indoor Air Quality | | | | | | | |
| Yes | H6.1 Meet ASHRAE Standard 62.2-2010 Ventilation Residential Standards | Y | R | R | R | R | R |
| Yes | H8. High Efficiency HVAC Filter (MERV 13+) | 1 | | | 1 | | |
| J. BUILDING PERFORMANCE AND TESTING | | | | | | | |
| J5. Building Performance Exceeds Title 24 Part 6 | | | | | | | |
| Option 1: Compliance Over Title 24 | J5.1 Home Outperforms Title 24 | 25 | | 25+ | | | |
| K. FINISHES | | | | | | | |
| K1. Entryways Designed to Reduce Tracked-In Contaminants | | | | | | | |
| Yes | K1.2 Entryways to Buildings | 1 | | | 1 | | |
| L. FLOORING | | | | | | | |
| ≥75% | L2. Low-Emitting Flooring Meets CDPH 2010 Standard Method—Residential | 3 | | | 3 | | |
| M. APPLIANCES AND LIGHTING | | | | | | | |
| Yes | M1. ENERGY STAR® Dishwasher | 1 | | | | | 1 |
| Yes | M2. Efficient Clothes Washing and Drying | | | | | | |
| | M2.2 Energy Star Dryer | 1 | | 1 | | | |
| <20 cubic feet | M3. Size-Efficient ENERGY STAR Refrigerator | 2 | | 2 | | | |
| Full Circuit | M6. Electric Vehicle Charging Stations and Infrastructure | 2 | | 2 | | | |
| Yes | M8. Gearless Elevator | 1 | | 1 | | | |
| N. COMMUNITY | | | | | | | |
| N1. Smart Development | | | | | | | |
| Yes | N1.1 Infill Site | 2 | 1 | | | 1 | |
| >35 | N1.3 Conserve Resources by Increasing Density | 4 | | 2 | | 2 | |
| | N1.5 Home Size Efficiency | 8 | | | | 10 | |
| 740 | Enter the area of the home, in square feet | | | | | | |
| 2 | Enter the number of bedrooms | | | | | | |
| N2. Home(s)/Development Located Near Transit | | | | | | | |
| Yes | N2.2. Within 1/2 mile of a Major Transit Stop | 2 | 2 | | | | |
| N3. Pedestrian and Bicycle Access | | | | | | | |
| Yes | N3.2 Connection to Pedestrian Pathways | 1 | 1 | | | | |
| Yes | N3.3 Traffic Calming Strategies | 2 | 2 | | | | |
| Yes | N3.5 Bicycle Storage for Residents | 1 | 1 | | | | |
| 1 space per unit | N3.7 Reduced Parking Capacity | 2 | 2 | | | | |
| N4. Outdoor Gathering Places | | | | | | | |
| Yes | N4.1 Public or Semi-Public Outdoor Gathering Places for Residents | 1 | 1 | | | | |
| Yes | N4.2 Public Outdoor Gathering Places with Direct Access to Tier 1 Community Services | 1 | 1 | | | | |
| Yes | N9.2 Community Location | 2 | 1 | | 1 | | |
| N11. Mixed-Use Developments | | | | | | | |
| Yes | N11.2 At Least 2% of Development Floor Space Supports Mixed Use | 1 | 1 | | | | |
| O. OTHER | | | | | | | |
| Yes | O1. GreenPoint Rated Checklist in Blueprints | Y | R | R | R | R | R |
| Yes | O2. Pre-Construction Kickoff Meeting with Rater and Subcontractors | 2 | | 0.5 | | 1 | 0.5 |
| Yes | O7. Green Appraisal Addendum | Y | R | R | R | R | R |
| Yes | O11. Tobacco Free Buildings | 2 | | | 2 | | |
| Summary | | | | | | | |
| Total Available Points in Specific Categories | | 375.5 | 46 | 110.5 | 70 | 95 | 54 |
| Minimum Points Required in Specific Categories | | 50 | 2 | 25 | 6 | 6 | 6 |
| Total Points Targeted | | 85 | 15 | 32.5 | 11 | 16 | 10.5 |



MANDELA STATION
@WEST OAKLAND
BART
1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: June 6, 2020

GREENPOINTRATED

SHEET: A-01.07

WEST OAKLAND STATION T3




NEW HOME RATING SYSTEM, VERSION 7.0

Blueprint Scoresheet



| | | Points Targeted | Community | Energy | IAQ/Health | Resources | Water | Responsible Party | Blueprint Page No. | |
|---|---|-----------------|-----------|-------------|------------|-----------|------------|-------------------|--------------------|--|
| | | Possible Points | | | | | | | | |
| CALGreen | | | | | | | | | | |
| Yes | CALGreen Res (REQUIRED) | 4 | | 1 | 1 | 1 | 1 | | | |
| C. LANDSCAPE | | | | | | | | | | |
| Yes | C1. Plants Grouped by Water Needs (Hydrozoning) | 1 | | | | | 1 | | | |
| C3. Resource Efficient Landscapes | | | | | | | | | | |
| Yes | C3.1 No Invasive Species Listed by Cal-IPC | 1 | | | | 1 | | | | |
| Yes | C3.3 Drought Tolerant, California Native, Mediterranean Species, or Other Appropriate Species | 1 | | | | | 3 | | | |
| E. EXTERIOR | | | | | | | | | | |
| Yes | E4. Durable and Non-Combustible Cladding Materials | 1 | | | | 1 | | | | |
| E5. Durable Roofing Materials | | | | | | | | | | |
| Yes | E5.2 Roofing Warranty for Shingle Roofing | Y | R | R | R | R | R | | | |
| F. INSULATION | | | | | | | | | | |
| F1. Insulation with 30% Post-Consumer or 60% Post-Industrial Recycled Content | | | | | | | | | | |
| Yes | F1.1 Walls and Floors | 1 | | | | 1 | | | | |
| F2. Insulation that Meets the CDPH Standard Method—Residential for Low Emissions | | | | | | | | | | |
| Yes | F2.1 Walls and Floors | 1 | | | 1 | | | | | |
| Yes | F2.2 Ceilings | 1 | | | 1 | | | | | |
| G. PLUMBING | | | | | | | | | | |
| G2. Install Water-Efficient Fixtures | | | | | | | | | | |
| Yes | G2.1 WaterSense Showerheads 1.8 gpm with Matching Compensation Valve | 2 | | | | | 2 | | | |
| Yes | G2.2 WaterSense Bathroom Faucets with 1.0gpm or less | 1 | | | | | 1 | | | |
| 1.28 gpf | G2.3 WaterSense Toilets with a Maximum Performance (MaP) Threshold of No Less Than 500 Grams 1.28gpf OR 1.1 gpf | 1 | | | | | 2 | | | |
| H. HEATING, VENTILATION, AND AIR CONDITIONING | | | | | | | | | | |
| H6. Whole House Mechanical Ventilation Practices to Improve Indoor Air Quality | | | | | | | | | | |
| Yes | H6.1 Meet ASHRAE Standard 62.2-2010 Ventilation Residential Standards | Y | R | R | R | R | R | | | |
| J. BUILDING PERFORMANCE AND TESTING | | | | | | | | | | |
| J5. Building Performance Exceeds Title 24 Part 6 | | | | | | | | | | |
| Option 1: Compliance Over Title 24 | J5.1 Home Outperforms Title 24 | 25 | | 25+ | | | | | | |
| N. COMMUNITY | | | | | | | | | | |
| N1. Smart Development | | | | | | | | | | |
| Yes | N1.1 Infill Site | 2 | 1 | | | 1 | | | | |
| N2. Home(s)/Development Located Near Transit | | | | | | | | | | |
| Yes | N2.2. Within 1/2 mile of a Major Transit Stop | 2 | 2 | | | | | | | |
| N3. Pedestrian and Bicycle Access | | | | | | | | | | |
| | N3.1 Pedestrian Access to Services Within 1/2 Mile of Community Services | 2 | 2 | | | | | | | |
| 10 | Enter the number of Tier 1 services | | | | | | | | | |
| 10 | Enter the number of Tier 2 services | | | | | | | | | |
| Yes | N9.2 Community Location | 2 | 1 | | 1 | | | | | |
| O. OTHER | | | | | | | | | | |
| Yes | O1. GreenPoint Rated Checklist in Blueprints | Y | R | R | R | R | R | | | |
| Yes | O2. Pre-Construction Kickoff Meeting with Rater and Subcontractors | 2 | | 0.5 | | 1 | 0.5 | | | |
| Yes | O7. Green Appraisal Addendum | Y | R | R | R | R | R | | | |
| P. DESIGN CONSIDERATIONS | | | | | | | | | | |
| P3. Commissioning | | | | | | | | | | |
| Yes | P3.1 Design Phase | 2 | | 1 | 1 | | | | | |
| Yes | P3.2 Construction Phase | 3 | | 2 | 1 | | | | | |
| Yes | P3.3 Post-Construction Phase | 3 | | 2 | 1 | | | | | |
| Summary | | | | | | | | | | |
| Total Available Points in Specific Categories | | 375.5 | 46 | 110.5 | 70 | 95 | 54 | | | |
| Minimum Points Required in Specific Categories | | 50 | 2 | 25 | 6 | 6 | 6 | | | |
| Total Points Targeted | | 58 | 6 | 31.5 | 7 | 6 | 7.5 | | | |

MANDELA STATION
@WEST OAKLAND
BART
1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: June 6, 2020

GREENPOINT RATED

SHEET:

A-01.08

MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com







PROJ. # 168-153 WO BART
 DATE: July 24, 2020

CONTEXT
MAP

SHEET: A-01.09


SITE LOCATION



LOCATION OF PROJECT SITE WITHIN WEST OAKLAND NEIGHBORHOOD




5 ACRE PROJECT SITE



SITE



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607




**JRDV URBAN
INTERNATIONAL**
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: July 24, 2020

**CONTEXT
PHOTOS**

SHEET: A-01.10




PLATFORM LEVEL PLAN




CONCOURSE LEVEL PLAN


| DOOR/ROOM LEGEND | | | | | |
|------------------|------------------|--------|-----------------|--------|---------------|
| DR.NO. | USE | DR.NO. | USE | DR.NO. | USE |
| 101 | STAFF RESTROOM | 109 | CUSTODIAN | 113A | BATTERY RM. |
| 102 | ELEV. EQUIP. RM. | 110 | STAFF BREAKROOM | 114 | TRAIN CONTROL |
| 103 | STORAGE | 111 | ELECT. EQUIP. | 115 | ELECT. EQUIP. |
| 107 | STORAGE | 112 | STORAGE | 116 | TRANSFORMER |
| 107A | GATE | 112A | GATE | 117 | FAN ROOM |
| 107B | STORAGE | 112B | STORAGE | | |
| 108 | STORAGE | 113 | TRAIN CONTROL | | |

**WEST OAKLAND STATION - OWS
"M" LINE - STATION M-10
FLOOR PLANS**



NOTE:
 EXISTING BOUNDARY FROM RECORD INFORMATION FOR
 PLANNING PURPOSES ONLY





BASIS OF BEARINGS

THE BEARING OF NORTH 72°53'28" WEST BETWEEN FOUND MONUMENTS ON 5TH AVENUE BETWEEN HENRY STREET AND KIRKHAM STREET AS SHOWN ON THAT RECORD OF SURVEY, R/S 1687, FILED AUGUST 7, 2000 IN BOOK 25 OF RECORDS OF SURVEY AT PAGES 58-69, INCLUSIVE, ALAMEDA COUNTY RECORDS, WAS TAKEN AS THE BASIS OF BEARINGS FOR THIS SURVEY.

BENCHMARK

THE ELEVATIONS SHOWN HEREON ARE BASED ON A FOUND CITY OF OAKLAND BENCHMARK, DESIGNATION 25/H, BEING A BRONZE DISK STAMPED, "SEC 25 STA H," ELEVATION 10.784 FEET (DATUM = MEAN SEA LEVEL).

NOTES

1. THE SURVEY WAS CONDUCTED IN NOVEMBER OF 2018.
2. ALL UNITS ARE IN US SURVEY FEET AND DECIMALS THEREOF.
3. THE TOPOGRAPHIC MAPPING SHOWN HEREON IS A WORKING DOCUMENT. THE TOPOGRAPHIC SURVEY AND MAPPING IS IN PROGRESS AND HAS NOT BEEN COMPLETED OR FINALIZED.

SURVEYOR'S STATEMENT:

THIS MAP CORRECTLY REPRESENTS A SURVEY MADE BY ME OR UNDER MY DIRECTION IN CONFORMANCE WITH THE REQUIREMENTS OF THE PROFESSIONAL LAND SURVEYOR'S ACT.

KEVIN STEIN, P.L.S. NO. 9028

DATE:




| Revisions | |
|-----------|-------------|
| No. | Description |
| | |
| | |
| | |
| | |
| | |

| | |
|-----------|------------|
| Date: | 12/06/2018 |
| Scale: | AS SHOWN |
| Design: | N/A |
| Drawn: | ADD |
| Approved: | KS |
| Job No.: | 180384 |

Drawing Number:
180384
1 of 5

DATE PLOTTED: 12/06/2018 10:00:00 AM
DRAWN BY: J. STEIN
CHECKED BY: K. STEIN
DATE: 12/06/2018



- SYMBOLS & LEGEND**
- EXISTING**
- FOUND CITY OF OAKLAND MONUMENT
 - VALVE
 - FIRE HYDRANT
 - BACKFLOW PREVENTION DEVICE
 - RISER
 - SIGN
 - STREET LIGHT (UNLESS NOTED OTHERWISE)
 - LIGHT POLE (UNLESS NOTED OTHERWISE)
 - UTILITY POLE
 - GUY ANCHOR
 - TELEPHONE MANHOLE
 - MANHOLE
- ABBREVIATIONS**
- AC ASPHALT CONCRETE
 - CA CABLE
 - CB CATCH BASIN
 - CO CLEAN OUT
 - COMM COMMUNICATION
 - CONC CONCRETE
 - DI DROP INLET
 - DWY DRIVEWAY
 - E ELECTRIC
 - EP EDGE OF PAVEMENT
 - FL SURFACE FLOWLINE
 - G GAS
 - GYP GUY POLE
 - INV BOTTOM INSIDE OF PIPE
 - LG LIP OF GUTTER
 - M METER
 - MH MANHOLE
 - OH OVERHEAD UTILITY LINE
 - SD STORM DRAIN
 - SL STREETLIGHT
 - SS SANITARY SEWER
 - TC TOP FACE OF CURB
 - TEL TELECOMMUNICATION LINE
 - TG TOP OF GRATE
 - TS TRAFFIC SIGNAL
 - TV TELEVISION
 - UB UTILITY BOX
 - V VALVE
 - VL VULT
 - W WATER
 - WM WATER METER



1646 N. CALIFORNIA BLVD.,
SUITE 400
WALNUT CREEK, CA 94596
(925) 940-2200
www.bkf.com

BKF 100 YEARS
ENGINEERS · SURVEYORS · PLANNERS

TOPOGRAPHIC AND BOUNDARY SURVEY
WEST OAKLAND BART

OAKLAND COUNTY OF ALAMEDA CALIFORNIA

| | | | |
|-----------------|------------|------------|--|
| Date: | 12/06/2018 | No.: | |
| Scale: | AS SHOWN | Revisions: | |
| Design: | N/A | | |
| Drawn: | ADD | | |
| Approved: | KS | | |
| Job No.: | 180384 | | |
| Drawing Number: | 180384 | | |
| | 5 of 5 | | |

DRAWING NAME: K:\Projects\180384\180384_001\180384_001.dwg; DATE: 12/06/2018 10:00:00 AM; USER: bkf\jason; PLOT DATE: 12/06/2018 10:00:00 AM; PLOT USER: bkf\jason

VESTING TENTATIVE PARCEL MAP NO. 10940

FOR CONDOMINIUM PURPOSES

SHEET INDEX


| SHEET # | SHEET TITLE |
|---------|-----------------------------------|
| 1 | TITLE SHEET/EXISTING SITE PLAN |
| 2 | PROPOSED SITE PLAN |
| 3 | EMERGENCY VEHICLE ACCESS EASEMENT |

SYMBOLS & LEGEND

| EXISTING | SYMBOL | DESCRIPTION |
|----------------------------|--------|----------------------------|
| VALVE | | VALVE |
| FIRE HYDRANT | | FIRE HYDRANT |
| BACKFLOW PREVENTION DEVICE | | BACKFLOW PREVENTION DEVICE |
| RISER | | RISER |
| SIGN | | SIGN |
| STREET LIGHT | | STREET LIGHT |
| LIGHT POLE | | LIGHT POLE |
| GUY ANCHOR | | GUY ANCHOR |
| UTILITY POLE | | UTILITY POLE |
| TELEPHONE MANHOLE | | TELEPHONE MANHOLE |
| MANHOLE | | MANHOLE |
| EXISTING PROPERTY LINE | | EXISTING PROPERTY LINE |
| ADJOINING LOT CENTERLINE | | ADJOINING LOT CENTERLINE |
| SURVEY TRIE | | SURVEY TRIE |
| STORM DRAIN | | STORM DRAIN |
| SANITARY SEWER | | SANITARY SEWER |
| OVERHEAD UTILITY LINE | | OVERHEAD UTILITY LINE |
| CONCRETE | | CONCRETE |
| DETECTABLE WARNING | | DETECTABLE WARNING |
| BOUNDARY LINE | | BOUNDARY LINE |


ABBREVIATIONS

| | |
|------|-----------------------------------|
| AC | ASPHALT CONCRETE |
| CA | CABLE |
| CB | CATCH BASIN |
| CO | CLEAN OUT |
| COMM | COMMUNICATION |
| CONC | CONCRETE |
| DBH | DIAMETER AT BREAST HEIGHT |
| DI | DROP INLET |
| DWY | DRIVEWAY |
| E | ELECTRIC |
| EP | EDGE OF PAVEMENT |
| EVAE | EMERGENCY VEHICLE ACCESS EASEMENT |
| FL | SURFACE FLOWLINE |
| G | GAS |
| GYP | GUY POLE |
| INV | BOTTOM INSIDE OF PIPE |
| LG | LIP OF GUTTER |
| M | METER |
| MH | MANHOLE |
| MIN | MINIMUM |
| OH | OVERHEAD UTILITY LINE |
| PL | PROPERTY LINE |
| R | RADIUS |
| SD | STORM DRAIN |
| SF | SQUARE FEET |
| SL | STREETLIGHT |
| SS | SANITARY SEWER |
| (T) | TOTAL |
| TC | TOP FACE OF CURB |
| TEL | TELECOMMUNICATION LINE |
| TG | TOP OF GRATE |
| TV | TRAFFIC SIGNAL |
| TS | TELEVISION |
| UB | UTILITY BOX |
| V | VALVE |
| VT | VAULT |
| W | WATER |
| WM | WATER METER |



EXISTING CONDITIONS
SCALE 1"=40'

| Tree number | DBH (in) | Species Name |
|-------------|----------|-------------------------|
| 16 | 36 | Pinus Pinea |
| 17 | 32 | Pinus Pinea |
| 20 | 13 | Liriodendron Tulipifera |
| 29 | 12 | Maytenus Boaria |
| 29 | 16 | Maytenus Boaria |
| 31 | 13 | Liriodendron Tulipifera |
| 33 | 13 | Liriodendron Tulipifera |
| 36 | 12 | Liriodendron Tulipifera |
| 48 | 18 | Platanus X Acerifolia |
| 51 | 17 | Platanus X Acerifolia |
| 52 | 12 | Liriodendron Tulipifera |



KEY MAP
SCALE 1"=500'

PROPERTY ADDRESS:
1451 7TH STREET
OAKLAND, CA 94607

OWNER AND SUBDIVIDER:
SAN FRANCISCO BAY AREA RAPID TRANSIT DISTRICT
300 LAKESIDE DRIVE, 22ND FLOOR
OAKLAND, CA 94612
PHONE: 510-597-6300

BASIS OF BEARINGS

THE BEARING OF NORTH 72°53'28" WEST BETWEEN FOUND MONUMENTS ON 5TH STREET BETWEEN HENRY STREET AND KIRKHAM STREET AS SHOWN ON THAT RECORD OF SURVEY, R/S 1687, FILED AUGUST 7, 2000 IN BOOK 25 OF RECORDS OF SURVEY AT PAGES 58-59, INCLUSIVE, ALAMEDA COUNTY RECORDS, WAS TAKEN AS THE BASIS OF BEARINGS FOR THIS SURVEY.

BENCHMARK

THE ELEVATIONS SHOWN HEREON ARE BASED ON A FOUND CITY OF OAKLAND BENCHMARK, DESIGNATION 25/H, BEING A BRONZE DISK STAMPED, "SEC 25 STA H," ELEVATION 10.784 FEET (DATUM = MEAN SEA LEVEL).

NOTES

- BASED ON INFORMATION CONTAINED IN THE PRELIMINARY TITLE REPORT, ORDER NUMBER NCS-891862-SC, DATED JANUARY 31, 2018, PROVIDED BY FIRST AMERICAN TITLE COMPANY, THE SUBJECT PROPERTY IS OWNED BY SFBART BEING ASSESSOR PARCEL NUMBERS 004-0077-003, 004-0071-003, AND THE VACATION OF CENTER STREET; THERE ARE 36 PARCELS, NOT INCLUDING THE VACATION OF CENTER STREET. THE EXISTING PARCELS WILL BE RECONFIGURED TO CREATE 3 LOTS AND ONE REMAINDER PARCEL VIA PARCEL MAP TO BE PROCESSED.
- THE INTENT OF THE MAP IS TO MERGE THE 36 PARCELS AND THE VACATED CENTER STREET INTO THE FOUR CONSOLIDATE PARCELS DEFINING THE KEY COMPONENTS OF THE NEW DEVELOPMENT: LOT 1 MARKET RATE RESIDENTIAL TOWER, LOT 2 OFFICE BUILDING, LOT 3 AFFORDABLE HOUSING, AND THE DESIGNATED REMAINDER PARCEL FOR THE EXISTING WEST OAKLAND BART STATION AND NEW ENTRY PLAZAS.
- THE CONTROL SURVEY WAS CONDUCTED IN NOVEMBER OF 2018.
- ALL UNITS ARE IN US SURVEY FEET AND DECIMALS THEREOF.
- THE TOPOGRAPHIC SURVEY IS BASED ON A FIELD SURVEY COMPLETED IN DECEMBER 2018.
- ALL BUILDINGS TO THE NORTH OF THE BART STATION SHALL BE 30' FROM THE BART PLATFORM, AND ALL BUILDINGS TO THE SOUTH OF THE BART STATION SHALL BE 33' FROM THE BART PLATFORM.
- ALL EMERGENCY VEHICLE ACCESS EASEMENTS SHALL BE 26' WIDE.
- LOTS 1, 2 AND 3 ARE ALLOWED UP TO FOUR COMMERCIAL CONDOMINIUMS ON EACH LOT.
- MULTIPLE MAPS MAY BE FILED FOR THIS PROJECT.

SURVEYOR'S STATEMENT:

THIS MAP CORRECTLY REPRESENTS A SURVEY MADE BY ME OR UNDER MY DIRECTION IN CONFORMANCE WITH THE REQUIREMENTS OF THE PROFESSIONAL LAND SURVEYOR'S ACT.

PAUL KITTRIDGE
PROJECT MANAGER
P.L.S. # 5790



DATE:

1646 N. CALIFORNIA BLVD., SUITE 400
WALNUT CREEK, CA 94596
(925) 940-2200
www.bkf.com

BKF100
YEARS
ENGINEERS • SURVEYORS • PLANNERS

VESTING TENTATIVE PARCEL MAP NO. 10940
TITLE SHEET

CALIFORNIA
COUNTY OF ALAMEDA
CITY OF OAKLAND

DRAWING NAME: K:\2018\190384_WestOakland_BART_TOD_Survey\ENG\TENTATIVE PARCEL MAP\SHEETS\01\WOBTMS.dwg
PLOT DATE: 04-06-20 PLOTTED BY: mitr

| Revisions | No. | DATE | BY | DESCRIPTION |
|-----------|-----|------------|----|-------------|
| AS SHOWN | | 04/06/2020 | | |
| CC | | | | |
| ES | | | | |



TENTATIVE
PARCEL MAP
C-1.01A



| Revisions | No. | Date |
|--------------|-----|------------|
| AS SHOWN | | 04/06/2020 |
| BY CC | | |
| BY EC | | |
| BY ES | | |
| No. 20180384 | | |


TENTATIVE
PARCEL MAP
C-1.01B

DRAWING NAME: K:\2018\190384_WestOakland_BART_TOD_Survey\ENG\TENTATIVE PARCEL MAP\SHEETS\02\0201MPL.dwg
PLOT DATE: 04-06-20 PLOTTED BY: mtr

LEGEND
BOUNDARY LINE
PROPOSED PARCEL LINE







ABBREVIATIONS:

| | |
|----|------------------|
| FF | FINISHED FLOOR |
| FG | FINISHED GROUND |
| FS | FINISHED SURFACE |
| FL | FLOW LINE |
| MA | MATCH |
| TC | TOP OF CURB |
| TS | TOP OF STEP |
| TW | TOP OF WALL |

LEGEND:


| | |
|--|--------------------------------|
| | DIRECTION OF PROPOSED DRAINAGE |
| | GRADE BREAK |
| | CONTOUR |

GRADING NOTES:





1. TC ELEVATIONS ARE 6" ABOVE ADJACENT PAVEMENT FL ELEVATIONS, UNLESS OTHERWISE NOTED ON PLAN.

EARTHWORK SUMMARY:

TOTAL EXCAVATION: 51,303 CUBIC YARDS
 TOTAL FILL: 0 CUBIC YARDS
 TOTAL OFFHAUL: 51,303 CUBIC YARDS




LEGEND:

-  DRAINAGE MANAGEMENT AREA (DMA)
-  PERMEABLE PAVING
-  FILTER VAULT
SEE SHEET C3.01
-  TREATMENT AREA LABEL



STORMWATER MANAGEMENT NOTES:

1. THE TREATMENT VAULTS WERE SELECTED BASED ON 243,131 SF OF IMPERVIOUS SURFACE AND A TREATMENT INTENSITY OF 0.2 IN/HR. SEE OLD CASTLE WASHINGTON GULD PF-V-8-WA-0001 PERK FILTER DETAIL ON SHEET C3.01. ALL FILTER VAULTS SHOWN ARE COMPRISED OF (31) - 18" CARTRIDGES.



| TOTAL SITE AREA (SF) | TOTAL LAND AREA DISTURBED (SF) | TOTAL EXISTING/PRE-PROJECT IMPERVIOUS SURFACE (SF) | REPLACED IMPERVIOUS SURFACE (SF) | NEW IMPERVIOUS SURFACE (SF) | TOTAL POST-PROJECT IMPERVIOUS SURFACE (SF) |
|----------------------|--------------------------------|--|----------------------------------|-----------------------------|--|
| 243,130 | 243,130 | 212,865 | 177,410 | 25,135 | 202,545 |



| DMA | Impervious Area (SF) | Pervious Area (SF) | Treatment Type | Designated Treatment Area |
|-----|----------------------|--------------------|------------------|---------------------------|
| 1 | 74,600 | 28,445 | Filter Vault | T1 |
| 2 | 58,278 | 0 | Filter Vault | T2 |
| 3 | 69,667 | 0 | Filter Vault | T3 |
| 4 | 0 | 12,140 | Permeable Paving | T4 |



Special Projects

Non-I.I.D Treatment Summary

| Category | Impervious Area Created/Replaced (acres) | Site Coverage (%) | Project Density or FAR | Density/Criteria | Allowable Credit (%) | Applied Credit (%) |
|---------------------------|--|-------------------|------------------------|--|----------------------|--------------------|
| A | | | N.A. | N.A. | 100% | |
| B | | | | Res ≥ 50 DU/ac or FAR ≥ 2:1 | 50% | |
| | | | | Res ≥ 75 DU/ac or FAR ≥ 3:1 | 75% | |
| | | | | Res ≥ 100 DU/ac or FAR ≥ 4:1 | 100% | |
| C | | | | Location credit (select one)⁵: | | |
| | | | | Within ¼ mile of transit hub | 50% | 50% |
| | | | | Within ½ mile of transit hub | 25% | |
| | | | | Within a planned PDA | 25% | |
| | | | | Density credit (select one): | | |
| | | | | Res ≥ 30 DU/ac or FAR ≥ 2:1 | 10% | |
| | | | | Res ≥ 60 DU/ac or FAR ≥ 4:1 | 20% | |
| | | | | Res ≥ 100 DU/ac or FAR ≥ 6:1 | 30% | 30% |
| | | | | Parking credit (select one): | | |
| | | | | ≥ 10% at-grade surface parking ⁶ | 10% | |
| No surface parking | 20% | 20% | | | | |
| TOTAL TOD CREDIT = | | | | | 100% | |




SECTION A-A


NOTES:

1. PLACE CURB TYPE SEDIMENT BARRIERS ON GENTLY SLOPING STREET SEGMENTS, WHERE WATER CAN POND AND ALLOW SEDIMENT TO SEPARATE FROM RUNOFF.
2. SANDBAGS OF EITHER BURLAP OR WOVEN 'GEOTEXTILE' FABRIC, ARE FILLED WITH GRAVEL LAYERED AND PACKED TIGHTLY.
3. LEAVE A ONE SANDBAG GAP IN THE TOP ROW TO PROVIDE A SPILLWAY FOR OVERFLOW.
4. INSPECT BARRIERS AND REMOVE SEDIMENT AFTER EACH STORM EVENT. SEDIMENT AND GRAVEL MUST BE REMOVED FROM THE TRAVELED WAY IMMEDIATELY.

① CURB INLET SEDIMENT BARRIER
NOT TO SCALE



ENTRENCHMENT DETAIL
IN FLAT AREA




ENTRENCHMENT DETAIL
IN SLOPED AREA

NOTES:

1. FIBER ROLLS ARE TUBES MADE FROM POROUS BIODEGRADABLE FIBER STUFFED IN A PHOTO-DEGRADABLE OPEN WEAVE NETTING. THEY ARE APPROXIMATELY 8" DIAMETER.
2. FIBER ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE ROLL IN A TRENCH; 2"-4" DEEP, DUG ON CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND ROLL. ROLLS SHOULD BE ABUTTED SECURELY TO PROVIDE A TIGHT JOINT, NOT OVERLAPPED.


② FIBER ROLL
NOT TO SCALE



Notes:

1. The entrance shall be maintained to prevent sediment tracking or flowing onto public right-of-ways. This may require top dressing, repair and/or cleanout or other measures that trap sediment.
2. When necessary, wheels shall be cleaned prior to entering public right-of-way.
3. When washing is required, it shall be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin.

③ Site Entrance





UTILITY KEYNOTES:

- ① NEW OLD CASTLE WASHINGTON GULD PV-V-8-WA-0001 PERK FILTER OR APPROVED EQUAL SEE DETAIL ON SHEET C3.01
- ② POTENTIAL CONNECTION LOCATION FOR ELECTRICAL AND TELECOM
- ③ REBUILD/UPSIZE SANITARY SEWER LINE TO CONNECTION AT CENTER ST x 3RD ST

UTILITY LEGEND:

- SD— STORM DRAIN LINE
- IRR— IRRIGATION LINE
- FW— FIRE WATER LINE
- DW— DOMESTIC WATER LINE
- SS— SANITARY SEWER LINE
- - - JT - - - JOINT TRENCH: ELEC + TELECOM
- DOMESTIC WATER MANHOLE PER CITY OF OAKLAND STANDARD DETAIL D-11
- STORM DRAIN MANHOLE
- ⊗ WATER VALVE
- DRAIN INLET







CYCLE TRACK CASE STUDY



CYCLE TRACK CASE STUDY

Rendering of Better Market Street with trapezoidal delineator between pedestrians and bicycles

Source:
San Francisco Public Works
Better Market Street Project

Trapezoidal delineator

Enhancing Mobility, Access and Safety for Pedestrians (Part II)

Recommendation
Use a trapezoidal indicator between bicycle and pedestrian sides of a separated bikeway at sidewalk level

PLAN, Regular Tile: 12.00" (300 mm) width, 12.00" (300 mm) height


PLAN, End Tile: 12.00" (300 mm) width, 12.00" (300 mm) height

SECTION: 10.00" (250 mm) width, 6.25" (160 mm) width, 0.75" (20 mm) depth

DETAIL: 1.875" (48 mm) width, 1.00" (25 mm) width, 0.75" (20 mm) depth, 22° angle

DETAIL 1 - LANE DROP

CONTINUE 1-WAY CLEAR REFLECTIVE MARKERS AT 12'




DETAIL 2 - LANE LINE EXTENSIONS THROUGH INTERSECTIONS



DETAIL 3 - CROSSWALKS



DETAIL 4 - LEFT EDGE LINE



CONTINUE 1-WAY YELLOW REFLECTIVE MARKERS AT 24'



WITH REFLECTIVE STRIPS (MINIMUM 100000 REFLECTIVITY) AT 12' SPACING THROUGHOUT THE LENGTH OF THE MARKING. THE SPACING OF MARKERS AT THE END OF THE MARKING SHALL BE 3' FROM THE END OF THE MARKING TO THE LAST MARKER.

CITY OF OAKLAND DESIGN AND CONSTRUCTION SERVICES DEPARTMENT



**PAVEMENT MARKING
DETAIL**

| | | |
|---------------------------------|-------------|---------|
| TRANSPORTATION SERVICES MANAGER | | |
| DATE | DESIGNED BY | CHKD BY |
| REV. DATE | | |
| | | T-3 |





CITY OF OAKLAND DESIGN AND CONSTRUCTION SERVICES DEPARTMENT



**SIGN INSTALLATION
DETAILS**

| | | |
|---------------------------------|-------------|---------|
| TRANSPORTATION SERVICES MANAGER | | |
| DATE | DESIGNED BY | CHKD BY |
| REV. DATE | | |
| | | T-4 |



SECTION A-A

1/4" THICK FLANGE,
USE 3/8" DIA. X 3" LENGTH
ANCHOR BOLTS. HLT, KWK OR
EQUAL.




WITH REFLECTIVE STRIPS (MINIMUM 100000 REFLECTIVITY) AT 12' SPACING THROUGHOUT THE LENGTH OF THE MARKING. THE SPACING OF MARKERS AT THE END OF THE MARKING SHALL BE 3' FROM THE END OF THE MARKING TO THE LAST MARKER.




CITY OF OAKLAND DESIGN AND CONSTRUCTION SERVICES DEPARTMENT




**SIGN INSTALLATION
DETAILS**

| | | |
|---------------------------------|-------------|---------|
| TRANSPORTATION SERVICES MANAGER | | |
| DATE | DESIGNED BY | CHKD BY |
| REV. DATE | | |
| | | T-5 |






1. Curb ramps shall have 4 ft. by 2 ft. long detectable warning border centered and squared at the ramp bottom.
2. The detectable warning border shall contrast visually with the adjoining surfaces, either light or dark. The material used to provide contrast shall be an integral part of the walking surface and shall contrast by at least 70 percent. A fully cured 2 ft. x 2 ft. sample of both the cast-in-place detectable warning border and the adjacent curb ramp shall be submitted to the Engineer for review and approval prior to installation.
3. Dome orientation shall conform to the latest ADA / Title 24 regulations.
4. The closest corner of the truncated dome tile to the street shall be set 6" from the flowline.
5. Detectable dome warning tiles or strips made of materials other than concrete shall only be used with the written approval of the Director of Public Works.
6. Precast concrete detectable warning dome pavers shall be installed on top of a 4 inch thick concrete pad. Mortared joints shall be flush with top surface and finished to provide a smooth surface. Pavers shall be laid such that joints are level with adjoining joints to provide a smooth transition from paver to paver and from paver to concrete surface.



Bottom Diameter = 0.9 inches
 Top Diameter = 0.4 inches
 Height = 0.2 inches
 Center-to-Center Spacing = 2.35 inches

PLAN VIEW OF DETECTABLE WARNING DOMES
 NTS



THIS SHEET IS FOR GUIDANCE ONLY. ALL CURB RAMPS SHALL BE CONSTRUCTED FOR THE MOST RECENT EDITIONS OF THE AMERICAN WITH DISABILITIES ACT (ADA), AND THE CALIFORNIA TITLE 24 ACCESSIBILITY GUIDELINES.

| | |
|---|---|
| CITY OF OAKLAND | DESIGN AND CONSTRUCTION SERVICES |
| | CURB RAMP DETAILS SHEET 5 OF 6 DETECTABLE WARNINGS |
| ENGINEERING DESIGN MANAGER REV. DATE: OCTOBER 2012 | CHK: S-7 |

CASE "C" CURB RAMP NOTES

1. If site conditions do not accommodate a Case E ramp, a Case "C" Curb Ramp shall be constructed.
2. If the sidewalk is less than 5-feet wide, a Case C ramp shall be installed.
3. The maximum slope of the lower landing of a Case C ramp shall be 2%. In all cases the lower landing shall be sloped to drain.
4. No vertical obstructions shall be allowed within a Case C curb ramp.


CASE "E" CURB RAMP NOTES:

5. Two ramps shall be provided at each corner of an intersection, unless otherwise allowed by the plans or by the Engineer. The centerline and path of travel of both curb ramps must be perpendicular to the gutter.
6. A level landing (4-ft deep with 2% max. slope) shall be provided at the upper end of each Case E curb ramp over its full width to permit safe exit from the ramp surface. If a level landing cannot be installed, then the side flares of the ramp shall slope less than or equal to 8.33%.



GENERAL CURB RAMP NOTES:


7. When constructing curb ramps, construct concrete gutter to match existing gutter widths. The new gutter shall be flush with the bottom of the curb ramp and the new gutter shall be considered part of the curb ramp construction.
8. Each curb ramp shall be bounded by a 12-inch border band with 1/4 inch deep grooves scored 3/4 inches apart except in the curb and gutter area.
9. Vertical obstructions, such as utility poles and traffic signals, shall only be allowed with the approval of the Engineer.
10. Existing utility boxes and covers shall be adjusted to conform flush with the curb ramp surface. All utility boxes and covers located within the detectable warning border area shall be relocated.

| | |
|--|---|
| CITY OF OAKLAND | ENGINEERING DESIGN DIVISION |
| | CURB RAMP DETAILS SHEET 6 OF 6 GENERAL NOTES |
| ENGINEERING DESIGN MANAGER CHK: S-8 | CHK: S-8 |



CONCRETE MOUNTABLE CURB AND TRANSITION
 SCALE: NONE





Trees Proposed for Removal

| Key | Species | DBH (in) |
|-----|---------------------------|----------|
| 1 | <i>Pistacia chinensis</i> | 4 |
| 2 | <i>Pistacia chinensis</i> | 4 |
| 3 | <i>Pistacia chinensis</i> | 4 |
| 4 | <i>Pistacia chinensis</i> | 3 |
| 5 | <i>Pistacia chinensis</i> | 5 |
| 6 | <i>Pistacia chinensis</i> | 4 |
| 7 | <i>Pistacia chinensis</i> | 4 |
| 8 | <i>Pistacia chinensis</i> | 4 |
| 9 | <i>Pistacia chinensis</i> | 4 |
| 10 | <i>Pistacia chinensis</i> | 4 |
| 11 | <i>Pistacia chinensis</i> | 4 |
| 12 | <i>Pistacia chinensis</i> | 4 |
| 13 | <i>Pistacia chinensis</i> | 4 |

| Key | Species | DBH (in) |
|-----|--------------------------------|----------|
| 14 | <i>Pistacia chinensis</i> | 4 |
| 15 | <i>Pistacia chinensis</i> | 4 |
| 16 | <i>Pinus pinea</i> | 36 |
| 17 | <i>Pinus pinea</i> | 32 |
| 18 | <i>Liriodendron tulipifera</i> | 9 |
| 19 | <i>Liriodendron tulipifera</i> | 11 |
| 20 | <i>Liriodendron tulipifera</i> | 13 |
| 21 | <i>Pistacia chinensis</i> | 4 |
| 22 | <i>Pistacia chinensis</i> | 4 |
| 23 | <i>Pistacia chinensis</i> | 4 |
| 24 | <i>Pistacia chinensis</i> | 4 |
| 25 | <i>Pistacia chinensis</i> | 5 |
| 26 | <i>Maytenus boaria</i> | 7 |

| Key | Species | DBH (in) |
|-----|--------------------------------|----------|
| 27 | <i>Maytenus boaria</i> | 12 |
| 28 | <i>Maytenus boaria</i> | 5 |
| 29 | <i>Maytenus boaria</i> | 16 |
| 30 | <i>Maytenus boaria</i> | 2 |
| 31 | <i>Liriodendron tulipifera</i> | 13 |
| 32 | <i>Liriodendron tulipifera</i> | 11 |
| 33 | <i>Liriodendron tulipifera</i> | 13 |
| 34 | <i>Liriodendron tulipifera</i> | 11 |
| 35 | <i>Liriodendron tulipifera</i> | 9 |
| 36 | <i>Liriodendron tulipifera</i> | 12 |
| 37 | <i>Liriodendron tulipifera</i> | 11 |
| 38 | <i>Liriodendron tulipifera</i> | 10 |
| 39 | <i>Liriodendron tulipifera</i> | 11 |


| Key | Species | DBH (in) |
|-----|--------------------------------|----------|
| 40 | <i>Liriodendron tulipifera</i> | 9 |
| 41 | <i>Liriodendron tulipifera</i> | 10 |
| 42 | <i>Liriodendron tulipifera</i> | 10 |
| 43 | <i>Liriodendron tulipifera</i> | 9 |
| 44 | <i>Liriodendron tulipifera</i> | 7 |
| 45 | <i>Liriodendron tulipifera</i> | 8 |
| 46 | <i>Liriodendron tulipifera</i> | 8 |
| 47 | <i>Liriodendron tulipifera</i> | 9 |
| 48 | <i>Platanus X acerifolia</i> | 18 |
| 49 | <i>Platanus X acerifolia</i> | 10 |
| 50 | <i>Platanus X acerifolia</i> | 10 |
| 51 | <i>Platanus X acerifolia</i> | 17 |
| 52 | <i>Liriodendron tulipifera</i> | 12 |

| Key | Species | DBH (in) |
|-----|--------------------------------|----------|
| 53 | <i>Liriodendron tulipifera</i> | 8 |
| 54 | <i>Liriodendron tulipifera</i> | 8 |
| 55 | <i>Liriodendron tulipifera</i> | 9 |
| 56 | <i>Liriodendron tulipifera</i> | 10 |
| 57 | <i>Liriodendron tulipifera</i> | 5 |
| 58 | <i>Liriodendron tulipifera</i> | 8 |
| 59 | <i>Liriodendron tulipifera</i> | 7 |
| 60 | <i>Liriodendron tulipifera</i> | 9 |
| 61 | <i>Maytenus boaria</i> | 5 |
| 62 | <i>Maytenus boaria</i> | 5 |
| 63 | <i>Maytenus boaria</i> | 7 |

Bolded trees are protected trees.

OWNER
 HENSEL PHELPS
 suda
 BUILDING T1
 FDP PACKAGE
 PROJECT
WEST OAKLAND BART
 1451 7th St, Oakland, CA 94607
 ARCHITECT
 jrdv ARCHITECTS
 PROJECT TEAM
 BKF ENGINEERS
 BKF100
 PGA DESIGN
 stok
 STAMP
 KEY
 PROJ #: 168-153 WO BART
 DATE: 06/04/20
 SCALE: 1"=60' - 0"
 TITLE:
**TREE
 REMOVAL
 PLAN**
 SHEET:
L1.00

OWNER
HEC
HENSEL PHELPS
suda
 BUILDING T1 FDP PACKAGE
 PROJECT
WEST OAKLAND BART
 1451 7th St, Oakland, CA 94607
 ARCHITECT
jrdrv
 PROJECT TEAM
BKF ENGINEERS
BAF100
PGA DESIGN
stok
 STAMP
 KEY
 PROJ #: 168-153 WO BART
 DATE: 03/26/20
 SCALE: 1"=60' - 0"
 TITLE: **LAYOUT & MATERIALS PLAN**
 SHEET: **L1.01**



THE PLAZA IS DESIGNED TO SUPPORT AND BALANCE THE NEEDS OF FUTURE USERS. THESE PATRONS WILL VARY FROM COMMUTERS TO THOSE COMING TO ATTEND LARGE EVENTS OR SIMPLY TO VISIT THE UNIQUE MARKETS. VARIOUS SIZED GATHERING SPACES ACCOMMODATE DIVERSE USES.


IRRIGATION METHOD & WATER EFFICIENT LANDSCAPE ORDINANCE

- IRRIGATION SYSTEM WILL BE DESIGNED TO PROVIDE THE MINIMUM AMOUNT OF WATER NECESSARY TO SUSTAIN GOOD PLANT HEALTH. ALL SELECTED COMPONENTS TO BE COMMERCIAL GRADE, SELECTED FOR DURABILITY, VANDAL RESISTANCE AND MINIMUM MAINTENANCE REQUIREMENT.
- THE SYSTEM WILL BE DRIPLINE IRRIGATION AS APPROPRIATE TO PLANT TYPE, EXPOSURE AND SLOPE CONDITIONS.
- CONTROL OF THE SYSTEM WILL BE VIA A WEATHER-ENABLED CONTROLLER CAPABLE OF DAILY SELF-ADJUSTMENT BASED ON REAL-TIME WEATHER CONDITIONS AS MEASURED BY AN ON-SITE WEATHER SENSOR.
- THE SYSTEM WILL INCLUDE A MASTER CONTROL VALVE AND FLOW SENSING CAPABILITY WHICH WILL SHUT DOWN ALL OR PART OF THE SYSTEM IF LEAKS ARE DETECTED.
- THE LANDSCAPE IS OVER 500 SQUARE FEET OF NEW LANDSCAPING AND WILL THEREFORE MEET THE REQUIREMENTS OF THE WATER EFFICIENCY LANDSCAPE ORDINANCE (WELO): [HTTPS://WATER.CA.GOV/LEGACYFILES/WATERUSEEFFICIENCY/LANDSCAPEORDINANCE/DOCS/TITLE%2023%20EXTRACT%20-%20OFFICIAL%20CCR%20PAGES.PDF](https://water.ca.gov/legacy/files/wateruseefficiency/landscapeordinance/docs/title%2023%20extract%20-%20official%20CCR%20PAGES.PDF)



WEST OAKLAND STATION CRIME PREVENTION THROUGH ENVIRONMENTAL DESIGN STRATEGIES



- AREA LIGHTING:**
- ALL LOADING, UNLOADING, KISS AND RIDE, DROP OFF, PICK UP AREAS WILL BE LIT TO 5 CANDLE FOOT. SIDEWALKS AROUND THE SITE WILL BE LIT TO 1.25 CANDLE FOOT (CITY STANDARD). BIKE LOCKER AREAS WILL BE LIT TO 10 CANDLE FOOT, AND EXTERIOR PATRON WAITING AREAS OUTSIDE THE BART FAIR GATES WILL BE LIT TO 10 CANDLE FOOT. SEE SHEET L1.07 FOR MORE DETAIL REGARDING THE LOCATION OF THESE AREAS.
 - POLE LIGHTS ARE KEPT 20' CLEAR OF TREES AND LANDSCAPING. LIGHT POLES ARE LESS THAN 22' HIGH. OTHER LIGHTS WILL BE MOUNTED ON BUILDING, ON BOLLARDS OR ALONG OVERHEAD WIRES (<20' HIGH).
 - THE LIGHTING WILL USE A FULL COLOR INDEX IN ORDER TO BETTER DISTINGUISH FORM AND MOVEMENT.
- AREA PLANTING:**
- PLANTINGS, INCLUDING THE RAISED PLANTERS AND BERMS THEY ARE IN, WILL NOT EXCEED 36" IN HEIGHT. TREES WILL BE LIMBED UP TO 7' HIGH. THE INTENTION IS TO AVOID BLIND SPOTS CAUSED BY HIGH PLANTS AND PLANTERS. TREES WILL BE THE TYPE THAT RETAIN A THIN TRUNK AS THEY GROW AND MATURE. THE TREE CANOPIES WILL NOT BE OVERLY DENSE AND WILL ALLOW LIGHT IN FROM ABOVE.

- AREA SITE FURNISHINGS:**
- SITE FURNISHINGS, EARTH FORMS, AND ARTWORK WILL BE DESIGNED NOT TO OBSCURE VISIBILITY. BENCHES HAVE SEPARATORS/ARMRESTS, SO THEY ARE USED FOR SITTING ONLY. PLANTER BOXES AND LANDSCAPE WALLS WILL HAVE GROOVES OR ELEMENTS TO DETER SKATEBOARDERS. FENCES ARE DESIGNED TO RESIST TEMPERING AND CLIMBING.
- AREA SIGNAGE:**
- DIRECTIONAL AND WAYFINDING SIGNAGE WILL BE PLACED AT APPROPRIATE LOCATIONS TO HELP DIRECT THE VISITOR TO THEIR DESTINATION.
- SURVEILLANCE CAMERAS:**
- A SERIES OF SURVEILLANCE CAMERAS WILL BE PLACED TO COVER THE ENTIRE SITE. THESE CAMERAS WILL COMPLY WITH BART FACILITY STANDARDS.



LEGEND

-  8' CLEAR ZONE FOR PEDESTRIAN
-  PROPERTY LINE



OWNER



BUILDING T1
FDP PACKAGE

PROJECT

WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT



PROJECT TEAM

BNF ENGINEERS
1548 N CALIFORNIA
BLVD, SUITE 400
WALNUT CREEK
CA 94598
(925) 940-2200

PGA DESIGN
444 17th Street
Oakland
CA 94612
(510) 465-1284

STOK
949B Front Street
San Francisco
CA 94111
(415) 329-7100



STAMP

KEY

PROJ #: 168-153 WO BART
DATE: 03/26/20
SCALE: 1"=60' - 0"

TITLE:
LANDSCAPE
WALL HEIGHT
PLAN

SHEET:
L1.02







1 SECTION 1
L1.03 1/16" = 1'-0"




2 SECTION 2
L1.03 1/16" = 1'-0"






1 SECTION 3
L1.04 1/16" = 1'-0"



2 SECTION 4
L1.04 1/16" = 1'-0"



PROJECT

MANDELA STATION @ WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT

jrdv ARCHITECTS
JRDV Architects, Inc.
The Cathedral
Building
Broadway and
Telegraph
PO Box 70126
Oakland, CA 94612
USA
510.295.4302 T
www.jrdv.com

PROJECT TEAM


ENR ENGINEERS
1548 N CALIFORNIA
BLVD, SUITE 400
WALNUT CREEK
CA 94598
(925) 940-2200

PGA DESIGN
444 17th Street
Oakland
CA 94612
(510) 465-1284

STOK
9455 Front Street
San Francisco
CA 94111
(415) 329-7100

STAMP

KEY




PROJ.#: 148-153 WO BART
DATE: July 24, 2020
SCALE: 1/16" = 1'-0"
TITLE:

SECTIONS

SHEET:

L1.04



LEGEND - LIGHTING PLAN

- AREA LIGHTS FOR PLAZA
- AREA LIGHTS WITH MULTIPLE HEADS FOR EVENT PLAZA
- STREET LIGHTS AS CITY REQUIRED



OWNER
 HEC
 HENSEL PHELPS
 suda
 BUILDING T1
 FDP PACKAGE
 PROJECT
WEST OAKLAND BART
 1451 7th St, Oakland, CA 94607
 ARCHITECT
 jrdv ARCHITECTS
 PROJECT TEAM
 BKF ENGINEERS
 BKF 100
 PGA DESIGN
 stök
 STAMP
 KEY
 PROJ #: 168-153 WO BART
 DATE: 03/26/20
 SCALE: 1"=60' - 0"
 TITLE:
LIGHTING PLAN
 SHEET:
L1.06



PLANTING LEGEND

- | | | |
|---|--|---|
| <p>PLANTING ZONE 1: MANDELA PLAZA ENTRY</p> <ul style="list-style-type: none"> CAREX DIVULSA NANDINA DOMESTICA ALBA 'LEMON-LIME' BERBERIS 'ORANGE ROCKET' IRIS DOUGLASIANA 'CANYON SNOW' MUHLENBERGIA DUBIA 'PINE MUHLY' PITTOSPORUM TOBIRA 'MOJO' PHORMIUM 'YELLOW WAVE' CORDYLINE 'DESIGN-A LINE' DIGIPLIXIS ILLUMINATION 'APRICOT' | <p>PLANTING ZONE 2: SHADE TOLERANT PLANTS BELOW BART TRACKS</p> <ul style="list-style-type: none"> MAHONIA 'SOFT CARESS' MUHLENBERGIA DUBIA 'PINE MUHLY' BLECHNUM SPICANT 'DEER FERN' HELLEBORUS ARGUTIFOLIUS WOODWARDIA FIMBRIATA 'GIANT CHAIN FERN' CORDYLINE 'DESIGN-A LINE' EUPHORBIA CHARACIAS SSP. PHORMIUM 'YELLOW WAVE' | <p>PLANTING ZONE 3: SOUTH FACING ALLEY</p> <ul style="list-style-type: none"> CAREX DIVULSA MUHLENBERGIA DUBIA 'PINE MUHLY' IRIS DOUGLASIANA 'CANYON SNOW' MONARDELLA VILLOSA 'RUSSIAN RIVER' SALVIA SPATHACEA 'HUMMINGBIRD SAGE' SALVIA 'DARA'S CHOICE' |
|---|--|---|

PLEASE SEE RELATED IMAGES ON THE NEXT PAGE

OWNER
HEC
 HENSEL PHELPS
 suda
 BUILDING T1
 FDP PACKAGE
 PROJECT

WEST OAKLAND BART
 1451 7th St, Oakland, CA 94607

ARCHITECT
jrdr
 ARCHITECTS


PROJECT TEAM
 CIVIL ENGINEERS
 TARA N. CALIFORNIA
 8115 EURE ASB
 PALM BEACH
 CA 94706
 (510) 464-2200
 PDA DESIGN
 444 13th Street
 DUBLIN
 CA 94568
 (916) 464-1364
 STON
 1449 First Street
 SAN FRANCISCO
 CA 94111
 (415) 391-1500

STAMP

KEY

PROJ.# 09-153 WO BART
 DATE 09/24/10
 SCALE 1"=60'-0"
 TITLE
PLANTING ZONE

SHEET **L1.07**



TREES

STREET TREES



ACER RUBRUM 'ARMSTRONG'



QUERCUS COCCINEA



AFROCARPUS FALCATUS



PISTACIA CHINENSIS

PLAZA TREES



POPULUS DELTOIDES



CHITALPA TASHKENTENSIS



ALBIZIA JULIBRISSIN

SHRUBS & GROUNDCOVER

PLANTING ZONE 1 : ON THE PLAZA



CAREX DIVULSA



PHORMIUM 'YELLOW WAVE'



BERBERIS 'ORANGE ROCKET' 4'H X 2'W



NANDINA DOMESTICA ALBA 'LEMON-LIME' 4'H X 3'W



CORDYLIN 'DESIGN-A LINE' 3'X3'



PITTIOSPORUM TOBIRA 'MOJO' 3'X3'



DIGIPLEXIS ILLUMINATION 'APRICOT' 2'H X 18"W



IRIS DOUGLASIANA 'CANYON SNOW'



MUHLENBERGIA DUBIA 'PINE MUHLY'

PLANTING ZONE 2 : UNDER THE TRUCK



MAHONIA 'SOFT CARESS' 4'X4'



PHORMIUM 'YELLOW WAVE'



CORDYLIN 'DESIGN-A LINE' 3'X3'



EUPHORBIA CHARACIAS SSP.



BLECHNUM SPICANT 'DEER FERN'



WOODWARDIA FIMBRIATA 'GIANT CHAIN FERN'



HELLEBORUS ARGUTIFOLIUS 3'X3'



MUHLENBERGIA DUBIA 'PINE MUHLY'

PLANTING ZONE 3 : IN THE ALLEY



MUHLENBERGIA DUBIA 'PINE MUHLY'



MONARDELLA VILLOSA 'RUSSIAN RIVER'



IRIS DOUGLASIANA 'CANYON SNOW'




SALVIA SPATHACEA 'HUMMINGBIRD SAGE'



SALVIA 'DARA'S CHOICE'



CAREX DIVULSA



PHORMIUM TONY TIGER 2.5'X2.5

OWNER
 HENSEL PHELPS

BUILDING T1 FDP PACKAGE PROJECT

WEST OAKLAND BART
 1451 7th St, Oakland, CA 94607

ARCHITECT
 jrdv ARCHITECTS

PROJECT TEAM
 BKF ENGINEERS
 1566 K CALIFORNIA BLVD, SUITE 400 WALKIT CREEK CA 94609 (925) 940-2200
 PGA DESIGN
 444 17th Street Oakland CA 94612 (510) 465-1284
 STOK
 945B Front Street San Francisco CA 94111 (415) 329-7100

STAMP


KEY

PROJ #: 168-153 WO BART
 DATE: 06/04/20
 SCALE:
 TITLE: LANDSCAPE PLANTS
 SHEET: L1.08

CAST-IN-PLACE CONCRETE PAVING



COLORED C.I.P w/ SAWCUT BANDING



COLORED C.I.P w/ SAWCUT BANDING



C.I.P w/ SAWCUT BANDING

NOTE: ALL PAVING SHALL BE ADA COMPLIANT AND MINIMIZE UNDULATING AFFECTS WHEN TRAVELING OVER SURFACE

PLANTER WALL



POUR-IN-PLACE CONCRETE WITH SACK FINISH

SITE FEATURES



SLOPED TURF



EVENT PLAZA

SITE FURNITURES



BENCH: MODEL: NEW STANDARD BENCH, MANUFACTURER: STREETLIFE, TEL: 215.247.0148, WEBSITE: <https://www.streetlife.nl/us>




BIKE RACK: MODEL: BOLA BIKE RACK, MANUFACTURER: LANDSCAPEFORMS, TEL: 800.430.6209, WEBSITE: <https://www.landscapeforms.com/en-US>



TRASH BIN: MODEL: CHASE PARK LITTER, MANUFACTURER: LANDSCAPEFORMS, WEBSITE: <https://www.landscapeforms.com/en-US>



PICNIC TABLE SET: MODEL: GRETCHEN PICNIC TABLE, ADA COMPLIANT STYLE, MANUFACTURER: LANDSCAPE FORMS, TELEPHONE: 800.430.6209, WEBSITE: WWW.LANDSCAPEFORMS.COM



DINING TABLE & CHAIR SET: 21 CHAIR WITH ARMS BY LANDSCAPE FORMS, 4 CHAIRS PER TABLE, CATENA TABLE, 48" DIAMETER, NO UMBRELLA HOLE, ADA COMPLIANT QUAD SUPPORT LEGS, ADJUSTABLE GLIDES. FINISH: LANDSCAPE FORMS PROPRIETARY PANGARD II® POLYESTER POWDERCOAT COLOR: TBD FROM MANUFACTURER'S STANDARD PALETTE MANUFACTURER: LANDSCAPE FORMS, TELEPHONE: 800.430.6209, WEBSITE: WWW.LANDSCAPEFORMS.COM



OWNER



BUILDING T1
FDP PACKAGE

PROJECT

WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT



PROJECT TEAM



STAMP

KEY

PROJ #: 168-153 WO BART

DATE: 06/04/20

SCALE:

TITLE:

LANDSCAPE MATERIALS

SHEET:

L1.09

STREET LIGHT

Domus Luminaire



Manufacturer(s): Lumec

Catalog #: DM550-HPS-SC3M-5MB-SCITX (Large Domus)
DOSHPS-SG3-5MB-SCITX-LMS (Small Domus)

Photometric File: 50105312.ies (Domus DM550, 200-250W)
50206072.ies (Domus DOS, 35-150W)

Application: Domus DM550 - Arterial and/or collector street lighting
Domus DOS - Residential street lighting and/or sidewalk side pedestrian lighting

Lamp Type: 35W, 100W, 150W, 250W HPS

Optical System: Type III

Ballast Voltage: Multi-tap 120/240V

Color: Teal Green only

Special Requirements:

Luminaire Cost: \$\$\$



As shown: Domus DOS luminaire w/ 3' arm on 16' octagonal pole.

Color: Teal Green

Location: Coliseum Gardens



Page 19 of 71

PEDESTRIAN LIGHTING



PLAZA LIGHTS



landscape lighting

landscape lighting


PEDESTRIAN ACCENT LIGHT



OVERHEAD CABLE LIGHTS

Lumera LED Ceiling

selux



See Page 11

Specifications

Luminaire Housing/Hanger

LED Driver

LED Array

LED Optics

5 Year Limited LED Luminaire Warranty

Settings and Ratings

Luminaire suitable for ambient temperatures from 40°F (5MP) maximum to 40°F (-40°F) minimum.

WARRANTY (See UL, CSA)

Visit us on our LED End of Life recycling policy.

5 Year Limited LED Luminaire Warranty

Settings and Ratings

Luminaire suitable for ambient temperatures from 40°F (5MP) maximum to 40°F (-40°F) minimum.

WARRANTY (See UL, CSA)

Visit us on our LED End of Life recycling policy.

5 Year Limited LED Luminaire Warranty

Settings and Ratings

Luminaire suitable for ambient temperatures from 40°F (5MP) maximum to 40°F (-40°F) minimum.

WARRANTY (See UL, CSA)

Visit us on our LED End of Life recycling policy.

ALCOTT AREA LIGHT



General Description

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

The Alcott Area Light is a contemporary interpretation of a traditional lantern.

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

ALCOTT AREA LIGHT



Finish

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5



To Order

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

Alcott Type 3

Alcott Type 5

UNDERTRACK LIGHTING

UZA-20001

Zaab 2 Single Side Cluster Column



Adjustable surface spotlight family.

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001

UZA-20001


UZA-20001

UZA-20001

UZA-20001

UZA-20001

LIGMAN LIGHTING USA



Adjustable surface spotlight family.

Ligman Lighting USA

Ligman Lighting USA

Ligman Lighting USA

Ligman Lighting USA

Ligman Lighting USA

Ligman Lighting USA

Ligman Lighting USA

Ligman Lighting USA

Ligman Lighting USA

Ligman Lighting USA



1 - Mandela Plaza Center Street Entrance




2 - Artwalk from Center Street




3 - Undertrack Plaza from Artwalk




4 - Mandela Plaza Chester Street Entrance and Blues Walk of Fame





MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607



JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com

LANDSCAPE ARCHITECTS


PROJ. # 168-153 WO BART
 DATE: July 24, 2020

SITE PLAN

SHEET:

A-9.00

The recycling space on T1 site is 1,150 cubic feet minimum, on T3 site is 510 cubic feet minimum, and on T4 site is 647 cubic feet minimum. The total recycling space on site is 2,307 cubic feet minimum.



Public Space Design

Public Space Improvements:


The public spaces for the Mandela Station site are designed to reinforce the vibrant mixed-use development that furthers Oakland's efforts to promote urban living at key transit sites, and provides an active and delightful center for the West Oakland community.

The site is designed with a series of important civic open spaces, including:

- Mandela Plaza, a major community civic plaza at 7th Street fronting BART Station entrance. This plaza is designed with varied paving and green spaces. It is designed with a delightful series of sculptural seating areas arranged to promote community interaction – a "Living Room" for the residents and surrounding neighborhood.
- Center Square, a pedestrian plaza replacing the vacated Center Street. This plaza is focused on providing food related tenants along T3 and T4, and will be designed with fixed and permanent seating to become a destination food hub for the neighborhood, BART patrons and the on-site residents.

- Art Alley, a pedestrian paseo that activates the area south of the BART tracks. This area is lined with small gallery spaces and will have a expansive "art wall" along the north façade of T3 framing the alley space.

- Undertrack Area, a flexible event space that will provide a venue for the programs that activate Mandela Plaza and Art Alley. The under track will feature movable food kiosks, pop-up events, farmers markets, art fairs, live music and other programmed events that will help make Mandela Station a destination location.




Hardscape and Green-scape Design: Landscape plan is designed to enhance the pedestrian public spaces, and to create a high quality of pedestrian experience and civic prominence. The existing trees will be replaced because of conflicts with the access plan. The new tree planting complements the overall landscape strategy of the 7th and 5th Street corridors to ensure a continuous, interesting and varied visual experience.

Landscape Materials: The landscape materials are designed with pavers or stamped concrete and other decorative materials to create a high quality public pedestrian experience and to maximize the types of uses that can occur on site. The landscape is designed to become a catalyst to a larger vision for the 7th Street corridor. The new tree planting complements the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience.

Site Lighting: The Lighting plan is designed to create well lighted plazas and pedestrian pathways through the site. The visual security of all pedestrian spaces within the site is facilitated by locating retail and other public activities along all edges of the development. The landscape plan provides adequate lighting to provide a safe environment while conforming to current best practices to mitigate light pollution.



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



JRDV URBAN INTERNATIONAL
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: July 24, 2020


**PUBLIC SPACE
IMPROVEMENT:
PUBLIC SPACE
DESIGN**

SHEET: **A-9.01**

Mandela Plaza



MANDELA STATION
@WEST OAKLAND
BART
1451 7th St, Oakland,
CA 94607



JRDV URBAN INTERNATIONAL
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com

BKF 100 YEARS
ENGINEERS · SURVEYORS · PLANNERS
stök
PGAdesign
LANDSCAPE ARCHITECTS



PROJ. # 168-153 WO BART
DATE: July 24, 2020

PUBLIC SPACE IMPROVEMENT: MANDELA PLAZA

SHEET:

A-9.02

Note: Undertrack painting is optional pending BART's approval.



PUBLIC SPACE
IMPROVEMENT:
MANDELA PLAZA

Mandela Plaza Features

- 1 **SCULPTED BERMS** - Artificial turf berms to promote informal seating and interactive play options for a wide range of age groups.
- 2 **OUTDOOR 'LIVING ROOMS'** - Nodes framed with integral bench seating for small gatherings.
- 3 **BLUES WALK OF FAME** - Relocated plaques cast into 7th Street sidewalk paving north of Mandela Plaza and the T1 building.
- 4 **BENCH PLANTERS** - Concrete planters with consistent, bench-height edge to provide fixed seating option for plaza events.
- 5 **MAZE STRIPING** - Maze for public interaction. This open space is flexible for performances and other event activities.
- 6 **ADDITIONAL OPEN SPACE** - Framed open space for food trucks, outdoor dining, and other temporary programming.

Public Space Programming and Activation

The Developer will provide regular programming in the public plazas of the proposed Mandela Station at West Oakland BART Station as required in the Conditions of Approval (COA #66) approved on February 6, 2019 by the City of Oakland Planning Commission. The purpose of the programming is to provide future BART riders, project-site residents, shoppers and workers, and the larger community of West Oakland with excellent opportunities to relax and enjoy as well as providing local businesses and non-profits to financially support themselves and promote their services and products.

Programmed events may include:

1. Concert events will be held on a monthly schedule in co-operation with the Developer and local non-profit Zoo Labs among others. Zoo Labs empowers music artists as leaders and directs resources toward their ventures.
2. Farmers Market events will be held monthly in collaboration with the Mandela Grocery Cooperative, a worker-owned grocery store that provides nourishing foods and enhanced opportunities for food vendors, including the Freedom Farmers Market weekly from July to November.
3. Local vendor Pop-Ups events will be held monthly and co-sponsored by PopUp Village. Popupvillage.org features opportunities including:
 - Arts and Culture classes and exhibits
 - Food & Agriculture
 - Health & wellness
 - Youth Activities
 - Highlights local retail vendors
 - Performers of music, dance, spoken word
 - Education
 - These are a few of the collaborator of existing programs on 7th Street that as developers we intend to support and expand in collaboration with these organizations.

All program schedules and events will be advertised widely using: BART Station Public Information System, the networks of organizations that participated in the West Oakland Advisory Committee process and the local media outlets.



Community Art Fair



Local Farmers Market



Undertrack Program Events



Food Truck Events



Undertrack Program Events




Undertrack Program Events




Food Truck Events




Sunday Music Show



Public Open Space Map



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



**JRDV URBAN
INTERNATIONAL**
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

EVENT SPACE PROGRAM

SHEET:

A-9.04

Under Track Strategy

The Under-Track area is designed to integrate with both Mandela Plaza on 7th Street and Art Alley to the south. These combination of these spaces are planned to be programmed and perceived both separately and as linked spaces.

Programmed Activation. Under-Track area is designed as a flexible and activated space that will support food kiosks, exhibits and a wide range of staged events. The physical space of the Under-Track area serves these programmed activities by creating a defined space with high “ceiling” and significant scale, that is visually connected to the surrounding Public Spaces. The space also functions as an interesting urban plaza when no events are staged. It becomes an delightful and safe passage through the site.

Landscape Paving. The paving patterns are designed to define the space and encourage pedestrians to flow through the space. The variety of paving materials is designed to reduce the scale of the space, by implying nodes and clusters that can contain smaller groups or events. The paving pattern and variety of materials will also create a visually interesting plaza surface that does not require any activation or events.

Seating. Seating is provided with a combination of fixed-seating that is integrated into the planters. And, movable café-seating and tables to be placed and managed by specific events. The goal is to promote this space as both safe pedestrian passage through the site, and as a place to rest or participate in a planned event. The number of movable seats will be managed by the client and will respond to the actual demand.

Lighting. The lighting of the Under-Track area is designed to provide a high level of ambient light and “decorative” feature lighting. The ambient light is provided by a double row of 10’high light standards with a fixture that provide directional up-lighting and ground-lighting. Feature lighting will be provided with either fixtures attached to the BART structure, or fixtures attached to the light standards. This lighting will provide changeable artistically colored lighting that creates a powerful night presence that extends to the plaza and 7th Street. Lighting levels are designed to ensure visual safety for this space at all times.

Decorative Surface Painting. The columns of the BART structure may be painted with a surface graphic that is colorful and visually animates the space. This painted surface will create a delightful backdrop that will enhance the space for events and for the enjoyment of the public.

Note: Undertrack painting is optional pending BART’s approval.



1 - From BART Station North Entrance




2 - From Art Walk




3 - From Mandela Plaza




4 - From Under Track Plaza



Partial Site Plan



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



**JRDV URBAN
INTERNATIONAL**
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

**UNDER TRACK
SPACE**

SHEET:

A-9.05

Under-Track Activation



Farmers Markets



Food Trucks and Mobile Enterprise



Music and Staged Events



Off The Grid Events



Night Markets




Art Fairs and Pop-up Events



MANDELA STATION
@WEST OAKLAND
BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

UNDER TRACK
SPACE

SHEET:

A-9.07

Mandela Plaza - Community Civic Space:

This urban plaza creates a major community civic plaza at 7th Street fronting BART Station entrance. It is designed with a delightful series of sculptural seating and green-berm areas arranged to promote community use – a “Living Room” for the residents and surrounding neighborhood. The plaza provides access to the BART station, and also celebrates the civic importance of this site in the community. This plaza is located centrally to the overall site in order to increase its public importance, public access, and public use for community, arts and cultural events. This central plaza is designed to enhance the 7th Street corridor activation and overall public experience.

This plaza is designed with varied paving and green spaces. The Landscape plan is designed to complement the importance and use of the space by the neighborhood and residents on site. The arced cluster seating and green berms along 7th Street create a welcoming pedestrian and community experience.

The new tree planting complements the overall landscape strategy of the 7th Street corridor to ensure a continuous, interesting and varied visual experience. Paving materials are quality pavers or stamped colored concrete and are aesthetically designed to differentiate unique spaces within the pedestrian plazas, promote visual access to the BART station entrance, and to create opportunities for cultural, community and arts events. The landscape plan is designed to create a delightful destination for the West Oakland community and users of the transit hub.



VIEW FROM 7TH STREET




VIEW FROM 7TH STREET



MANDELA STATION @WEST OAKLAND BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

MANDELA PLAZA

SHEET:

A-9.08




VIEW OF BART ENTRANCE AT 7TH STREET



VIEW FROM CHESTER STREET

MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com







PROJ. # 168-153 WO BART
 DATE: July 24, 2020

MANDELA PLAZA

SHEET:

A-9.09



VIEW FROM 7TH STREET




VIEW FROM 7TH STREET



VIEW OF 7TH STREET SIDEWALK AND LANDSCAPED BERM

MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com







PROJ. # 168-153 WO BART
 DATE: July 24, 2020

MANDELA PLAZA

SHEET:

A-9.10



VIEW FROM 7TH STREET




VIEW OF MANDELA PLAZA



**MANDELA STATION
@WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

MANDELA PLAZA

SHEET:

A-9.11

Art Alley




Art Walk Events




Art Walk Activated Edges



Places for Music and Poetry Events



MANDELA STATION
@WEST OAKLAND
BART
1451 7th St, Oakland,
CA 94607




JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: July 24, 2020

PUBLIC SPACE
IMPROVEMENT:
ART ALLEY

SHEET: A-9.12



MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com







 LANDSCAPE ARCHITECTS

PROJ. # 168-153 WO BART
 DATE: July 24, 2020

ART ALLEY

SHEET:
A-9.14

Center Square

Center Square: The vacated Center Street has been transformed into an active urban destination for the neighborhood. This space is both an important pedestrian connection to the BART station and a significant public plaza for the surrounding community. It is lined with a wide variety of local food offerings that showcase the cultural and ethnic diversity of West Oakland. The space creates an inviting place for the neighborhood to shop, dine, and relish a quality community experience.

The landscape materials are designed with high quality paver, brick, finished concrete and other materials to create a high quality public pedestrian experience and to maximize the types of uses that can occur on site.



Site Lighting: The Lighting plan has been designed to create a well lit space that connects BART to 5th Street. The visual security of pedestrians within this space is facilitated by locating retail and other public activities along all edges of the development. The landscape plan is designed with adequate lighting to provide a safe environment while conforming to current best practices to mitigate light pollution.



Evening Food Festivals



Neighborhood Food Destination






BIRDSEYE OF CENTER SQUARE



**MANDELA STATION
@WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020


**CENTER
SQUARE**

SHEET: **A-9.16**



**MANDELA STATION
@WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607



VIEW OF CENTER SQUARE



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

**CENTER
SQUARE**

SHEET: **A-9.17**




VIEW FROM 5TH STREET



VIEW OF CENTER SQUARE

MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com







 LANDSCAPE ARCHITECTS

PROJ. # 168-153 WO BART
 DATE: July 24, 2020

SHEET: **CENTER SQUARE**
A-9.18




VIEW OF EXTERIOR STAIR



VIEW OF ART ALLEY FROM CENTER SQUARE

MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607




 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com




 LANDSCAPE ARCHITECTS

PROJ. # 168-153 WO BART
 DATE: July 24, 2020

SHEET: **CENTER SQUARE**
A-9.19

Crosswalks & Intersections

5th Street/Center Street and 5th Street/Chester Street Intersection: High-visibility crosswalks will be installed along with directional, ADA compliant curb ramps.


Chester Street/7th Street Intersection: To facilitate safe pedestrian, bicycle and vehicle movements, the curbs and crosswalks have been engineered to separate pedestrian and bicycle movements with clear non-conflicting pathways.

Bulb-outs have been provided where possible, including the NW, NE, and SW corners. Bus turning requirements prevent this on the SE corner.

Mandela Parkway/7th Street Intersection: This is a significant bike and pedestrian access point. To facilitate safe pedestrian, bicycle and vehicle movements, the curbs and crosswalks have been engineered to clearly separate pedestrian and bicycle movements with clear non-conflicting pathways. A dedicated bicycle signal phase will be evaluated for further consideration.

Mandela Parkway/5th Street Intersection: The NE, SE and SW crosswalks at this intersection have been bulbed out to minimize pedestrian crossing distances and ADA-compliant, directional curb ramps will be installed. Crosswalks will be reconfigured to create more directional connectivity.

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.




Mid-Block Crossing on Mandela: A high-visibility, mid-block pedestrian crossing will be added on Mandela Parkway between 7th and 5th Streets. The crossing design is raised and coordinated with the design of the two-way cycle track to facilitate safe pedestrian crossing of both the roadway and the cycle track.

7th Street/Center Street Intersection: The intersection crossing will be designed with a scramble pedestrian crossing to facilitate access. Bike and pedestrian access will be designed to prevent conflicts and promote ease of use. A protected intersection design will be provided with separated pedestrian crossing and bikeway crossing.



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



**JRDV URBAN
INTERNATIONAL**
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020


PUBLIC SPACE IMPROVEMENT: CROSSWALKS & INTERSECTIONS

SHEET:

A-10.04

7TH STREET

8' SIDEWALK
 6' CYCLE TRACK
 +(2) 1' DET. BARRIERS
 4' SIDEWALK
 10' BUS LOADING
 11.5' WESTBOUND
 11' EASTBOUND
 11.5' EASTBOUND
 10' PASSENGER LOADING
 8.5' SEPARATION
 6' CYCLE TRACK
 +(2) 1' DET. BARRIERS
 8' SIDEWALK
 PLAZA



RAMP NOTES:


1. BICYCLE AND PEDESTRIAN RAMPS SHALL BE SEPERATED.
2. DETECTABLE WARNING DOMES SHALL BE INSTALLED AT ALL RAMPS, SEE SHEET C5.03.

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.



MANDELA STATION
 @WEST OAKLAND
 BART

1451 7th St, Oakland,
 CA 94607



JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com





PROJ. # 168-153 WO BART
 DATE: July 24, 2020

CROSSWALKS &
 INTERSECTIONS

SHEET:

A-10.04.01



RAMP NOTES:

1. BICYCLE AND PEDESTRIAN RAMPS SHALL BE SEPERATED.
2. DETECTABLE WARNING DOMES SHALL BE INSTALLED AT ALL RAMPS, SEE SHEET C5.03.

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.



 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com









PROJ. # 168-153 WO BART
 DATE: July 24, 2020

CROSSWALKS &
INTERSECTIONS

SHEET:

A-10.04.02



MODIFY SIGNAL TIMING FOR
 WESTBOUND BUS-ONLY PHASE.
 REDUCE CYCLE TIME TO 90
 SECONDS.

MANDELA PARKWAY

- 8' MIN. TO BUILDING
- 6' CYCLE TRACK
- +(2) 1' DET. BARRIERS
- 3.5' SIDEWALK
- 11.5' SOUTHBOUND
- 11.5' NORTHBOUND
- 2.5' BUFFER ZONE
- 6' BIKE LANE
- 10' SIDEWALK LANE

RAMP NOTES:

1. BICYCLE AND PEDESTRIAN RAMPS SHALL BE SEPERATED.
2. DETECTABLE WARNING DOMES SHALL BE INSTALLED AT ALL RAMPS, SEE SHEET C5.03.





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com







 LANDSCAPE ARCHITECTS

PROJ. # 168-153 WO BART
 DATE: July 24, 2020


CROSSWALKS & INTERSECTIONS

SHEET:


A-10.04.03

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.

**DETECTABLE WARNING
DOMES BOTH SIDES**



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



RAMP NOTES:

1. BICYCLE AND PEDESTRIAN RAMPS SHALL BE SEPERATED.
2. DETECTABLE WARNING DOMES SHALL BE INSTALLED AT ALL RAMPS, SEE SHEET C5.03.



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www. jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020


**CROSSWALKS &
INTERSECTIONS**

SHEET:

A-10.04.04

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.
*The Hall of Fame Plaques will be removed from the right of way to be relocated back into the 7th Street right of way at an appropriate realigned location by the completion of T1.
*The dancing lights will be removed from the right of way and there is no plan for their relocation as part of the FDP at this time.

MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com








 LANDSCAPE ARCHITECTS

PROJ. # 168-153 WO BART
 DATE: July 24, 2020

CROSSWALKS & INTERSECTIONS

SHEET:

A-10.04.05




- 5TH STREET**
- 10' SIDEWALK
 - 9' BUS LOADING
 - 11.5' WESTBOUND
 - 11.5' WESTBOUND
 - 11.5' EASTBOUND
 - 9' ON-STREET PARKING
 - 6' MIN SIDEWALK
 - 12' TO PROPERTY LINE




- RAMP NOTES:**
1. BICYCLE AND PEDESTRIAN RAMPS SHALL BE SEPERATED.
 2. DETECTABLE WARNING DOMES SHALL BE INSTALLED AT ALL RAMPS, SEE SHEET C5.03.

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.



MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607





 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com







PROJ. # 168-153 WO BART
 DATE: July 24, 2020

CROSSWALKS & INTERSECTIONS

SHEET:

A-10.04.06



RAMP NOTES:

1. BICYCLE AND PEDESTRIAN RAMPS SHALL BE SEPERATED.
2. DETECTABLE WARNING DOMES SHALL BE INSTALLED AT ALL RAMPS, SEE SHEET C5.03.

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.

CHESTER STREET


14' SIDEWALK

9' ON-STREET PARKING

12.5' SOUTHBOUND

14.5' NORTHBOUND

10' SIDEWALK



CONVERT INTERSECTION TO
ALL-WAY STOP CONTROL;
INSTALL CALTRANS R1-1 SIGNS



RAMP NOTES:


1. BICYCLE AND PEDESTRIAN RAMPS SHALL BE SEPERATED.
2. DETECTABLE WARNING DOMES SHALL BE INSTALLED AT ALL RAMPS, SEE SHEET C5.03.

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.



MANDELA STATION
@WEST OAKLAND
BART

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

CROSSWALKS &
INTERSECTIONS

SHEET:

A-10.04.07

Sidewalks

7th Street (between Mandela Parkway and Chester Street):
The sidewalk widths are range from 10'-15', and are designed to allow adequate clearances in order to accommodate the needs of pedestrians, bus passengers, and curbside passenger loading. The sidewalk is clear space for passanger loading at the curb, and a protected class 4 cycle track with clearly marked pedestrian crossing indicators.


Street lighting and street trees are located to reinforce the visual experience of the sidewalk space.

5th Street (between Mandela Parkway and Center Street):
The sidewalk width will be 10-15 feet min. wide in order to accommodate the needs of pedestrians, bus passengers, and curbside passenger loading.

5th Street (between Center and Chester Street):
Between 5th and 7th Streets, sidewalks adjacent to the project site are a minimum of 10 feet wide, and provide 8' clear path. The sidewalk is buffered from adjacent loading and street traffic by street pedestrian-scale lighting and street trees.

Chester Street Section
3/L1.05

7th Street Section
2/L1.05




Mandela Parkway Section
4/L1.05

5th Street Section
5/L1.05

Parking and Truck Loading Entrances: for the project are designed to provide clear sight lines, and include ADA features such as tactile warning strips, and audible warnings for when vehicles cross the pedestrian path of travel.



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



**JRDV URBAN
INTERNATIONAL**
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

**PUBLIC SPACE
IMPROVEMENT:
SIDEWALKS**

SHEET:
A-10.05

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.
*The developer will coordinate with the City of Oakland and the appropriate property owners, and document in the CMP prior to building permit, to determine the feasibility of and if deemed feasible, complete the sidewalk gap on the south side of 5th Street just east of Center Street.

Bikeways & Bike Parkings

Mandela Cycle Tracks:

To facilitate bicycle access from the bicycle lanes on Mandela Parkway south of 7th Street and north of 5th Street, two raised, one-way cycle tracks are located along the west and east sides of Mandela Parkway between 7th and 5th Streets.

These one-way cycle tracks are 6 feet wide, with an 8' and 10' separation from face of curb to the edge of the cycle track. In addition to the cycle track, sidewalks with a minimum width of 8' clear are provided.

7th St Cycle Tracks Eastbound:

To facilitate bicycle access in conjunction with passenger loading from vehicles and buses along eastbound 7th Street between Chester Street and Mandela Parkway, a raised, one-way cycle track is provided.

The cycle track travel surface is 6 feet, with an 8'-10' foot setback from sidewalk to the face of curb.

7th St Cycle Tracks Westbound:

On westbound 7th Street between Mandela Parkway and Chester Street, a raised, one-way cycle track is located with a width of 6 feet.


The cycle track is provided an 8' setback sidewalk from the face of curb to the edge of the cycle track to provide adequate space for pedestrian loading.

Ford Go-bike: has been co-relocated with the Bike Station, to provide ease of access, prevent plaza use conflicts and to reinforce the bike station as a central hub for bike users.

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.

*Accommodating a pedestrian walkway and in-lane bicycle facility on 7th Street and Mandela Pkwy during the construction period of T1 may be accommodated, but it may require changes to the street lanes during construction which need to be studied by the developer and DOT and documented in the Construction Management Plan.

* The phasing of the bike station will be determined based on funding and construction phasing of the surrounding parcels; and will be documented within the Construction Management Plans. The phasing will likely follow completion of T1 and/or the completion of the adjacent EVA access routes; but, will be based on availability of grants and/or other funding.



Install high-visibility crosswalks, directional curb ramps & pedestrian refuges on 5th St

Install 2 one-way cycle tracks on Mandela between 7th & 5th on grade with sidewalk

Install high-visibility mid-block crosswalk

Install dedicated bicycle signal phase

Bike Station:

The project will include an enhanced bicycle station located on the east side of the station structure. The bike station will be programmed, designed with BART and the project sponsor; and permitted by BART. The city will be responsible for design review.

Additional bicycle parking for BART and commercial patrons is provided throughout the site in the form of bicycle racks. Bicycle parking for the TOD's commercial and residential tenants will also be provided in accordance with City of Oakland requirements.

Bike Parking Account:


ON SITE SHORT TERM PARKING: 82

BIKE STATION: The bike station will be programmed, designed with BART and the project sponsor; and permitted by BART. The city will be responsible for design review.

GO BIKE PARKING NUMBER: 21



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



**JRDV URBAN
INTERNATIONAL**
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510.295.4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

**PUBLIC SPACE
IMPROVEMENT:
BIKES**

SHEET:

A-10.06

Passenger Loading

7th Street Passenger Loading:

Will be located on the south side of 7th Street west of Center Street. A portion (50 linear feet) of this loading area closest to the intersection with Center Street is designated as a loading space for passengers with disabilities. This area provides the most direct access to the station entrance.


Another 200 feet of linear curb is on north side of 7th Street between Center Street and Mandela Parkway for passenger loading and unloading and 100 feet of linear curb near the Chester Street intersection.

5th Street Passenger Loading:


130 feet of linear curb is proposed along westbound 5th Street on the west side of the intersection with Center Street.

Wayfinding:

Signage directing vehicles to loading zones will be provided at key decision points like the Mandela Parkway and 7th Street intersection and the 5th Street and Kirkham or Union Street intersections. Loading zone locations will be incorporated into smartphone mapping and TNC apps to facilitate safe and efficient circulation and access.



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



**JRDV URBAN
INTERNATIONAL**
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com



PROJ. # 168-153 WO BART
DATE: July 24, 2020

**PUBLIC SPACE
IMPROVEMENT:
PASSENGER
LOADING**

SHEET:

A-10.07

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.

Bus Stops

Install bus stop for intercity coaches (Bolt, Megabus) - optional location east of Mandela

Install bus stop for line 29 and Emery-Go-Round

Start sidewalk taper immediately after crosswalk to better accommodate bus access

7th Street Eastbound:


The existing bus stop on eastbound 7th Street will be retained and extended to the intersection with Center Street for an approximate total length of 260 linear feet. This stop would serve AC Transit Lines 29, 36, and 62 and will serve as both a stop and layover space for AC Transit Line 14. If Emery-Go-Round service is extended to the West Oakland Station, this stop could serve Emery-Go-Round vehicles as well.

7th Street Westbound: A new bus stop will be installed on westbound 7th Street to serve AC Transit Line 29 and Emery-Go-Round, if the service is extended to the West Oakland Station. 90 feet of linear curb is provided at this location to accommodate transit vehicles, as well as a concrete bus pad in the roadway.

5th Street Westbound: The bus stop and layover for lines 36 and 62 will be relocated to westbound 5th Street on the far side of the intersection with Mandela Parkway. 235 feet of curb length is provided to accommodate the bus stop and layovers, and a concrete bus pad will be installed in the roadway.

*The off-site phasing will be determined based on the Construction Management Plans. The off-site phasing will be complete prior to the Certificate of Occupancy of T1.

*The developer will work with the City to designate a bus stop for intercity coaches (e.g., Megabus and Bolt) and other shuttles on 7th Street between Henry and Chester Streets.



Potential layover space for lines 36 & 62, requires further evaluation

Redesign Chester St cross-section to facilitate buses turning right

Install median barrier to prevent jaywalking to/from bus stop


Bus stop and layover for lines 62 & 36

Intercity & Private Bus Stops: A bus stop for intercity coaches (e.g., Megabus and Bolt) could be installed on 7th Street between Henry and Chester Streets. Private employer shuttle could also utilize this stop. The existing BART surface parking immediately adjacent to this curb could be utilized for bus and shuttle transit passenger pick-up and drop-off (if not utilized as a layover space for AC Transit buses). A option to locate this bus stop east of Mandela Parkway is under consideration.

Passenger Amenities: All bus stops are provide with a high level of passenger amenities, including shelters with seating, maps and other information, and real-time bus arrival information; trash receptacles; and lighting.



**MANDELA STATION
@WEST OAKLAND
BART**
1451 7th St, Oakland,
CA 94607



**JRDV URBAN
INTERNATIONAL**
JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: July 24, 2020


**PUBLIC SPACE
IMPROVEMENT:
BUS STOPS**

SHEET:

A-10.08



MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607



JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com


LANDSCAPE ARCHITECTS

PROJ. # 168-153 WO BART
 DATE: July 24, 2020


EMERGENCY
VEHICLE
ACCESS

SHEET:

The recycling space on T1 site is 1,150 cubic feet minimum, on T3 site is 510 cubic feet minimum, and on T4 site is 647 cubic feet minimum. The total recycling space on site is 2,307 cubic feet minimum.



INCIDENT COMMAND CENTER LOCATION OPTIONS




Note:
Options 2&3 are preferred locations by BART and Oakland Fire.


The final location for the ICC will be mutually determined by the City, BART, and developer.



Final Development Plan
Mandela Station @ West Oakland BART:
1451 7th St, Oakland, CA 94607
July 24, 2020



**MANDELA STATION
 @WEST OAKLAND
 BART**
 1451 7th St, Oakland,
 CA 94607




**JRDV URBAN
 INTERNATIONAL**
 JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com

**BKF 100
 YEARS**
 ENGINEERS · SURVEYORS · PLANNERS
stök
PGAdesign
 LANDSCAPE ARCHITECTS

PROJ. # 168-153 WO BART
 DATE: July 24, 2020

SIGN PLAN

SHEET:



- COMMERCIAL BLADE SIGN
- GARAGE ENTRANCE SIGN
- ART DISTRICT SIGN
- COMMUNITY BLADE SIGN



ART DISTRICT SIGN



COMMERCIAL BLADE SIGN




COMMERCIAL BLADE SIGN




T1 NORTH / 7TH STREET ELEVATION - PODIUM




4-6TH FLOOR




GROUND-3RD FLOOR




WINDOW SYSTEM



WINDOW SYSTEM FOR GARAGE



STOREFRONT SYSTEM



T1 NORTH / 7TH STREET ELEVATION - TOWER

7-31ST FLOOR



ROOF



CHANNEL METAL
MECHANICAL SCREEN


7-31ST FLOOR




ALUMINUM
MULLION



PRECAST
CONCRETE
WALL PANEL



PRECAST CONCRETE WALL
PANEL



PRECAST
CONCRETE
WALL PANEL



PRECAST
CONCRETE WALL
PANEL



PRECAST CONCRETE WALL
PANEL



PRECAST
CONCRETE
WALL PANEL



HIGH PER-
FORMANCE
INSULATED
GLAZING

WINDOW SYSTEM




ALUMINUM
MULLION



HIGH PERFORMANCE INSULATED
GLAZING

Final Development Plan

Mandela Station @ West Oakland BART:
1451 7th St, Oakland, CA 94607
July 24, 2020







MATERIAL BOARD





T3 SOUTH / 5TH STREET ELEVATION



7TH FLOOR




2-6TH FLOOR




GROUND FLOOR




WINDOW SYSTEM



BALCONY




STOREFRONT SYSTEM




BASE




T3 EAST / CENTER SQUARE ELEVATION



7TH FLOOR




2-6TH FLOOR




GROUND FLOOR




WINDOW SYSTEM



BALCONY



STOREFRONT SYSTEM




BASE






7TH FLOOR




2-6TH FLOOR




GROUND FLOOR



WINDOW SYSTEM



STOREFRONT SYSTEM








BASE






T3 WEST / CHESTER STREET ELEVATION



7TH FLOOR




2-6TH FLOOR




GROUND FLOOR



WINDOW SYSTEM



BALCONY




STOREFRONT SYSTEM




BASE





**MANDELA STATION
@WEST OAKLAND
BART**

1451 7th St, Oakland,
CA 94607



JRDV Architects, Inc
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612 USA
510 295 4392 T
www.jrdv.com




PROJ. # 168-153 WO BART
DATE: July 24, 2020


**MASSING
DIAGRAM**

SHEET:





MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607



JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com

ENGINEERS · SURVEYORS · PLANNERS

PGAdesign

LANDSCAPE ARCHITECTS


PROJ. # 168-153 WO BART
 DATE: July 24, 2020


SITE PLAN

SHEET:


The recycling space on T1 site is 1,150 cubic feet minimum, on T3 site is 510 cubic feet minimum, and on T4 site is 647 cubic feet minimum. The total recycling space on site is 2,307 cubic feet minimum.

*The Hall of Fame Plaques will be removed from the right of way to be relocated back into the 7th Street right of way at an appropriate realigned location by the completion of T1.
 *The dancing lights will be removed from the right of way and there is no plan for their relocation as part of the FDP at this time.





MANDELA STATION
@WEST OAKLAND
BART
 1451 7th St, Oakland,
 CA 94607



JRDV Architects, Inc
 The Cathedral Building
 Broadway and Telegraph
 PO Box 70126
 Oakland, CA 94612 USA
 510 295 4392 T
 www.jrdv.com

ENGINEERS · SURVEYORS · PLANNERS


PGAdesign
 LANDSCAPE ARCHITECTS


PROJ. # 168-153 WO BART
 DATE: July 24, 2020

SITE PLAN

SHEET:


1. The recycling space on T1 site is 1,150 cubic feet minimum, on T3 site is 510 cubic feet minimum, and on T4 site is 647 cubic feet minimum. The total recycling space on site is 2,307 cubic feet minimum.







1. The recycling space on T1 site is 1,150 cubic feet minimum, on T3 site is 510 cubic feet minimum, and on T4 site is 647 cubic feet minimum. The total recycling space on site is 2,307 cubic feet minimum.







PDP PACKAGE

PROJECT

MANDELA STATION @ WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT

jrdv ARCHITECTS
JRDV Architects, Inc.
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612
USA
510.266.4393 T
www.jrdv.com

PROJECT TEAM



INF ENGINEERS
1646 N CALIFORNIA
BLVD, SUITE 400
WALNUT CREEK
CA 94596
(925) 945-2200

PGA DESIGN
444 17th Street
Oakland
CA 94612
(510) 455-1284

STOK
845B Front Street
San Francisco
CA 94111
(415) 329-7100

STAMP


KEY



PROJ #: 168-153 WO BART
DATE: July 22, 20
SCALE: 1/32"=1'-0"
TITLE:

4TH
FLOOR
PLAN

SHEET: **A11.04**



PDP PACKAGE

PROJECT

MANDELA STATION @ WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT

jrdv ARCHITECTS
JRDV Architects, Inc.
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612
USA
510.266.4333 T
www.jrdv.com

PROJECT TEAM



BKF ENGINEERS
1646 N. CALIFORNIA
BLVD, SUITE 400
WALNUT CREEK
CA 94596
(925) 940-2200

PGA DESIGN
444 17th Street
Oakland
CA 94612
(510) 455-1284

STOK
845B Front Street
San Francisco
CA 94111
(415) 329-7100

STAMP

KEY



PROJ #: 168-153 WO BART
DATE: July 22, 20
SCALE: 1/32"=1'-0"
TITLE:

6TH-7TH
FLOOR
PLAN

SHEET: **A11.06**

PDP PACKAGE

PROJECT

MANDELA STATION @ WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT

jrdv ARCHITECTS
JRDV Architects, Inc.
The Cathedral Building
Broadway and Telegraph
PO Box 70126
Oakland, CA 94612
USA
510.266.4333 T
www.jrdv.com

PROJECT TEAM

INF ENGINEERS
1646 N CALIFORNIA
BLVD, SUITE 400
WALNUT CREEK
CA 94596
(925) 940-2200



PGA DESIGN
444 17th Street
Oakland
CA 94612
(510) 455-1284





STOK
949B Front Street
San Francisco
CA 94111
(415) 329-7100



STAMP

KEY



PROJ #: 168-153 WO BART
DATE: July 22, 20
SCALE: 1/32"=1'-0"
TITLE:

8-18TH
FLOOR
PLAN

SHEET: **A11.07**

PDP PACKAGE

PROJECT

MANDELA STATION @ WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT

jrdv ARCHITECTS
JRDV Architects, Inc.
The Cathedral
Building
Broadway and
Telegraph
PO Box 70126
Oakland, CA 94612
USA
913.266.4333 T
www.jrdv.com

PROJECT TEAM

BEF ENGINEERS
1646 N CALIFORNIA
BLVD, SUITE 400
WALNUT CREEK
CA 94596
(925) 945-2200



PGA DESIGN
444 17th Street
Oakland
CA 94612
(510) 455-1284






STOK
949B Front Street
San Francisco
CA 94111
(415) 329-7100



STAMP

KEY



PROJ #: 168-153 WO BART
DATE: July 22, 20
SCALE: 1/32"=1'-0"
TITLE:

19TH
FLOOR
PLAN

SHEET: **A11.08**



PDP PACKAGE

PROJECT

MANDELA STATION @ WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT



JRDV Architects, Inc.
The Cathedral
Building
Broadway and
Telegraph
PO Box 70126
Oakland, CA 94612
USA
913.266.4333 T
www.jrdv.com

PROJECT TEAM

INF ENGINEERS
1646 N CALIFORNIA
BLVD, SUITE 400
WALNUT CREEK
CA 94596
(925) 945-2200



PGA DESIGN
444 17th Street
Oakland
CA 94612
(510) 455-1284





STOK
949B Front Street
San Francisco
CA 94111
(415) 329-7100



STAMP



KEY



PROJ #: 168-153 WO BART
DATE: July 22, 20
SCALE: 1/32"=1'-0"
TITLE:

20TH-31TH
FLOOR
PLAN

SHEET: **A11.09**



PDP PACKAGE

PROJECT

MANDELA STATION @ WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT

jrdv ARCHITECTS
JRDV Architects, Inc.
The Cathedral
Building
Broadway and
Telegraph
PO Box 70126
Oakland, CA 94612
USA
910.266.4332 T
www.jrdv.com

PROJECT TEAM

BNF ENGINEERS
1646 N CALIFORNIA
BLVD, SUITE 400
WALNUT CREEK
CA 94596
(925) 940-2200



PGA DESIGN
444 17th Street
Oakland
CA 94612
(510) 455-1284





STOK
949B Front Street
San Francisco
CA 94111
(415) 329-7100



STAMP

KEY



Note:
The Applicant is requesting for a loading variance.

PROJ #: 168-153 WO BART
DATE: July 22, 20
SCALE: 1/32"=1'-0"
TITLE:

B1
FLOOR
PLAN
SHEET: **A11.11**



PDP PACKAGE

PROJECT

MANDELA STATION @ WEST OAKLAND BART
1451 7th St, Oakland, CA 94607

ARCHITECT



PROJECT TEAM

INF ENGINEERS
1646 N CALIFORNIA
BLVD, SUITE 400
WALNUT CREEK
CA 94596
(925) 945-2200



PGA DESIGN
444 17th Street
Oakland
CA 94612
(510) 455-1284





STOK
949B Front Street
San Francisco
CA 94111
(415) 329-7100



STAMP



KEY



PROJ #: 168-153 WO BART
DATE: July 22, 20
SCALE: 1/32"=1'-0"
TITLE:

B2
FLOOR
PLAN



SHEET: A11.12








- ROOF 100'-0"
- 7TH FLOOR 90'-0"
- 6TH FLOOR 76'-6"
- 5TH FLOOR 63'-0"
- 4TH FLOOR 49'-6"
- 3RD FLOOR 36'-0"
- 2ND FLOOR 18'-0"
- GROUND FLOOR 0'-0"


- ROOF 320'-0"
- 31TH FLOOR 307'-4"
- 30TH FLOOR 296'-10"
- 29TH FLOOR 286'-4"
- 28TH FLOOR 276'-8"
- 27TH FLOOR 267'-0"
- 26TH FLOOR 257'-4"
- 25TH FLOOR 247'-8"
- 24TH FLOOR 238'-0"
- 23TH FLOOR 228'-4"
- 22TH FLOOR 218'-8"
- 21TH FLOOR 209'-0"
- 20TH FLOOR 199'-4"
- 19TH FLOOR 189'-8"
- 18TH FLOOR 180'-0"
- 17TH FLOOR 170'-4"
- 16TH FLOOR 159'-8"
- 15TH FLOOR 150'-0"
- 14TH FLOOR 140'-4"
- 13TH FLOOR 130'-8"
- 12TH FLOOR 121'-0"
- 11TH FLOOR 111'-4"
- 10TH FLOOR 101'-8"
- 9TH FLOOR 92'-0"
- 8TH FLOOR 82'-4"
- 7TH FLOOR 72'-8"
- 6TH FLOOR 63'-0"
- 5TH FLOOR 53'-4"
- 4TH FLOOR (AMENITY) 39'-4"
- 3RD FLOOR 29'-8"
- 2ND FLOOR 20'-0"
- GROUND FLOOR 0'-0"











1 5





